Appendix A: Analysis and Final Report: "Building 1—Core Wall Only" Sample Design for PEER/CSSC, Los Angeles, California

ANALYSIS AND DESIGN FINAL REPORT

"Building 1 – Core Wall Only" Sample Design for PEER/CSSC
Los Angeles, California

December 9, 2009

MAGNUSSON KLEMENCIC ASSOCIATES

Structural + Civil Engineers
1301 Fifth Avenue, Suite 3200
Seattle, Washington 98101-2699
T: 206 292 1200 F: 206 292 1201

PROJECT DESCRIPTION 1

ANALYSIS AND DESIGN COMPARISON 7

BUILDING CODES 9
- Building Codes 9
- Material Codes 10

LOADING CRITERIA 10
- Gravity Loading 10
- Wind Design Criteria 11
- Seismic Design Criteria 12
- Seismic Response Spectra and Ground Motions for Non-Linear Response History Analysis 13

MATERIALS 14

ANALYSIS AND DESIGN SOFTWARE 15

LOAD COMBINATIONS
- Building 1A Load Combinations 16
- Building 1B and 1C Serviceability Load Combinations 17
- Building 1B and 1C MCE Load Combinations 17

LATERAL MODEL SUMMARY
- Elastic Models 18
- Non-Linear Models 20

ACCEPTANCE CRITERIA 20
- Serviceability Analysis 20
- NLRHA Acceptance Criteria 21

DESIGN SUMMARY
- Building 1 22
- Design Comparison Results 23

OBSERVATIONS AND CONCLUSIONS 43

APPENDICES

Appendix 1: Rebar Design Drawings (Buildings 1A, 1B, and 1C)
Appendix 2: Coupling Beam Design Charts (Buildings 1A, 1B, and 1C)
Appendix 3: Drift Plots – MCE Level (Buildings 1B and 1C)
Appendix 4: Shear and Overturning Plots – MCE Level (Buildings 1B and 1C)
Appendix 5: Coupling Beam Rotations – MCE Level (Buildings 1B and 1C)
Appendix 6: Compression and Tension Strains – MCE Level (Buildings 1B and 1C)
Appendix 7: Wall Panel Shear – MCE Level (Buildings 1B and 1C)

PROJECT DESCRIPTION

Magnusson Klemencic Associates (MKA) performed the structural design for a sample building on behalf of the Pacific Earthquake Engineering Research Center (PEER) as part of the Tall Buildings Initiative (TBI). The research project is done on behalf of the California Seismic Safety Commission (CSSC) and the California Office of Emergency Services. The goal of the overall research project is to quantify and compare seismic performance and expected losses of three hypothetical, yet realistic, tall buildings in California.

The building designed by MKA consists of a representative structure with concrete core walls alone serving as the lateral system. The building is located in Los Angeles, California, and is a 42-story hotel. For the purposes of reporting, the building designed by MKA is called Building 1.

Three different designs for Building 1 were performed, as summarized below:

- **Building 1A: Prescriptive provisions of the IBC.** All prescriptive provisions of the building code, the 2006 edition of the International Building Code (IBC), were observed with one exception: the height limit. Capacity design principles were not employed. A non-linear model of the resulting design was created; however, a Non-Linear Response History Analysis (NLRHA) was not performed.

- **Building 1B: Performance-based design per LATBSDC criteria.** A performance-based design (PBD) was performed according to the 2008 edition of the seismic design criteria published by the Los Angeles Tall Buildings Structural Design Council (LATBSDC), with the following exceptions:

  — The serviceability analysis considered an earthquake event with a 25-year mean recurrence interval (MRI) and 2.5 percent viscous damping. Less than 20 percent of the ductile elements were allowed to reach 150 percent of their capacity in the serviceability analysis.

  — The minimum base shear specified in the LATBSDC document was waived. The serviceability earthquake in conjunction with design for wind forces determined the minimum strength of the lateral system.

- **Building 1C: Higher seismic hazard PBD per PEER guidelines.** A performance-based design was performed similar to Building 1B but in accordance with the draft Guidelines for Seismic Design of Tall Buildings dated August 4, 2009, as developed by the PEER under its TBI. For this design the serviceability analysis considered an earthquake event with a 43-year MRI and 2.5 percent viscous damping. All ductile elements were allowed to reach 150 percent of their capacity in the serviceability analysis.

The seismological data (response spectra and earthquake records) for use in the design of the project were provided by Mactec. Three sets of earthquake records were provided by Mactec:

- Original Records: Used to complete the design of Building 1B.

- Revised Records: Used to complete the design of Building 1C. The results in this report for Building 1B also consider the revised records. However, the design for Building 1B was not updated.

- Service-Level Records: Not used in MKA's design.

Conceptual images of Building 1 are shown in Figures 1 through 5.

Figure 1. Building 1 Foundation Plan

Figure 2. Building 1 Tower Plan

Figure 3. Building 1 Tower Isometric

Figure 4. Building 1 Core Wall Elevations

Figure 5. Building 1 Core Wall Isometric

ANALYSIS AND DESIGN COMPARISON OVERVIEW

Since the results of the three designs will be compared, it is important to note the differences in design approach taken for each of the three buildings. Comparison studies performed by others may not provide the expected results. The shaded cells in Table 1 highlight the primary differences between the three designs.

Table 1. Analysis and Design Approach Comparison

Topic	Building 1A Prescriptive Code Design	Building 1B LATBSDC PBD Design	Building 1C PEER TBI PBD Design
Minimum Strength	0.060 * 85% = 0.051W (ASCE Equation 12.8-6)	25-year MRI, 2.5% damped serviceability spectrum	43-year MRI, 2.5% damped serviceability spectrum
Elastic Computer Model	▪ Specified material properties ▪ Gravity system not included ▪ Stiffness assumptions assume cracking at DBE level ("more cracked" model)	▪ Expected material properties ▪ Gravity system included ▪ Stiffness assumptions assume cracking at Service level ("less cracked" model)	▪ Expected material properties ▪ Gravity system included ▪ Stiffness assumptions assume cracking at Service level ("less cracked" model)
Model of Below-Grade Structure	Model extends to foundation mat including basement walls and below-grade slabs. Mass and mass moment-of-inertia are included in the model. Lateral resistance of the soil on the foundation walls is neglected.	Model extends to foundation mat including basement walls and below-grade slabs. Mass and mass moment-of-inertia are included in the model. Lateral resistance of the soil on the foundation walls is neglected.	Model extends to foundation mat including basement walls and below-grade slabs. Mass and mass moment-of-inertia are not included in the model. Lateral resistance of the soil on the foundation walls is neglected.

Topic	Building 1A Prescriptive Code Design	Building 1B LATBSDC PBD Design	Building 1C PEER TBI PBD Design
Procedure Used to Provide Initial Design of Elements	Design followed the prescriptive provisions of the building code including the use of strength reduction factors and specified material properties.	▪ Story drift limited to 0.5% ▪ Coupling beams were designed using specified material strengths and strength reduction factors in accordance with material codes. No more than 20% of the beams are allowed to have a demand-capacity ratio greater than 1.0 but less than 1.5. ▪ Core wall shear and flexure were designed using specified material strengths and strength reduction factors in accordance with material codes. All demand-capacity ratios less are than 1.0.	▪ Story drift limited to 0.5% ▪ Coupling beams were designed using expected material strengths and strength reduction factors set to unity. 100% of the beams are allowed to have a demand-capacity ratio greater than 1.0 but less than 1.5. ▪ Core wall shear was designed using specified material strengths and strength reduction factors in accordance with material codes. All demand-capacity ratios are less than 1.0. ▪ For core wall flexure, where the axial load on a wall pier including EQ effect (Pu) is less than or equal to 0.3(f'c) using expected material props, P-M-M interaction design considered expected material strengths and strength reduction factors set to unity. The wall piers were allowed to have a demand-capacity ratio greater than 1.0 but less than 1.5. Where Pu was greater than 0.3(f'c), P-M-M interaction design considered specified material strengths and strength reduction factors in accordance with material codes. All demand-capacity ratios were less than 1.0.

Topic	Building 1A Prescriptive Code Design	Building 1B LATBSDC PBD Design	Building 1C PEER TBI PBD Design
Non-Linear Computer Model	Model created using similar techniques to Building 1B. Model includes gravity system approximation.	Non-linear model created as summarized in MKA's Non-Linear Response History Analysis Model Report.	Model created using similar techniques to Building 1B with updated element properties based on the design of Building 1C.
MCE-Level Hazard	MCE-level checks were not performed.	Seven earthquake records (original records) were used. The revised records were evaluated, but the design was not updated for the new results.	Seven earthquake records (revised records) were used.
MCE-Level Checks	MCE-level checks were not performed.	▪ **Ductile Actions and Drift**: Mean demands were used. Capacities were calculated using expected material properties and strength reduction factors set to unity. ▪ **Brittle Actions**: 1.5 times the mean demands were used. Capacities were calculated using specified material properties and strength reduction factors set to unity.	▪ **Ductile Actions and Drift**: Mean demands were used. Capacities were calculated using expected material properties and strength reduction factors set to unity. ▪ **Brittle Actions**: 1.5 times the mean demands were used. Capacities were calculated using specified material properties and strength reduction factors set to unity.

BUILDING CODES

The following building and material codes were used for the design:

BUILDING CODE

- International Building Code, 2006 Edition (IBC 2006) with reference to Minimum Design Loads for Buildings and Other Structures by the American Society of Civil Engineers, 2005 Edition (ASCE 7).
- Alternative Seismic Design Criteria published by the Los Angeles Tall Buildings Structural Design Council (LATBSDC), 2008 Edition.
- Guidelines for Seismic Design of Tall Buildings developed by the Pacific Earthquake Engineering Research Center under its Tall Buildings Initiative, March 21, 2009 draft with August 4, 2009 updates.

MATERIAL CODES

- Reinforced Concrete: Building Code Requirements for Structural Concrete and Commentary by the American Concrete Institute, 2008 Edition (ACI 318).

LOADING CRITERIA

A summary of the project-specific loading criteria follows.

GRAVITY LOADING

The gravity loads listed in Table 2 are in addition to the self weight of the structure. The minimum loading requirements were taken from Table 4-1 of ASCE 7 as well as the loading criteria supplied by PEER. Live loads were reduced where permitted in accordance with Section 4.8 of ASCE 7. Loads are given in pounds per square foot (psf).

Table 2. Gravity Loads

Use	Live Loading	Superimposed Dead Loading
Parking Garage	40 (not reduced)	3
Level 1 Retail (under tower footprint)	100 (not reduced)	110
Level 1 Plaza (outside tower footprint)	100 (not reduced)	350
Exit Areas (assumed inside core walls only)	100 (not reduced)	28
Residential/Hotel (used for all elevated levels of the tower outside the core walls)	40	28
Mechanical/Electrical	0	100 kips at roof level only
Roof	25	28

In addition to these uniform slab loads, a perimeter dead load as shown in Table 3 was applied to the structure to account for the weight of the cladding system.

Table 3. Cladding Loads

Load Type	Load (psf)
Exterior Cladding (curtain wall)	15 psf (wall area)

WIND DESIGN CRITERIA

Wind loading is in accordance with the ASCE 7 requirements as shown in Table 4. It was determined that wind did not govern any portion of the design of Building 1.

Table 4. Wind Design Criteria

Parameter	Value
Basic Wind Speed, 3-second gust *(V)*	85 mph
Basic Wind Speed, 3-second gust *(V)*, for serviceability wind demands based on a 10-year mean recurrence interval	67 mph
Exposure	B
Occupancy Category	II
Importance Factor *(I_w)*	1.0
Topographic Factor (K_{zt})	1.0
Enclosure Classification	Enclosed
Internal Pressure Coefficient *(GC_{pi})*	0.18
Mean Roof Height *(h)*	409'-10"

SEISMIC DESIGN CRITERIA

Seismic loads are in accordance with the ASCE 7 requirements as shown in Table 5. These code values were used only in the design of Building 1A.

Table 5. Seismic Design Criteria – Used for Building 1A Only

Parameter	Value
Building Latitude/Longitude	34.0495° N, 118.252° W
Occupancy Category	II
Importance Factor *(I_e)*	1.0
Mapped Spectral Acceleration	$S_s = 2.147$; $S_1 = 0.720$
Site Class	C
Site Class Coefficients	$F_a = 1.00$; $F_v = 1.30$
Spectral Response Coefficients	$S_{DS} = 1.145$; $S_{D1} = 0.521$
Seismic Design Category	D
Lateral System	Building Frame, Special Reinforced Concrete Shear Walls
Response Modification Coefficient *(R)*	6
Building Period (T_{code}), Section 12.8.2	T_{code} = 2.55 seconds (Based on H= 409'-10")
C_s (Equation 12.8-2)	$C_s = \frac{S_{DS}}{(R/I)} = 0.19$
C_s^{max} (Equation 12.8-3)	$C_s^{max} = \frac{S_{D1}}{T_{code}(R/I)} = 0.034$
C_s^{min} (Equation 12.8-5, including ASCE 7 supplement 2)	$C_s^{min} = 0.044 S_{DS} I = 0.050$
C_s^{min} (Equation 12.8-6)	$C_s^{min} = \frac{0.5 S_1}{R/I} = 0.060 \leftarrow governs$
Seismic Response Coefficient	$C_s = 0.060$
Seismic Weight, weight above Level 1	W = 89,500 kips
Design Base Shear	$V = 0.85 C_s W = 0.051 W = 4{,}565 kips$
Analysis Procedure Used	Modal Analysis Procedure

SEISMIC RESPONSE SPECTRA AND GROUND MOTIONS FOR NON-LINEAR RESPONSE HISTORY ANALYSIS (NLRHA)

Seismic response spectra and seven pairs of site-specific ground motions were provided by Mactec for this study. All spectra provided are at the ground surface level. Ground motions were provided as free-field motions (i.e., at the ground surface) and were spectrally matched to the Maximum Considered Earthquake (MCE) spectrum. All spectra and ground motions were applied to the lateral models at the level of the mat foundation.

The design spectra for the project, generated using the provisions of ASCE 7 -05, Section 21.3, are shown in Figure 6.

Figure 6. Design Spectra

MATERIALS

The material properties used for the design are summarized in Tables 6 through 8. The modulus of elasticity for concrete was calculated using Equation 5-1 of ACI 363.

Table 6. Concrete Properties, Compressive Strength, and Modulus of Elasticity

Member	Nominal f'_c	Expected f'_c	Nominal E	Expected E
Basement Walls	5.0 ksi	6.5 ksi	3,830 ksi	4,225 ksi
Foundation Mats	6.0 ksi	7.8 ksi	4,100 ksi	4,530 ksi
Non-Post-Tensioned Beams and Slabs	5.5 ksi	7.2 ksi	3,970 ksi	4,395 ksi
Post-Tensioned Floor Slabs	5.5 ksi	7.2 ksi	3,970 ksi	4,395 ksi
Columns	8.0 ksi	10.4 ksi	4,580 ksi	5,080 ksi
Shear Walls	8.0 ksi	10.4 ksi	4,580 ksi	5,080 ksi

Table 7. Reinforcement and Post-Tensioning Properties

Standard	Nominal f_y	Expected f_y	Expected f_u
ASTM A615 Grade 60	60 ksi (non-seismic)	N/A	N/A
ASTM A706 Grade 60	60 ksi (seismic)	70 ksi	105 ksi
ASTM A615 Grade 75	75 ksi (used in coupling beams)	85 ksi	130 ksi

Table 8. Post-Tensioned Tendon Properties

Standard	Nominal f_u	Expected f_u
0.5-inch-diameter, 7-wire strand	f_{pu} = 270 ksi	N/A

DESIGN AND ANALYSIS SOFTWARE

The computer software employed for the analysis of the structure is listed in Table 9.

Table 9. Design and Analysis Software

Structural Analysis	Computer Software
Elastic Response Spectrum Analysis	ETABS, version 9
Non-linear Response History Analysis	CSI Perform-3D, version 4
Concrete Core Wall Flexural Design	PCA Column, version 4
Concrete Core Wall Moment Curvature Analysis	UC Fyber, version 2.4
Post-tensioned Slab Analysis	Ram-Concept, version 2.1
Reinforced Concrete Slab Analysis	SAFE, version 8

LOAD COMBINATIONS

BUILDING 1A LOAD COMBINATIONS

The design basis event was analyzed with modal response spectrum analysis. The load combinations shown in Table 10 follow the strength design load combinations listed in ASCE 7, Section 12.4.2.3.

Table 10. DBE Load Combinations

Identifier	Load Combinations
Load Combination 1	$(1.2+0.2S_{DS})D \pm \rho Q_E + f_1 L$
Load Combination 2	$(0.9-0.2S_{DS})D \pm \rho Q_E$

Where: D = dead load
L = reduced live load
f_1 = 0.5 per ASCE 7, Section 12.4.2.3, Note 1
ρ = the redundancy factor
$0.2S_{DS}D = E_v$ per ASCE 7, Section 12.4.2.2
$\rho Q_E = E_h$ per ASCE 7, Section 12.4.2.1

Seismic directional effects were considered as follows:

- $Q_{EX} = \pm 1.0\ E_{hx} \pm 0.3\ E_{hy} \pm T_{hx}$
- $Q_{EY} = \pm 0.3\ E_{hx} \pm 1.0\ E_{hy} \pm T_{hy}$

Where: E_{hx} and E_{hy} = earthquake forces in the primary structural directions, determined by spectral analysis
T_{hx} and T_{hy} = accidental torsion per ASCE 7, Section 12.8.4.2 (forces in X and Y directions, respectively)

BUILDING 1B AND 1C SERVICEABILITY LOAD COMBINATION

The serviceability event was analyzed using a modal response spectrum analysis. Accidental torsion was not considered in this analysis, and one load combination was used, as shown in Table 11.

Table 11. Serviceability Load Combination

Identifier	Load Combination
Load Combination	$1.0D + 0.25L \pm 1.0E_{service}$

Where: D = dead load
L = unreduced live load
$E_{service}$ = serviceability response spectrum

Seismic directional effects were considered as follows:

- $E_{service} = \pm 1.0\ E_{service_x} \pm 0.3\ E_{service_y}$ and $\pm 0.3\ E_{service_x} \pm 1.0\ E_{service_y}$

BUILDING 1B AND 1C MCE LOAD COMBINATIONS

The NLRHA utilized one load combination for the MCE event, as shown in Table 12. This load combination was used for each of the seven ground motion records. Accidental torsion was not considered in this analysis.

Table 12. NLRHA Load Combination

Identifier	Load Combination
Load Combination	1.0D + 0.25L +1.0E

Where: D = dead load
L = unreduced live load
E = earthquake load (ground motion records)
The ground motion records consist of two components. The components were not rotated to match the building axes.

LATERAL MODEL SUMMARY

ELASTIC MODELS

Complete, three-dimensional elastic computer models for each building were analyzed using ETABS. The models included the core walls, ground-level diaphragm, below-grade diaphragms, and basement walls. The diaphragms and walls were modeled using shell elements. The coupling beams were modeled using frame elements. Openings through the core walls were modeled with separate wall elements coupled together with concrete beams.

The elastic model was used for both the code-level design of Building 1A and the serviceability analysis of Buildings 1B and 1C. The stiffness parameters for the various elements were varied in each of the models. Table 13 summarizes the stiffness assumptions in the computer models.

For the serviceability analyses only, slab outrigger effects were modeled using wide, shallow beams connecting the core walls to lumped concrete columns in the ETABS model. The modeling approach used for the slab outrigger beams is shown in Figure 7.

Figure 7. Slab Outrigger Modeling Approach

Stiffness

The stiffness assumptions used vary for each computer model based on the expected demand level. A summary of stiffness assumptions is shown in Table 13.

Table 13. Computer Model Stiffness Assumptions

Concrete Element	Serviceability Analysis and Wind – All Buildings	Code-Level Analysis – Building 1A Only	MCE-Level Non-Linear Models – All Buildings
Specified vs. Expected Concrete Strength	Expected concrete strength	Specified concrete strength	Expected concrete strength
Core Walls/Shear Walls	Flexural – 0.9Ig Shear – 1.0A	Flexural – 0.6Ig Shear – 1.0A	Refer to non-linear model summary
Basement Walls	Flexural – 1.0Ig Shear – 1.0A	Flexural – 0.8Ig Shear – 0.8A	Flexural – 0.8Ig Shear – 0.8A
Coupling Beams	Flexural – 0.5Ig Shear – 1.0A	Flexural – 0.2Ig Shear – 1.0A	Refer to non-linear model summary
Ground Level Diaphragm	Flexural – 0.5Ig Shear – 0.8A	Flexural – 0.25Ig Shear – 0.5A	Flexural – 0.25Ig Shear – 0.25A
Basement Diaphragms	Flexural – 0.5Ig Shear – 0.8A	Flexural – 0.25Ig Shear – 0.5A	Flexural – 0.25Ig Shear – 0.25A
Concrete Columns	Flexural – 1.0Ig Shear – 1.0A Axial – 1.0A	Not included in code design	Refer to non-linear model summary
Outrigger Slabs	Flexural – 0.35Ig Shear – 1.0A	Not included in code design	Refer to non-linear model summary

Soil Structure Interaction Assumptions

Design spectra were applied to all computer models at the level of the top of the mat foundation. The flexibility of the subgrade and mat foundation was ignored, and the model was "fixed" at the top of the mat. Vertical and horizontal supports with no rotational restraints were assigned to all of the nodes of the model at the foundation level. The lateral resistance and damping effects of the soil on the sides of the basement walls were neglected in all models.

NON-LINEAR MODELS

Non-linear verification models were built in CSI Perform-3D for each building. The models include inelastic member properties for elements that are anticipated to be loaded beyond their elastic limits. These include the coupling beams, core wall flexural behavior, and "slab-beams" to account for any outriggering effect of the flat slabs. Elements that are assumed to remain elastic were modeled with elastic member properties. These include core wall shear behavior, diaphragm slabs, columns, and basement walls.

A detailed description of the non-linear modeling assumptions is included in a separate report entitled "Non-Linear Response History Analysis Model Report".

ACCEPTANCE CRITERIA

Acceptance criteria were required for the performance-based designs of Buildings 1B and 1C. The acceptance criteria for each of the two demand levels evaluated are listed in Tables 14 and 15.

SERVICEABILITY ANALYSIS

Table 14. Serviceability Acceptance Criteria

Item	Value
Story Drift	0.5%
Coupling Beams	Shear strength to remain essentially elastic
Core Wall Flexure	Remains essentially elastic
Core Wall Shear	Remains elastic
Slab Outrigger Beams	End moment to remain essentially elastic
Columns	Remains elastic

Acceptance criteria related to essentially elastic behavior for ductile elements in Buildings 1B and 1C were slightly different. A comparison can be found in Table 1 of this report.

NLRHA ACCEPTANCE CRITERIA

The following acceptance criteria were selected for Collapse Prevention performance under the MCE-level demand.

Table 15. NLRHA Acceptance Criteria

Item	Value
Story Drift	3% under MCE, taken as the average of seven response history results.
Coupling Beam Rotation	0.06 radian rotation limit, taken as the average of seven response history results.
Core Wall Reinforcement Axial Strain	Rebar tensile strain = 0.05 in tension and 0.02 in compression, taken as the average of seven response history results.
Core Wall Concrete Axial Strain	Fully Confined Concrete Compression Strain = 0.015, taken as the average of seven response history results.
Core Wall Shear	Verification performed for elastic behavior.
Slab Outrigger Beams	Included to study impact to core and column only. The performance of the moment hinges was not specifically reviewed.
Columns	Increases in column axial demands were reviewed.

The MCE-level acceptance criteria are summarized below:

- Ductile Actions and Drift: Mean demands were used. Capacity was calculated using expected material properties and strength reduction factors set to 1.0.
- Brittle Actions: 1.5 times the mean demands were used. Capacity was calculated using specified material strengths and strength reduction factors set to 1.0.

DESIGN SUMMARY

BUILDING 1

The gravity column sizes determined for all three buildings are summarized in Table 16. While rectangular columns would be expected in this type of building, square columns were selected for simplicity.

Table 16. Column Sizes

Column Mark	Levels	Size
D/3.5	Level 34 – Roof	18"×18"
	Level 22 – 34	21"×21"
	Level 12 – 22	25"×25"
	Fdn – Level 12	30"×30"
D/5	Level 34 – Roof	18"×18"
	Level 22 – 34	19"×19"
	Level 12 – 22	24"×24"
	Fdn – Level 12	29"×29"
D/6	Level 34 – Roof	18"×18"
	Level 22 – 34	18"×18"
	Level 12 – 22	18"×18"
	Fdn – Level 12	24"×24"
E/5	Level 34 – Roof	18"×18"
	Level 22 – 34	22"×22"
	Level 12 – 22	26"×26"
	Fdn – Level 12	33"×33"
E/6	Level 34 – Roof	18"×18"
	Level 22 – 34	18"×18"
	Level 12 – 22	19"×19"
	Fdn – Level 12	26"×26"
F/4	Level 34 – Roof	18"×18"
	Level 22 – 34	21"×21"
	Level 12 – 22	26"×26"
	Fdn – Level 12	34"×34"
F/5	Level 34 – Roof	18"×18"
	Level 22 – 34	18"×18"
	Level 12 – 22	21"×21"
	Fdn – Level 12	28"×28"

Column Marks

DESIGN COMPARISON RESULTS

Key values from the design and selected element sizes are included in Table 17.

Table 17. Building 1 Comparison Results

	Building 1A	Building 1B	Building 1C
Code/Service EQ Base Shear (kips)	V_x = 4,581 (code) V_y = 4,581	V_x = 5,013 (service EQ) V_y = 6,018	V_x = 6,686 (service EQ) V_y = 8,151
Code/Service EQ Overturning Moment (kip-ft)	M_y = 587,000 (code) M_x = 697,000	M_y = 591,000 (service EQ) M_x = 921,000	M_y = 892,000 (service EQ) M_x =1,371,000
MCE Base Shear (kips) Average of 7 EQs	—	V_X = 13,718 V_Y = 13,899	V_X = 13,025 V_Y = 12,449
MCE Overturning Moment (kip-ft) Average of 7 EQs	—	M_Y = 1,629,000 M_X = 1,227,000	M_Y = 1,504,000 M_X = 1,221,000
Core Wall Thicknesses (inches)	Grade – Lvl 25: 24 Lvl 25 – Roof: 21	Grade – Lvl 13: 28 (E-W) 32 (N-S) Lvl 13 – Lvl 31: 24 Lvl 31 – Roof: 21	Grade – Lvl 13: 32 (E-W) 36 (N-S) Lvl 13 – Lvl 31: 24 Lvl 31 – Roof: 21
Period (seconds) in ETABS Model	T_1 = 6.7 T_2 = 4.8 T_T = 2.6	T_1 = 4.0 T_2 = 3.0 T_T = 1.5	T_1 = 4.0 T_2 = 3.0 T_T = 1.5
Period (seconds) in Perform3D Model	T_1 = 5.0 T_2 = 3.8 T_T = 2.4	T_1 = 4.2 T_2 = 3.4 T_T = 2.3	T_1 = 4.0 T_2 = 3.2 T_T = 2.2
Maximum Story Drift (Service)	—	δ_X = 0.25% δ_Y = 0.20%	δ_X = 0.35% δ_Y = 0.28%
Maximum Story Drift (MCE)	δ_X = 1.1% δ_Y = 0.8% Ref: Section 12.8.6	δ_X = 2.0% δ_Y = 1.3% Average of 7 EQs	δ_X = 1.8% δ_Y = 1.1% Average of 7 EQs

Figures 8 and 9 compare the shear and overturning moment demands on the three buildings.

Figure 8. Core Wall Shear Force Comparison

Figure 9. Core Wall Overturning Moment Comparison

The design of the coupling beams varied the most between the three different analyses. Figures 10 to 12 compare the rebar selected for each design.

Figure 10. Coupling Beam Reinforcement Comparison

Figure 11. Coupling Beam Reinforcement Comparison

Figure 12. Coupling Beam Reinforcement Comparison

Comparisons of the vertical and horizontal reinforcing distributions that resulted from the three designs are illustrated in Figures 13 through 20.

Figure 13. Wall Vertical Reinforcing Comparison

Figure 14. Wall Vertical Reinforcing Comparison

Figure 15. Wall Vertical Reinforcing Comparison

Figure 16. Wall Horizontal Reinforcing Comparison

Figure 17. Wall Horizontal Reinforcing Comparison

Figure 18. Wall Horizontal Reinforcing Comparison

Figure 19. Wall Horizontal Reinforcing Comparison

Figure 20. Wall Horizontal Reinforcing Comparison

Figures 21 and 22 compare the MCE shear force and overturning moment demands for Buildings 1B and 1C.

Figure 21. MCE Core Wall Shear Force Comparison

Figure 22. MCE Core Wall Overturning Moment Comparison

Figure 23 compares the calculated MCE drifts for Buildings 1B and 1C.

Figure 23. MCE Story Drift Comparison

Figures 24 to 26 compare the MCE coupling beam rotations for Buildings 1B and 1C.

Figure 24. MCE Coupling Beam Rotation Comparison

Figure 25. MCE Coupling Beam Rotation Comparison

Figure 26. MCE Coupling Beam Rotation Comparison

The appendices to this report contain more detailed information related to the design and verification analyses performed on the three buildings.

Appendix	Title	Buildings
1	Rebar Design Drawings	1A, 1B, and 1C
2	Coupling Beam Design Charts	1A, 1B, and 1C
3	Drift Plots – MCE Level	1B and 1C
4	Shear and Overturning Plots – MCE Level	1B and 1C
5	Coupling Beam Rotations – MCE Level	1B and 1C
6	Compression and Tension Strains – MCE Level	1B and 1C
7	Wall Panel Shear – MCE Level	1B and 1C

OBSERVATIONS AND CONCLUSIONS

The following observations are made regarding the comparison of the three designs.

- Core wall shear is the prevailing design parameter and governs the determination of wall thickness for all of the designs. The thickest walls were required for Building 1C, and the thinnest walls were required for Building 1A.

- While MCE-level checks were not performed on Building 1A, wall shear demands are expected to be well above the provided capacity and may lead to an increased likelihood of collapse when compared to Buildings 1B and 1C. The provided shear reinforcing only meets the demands required by the building code without consideration of the flexural strength of the core walls.

- Serviceability-level demands for Building 1C were approximately 40 percent greater than those for Building 1B due to the increase in seismic hazard (43-year MRI versus 25-year MRI). Wind demands were not a controlling parameter in any of the designs.

- Coupling beam reinforcement is smallest for Building 1C even though it has the largest calculated coupling beam demands under the serviceability analysis. The reinforcement selected for the coupling beams for Buildings 1A and 1B is approximately the same.

- The provided vertical wall reinforcement is greatest for Building 1C and smallest for Building 1A. This would indicate that Building 1C exhibits greater strong pier/weak coupling beam behavior than do the other two designs.

Regarding the performance of Buildings 1B and 1C under MCE-level demands, the following observations are made:

- The average inter-story drifts fall below the acceptance criteria of 3 percent for both buildings. Drift demands are slightly higher in Building 1B.

- Coupling beam rotation demands are between 1 and 3 percent for Building 1C. Building 1B has slightly lower demands of between 1 and 2 percent. For both buildings, coupling beam rotation demands fall well below the acceptance criteria.

- A preliminary assumption for areas of confined and unconfined concrete was needed in order to build the non-linear model. The compression strain plots indicate that the concrete material used in the core wall models remains elastic in compression for the full height of the tower. As a result, it should be possible to reduce the amount of confinement initially assumed in the non-linear model. This refinement was not employed for this case study.

- At every level, the tensile strain demands meet the acceptance criteria. Small amounts of distributed yielding are observed over nearly the full height of both buildings, with the largest tensile strains occurring at the base of the core walls.

- The revised earthquake records when applied to Building 1B lead to some of the wall panels being slightly overstressed in shear. If this design were further developed, additional shear reinforcing would need to be provided to address these localized areas of overstress. Based on the data from the shear plot of Wall Pier 11, the thickness of the short walls of the core may also need to be increased to limit shear stress to $10\sqrt{f'c}$.

- Most of the wall panels for Building 1B were designed for roughly 3 to 3.5 times the shear force calculated under the service-level analysis. The ratio for Building 1C is slightly lower, as design values are two to three times the shear force calculated under the service-level analysis.

- The wall thickness selected for Building 1C appears to be somewhat thicker than optimal. MCE-level wall pier shear demands fall below the code limit on shear stress, particularly in the lower floors of the core. If this building were going to be constructed, MKA would likely iterate a few times on the wall thickness to determine the optimal balance of concrete volume and rebar density.

APPENDIX 1
REBAR DESIGN DRAWINGS
(BUILDINGS 1A, 1B, AND 1C)

MAGNUSSON
KLEMENCIC
ASSOCIATES

BUILDING 1A - VERTICAL REINFORCING

A NORTH & SOUTH ELEVATION

B EAST & WEST ELEVATION

BUILDING 1A - HORIZONTAL & COUPLING BEAM REINFORCING

A NORTH & SOUTH ELEVATION

B EAST & WEST ELEVATION

BUILDING 1A

NOTES:

1. IF EMBED LENGTH OF BAR "a" CANNOT BE ACHIEVED DUE TO EDGE OF CORE WALL, PROVIDE "L_{TERM}" LENGTH BEYOND EDGE OF OPENING AND USE A LENTON TERMINATOR AT END OF REINFORCING.

   FOR Fy = 60KSI, "L_{TERM}" IS AS FOLLOWS:

SIZE	"L_{TERM}"
#5	14"
#6	17"
#7	20"
#8	22"
#9	24"
#10	27"
#11	30"

2. FOR Fy = 75 KSI, MULTIPLY L_{TERM} VALUES BY 1.25.
3. "EMBED" = LENGTH FROM "EMBED TABLE 1" OR "EMBED TABLE 2" DEPENDING ON WHETHER OR NOT THE HOOPS AND CROSS TIES FULLY ENCLOSE THE REBAR EMBED LENGTH IN THE WALL.

TYPICAL COUPLING BEAM 9

TYPICAL COUPLING BEAM SECTION 10

NOTES:

1. DEPTH OF COUPLING BEAMS PER "SHEAR WALL ELEVATIONS". COUPLING BEAM WIDTH MATCHES ADJACENT SHEAR WALLS.
2. CONCRETE STRENGTH OF ALL COUPLING BEAMS SHALL MATCH THAT OF THE ADJACENT WALLS.
3. ALTERNATE CROSSTIES END FOR END.
4. REINFORCING "a", "b", & "c" SHALL BE SPECIAL DUCTILE QUALITY. SEE "GENERAL NOTES" FOR CRITERIA. ALL BARS ARE GRADE 60 UNLESS NOTED OTHERWISE.
5. REFER TO "COUPLING BEAM DETAILS FOR DESCRIPTIONS OF "W" AND "H" DIMENSIONS. THESE DIMENSIONS REFER TO THE PERIMETER BAR CENTER LINES FOR EACH REINFORCING "a" LAYOUT TYPE. THE "W" DIMENSION IS A MINIMUM. THE "H" DIMENSION IS A MAXIMUM.
6. TYPE "c" REINFORCEMENT IS BASED ON DEPTH:
   30" = (4) #5
   34" = (5) #5
   42" = (6) #5

REINFORCING "a" LAYOUT TYPES

STIRRUP TYPES

COUPLING BEAM SCHEDULE

MARK	DIMENSIONS (INCHES) W	DIMENSIONS (INCHES) H	REINFORCING a #	REINFORCING a SIZE	REINFORCING b #	REINFORCING b SIZE	STIRRUP SIZE	STIRRUP TYPE	STIRRUP SPCG	REINFORCING "a" LAYOUT TYPE	REMARKS
1A	6	4	4	#8	3	#5	#5	3	4"	1	
2A	6	4	4	#8	4	#5	#5	4	4"	1	
3A	8	4	6	#10	3	#5	#5	3	4"	2	
4A	8	4	6	#10	4	#5	#5	4	4"	2	
5A	10	8	9	#10	3	#5	#5	3	4"	6	
6A	10	8	9	#10	4	#5	#5	4	4"	6	
7A	12	8	9	#11	4	#5	#5	4	4"	6	

COUPLING BEAM SCHEDULE 15

BUILDING 1B - VERTICAL REINFORCING

A NORTH & SOUTH ELEVATION

B EAST & WEST ELEVATION

BUILDING 1B - HORIZONTAL & COUPLING BEAM REINFORCING

A NORTH & SOUTH ELEVATION

B EAST & WEST ELEVATION

BUILDING 1B

NOTES:

1. IF EMBED LENGTH OF BAR "a" CANNOT BE ACHIEVED DUE TO EDGE OF CORE WALL, PROVIDE "L_{TERM}" LENGTH BEYOND EDGE OF OPENING AND USE A LENTON TERMINATOR AT END OF REINFORCING.

   FOR Fy = 60KSI, "L_{TERM}" IS AS FOLLOWS:

SIZE	"L_{TERM}"
#5	14"
#6	17"
#7	20"
#8	22"
#9	24"
#10	27"
#11	30"

2. FOR Fy = 75 KSI, MULTIPLY L_{TERM} VALUES BY 1.25.
3. "EMBED" = LENGTH FROM "EMBED TABLE 1" OR "EMBED TABLE 2" DEPENDING ON WHETHER OR NOT THE HOOPS AND CROSS TIES FULLY ENCLOSE THE REBAR EMBED LENGTH IN THE WALL.

TYPICAL COUPLING BEAM 9

TYPICAL COUPLING BEAM SECTION 10

NOTES:

1. DEPTH OF COUPLING BEAMS PER "SHEAR WALL ELEVATIONS". COUPLING BEAM WIDTH MATCHES ADJACENT SHEAR WALLS.
2. CONCRETE STRENGTH OF ALL COUPLING BEAMS SHALL MATCH THAT OF THE ADJACENT WALLS.
3. ALTERNATE CROSSTIES END FOR END.
4. REINFORCING "a", "b", & "c" SHALL BE SPECIAL DUCTILE QUALITY. SEE "GENERAL NOTES" FOR CRITERIA. ALL BARS ARE GRADE 60 UNLESS NOTED OTHERWISE.
5. REFER TO "COUPLING BEAM DETAILS FOR DESCRIPTIONS OF "W" AND "H" DIMENSIONS. THESE DIMENSIONS REFER TO THE PERIMETER BAR CENTER LINES FOR EACH REINFORCING "a" LAYOUT TYPE. THE "W" DIMENSION IS A MINIMUM. THE "H" DIMENSION IS A MAXIMUM.
6. TYPE "c" REINFORCEMENT IS BASED ON DEPTH:
   30" = (4) #5
   34" = (5) #5
   42" = (6) #5

REINFORCING "a" LAYOUT TYPES

STIRRUP TYPES

COUPLING BEAM SCHEDULE

MARK	DIMENSIONS (INCHES) W	DIMENSIONS (INCHES) H	REINFORCING a #	REINFORCING a SIZE	REINFORCING b #	REINFORCING b SIZE	STIRRUP SIZE	STIRRUP TYPE	STIRRUP SPCG	REINFORCING "a" LAYOUT TYPE	REMARKS
1B	6	4	4	#8	3	#5	#5	3	4"	1	
2B	6	4	4	#8	4	#5	#5	4	4"	1	
3B	6	4	6	#8	3	#5	#5	3	4"	2	
4B	8	4	6	#10	3	#5	#5	3	4"	2	
5B	8	4	6	#10	4	#5	#5	4	5"	2	
6B	8	4	6	#10	4	#5	#5	4	4"	2	
7B	10	8	9	#10	4	#5	#5	4	5"	6	
8B	10	8	9	#10	4	#5	#5	4	4"	6	
9B	12	8	9	#11	4	#5	#5	4	5"	6	
10B	12	8	9	#11	4	#5	#5	4	4"	6	
11B	12	8	9	#11	5	#5	#5	5	5"	6	
12B	12	8	12	#10	4	#5	#5	4	4"	7	
13B	12	8	12	#10	5	#5	#5	5	5"	7	
14B	12	8	12	#11	4	#5	#5	4	4"	7	

COUPLING BEAM SCHEDULE 15

BUILDING 1C - VERTICAL REINFORCING

A NORTH & SOUTH ELEVATION

B EAST & WEST ELEVATION

BUILDING 1C - HORIZONTAL & COUPLING BEAM REINFORCING

A NORTH & SOUTH ELEVATION

B EAST & WEST ELEVATION

BUILDING 1C

NOTES:

1. IF EMBED LENGTH OF BAR "a" CANNOT BE ACHIEVED DUE TO EDGE OF CORE WALL, PROVIDE "L_{TERM}" LENGTH BEYOND EDGE OF OPENING AND USE A LENTON TERMINATOR AT END OF REINFORCING.

   FOR Fy = 60KSI, "L_{TERM}" IS AS FOLLOWS:

SIZE	"L_{TERM}"
#5	14"
#6	17"
#7	20"
#8	22"
#9	24"
#10	27"
#11	30"

2. FOR Fy = 75 KSI, MULTIPLY L_{TERM} VALUES BY 1.25.
3. "EMBED" = LENGTH FROM "EMBED TABLE 1" OR "EMBED TABLE 2" DEPENDING ON WHETHER OR NOT THE HOOPS AND CROSS TIES FULLY ENCLOSE THE REBAR EMBED LENGTH IN THE WALL.

TYPICAL COUPLING BEAM 9

TYPICAL COUPLING BEAM SECTION 10

NOTES:

1. DEPTH OF COUPLING BEAMS PER "SHEAR WALL ELEVATIONS". COUPLING BEAM WIDTH MATCHES ADJACENT SHEAR WALLS.
2. CONCRETE STRENGTH OF ALL COUPLING BEAMS SHALL MATCH THAT OF THE ADJACENT WALLS.
3. ALTERNATE CROSSTIES END FOR END.
4. REINFORCING "a", "b", & "c" SHALL BE SPECIAL DUCTILE QUALITY. SEE "GENERAL NOTES" FOR CRITERIA. ALL BARS ARE GRADE 60 UNLESS NOTED OTHERWISE.
5. REFER TO "COUPLING BEAM DETAILS FOR DESCRIPTIONS OF "W" AND "H" DIMENSIONS. THESE DIMENSIONS REFER TO THE PERIMETER BAR CENTER LINES FOR EACH REINFORCING "a" LAYOUT TYPE. THE "W" DIMENSION IS A MINIMUM. THE "H" DIMENSION IS A MAXIMUM.
6. TYPE "c" REINFORCEMENT IS BASED ON DEPTH:
   30" = (4) #5
   34" = (4) #5
   42" = (7) #5

REINFORCING "a" LAYOUT TYPES

STIRRUP TYPES

COUPLING BEAM SCHEDULE

MARK	DIMENSIONS (INCHES) W	H	REINFORCING a #	SIZE	REINFORCING b #	SIZE	STIRRUP SIZE	TYPE	SPCG	REINFORCING "a" LAYOUT TYPE	REMARKS
1C	6	4	4	#7	4	#5	#5	4	5"	1	
2C	6	4	4	#7	5	#5	#5	5	4"	1	
3C	6	4	4	#8	4	#5	#5	4	5"	1	
4C	6	4	6	#8	4	#5	#5	4	5"	2	
5C	6	4	6	#8	5	#5	#5	5	4"	2	
6C	4	8	6	#9	4	#5	#5	4	5"	5	
7C	8	4	6	#10	5	#5	#5	5	4"	2	
8C	4	8	6	#10	4	#5	#5	4	5"	5	
9C	4	8	6	#11	4	#5	#5	4	5"	5	
10C	10	8	9	#10	5	#5	#5	5	4"	6	
11C	10	8	9	#10	6	#5	#5	6	4"	6	
12C	10	8	12	#9	5	#5	#5	5	4"	7	
13C	12	8	9	#11	5	#5	#5	5	4"	6	

COUPLING BEAM SCHEDULE 15

APPENDIX 2

COUPLING BEAM DESIGN CHARTS (BUILDINGS 1A, 1B, AND 1C)

MAGNUSSON KLEMENCIC ASSOCIATES

Building 1A

PEER TBI - Building 1A - Core Only Building for CSSC

PEER TBI - Building 1A - Core Only Building for CSSC

Building 1A

PEER TBI - Building 1A - Core Only Building for CSSC

PEER TBI - Building 1A - Core Only Building for CSSC

Building 1A

PEER TBI - Building 1A - Core Only Building for CSSC

PEER TBI - Building 1A - Core Only Building for CSSC

Building 1B

PEER TBI - Building 1B - Core Only Building for CSSC

PEER TBI - Building 1B - Core Only Building for CSSC

Building 1B

PEER TBI - Building 1B - Core Only Building for CSSC

PEER TBI - Building 1B - Core Only Building for CSSC

Building 1B

PEER TBI - Building 1B - Core Only Building for CSSC

PEER TBI - Building 1B - Core Only Building for CSSC

Building 1C

PEER TBI - Building 1C - Core Only Building for CSSC

PEER TBI - Building 1C - Core Only Building for CSSC

Building 1C

PEER TBI - Building 1C - Core Only Building for CSSC

PEER TBI - Building 1C - Core Only Building for CSSC

Building 1C

PEER TBI - Building 1C - Core Only Building for CSSC

PEER TBI - Building 1C - Core Only Building for CSSC

APPENDIX 3

DRIFT PLOTS - MCE LEVEL (BUILDINGS 1B AND 1C)

MAGNUSSON KLEMENCIC ASSOCIATES

Building 1B

PEER TBI - Building 1B - Core Only Building for CSSC

PEER TBI - Building 1B - Core Only Building for CSSC

Building 1C

PEER TBI - Building 1C - Core Only Building for CSSC

PEER TBI - Building 1C - Core Only Building for CSSC

APPENDIX 4
SHEAR AND OVERTURNING PLOTS - MCE LEVEL (BUILDINGS 1B AND 1C)

MAGNUSSON KLEMENCIC ASSOCIATES

Building 1B

PEER TBI - Building 1B - Core Only Building for CSSC

PEER TBI - Building 1B - Core Only Building for CSSC

Building 1C

PEER TBI - Building 1C - Core Only Building for CSSC

PEER TBI - Building 1C - Core Only Building for CSSC

Building 1B

PEER TBI - Building 1B - Core Only Building for CSSC

PEER TBI - Building 1B - Core Only Building for CSSC

Building 1C

PEER TBI - Building 1C - Core Only Building for CSSC

PEER TBI - Building 1C - Core Only Building for CSSC

APPENDIX 5
COUPLING BEAM ROTATIONS - MCE LEVEL (BUILDINGS 1B AND 1C)

MAGNUSSON KLEMENCIC ASSOCIATES

Building 1B

PEER TBI - Building 1B - Core Only Building for CSSC

PEER TBI - Building 1B - Core Only Building for CSSC

Building 1C

PEER TBI - Building 1C - Core Only Building for CSSC

PEER TBI - Building 1C - Core Only Building for CSSC

Building 1B

PEER TBI - Building 1B - Core Only Building for CSSC

PEER TBI - Building 1B - Core Only Building for CSSC

Building 1C

PEER TBI - Building 1C - Core Only Building for CSSC

PEER TBI - Building 1C - Core Only Building for CSSC

Building 1B

PEER TBI - Building 1B - Core Only Building for CSSC

PEER TBI - Building 1B - Core Only Building for CSSC

Building 1C

PEER TBI - Building 1C - Core Only Building for CSSC

PEER TBI - Building 1C - Core Only Building for CSSC

APPENDIX 6
COMPRESSION AND TENSION STRAINS - MCE LEVEL (BUILDINGS 1B AND 1C)

MAGNUSSON KLEMENCIC ASSOCIATES

Building 1B

PEER TBI - Building 1B - Core Only Building for CSSC

PEER TBI - Building 1B - Core Only Building for CSSC

Building 1C

PEER TBI - Building 1C - Core Only Building for CSSC

PEER TBI - Building 1C - Core Only Building for CSSC

Building 1B

PEER TBI - Building 1B - Core Only Building for CSSC

PEER TBI - Building 1B - Core Only Building for CSSC

Building 1C

PEER TBI - Building 1C - Core Only Building for CSSC

PEER TBI - Building 1C - Core Only Building for CSSC

Building 1B

PEER TBI - Building 1B - Core Only Building for CSSC

PEER TBI - Building 1B - Core Only Building for CSSC

Building 1C

PEER TBI - Building 1C - Core Only Building for CSSC

PEER TBI - Building 1C - Core Only Building for CSSC

Building 1B

PEER TBI - Building 1B - Core Only Building for CSSC

PEER TBI - Building 1B - Core Only Building for CSSC

Building 1C

PEER TBI - Building 1C - Core Only Building for CSSC

PEER TBI - Building 1C - Core Only Building for CSSC

APPENDIX 7

WALL PANEL SHEAR - MCE LEVEL (BUILDINGS 1B AND 1C)

MAGNUSSON KLEMENCIC ASSOCIATES

Building 1B

PEER TBI - Building 1B - Core Only Building for CSSC

PEER TBI - Building 1B - Core Only Building for CSSC

Building 1C

PEER TBI - Building 1C - Core Only Building for CSSC

PEER TBI - Building 1C - Core Only Building for CSSC

Building 1B

PEER TBI - Building 1B - Core Only Building for CSSC

PEER TBI - Building 1B - Core Only Building for CSSC

Building 1C

PEER TBI - Building 1C - Core Only Building for CSSC

PEER TBI - Building 1C - Core Only Building for CSSC

Building 1B

PEER TBI - Building 1B - Core Only Building for CSSC

PEER TBI - Building 1B - Core Only Building for CSSC

Building 1C

PEER TBI - Building 1C - Core Only Building for CSSC

PEER TBI - Building 1C - Core Only Building for CSSC

Building 1B

PEER TBI - Building 1B - Core Only Building for CSSC

PEER TBI - Building 1B - Core Only Building for CSSC

Building 1C

PEER TBI - Building 1C - Core Only Building for CSSC

PEER TBI - Building 1C - Core Only Building for CSSC

Building 1B

PEER TBI - Building 1B - Core Only Building for CSSC

PEER TBI - Building 1B - Core Only Building for CSSC

Building 1C

PEER TBI - Building 1C - Core Only Building for CSSC

PEER TBI - Building 1C - Core Only Building for CSSC

Building 1B

PEER TBI - Building 1B - Core Only Building for CSSC

PEER TBI - Building 1B - Core Only Building for CSSC

Building 1C

PEER TBI - Building 1C - Core Only Building for CSSC

PEER TBI - Building 1C - Core Only Building for CSSC

Building 1B

PEER TBI - Building 1B - Core Only Building for CSSC

PEER TBI - Building 1B - Core Only Building for CSSC

Building 1C

PEER TBI - Building 1C - Core Only Building for CSSC

PEER TBI - Building 1C - Core Only Building for CSSC

Building 1B

PEER TBI - Building 1B - Core Only Building for CSSC

PEER TBI - Building 1B - Core Only Building for CSSC

Building 1C

PEER TBI - Building 1C - Core Only Building for CSSC

PEER TBI - Building 1C - Core Only Building for CSSC

Building 1B

PEER TBI - Building 1B - Core Only Building for CSSC

PEER TBI - Building 1B - Core Only Building for CSSC

Building 1C

PEER TBI - Building 1C - Core Only Building for CSSC

PEER TBI - Building 1C - Core Only Building for CSSC

Building 1B

PEER TBI - Building 1B - Core Only Building for CSSC

PEER TBI - Building 1B - Core Only Building for CSSC

Building 1C

PEER TBI - Building 1C - Core Only Building for CSSC

PEER TBI - Building 1C - Core Only Building for CSSC

APPENDIX B: PEER/SSC Tall Buildings Design Case Study #2

PEER/SSC TALL BUILDING DESIGN CASE STUDY #2

Tony Ghodsi
Jose A. Flores Ruiz
Claire Massie
Yangbo Chen

Analysis and Design Summary

Building #2, Los Angeles, California

Table of Contents

1.0 Dual System Basis of Design 1

2.0 General Building Properties 4

2.1 Stiffness Assumptions 5

3.0 Building 2A - Analysis Summary 6

3.1 Building 2A - Seismic Design 6

3.2 Building 2A - Wind Design 15

4.0 Building 2B - Analysis Summary 16

4.1 Serviceability Analysis Seismic Force Determination 21

4.1.1 Service Level Design Acceptance Criteria 22

4.2 Collapse Prevention Step by Step Non-linear Analysis 25

4.2.1 Collapse Prevention Acceptance Criteria 26

4.2.2 Core Wall Modeling Properties 27

4.2.3 Coupling Beam Modeling Properties 33

4.2.4 Moment Frame Beam Properties 37

4.2.5 Moment Frame Column Properties 42

4.2.6 Slab Modeling at Ground Level and Below 44

4.2.7 Basement Wall Properties 46

4.2.8 Damping 47

4.3 Results from Non-linear Analyses 49

4.3.1 Overall Behavior 49

4.3.2 Core Shear Wall 52

4.3.3 Frame Behavior 61

4.3.4 Basement walls 64

References 65

1.0 Dual System Basis of Design

This report shows the results obtained from two design approaches of a building located in Los Angeles, California, laterally braced by a concrete shear wall elevator core and two four-bay concrete special moment resisting frames (SMRF) in each direction. The building consists of 42 stories and a penthouse above ground level and four subterranean levels. For the purpose of this report, this building is referred to as Building 2.

The design was first based on a modal response spectrum analysis as prescribed by International Building Code 2006 (ICC 2006). The building was then redesigned to satisfy the service level criteria, and then its components were checked to comply with the collapse prevention criteria under the Maximum Considered Seismic Event (MCE) as described in Los Angeles Tall Building Structural Design Council "An Alternative Design Approach for Tall Buildings" (LATBSDC 2008) with the exceptions mentioned under the *Building 2B Analysis Summary* section. The resulting structure with its components designed per IBC 2006 is referred to as Building 2A, and the structure with its components designed and revised to comply with the service and MCE level of forces is referred to as Building 2B.

In all cases the X direction of the building is parallel to letter-gridlines and the Y direction parallel to number-gridlines as shown in Figure 3.

Figure 1 - Three dimensional rendering of structure from ETABS (2008) model

Figure 2 - Typical plan view at ground floor and below

Figure 3 - Typical plan view at level 2 and above

2.0 General Building Properties

Figures 2 and 3 show the typical plan view of the ground floor and below and of the second level and above. Table 1 shows the general building properties.

Table 1 – General Building Properties

Story Height	10.5' At levels below Ground 13.67' From ground to 2nd 10.5' Typical from 2nd to 42nd 11.5' Roof 20' Pent-house
Number of Stories	42 above ground plus Pent-house 4 below ground
Slab Construction	10" thick reinforced concrete at Basement levels 12" thick reinforced concrete at Ground floor 8" thick post-tensioned concrete typical above Ground 10" thick reinforced concrete at Roof
Coupling Beam Depth	30" Typical
Basement Shear Walls	16" thick, f'c = 5ksi
Moment Frames	(2) 4-bay SMRF in each direction

In addition to the self-weight of the structure, the loads listed in Table 2 are used for the calculation of superimposed dead and live loads.

Table 2 – Load Criteria

Use	Location	Superimposed dead load (psf)	Live Load (psf)
Parking	4 stories below ground	3	50 (Reducible)
Retail	Ground Level inside area	110	100 (Non-Reducible)
Cladding	Perimeter of tower	15 psf per elevation	
Outside Plaza	Ground level outside area	350	100 (Non-Reducible)
Corridors and Exit Areas	Inside elevator core	28	100 (Non-Reducible)
Residential	2nd floor up to 42nd floor	28	40 (Reducible)
Mechanical	At roof floor only	100 kip	25 (Reducible)
Roof	Roof floor	28	20 (Reducible)

2.1 Stiffness Assumptions

The stiffness assumptions are listed in Table 3. When non-linear behavior of elements is modeled, stiffness modifiers are applied to the assumed "*elastic*" portion of the force-displacement relationship.

Table 3 - Stiffness Assumptions

Element	Building 2A	Building 2B	
	Code-Level Analysis	**Serviceability Design**	**MCE Level**
Modulus of Elasticity [A]	Specified concrete strength	Expected concrete strength[B]	Expected concrete strength
Core Walls	Flexural – 0.6 EI_g Shear – 1.0 GA_g	Flexural – 0.9 EI_g Shear – 1.0 GA_g	Flexural – *See note C* Shear – 1.0 GA_g
Basement Walls	Flexural – 0.8 EI_g Shear – 0.8 GA_g	Flexural – 1.0 EI_g Shear – 1.0 GA_g	Flexural – 0.8 EI_g Shear – 0.8 GA_g
Coupling Beams	Flexural – 0.2 EI_g Shear – 1.0 GA_g	Flexural – 0.5 EI_g Shear – 1.0 GA_g	Flexural – 0.2 EI_g Shear – 1.0 GA_g
Ground Level and Basement slabs	Flexural – 0.25 EI_g Shear – 0.5 GA_g	Flexural – 0.5 EI_g Shear – 0.8 GA_g	Flexural – 0.25 EI_g Shear – 0.25 GA_g
Moment Frame Beams	Flexural – 0.35 EI_g Shear – 1.0 GA_g	Flexural – 0.7 EI_g Shear – 1.0 GA_g	Flexural – 0.35 EI_g Shear – 1.0 GA_g
Moment Frame Columns	Flexural – 0.7 EI_g Shear – 1.0 GA_g	Flexural – 0.9 EI_g Shear – 1.0 GA_g	Flexural – 0.7 EI_g Shear – 1.0 GA_g

A. Modulus of elasticity is based on the following equations:

$E_c = 57000\sqrt{f_c'}$ for $f'_c \leq 6000$ psi

$E_c = 40000\sqrt{f_c'} + 1\times10^6$ for $f'_c > 6000$ psi (per ACI 363R-92[1])

B. Per Table 2 of LATBSDC (2008), the expected material strengths are 1.3 f'c for concrete and 1.17 fy for reinforcing steel.

C. Core walls are modeled using fiber sections. is used, if the concrete doesn't crack, EI is close to 1.0 times the gross concrete properties (It is slightly bigger because of the steel). As the strains on the fiber elements increase, the effective EI decreases.

3.0 Building 2A - Analysis Summary

The design of Building 2A was performed in general compliance with the IBC 2006, which adopts the *ASCE 7 (2006)* and ACI 318 (2008).

The specified core wall thickness and strength throughout the height are shown in Table 4. For SMRF properties and for core wall reinforcing see Figures 4 through 7. Table 5 shows the periods of Building 2A using the stiffness assumptions listed in Table 3.

Table 4 – Building 2A Specified Core Wall Thickness and Strength

Thickness	24" from foundation to 20th 18" Above 20th
Specified concrete strength (f'_c)	6000 psi from foundation to 20th 5000 psi Above 20th
Specified reinforcing strength (f_y)	60 ksi (A706)

Table 5 – Building 2A Code Design Periods

Vibration Mode	Period	Dominant direction	Mass participation
1	5.50 s	Translation mode on X direction	67 %
2	4.97 s	Translation mode on Y direction	68 %
3	2.98 s	Torsional mode	75 %

3.1 Building 2A - Seismic Design

A linear modal response spectrum analysis was used for the seismic design of Building 2A. The design forces were obtained from a provided 5% damped site-specific response spectra scaled in accordance with ASCE 7 (2006), Chapter 21.

Table 6 summarizes the factors used for this analysis. A comparison between the prescribed code spectra and the site-specific spectra is shown in Figure 8.

The model for Building 2A was created using the program ETABS (2008) including only the lateral force resisting elements which were modeled with the stiffness modified to match Table 3. When modeling the structure, concrete shear walls and SMRF are modeled from the foundation level to the penthouse and roof levels, respectively. Soil-structure interaction is ignored and the lateral stiffness of gravity elements is not included.

The design of structural components was based only on the modal analyses results. No special effort other than those prescribed by code was made to detail building 2A.

The representative plots for the design of building 2A are shown in Figures 9 through 13.

Table 6 - Linear Dynamic Site Specific Response Spectrum Analysis Parameters

S_s	1.725 g
S_1	0.602 g
F_a	1
F_v	1.3
S_{Ms}	1.718 g
S_{M1}	0.782 g
S_{DS}	1.145 g
S_{D1}	0.521 g
R	7.0
Site Class	C
C_d	5.5
C_s	0.051[A]
Seismic Weight (W)[B]	102000 kips
Modal combination method	Complete quadratic combination (CQC)
Redundancy factor (ρ)[C]	1.0
Accidental eccentricity	5%
Base shear "V" (See section 12.8)	5202 kips[C]
Modal Base shear "V_t" (See section 12.9.2)	V_{tx} = 11436 / R = 1634 kips V_{ty} = 11760 / R = 1680 kips
Modal base shear scaled to match 0.85 V	0.85 x 5202 = 4421 kips

Notes:

A. C_s values for both cases are governed by equation 12.8-5 of *ASCE 7-05 (2006)* as shown in its supplement 2.

B. Seismic weight accounts for the dead load of 2nd level and above.

C. The structure complies with 12.3.4.2-b, the redundancy factor equals 1.

D. Per section 12.9.4 of ASCE 7-05 (2006), *"Where the combined response for the modal base shear (V_t) is less than 85 percent of the calculated base shear (V) using the equivalent lateral force procedure, the forces, but not the drifts, shall be multiplied by 0.85 V/V_t"*. Hence, for strength design, the modal analyses are scaled to match ***0.85V = 4421 kips***.

E. Refer to *ASCE 7-05 (2006)* for the definition of each design parameter.

Figure 4 - Elevation and Properties of Frames A and F for Building 2A

Figure 5 - Elevation and properties of frames 2 and 5 for building 2A

Figure 6 – Elevation A and shear wall reinforcing for building 2A

Figure 7 – Elevation B and shear wall reinforcing for building 2A

Figure 8 – 5% damped code and site specific design response spectra

Figure 9 – Building 2A inter-story drifts from seismic forces on X and Y directions

Figure 10 – Building 2A modal analysis peak shear from seismic forces on X direction

Figure 11 - Building 2A modal analysis peak shear from seismic forces on Y direction

Figure 12 - Building 2A modal analysis peak moments when seismic forces act parallel to the X direction (E_x)

Figure 13 - Building 2A modal analysis peak moments when seismic forces act parallel to the Y direction (E_y)

3.2 Building 2A - Wind Design

Wind forces were calculated using section 6 of ASCE 7-05 (2006). Table 7 shows the parameters and resulting forces used for wind design.

Table 7 – Wind Design Parameters per ASCE 7-05 (2006)

Basic wind speed (V)	85 mph
Occupancy category	II
Surface roughness	B
Exposure type	B
Gust effect factor (G_f)	0.89
Enclosure classification	Enclosed
Topographic factor (K_z)	1
Percent of critical damping ration (β)	2.5 %
Wind shear at ground floor	1,345 kip
Wind overturning moment at ground floor	272,378 kip

Comparing the base shears and overturning moments from the wind and seismic design it can be concluded that the design is governed by the seismic forces.

4.0 Building 2B - Analysis Summary

Building 2B was designed and checked for the following two performance levels:

1. Serviceability level using an elastic ETABS (2008) model.
2. Collapse prevention level using a three-dimensional non-linear step by step time-history analysis with the program Perform 3D (2007)

For both models the stiffness is obtained from expected material properties and the modification factors given in Table 3.

The provisions for seismic design according to the LATBSDC (2008) recommendations are followed with the following exceptions.

- Service level check is for an earthquake event of 25 year return period with 2.5% viscous damping. Up to 20% of the elements with ductile action are allowed to reach 150% of their capacity under the serviceability check.
- The minimum base shear specified in the LATBSDC (2008) is waived.

Building 2B core wall properties are summarized in Table 8. Table 9 shows the periods obtained from both the serviceability and collapse prevention models using the stiffness assumptions from Table 3 and expected material properties.

Table 8 - Building 2B Specified Core Wall Thickness and Strength

Thickness	24" from foundation to 20th 18" Above 20th up to 30th 16" Above 30th
Specified concrete strength (f'c)	8000 psi from foundation to 20th 6000 psi from 20th to 30th 5000 psi Above 30th
Expected concrete strength[A] ($f'c_{exp}$)	10400 psi from foundation to 20th 7800 psi from 20th to 30th 6500 psi Above 30th
Specified reinforcing strength (f_y)	60 ksi (A706)
Expected reinforcing strength[B] (fy_{exp})	70 ksi

A. f'_c expected equals 1.3 times specified f'_c
B. f_y expected equals 1.17 times specified f_y

Figure 14 - Elevation and properties of frames A and F for building 2B

Figure 15 - Elevation and properties of frames 2 and 5 for building 2B

Figure 16 - Elevation A and shear wall reinforcing for building 2B

Figure 17 - Elevation B and shear wall reinforcing for building 2B

The periods obtained by the program Perform 3D (2007) from the model used for collapse prevention are obtained before the non-linear analyses are performed. The frame beams, columns and coupling beams reflect a reduced stiffness as described in the stiffness assumption table when calculating the period, however, the core shear walls are modeled using the uncracked properties of concrete. When the non-linear analyses are run, the stiffness of the core shear walls is adjusted according to its strain profile. The periods obtained by the program ETABS (2008) reflect the stiffness of elements modified per Table 3. Table 9 shows a summary of the periods obtained for building 2B.

Table 9 – Building 2B Period Summary from the Computer Models Used to Check Serviceability and Collapse Prevention Performance Levels

Vibration Mode	Period			Dominant direction
	At service level	At collapse prevention level		
	ETABS	Perform 3D	ETABS	
1	4.01 sec.	4.28 sec.	4.93 sec.	Translation mode on X direction
2	3.53 sec.	3.87 sec.	4.50 sec.	Translation mode on Y direction
3	2.12 sec.	2.26 sec.	2.78 sec.	Torsional mode

4.1 Serviceability Analysis Seismic Force Determination

The design forces are obtained using an elastic site-specific response spectrum analysis where the spectrum represents a mean recurrence interval of 25 years. This spectrum is shown in Figure 18. The stiffness assumptions used are those summarized in Table 3.

Figure 18 – 2.5% Damped service level site specific response spectra

Accidental eccentricity is not considered for serviceability checks per Section 3.3.5 of the LATBSDC (2008) document.

4.1.1 Service Level Design Acceptance Criteria

Building 2B is checked for the load combinations using dead load, live load and wind load as described in IBC 2006 calculating the strength of each element as described in the same document.

For the seismic design, the load combination used is described by equation 1.

$$D_L + 0.25L_L \pm E_{service} \qquad \text{Eq. - 1}$$

D_L and L_L are the dead and live loads, respectively, and $E_{service}$ refers to the earthquake demand at service level. The live load is not reduced. $0.25L_L$ is also referred to as the expected live load.

Orthogonal load combinations for earthquake loads are applied as required per Section 12.5 of ASCE 7-05 (2006).

Per Section 3.3.6 of the LATBSDC (2008) document, the overall inter-story drift of the structure should not exceed 0.005 h_n.

When checking against the load combination shown in Equation 1, 20% of the elements with ductile actions are allowed to have a demand to capacity ratio between 1.0 and 1.5. The remainder of elements should have a demand to capacity ratio of 1.0 or less. All elements with brittle actions should have a demand capacity ratio of 1.0 or less. For both ductile and brittle actions, strengths should be calculated using a strength reduction factor in accordance with current material codes. For brittle actions, strength is calculated using specified material properties. For ductile actions expected material properties are used. Figures 19 through 23 show the representative plots for service level design.

Table 10 – Design Acceptance Criteria for Service Level Design Earthquake

Element	Action type	Classification
Reinforced Concrete Frame Beam	Flexure Shear[B]	Ductile Brittle
Reinforced Concrete Frame Column	Axial-Flexure interaction [C] Shear[B]	Ductile Brittle
Reinforced Concrete Shear walls	Flexure[C] Shear[B]	Ductile Brittle
Reinforced concrete coupling beams	Shear[D]	Ductile

Notes:

A. Care needs to be exercised when detailing elements for ductility. Refer to Paulay and Priestley (1992) or Englekirk (2003) for a detailed discussion on detailing reinforced concrete elements for ductility.
B. Shear design for shear walls, frame beams and columns should be done using capacity design procedures as described by Paulay and Priestley (1992).
C. To ensure that a column or a shear wall is ductile in flexure, the maximum axial compression should be limited as described in the acceptability criteria for collapse prevention.
D. It is important to note that when detailed per ACI 318 (2008), coupling beams behave in a ductile manner as shown by Naish et al (2009).

Figure 19 - Building 2B peak inter-story drifts at service level from seismic forces on X and Y directions

Figure 20 - Building 2B modal analysis peak shear at service level from seismic forces on X direction

Figure 21 - Building 2B modal analysis peak shear at service level from seismic forces on Y direction

Figure 22 - Building 2B modal analysis peak moments at service level when seismic forces are parallel to the X direction (E_x)

Figure 23 - Building 2B modal analysis peak moments at service level when seismic forces are parallel to the Y direction (E_y)

4.2 Collapse Prevention Step by Step Non-linear Analysis

Seven pairs of spectrally matched ground motions were used to represent the MCE with a mean recurrence interval of 2475 years (2% probability of exceedance in 50 years).

A model was built in Perform 3D (2007) to represent the lateral system of the building. The seismic mass equivalent to the dead load and its associated rotational moment of inertia is assigned at levels above the ground floor. The mass associated to the ground level and below is ignored.

The core walls and moment frames extend down to the foundation level. The diaphragms at the ground floor and below are modeled with a finite element mesh to account for their in-plane stiffness modified per Table 3. The diaphragms above ground level are modeled as rigid diaphragms by slaving the horizontal translation degrees of freedom. Ground motions are input at the top of the mat foundation. The foundation is idealized as rigid by providing lateral and vertical supports at the top of the foundation. The lateral resistance of the soil surrounding the subterranean walls is neglected.

Per LATBSDC (2008), if during the serviceability evaluation the factor A_x as described in ASCE 7-05 (2006) is greater than 1.5, accidental eccentricity should be considered during collapse prevention analysis. Because the building being studied is regular in plan and elevation, the factor A_x is always less than 1.5.

P-Delta effects are considered in the model by the inclusion of a "*P-Delta Column*" at the center of mass of the building with an axial load equivalent to the dead load plus the expected live load. This column is pinned at both ends on each level with its nodes slaved to the diaphragm defined at each floor.

Figure 24 – Target acceleration response spectra at MCE level.

4.2.1 Collapse Prevention Acceptance Criteria

To prevent collapse at the MCE level of forces, the acceptance criteria shown in Table 11 should be met.

For actions classified as ductile, the strength should be calculated using expected material properties and a strength reduction factor of 1.

For actions classified as brittle, the strength should be calculated using specified material properties and a strength reduction factor of 1. This capacity should exceed the smaller of the average demand from the seven time-history records times 1.5 or the maximum force that the structural system can deliver.

In order to achieve ductile behavior a plastic mechanism as described in the SEAOC Blue Book (2008) should be observed in the frames. Care needs to be exercised when detailing elements for ductility. Paulay and Priestley (1992) and Englekirk (2003) give an in-depth discussion on how to detail reinforced concrete elements to achieve ductile behavior. ACI 318 (2008) provides guidelines to detail coupling beams to sustain the allowed displacement demands as shown by Wallace (2007).

Table 11 – Collapse Prevention Non-Linear Model Acceptance Criteria

Element	Action type	Classification	Expected behavior	Acceptance limit for non-linear behavior
Reinforced Concrete Frame Beam	Plastic hinge rotation Beam Shear	Ductile Brittle	Non-linear Linear	Hinge rotation ≤ 0.045 rad N.A.
Reinforced Concrete Frame Column	Axial-Flexure interaction Shear	Ductile Brittle	Non-linear Linear	Axial compression ≤ 0.40 $f'c_{exp}$ Ag Hinge rotation ≤ 0.025 rad N.A.
Reinforced Concrete Shear walls	Axial-Flexure interaction Shear	Ductile Brittle	Non-linear Linear	Concrete compression strain ≤ 0.015 Reinforcing rebar tension strain ≤ 0.05 Axial compression force ≤ 0.35f'cAg N.A.
Reinforced concrete coupling beams	Shear	Ductile	Non-linear	0.06 rad chord rotation

N.A. Not applicable

4.2.2 Core Wall Modeling Properties

The core walls are modeled using non-linear vertical fiber elements representing the expected behavior of the concrete and reinforcing steel. The shear behavior is modeled as elastic.

The concrete stress-strain relationship is based on the modified Mander model for confined concrete (Mander et al., 1988) with a confining ratio as required per ACI 318 (2008), Section 21.4.4. The tension strength of concrete is neglected.

For the fiber elements, all concrete is defined as confined. The wall thickness used to calculate the flexural and shear stiffness of the wall section corresponds to the confined thickness in anticipation of spalling. If in the MCE time history non-linear analysis the average concrete compression strain exceeds 0.002, confinement is provided.

In order to match the curve defined by the modified Mander model (Mander et al., 1998), the initial elastic stiffness used to model the concrete material for the fiber sections differs from that calculated by the equations given in ACI 318 (2008) and ACI 363 (1992). Figure 25 shows the curve defined by the modified Mander model (Mander et al., 1998) and the values that were used to model the stress-strain curve of concrete with specified strength (f'_c) of 8 ksi in Perform 3D (2007).

Table **12** shows a comparison of the elastic modulus calculated per ACI 318 (2008) and ACI 363 (1992) using specified material properties, the same elastic modulus using expected material properties and the elastic modulus used in the non-linear model adjusted to match the modified Mander model (Mander et al., 1998). Figures 26 and 27 show the Perform 3D (2007) screen shots used to define the concrete material for shear walls with a specified strength of 8 ksi.

Figure 25 – Expected stress – strain curve for confined concrete with specified concrete strength (f'_c) of 8 ksi

The steel stress-strain relationship is based on the material specifications for A706 reinforcing steel. The steel material is modeled with a tri-linear stress-strain relationship with expected yield strength ($fy_{expected}$) of 70 ksi and an ultimate strength of 105 ksi in both compression and tension.

The post-yield stiffness and cyclic degradation of reinforcing steel has been adjusted by modeling in Perform 3D (2007) the rectangular wall described by Orakcal et al. (2006) and adjusting it to match the lateral load vs. top displacement curve. The parameters used to define the reinforcing steel are shown in Figures 28 and 29.

Table 12 – Concrete Elastic Modulus Comparison

f'_c	E_c Per ACI 318 (2008) and ACI 363 (1992)	$E_{c\ expected}$ (1.14 x E_c)	Initial elastic stiffness for non-linear model
(ksi)	(ksi)	(ksi)	(ksi)
5	4031	4595	3229
6	4098	4671	3597
8	4578	5219	4340
10	5000	5700	4941

$E_c = 57000\sqrt{f'c}$; for $f'c < 6$ ksi per ACI 318 (2008)

$E_c = 40000\sqrt{f'c} + 1x10^6$; for $f'c \geq 6$ ksi per ACI 363 (1992)

Figure 26 – Inelastic concrete material screen shot from Perform 3D (2007)

Figure 27 - Inelastic concrete material screen shot from Perform 3D (2007)

Figure 28 – Inelastic reinforcing rebar material screen shot from Perform 3D (2007)

Figure 29 – Inelastic reinforcing rebar material screen shot from Perform 3D (2007)

Figure 30 – Shear wall elastic shear material screen shot from Perform 3D (2007)

Figure 31 shows the cross section used to define a 24 in. wall with minimum reinforcing. As mentioned previously, the thickness is taken as 22 in. to account for concrete spalling. The reinforcing ratio is calculated per Equation 2. Figure 32 shows the compound element that defines a 24 in. shear wall with a reinforcing ratio of 0.0025 and specified concrete strength (f'_c) of 8 ksi.

$$\rho = 0.0025 \times 24'' / 22'' = 0.00272 \qquad \text{Eq-2}$$

Figure 31 – Fiber wall cross-section screen shot from Perform 3D (2007)

Figure 32 – Shear wall compound component screen shot from Perform 3D (2007)

4.2.3 Coupling Beam Modeling Properties

The coupling beams are defined as elastic beam elements with a nonlinear displacement shear hinge at the mid-span of the beam. These are connected to the shear walls using embedded elements as suggested by Powell (2007). The shear hinge behavior is based on test results by Naish et al. (2009).

To obtain the nominal expected shear capacity, the angle of the diagonals (α) is calculated using a distance from the center of gravity of the diagonal reinforcing to the face of the beam of 5 in. when the diagonal reinforcing consists of two layers of rebar and 7 in. when it consists of 3 layers of rebar. Figure 33 shows a sketch of the coupling beam diagonal reinforcing.

Figure 33 – Coupling beam diagonal reinforcing sketch

To define the behavior of the displacement shear hinge, the displacement is related to the rotation of the coupling beam as described in Equation 3.

$$\delta_\theta = \theta \times L_b \qquad \text{Eq. – 3}$$

Where θ is the rotation in radians, L_b is the length of the coupling beam and δ_θ is the equivalent displacement at a rotation θ. The following figures show the back bone parameters used to define the shear displacement hinges for coupling beams and screen shots from Perform 3D (2007) for a typical coupling beam.

Figure 34 – Shear displacement hinge backbone curve

Figure 35 – Coupling beam elastic segment screen shot from Perform 3D (2007)

Figure 36 – Coupling beam displacement shear hinge screenshot from Perform 3D (2007)

Figure 37 – Coupling beam displacement shear hinge screen shot from Perform 3D (2007)

Figure 38 – Coupling beam compound component screen shot from Perform 3D (2007)

4.2.4 Moment Frame Beam Properties

The moment frame beams are defined as elastic beam elements with nonlinear rotation hinges and rigid end zones at each end. The rigid end zones extend from the column centerline to the face of the column, with a stiffness of 10 times the elastic stiffness of the beam.

Tests performed by Popov et al. (1972) are used to define the post-yield stiffness of the rotation hinges in beams. Figure 40 shows the setup that was used to perform these tests as described by Englekirk (2003). Figure 41 shows the force displacement relationship for this beam.

Using a plastic hinge length of half the beam depth, the ultimate beam plastic rotation is 0.046 radians. Strength degradation is not accounted for given that the acceptable rotation for the plastic hinge is lower than that associated with this effect.

To define the post-yield stiffness, a ratio of 1.18 is observed between the strength at ultimate and at yield. Using these values, Figure 39 shows the backbone curve used to define the behavior of beam rotation plastic hinges in Perform 3D (2007).

Figure 39 – Back bone curve for beam rotation hinge

Figure 40 – Beam test subassembly as performed by Popov et al. (1972)

Figure taken from *The Seismic Design of Reinforced and Precast Concrete Buildings* by Englekirk (2003)

Figure 41 – Force–deflection curve from test performed by Popov et al. (1972)

Figure 42 – Frame beam cross section screen shot from Perform 3D (2007)

Figure 43 - Frame beam cross section screen shot from Perform 3D (2007)

Figure 44 - Frame beam rotation moment hinge screen shot from Perform 3D (2007)

Figure 45 - Frame beam rotation moment hinge screen shot from Perform 3D (2007)

Figure 46 - Frame beam rotation moment hinge screen shot from Perform 3D (2007)

Figure 47 - Frame beam compound component screen shot from Perform 3D (2007)

4.2.5 Moment Frame Column Properties

Plastic hinges are modeled at the top and bottom ends of every column. Columns at the upper levels are expected to remain elastic but incursions into non-linear behavior are acceptable if the integrity of the structure is not compromised.

To define a column plastic hinge, a moment-axial capacity interaction curve is calculated using the column's expected material properties. The back bone curve is elastic-perfectly plastic, meaning the column strength doesn't change once it reaches the "yield" point.

The following figures show an example used in Perform 3D (2007) to define a column at the seismic base with plastic hinges at the face of the beam.

Figure 48 – Frame column compound component screen shot from Perform 3D (2007)

Figure 49 – Frame column plastic hinge screen shot from Perform 3D (2007)

Figure 50 – Frame column plastic hinge screen shot from Perform 3D (2007)

4.2.6 Slab Modeling at Ground Level and Below

The slabs at ground level and below are modeled as a shell element with its stiffness modified per Table 3.

The stiffness factors are applied to the elastic modulus when defining the material. The shear modulus is calculated by Perform 3D (2007) using Poisson's ratio. The following figures show the screen shots used to define a slab in Perform 3D (2007).

Figure 51 – Slab elastic material screen shot from Perform 3D (2007)

Figure 52 – Slab elastic cross section screen shot from Perform 3D (2007)

Figure 53 – Slab compound component screen shot from Perform 3D (2007)

4.2.7 Basement Wall Properties

Basement walls are modeled as elastic finite elements with its stiffness modified per Table 3. The following figures show the screen shots used to define a basement wall in Perform 3D (2007).

Figure 54 – Basement wall cross section screen shot from Perform 3D (2007)

Figure 55 – Basement wall compound component screen shot from Perform 3D (2007)

4.2.8 Damping

Rayleigh damping is used to run the time-history non-linear analyses. To define the damping curve, the damping is set at 2.5% of critical damping at a period of $0.2T_1$.and at a period of 0.9 T_1, T_1 being the fundamental period of the structure. The α and β values are automatically calculated by Perform 3D (2007).

Figure 56 – Rayleigh damping as defined in Perform 3D

Figure 57 – Damping definition screen shot from Perform 3D

4.3 Results from Non-linear Analyses

The following figures represent the behavior of building 2B under the MCE records and its averages.

4.3.1 Overall Behavior

Table 13 – Summary of Building 2B Behavior under MCE

Shear at grade level	V_x = 10,732 kips	V_y = 10,000 kips
Core average peak shear at grade level	V_x = 8,240 kips	V_y = 7,150 kips
Core average peak overturning moment at grade level	M_y = 952,328 kip-ft	M_x = 739,130 kip-ft
Average maximum story drift from non-linear analyses	δ_x = 1.5 %	δ_y = 1.0 %

Figure 58 – Peak inter-story drifts on X direction

Figure 59 – Peak inter-story drifts on Y direction

Figure 60 – Peak displacements at center of mass on X direction

Figure 61 – Peak displacements at center of mass on Y direction

Figure 62 – Peak story shear on X direction

Figure 63 – Peak story shear on Y direction

4.3.2 Core Shear Wall

Figure 64 – Building 2B core peak shear on X direction

Figure 65 – Building 2B core peak shear on Y direction

Figure 66 – Building 2B average core peak shear values on X direction

Figure 67 – Building 2B average core peak shear values on Y direction

Figure 68 – Building 2B core peak overturning moment over X

Figure 69 – Building 2B core peak overturning moment over Y

Figure 70 – Building 2B Maximum compression strains at core corner by Pier 1

Figure 71 – Building 2B Maximum tension strains at core corner by Pier 1

Figure 72 – Building 2B Maximum compression strains at core corner by Pier 2

Figure 73 – Building 2B Maximum tension strains at core corner by Pier 2

Figure 74 – Building 2B Pier 1 peak shear on X direction

Figure 75 – Building 2B Pier 1 average peak shear on X direction

Figure 76 – Building 2B Pier 1 average peak shear on Y direction

Figure 77 – Building 2B Pier 1 average peak shear on Y direction

Figure 78 – Building 2B elevation "*A*" coupling beam peak rotations

Figure 79 – Building 2B elevation "*B*" coupling beam peak rotations

4.3.3 Frame Behavior

Figure 80 – Peak frame shear on X direction

Figure 81 – Peak frame shear on Y direction

Figure 82 – Corner column peak compression

Figure 83 – Maximum shear on X direction at corner column on gridlines A-2

Figure 84 – Mean shear on X direction at corner column on gridlines A-2

Figure 85 – Frame "A" beam rotation at face of column on gridlines A-2

4.3.4 Basement walls

Figure 86 – Peak shear of basement wall on gridline Y1

References

1. ACI Committee 363 (1992). "State-of-the-Art Report on High-Strength Concrete (ACI 363-92)," *ACI Manual of Concrete Practice*, American Concrete Institute, Detroit, 2005.

2. ACI (2008). *ACI 318-08: Building Code Requirements for Structural Concrete with Commentary*, 2008 edition. American Concrete Institute, Farmington Hills, MI.

3. Adebar, P., Mutrie, J., and DeVall, R., (2004). Displacement-Based Design of Concrete Wall Buildings: The 2004 Canadian Code Provisions, *13th World Conference on Earthquake Engineering*, Vancouver, B.C.

4. ASCE (American Society of Civil Engineers) (2006). ASCE 7-05, *Minimum Design Loads for Buildings and Other Structures, Including Supplement No. 1.* American Society of Civil Engineers, Reston, VA.

5. E. P, Popov, V. V. Bertero and H. Krawinkler (1972). C*yclic Behavior of Three R.C. Flexural Members with High Shear,* Report No. EERC 72-5, Earthquake Engineering Research Center, University of California, Berkeley, CA.

6. Englekirk Robert.E. (2003). *Seismic Design of Reinforced and Precast Concrete Buildings.* John Wiley & Sons, New York, NY.

7. Englekirk, Robert E. and Llovet, Dani (2000). *Cyclic Tests of Cast-in-Place High Strength Beam-Column Joints*, Carpenters/Contractors Cooperation Committee, Inc., *High Strength Concrete Research*, Los Angeles, CA.

8. ETABS Nonlinear Version 9.2.0 (2008). *Extended 3D Analysis of Building Structures*, Computers and Structures, Inc. Berkeley, CA.

9. ICC (International Code Council) (2006). *2006 International Building Code,* International Code Council, Falls Church, VA.

10. Los Angeles Tall Building Design Council (2008). *An Alternative Procedure for Seismic Analysis and Design of Tall Buildings Located in the Los Angeles Region,* Los Angeles, CA.

11. Mander, J.B., Priestley, M.J.N. and Park, R. (1988). "Theoretical Stress-Strain Model for Confined Concrete." *ASCE Journal of Structural Engineering*, 114 (8), 1804-1826.

12. Naish, David, Fry, Andy, Klemencic, Ron and Wallace, John. (2009). *Testing and Modeling of diagonally Reinforced Concrete Coupling Beams.* Paper submitted to ACI structural journal, Los Angeles, CA.

13. Orakcal, Kutay and Wallace, John W., (2006). *Flexural Modeling of Reinforced Concrete Walls – Experimental Verification,* ACI Structural Journal, V. 103, No. 2

14. Orakcal, Kutay, Wallace, John W. and Conte, Joel P., (2004). *Flexural Modeling of Reinforced Concrete Walls – Model Attributes,* ACI Structural Journal, V 101, No. 5

15. Paulay, T., and M.J.N. Priestley (1992). *Seismic Design of Reinforced Concrete and Masonry Buildings*. John Wiley & Sons, New York, NY.

16. Perform 3D Version 4.0.3 (2007). *Nonlinear Analysis and Performance Assessment of 3D Structures*, Computers and Structures, Inc. Berkeley, CA.

17. Powell, Graham H., (2007).*Detailed Example of a Tall Shear Wall Building Using CSI's Perform 3D Nonlinear Dynamic Analysis,* Computers and Structures Inc., Berkeley, CA.

18. SEAOC Seismology Committee (2008). "Reinforced concrete structures," September, 2008, *The SEAOC Blue Book: Seismic Design Recommendations*, Structural Engineers Association of California, Sacramento, CA. Accessible via the world wide web at: http://www.seaoc.org/bluebook/index.html

19. Wallace, John W., (2007). *Modeling Issues for Tall Reinforced Concrete Core Wall Buildings*, Published online by Wiley Interscience at: http://www.interscience.wiley.com

APPENDIX C: Detailed Design Write-up for BRBF Building

DETAILED DESIGN WRITE-UP FOR BRBF BUILDING

Table of Contents

1. Introduction 1-1

1.1 Purpose 1-1

1.2 Objective 1-1

1.3 Scope 1-2

1.4 Description of Project 1-2

1.5 Information Provided by Others 1-2

2. Code-based Design 2-1

2.1 Purpose 2-1

2.2 Design Description 2-1

2.2.1 Gravity Analysis & Design 2-1

2.2.2 Lateral Analysis 2-2

2.2.3 Lateral Force Resisting Member Design 2-9

2.2.4 Story Drifts for Code Design 2-12

3. PERFORMANCE BASED DESIGN 3-1

3.1 Service Level Earthquake Evaluation 3-1

3.2 Maximum Considered Earthquake Evaluation 3-3

3.2.1 Modeling of Critical Elements 3-4

3.2.2 Selected Results from Non Linear Analysis 3-9

4. Enhanced PERFORMANCE BASED DESIGN 4-1

4.1 Service Level Earthquake Evaluation 4-1

4.1 Maximum Considered Earthquake Evaluation 4-4

LIST OF FIGURES

Figure 1: Response Spectrum for Code Analysis 2-4

Figure 2: Plan at Eleventh through Fortieth Floors 2-6

Figure 3: Elevation of Frame Along Line 2 Following Removal of a Brace..... 2-7

Figure 4: Elevation of Frame Along Line D Following Removal of a Brace 2-8

Figure 5: Defining Box Column Section Properties in ETABS 2-11

Figure 6: Response Spectrum for Serviceability Analysis..... 3-2

Figure 7: Presumed Backbone Curve for Buckling Restrained Braces 3-4

Figure 8: BRBF Property Definition in Perform..... 3-5

Figure 9: BRBF Compound Element in Perform..... 3-6

Figure 10: Column Section Definition in Perform..... 3-7

Figure 11: Column Strength Definition in Perform 3-8

Figure 12: Peak Interstory Drifts in the Y Direction..... 3-9

Figure 13: Peak Interstory Drifts in the X Direction..... 3-10

Figure 14: BRBF Core Strain DCRs along Lines 2, 3 and 4 3-11

Figure 15: BRBF Core Strain DCR Along Line D..... 3-12

Figure 16: Seismic Frame Column Axial Flexure Interaction Ratio along Line E 3-13

Figure 17: Accumulated Peak Story Shear in Steel Superstructure in Y Direction..... 3-14

Figure 18: Accumulated Peak Story Shear in Steel Superstructure in X Direction..... 3-15

Figure 19: Response Spectrum for Enhanced PBE..... 4-1

Figure 20: 3D Computer Model used for the Enhanced Performance Based Evaluation 4-2

Figure 21: Peak Interstory Drifts in the Y Direction..... 4-5

Figure 22: Peak Interstory Drifts in the X Direction..... 4-6

1. INTRODUCTION

1.1 Purpose

This report presents the design basis for two alternative designs of a 39-story steel framed office building located at a generic site in Los Angeles, California. One of these designs, termed the code-based design conforms in all respects, except one, with the design criteria contained in the following codes and standards:

- 2007 California Building Code
- ASCE 7.05 Standard for Minimum Design Loads for Buildings and Other Structures
- AISC 360.05 Specification for Steel Buildings
- AISC 341.05 Seismic Specification
- ACUI 318-08 Building Code Requirements for Reinforced Concrete

The one exception to the requirements of these codes and standards is that the design does not have a backup special moment-resisting frame as required by ASCE 7.05 for structures with a height in excess of 160 ft.

The second design has been conducted using a performance-based approach generally based on the criteria contained in a document published by the Los Angeles Tall Buildings Council.

1.2 Objective

Simpson Gumpertz & Heger, Inc. developed the two designs presented in this report on behalf of the Pacific Earthquake Engineering Research Center (PEER) under its Tall Buildings Initiative (TBI). The objective of the TBI is to develop recommended performance-based design criteria for tall buildings as an alternative to the criteria contained in present building codes and standards. These alternative performance-based criteria are intended to provide performance that is at least equivalent to that intended for buildings designed in conformance with the code. The buildings presented in this report, together with designs using other structural systems developed by other designers, will be used by PEER to assess the cost and performance capability of buildings designed using alternative design approaches and criteria. This information will guide the development of the PEER recommendations.

1.3 Scope

Our scope of work included the following:

1. Meet with representatives of PEER and other design consultants engaged in the TBI project to develop the general criteria for the designs.

2. Develop a design, to a schematic level, for an essentially code-conforming steel-framed building

3. Develop a design, to a schematic level, for a performance-based steel framed building, of similar height and footprint, using the procedures contained in design recommendations prepared by the Los Angeles Tall Buildings Council.

4. Prepare schematic level drawings documenting the design

5. Prepare this design report

1.4 Description of Project

Both designs have typical above-grade floors comprised of lightweight concrete fill on metal deck supported by composite steel framing with a foot print of 170 ft by 107 ft. Both designs have four basement levels with a foot print of 227 ft by 220 ft. Both structures have lateral force resisting systems comprised of buckling-restrained braced frames.

1.5 Information Provided by Others

The Pacific Earthquake Engineering Research Center provided geotechnical/seismicity data for the hypothetical site including:

- Code spectral response acceleration coefficients – S_s and S_1
- Site Class
- Ground motion records for use in analysis
- General loading criteria

2. CODE-BASED DESIGN

2.1 Purpose

This section provides a brief overview of the code based design. As discussed in the Design Criteria, we used the International Building Code 2006 to perform this design.

2.2 Design Description

This design was conducted in conformance with all the prescriptive provisions of the International Building Code 2006, and its referenced standards, except for the limitation on the building height. The International Building Code would require that buildings in excess of 160 ft and located on the site selected for this building be provided with a special moment-resisting frame capable of resisting at least 25% of the specified design seismic forces. This design did not incorporate such a frame. Salient features of this design are provided in the following sections.

2.2.1 Gravity Analysis & Design

We designed the building's vertical-load resisting system using gravity loads that consist of a combination of self weight of the elements and additional superimposed loads. Based on the design criteria document provided to us by PEER, we considered the following superimposed loads at various floors in addition to the self weight.

Table 1 – Gravity Loading Criteria

Description/Location	Superimposed Dead	Live Load	Reducability
Roof	28 psf	25 psf	Yes
Mechanical, Electrical at Roof	Total of 100 kips	-	-
Residential including Balconies	28 psf	40 psf	Yes
Corridors, Lobbies and Stairs	28 psf	100 psf	No
Retail	110 psf	100 psf	No
Parking Garage, Ramp	3 psf	40 psf[1]	Yes
Construction Loading	3 psf	30 psf	No
Cladding	15 psf	-	-

1. PEER document showed 50 psf. SGH considered 40 psf in keeping with ASCE 7-05.

We combined the element self weights with the superimposed loading from the above table and performed a gravity-load design using the RAM Structural System software, version 12.1. We have included a complete flat load table in Appendix A (Pages A1 through A4) for reference. In those tables the highlighted cells add up to the superimposed loads shown in Table 1.

2.2.2 Lateral Analysis

Following design of the vertical-load carrying elements, we performed a lateral analysis of the building. We considered both wind and seismic forces and designed each element for the most severe requirements. A brief description of the wind and seismic design is given below.

2.2.2.1 Wind Analysis

We used ASCE 7-05, Method 2 for calculating the wind pressures. Table 2 lists the various parameters used for calculating the wind pressure.

Table 2 – Wind Design Criteria

Parameter	Value
Basic Wind Speed, 3 sec. gust (V)	85 mph
Basic Wind Speed, 3 sec gust (V), for serviceability wind demands based on a 10 year mean recurrence interval	67 mph
Exposure	B
Occupancy Category	II
Importance Factor (I_w)	1.0
Topographic Factor (K_{zt})	1.0
Exposure Classification	Enclosed
Internal Pressure Coefficient (GC_{pi})	± 0.18
Mean Roof Height (h)	544'-6"
Wind Base Shear along Two Orthogonal Directions	1436 kips and 2629 kips

We considered the four cases depicted in Figure 6-9 of ASCE 7-05. Each of these cases includes the direct wind force in each orthogonal direction either alone or in combination with story torsional moment caused by the eccentric application of this load.

We calculated the gust effect factor (G_f) following Section 6.5.8.2 of ASCE 7-05 for flexible or dynamically sensitive structures for 1% damping.

We have included the details of the wind analysis in Appendix A pages A5 through A10. Page A5 shows the calculation of the gust effect factor for the short normal (East West) direction of the building. Page A6 shows the calculation of the wind pressure for the same direction over the height of the building. Page A7 shows the story forces and story moments. Pages A8 through A10 show the identical quantities in the long normal (North South) direction of the building.

2.2.2.2 Seismic Analysis

We used linear response spectrum analysis to calculate seismic forces and displacements. Per ASCE 7-05, Cl 12.9.4, we scaled the forces to 85% of the base shear obtained from the equivalent lateral force procedure of Cl 12.8. Table 3 lists the various parameters that we used for the seismic design.

Table 3 – Seismic Design Parameters

Parameter	Value
Building Latitude/Longitude	Undefined
Occupancy Category	II
Importance Factor (I_e)	1.0
Spectral Response Coefficients	S_{DS} = 1.145; S_{D1} = 0.52
Seismic Design Category	D
Lateral System	Buckling restrained braced frames, non moment resisting beam column connections
Response Modification Factor (R)	7
Deflection Amplification Factor (C_d)	5.5
System Overstrength Factor (Ω_0)	2.0
Building Period (T) using Cl. 12.8.2	3.16 sec[1]
Seismic Response Coefficient C_s (Eq. 12.8-1)	0.051 W (Governed by $C_{s\text{-}min}$ from Eq. 12.8-5)
Scaled Spectral Base Shear	3504 kips (85% of Static Base Shear)
Analysis Procedure	Modal Response Spectral Analysis

1. Actual period from dynamic model: T_Y = 5.05 sec; T_X = 3.62 sec

We performed the lateral analysis using the program ETABS, version 9.5.0. Page A11 of the appendix A shows the modal information for the first 50 modes of the code model.

We used the 5% damped, acceleration response spectrum shown in Figure 1. We included sufficient modes to obtain participation of at least 90% of the structure's mass. We scaled the results of the response spectrum analysis such that the base shear immediately above the ground floor matched 85% of the static base shear from the equivalent static force analysis. Page A12 of the appendix shows the distribution of the static lateral force F_x and the diaphragm design force F_{px}. The last columns of the same sheet shows the mass and mass moment of inertia used in the model at various floors. Note that for levels below the ground floor, the mass of the perimeter walls are automatically calculated by the program.

Figure 1: Response Spectrum for Code Analysis

IBC 2006 also requires the designer to calculate the redundancy factor (ρ) for seismic design. We calculated the redundancy factor per 12.3.4.2 of ASCE 7-05. According to that section, a building will qualify for a ρ =1 provided that the removal of an individual brace or connection will not result in more than a 33% reduction in story strength, nor will the resulting system have an extreme torsional irregularity. Extreme torsional irregularity is defined to exist when the maximum story drift computed including accidental torsion, at one end of the structure

transverse to an axis is more than 1.4 times the average story drifts at the two ends of the structure.

In order to calculate the redundancy factor when the seismic forces are acting in the North South direction, we removed a brace from line 2 along the full height of the building. We then subjected the building to the static lateral forces along with the 5% accidental torsion. We term these forces as EQYPL (with the accidental eccentricity towards the positive right) and EQYMN (with the accidental eccentricity towards the negative left). Since the building has at least 6 bays of braced frame in each principal direction, loss of a brace or connection will never reduce the capacity by 33%. We found that that for the North South direction, the largest ratio of maximum story drift over the average drift over the height of the building was 1.39 at Story 13 (see page A12). Since this is less than 1.4, we concluded that the redundancy factor in the North South direction is 1. Figure 2 shows the plan view of the tower and Figure 3 shows the elevation at Line 2 after the removal of the brace.

We also performed a similar analysis in the X (East West direction). In this model we removed a single brace from Line D and subjected the building to static forces EQXPL ((with the accidental eccentricity towards the positive top) and EQXMN (with the accidental eccentricity towards the negative bottom). Figure 4 shows the elevation of the frame along Line D with the brace removed. We then calculated the ratio of maximum to average drifts and obtained ratios ranging from 1.468 to 1.408 from roof to Story 36. However, section 12.3.4.2 stipulates that this ratio should strictly be studied for floors resisting more 33% of the base shear which is numerically equal to 1156 kips. This only happens below Story 35 (see page A13). We found that the ratio of maximum to average drift is only marginally greater than 1.4 at two stories with a maximum value of 1.408 at Story 34 (D/C of 1.008). We arbitrarily declared that this met the requirements of ASCE-7 for a redundancy coefficient, ρ=1.

Figure 2: Plan at Eleventh through Fortieth Floors

Figure 3: Elevation of Frame Along Line 2 Following Removal of a Brace

Figure 4: Elevation of Frame Along Line D Following Removal of a Brace

2.2.3 Lateral Force Resisting Member Design

2.2.3.1 Buckling Restrained Brace Design

We designed the buckling restrained braces for the worst of the wind and seismic loads. In almost all cases, seismic loads governed the design. The capacity of the braces in tension and compression was both considered as $\phi A_s F_y$, with ϕ = 0.9 and F_y = 38 ksi. Pages A14 through A37 show the brace design details along lines 2, 3, 4 and D respectively.

2.2.3.2 Braced Frame Column Design

AISC's Seismic Provisions for Structural Steel Buildings (ANSI/AISC 341-05), require columns in buckling restrained braced frames need to be checked for

- Axial load and moment interaction for code level forces
- For axial load only corresponding to the sum of the vertical component of all buckling restrained braces that frame into the column along with tributary gravity loading

We checked the columns for both of the above criterion and found that the latter generally produced larger D/C ratios. Since the current configuration uses columns that form part of lateral framing in two orthogonal directions, we used the 100%-30% combination to calculate the maximum compression from the braces. We established the maximum compression forces from the brace as $R_y \omega \beta A_s F_y$, where R_y =1.1, ω = 1.25 and β = 1.1.

We used built up square box columns infilled with high strength (f'c = 10 ksi) concrete to resist the large compression force demands. The plate thicknesses of the box columns ranged from 1.5 in. at upper stories to 3 in. at lower ones. The plan dimension of the box columns ranged from 18 in. to 57 in. We calculated the strength, axial area and stiffness of infill columns using the provisions of Chapter I (Design of Composite Members) of the 13th edition LRFD Steel Code. We included this enhancement of axial area and stiffness over the bare steel section properties in the ETABS analysis model as well. We did this by defining a steel box section in ETABS and then using the property modifier to account for the infill concrete. Figure 5 shows the ETABS screen shot of how this is accomplished. Page A38 shows the detailed strength and stiffness calculation for the box columns. Note that the last two columns calculate the axial and inertial modifiers used in ETABS. Additionally pages A39 through A41 show the details of the column design at C/2, D/2 and D/3 respectively.

2.2.3.3 Braced Frame Beam Design

We designed the braced frame beams for the horizontal component of the brace compression along with unbalanced upward component of the buckling restrained brace given by $R_y \omega A_s F_y(\beta - 1)\sin \alpha$ where α is the brace angle. Since BRBs are always stronger in compression than tension, this moment is opposite in direction to the gravity moment. Page A42 shows a sample beam design for the frame along line 2.

Figure 5: Defining Box Column Section Properties in ETABS

2.2.4 Story Drifts for Code Design

We calculated interstory drifts using the response spectrum analysis. ASCE 7-05 stipulates the use of a response spectrum that is reduced by the response reduction factor, R. It also states that the drifts obtained from this reduced spectral analysis be amplified by C_d to yield the expected inelastic drifts. Table 4 shows the interstory drifts obtained at the various levels both for the X and Y directions. As can be seen, the maximum story drifts are less than the permissible value of 0.02 at all levels.

Table – 4 Story Drifts for Code Design

Story	Y Direction Drifts	X Direction Drifts
Story 40	0.013	0.005
Story 39	0.014	0.006
Story 38	0.014	0.006
Story 37	0.014	0.006
Story 36	0.014	0.006
Story 35	0.014	0.006
Story 34	0.014	0.006
Story 33	0.014	0.006
Story 32	0.014	0.006
Story 31	0.014	0.006
Story 30	0.014	0.006
Story 29	0.014	0.006
Story 28	0.014	0.006
Story 27	0.013	0.006
Story 26	0.013	0.006
Story 25	0.013	0.006
Story 24	0.013	0.006
Story 23	0.012	0.006
Story 22	0.012	0.006
Story 21	0.012	0.006
Story 20	0.012	0.006
Story 19	0.011	0.006
Story 18	0.011	0.006
Story 17	0.011	0.006

Story	Y Direction Drifts	X Direction Drifts
Story 16	0.010	0.006
Story 15	0.010	0.006
Story 14	0.010	0.005
Story 13	0.009	0.005
Story 12	0.008	0.005
Story 11	0.007	0.005
Story 10	0.004	0.004
Story 9	0.004	0.004
Story 8	0.004	0.004
Story 7	0.004	0.004
Story 6	0.004	0.004
Story 5	0.004	0.004
Story 4	0.003	0.004
Story 3	0.003	0.004
Story 2	0.003	0.003
Story 1	0.002	0.002

3. PERFORMANCE BASED DESIGN

We based the seismic design for this alternate on the seismic design criteria (dated 29 April 2008) published by the Los Angeles Tall Building Structural Design Council (LATBSDC). Since this design was not required to meet all of the prescriptive criteria contained in the building code, we were able to reduce the size and number of bays of the buckling restrained frames. Specifically, along lines 2 and 7 the two additional bays below level 10 were omitted and only a single bay of bracing is provided. Table 6 lists the performance objectives we followed for this design:

Table 6 – Seismic Performance Objectives

Level of Earthquake	Earthquake Performance Objectives
Frequent/Service : 25 year return period, 2.5% damping	Serviceability: Essentially elastic performance with minor yielding of brbf-s. Drift limited to 0.5%
Maximum Considered Earthquake (MCE): As defined by ASCE 7-05, Section 21.2, 2.5% damping.	Collapse Prevention: Extensive structural damage, repairs are required and may not be economically feasible. Drift limited to 3%

3.1 Service Level Earthquake Evaluation

We used a response spectrum analysis for this evaluation. We used the response spectrum shown in Figure 6, which was provided by PEER. The damping level was set at 2.5%. We neglected accidental torsion in this analysis.

Figure 6: Response Spectrum for Serviceability Analysis

We also evaluated the building for the same wind forces that we used for the code-based design described in the previous section. We found that wind always governed the required brace strength. Pages A43 through A48 show the representative details of the brace design along line 3. The interstory drifts for the service level earthquake is shown in the following table. As can be seen, the drifts are less than 0.5% at all levels.

Table 4 – Story Drifts for Service Level Earthquake

Story	Y Direction Drifts	X Direction Drifts
Story 40	0.0031	0.0014
Story 39	0.0032	0.0015
Story 38	0.0033	0.0016
Story 37	0.0033	0.0017
Story 36	0.0034	0.0017
Story 35	0.0033	0.0018
Story 34	0.0033	0.0018
Story 33	0.0033	0.0018
Story 32	0.0032	0.0018
Story 31	0.0031	0.0018
Story 30	0.0031	0.0018
Story 29	0.0029	0.0018

Story	Y Direction Drifts	X Direction Drifts
Story 28	0.0028	0.0018
Story 27	0.0027	0.0018
Story 26	0.0026	0.0018
Story 25	0.0026	0.0018
Story 24	0.0025	0.0018
Story 23	0.0024	0.0018
Story 22	0.0023	0.0018
Story 21	0.0022	0.0017
Story 20	0.0021	0.0017
Story 19	0.0021	0.0017
Story 18	0.002	0.0017
Story 17	0.002	0.0017
Story 16	0.0019	0.0017
Story 15	0.0019	0.0016
Story 14	0.0018	0.0016
Story 13	0.0018	0.0016
Story 12	0.0017	0.0016
Story 11	0.0017	0.0016
Story 10	0.0016	0.0017
Story 9	0.0016	0.0017
Story 8	0.0016	0.0017
Story 7	0.0015	0.0017
Story 6	0.0015	0.0017
Story 5	0.0015	0.0017
Story 4	0.0014	0.0017
Story 3	0.0014	0.0016
Story 2	0.0012	0.0014
Story 1	0.0008	0.001

3.2 Maximum Considered Earthquake Evaluation

As required by the LATBSDC document, we performed a non linear response history analysis of the building corresponding for maximum considered earthquake shaking as defined by the building code. We used seven pairs of acceleration histories provided to us by PEER for this

purpose. We used the non linear analysis program CSI Perform, version 4.0.1 with a constant modal damping level of 2.5% and 0.1% Rayleigh damping. We explicitly modeled the non linearities in the buckling restrained braces. We modeled columns and beams as elastic elements and later verified that demands on these elements remained within their elastic capacities. Details of the element modeling are discussed below.

3.2.1 Modeling of Critical Elements

3.2.1.1 Modeling of Buckling Restrained Braces

We modeled the buckling restrained braces (brb) using the perform BRB inelastic element in series with an elastic spring that models the end attachment of the braces. The backbone curve of the BRBs were modeled according to Figure 7 with R_y =1.1, ω = 1.25 and β = 1.1. Figure 8 shows the screen shot of the Perform input form for the BRB definition and Figure 9 shows the form for the compound element definition with the elastic end element in series. Note that the initial stiffness (K_0) of the buckling restrained brace is based on A_sE/L with L equal to 70% of the actual center to center length of the brace.

Figure 7: Presumed Backbone Curve for Buckling Restrained Braces

Figure 8: BRBF Property Definition in Perform

Figure 9: BRBF Compound Element in Perform

3.2.1.2 Modeling of the Columns and Beams

We modeled the columns using the non prismatic steel sections in Perform. The moment of inertia input in the form was adjusted to account for the additional stiffening due to the presence of the infill concrete. Figure 10 shows the stiffness and area definition form for the 48 sq in. box columns with 3 in. plates.

The axial load and moment strength for the same column is shown in Figure 11. The axial and flexural strengths are corresponding to nominal material properties without any strength reduction or ϕ factor.

The compound column element utilizes the cross sectional information and assembles the column element as an elastic element. We have ensured that the column element always stays elastic during the analysis by monitoring the axial flexure interaction ratios so that they are always less than 1.

Beams are modeled in an identical fashion as the columns except that standard W sections are used. Similar to the columns, the beams are also modeled as elastic elements.

Figure 10: Column Section Definition in Perform

Figure 11: Column Strength Definition in Perform

3.2.1.3 Modeling of the Diaphragms at Upper, Ground and Basement Levels

We modeled the diaphragms at all elevated floors as rigid diaphragms. However, the diaphragms at the ground and all basement floors were modeled with elastic shell elements with 30% of the gross cross section properties. We considered an effective thickness comprising of the total thickness of the topping plus half the rib thickness. Thus the ground floor was modeled as 10.5 in. thick slab as it represents a 9 in. topping and 1.5 in. half rib height. We followed the same approach for the basement slabs except that that the modulus of elasticity also included the λ modifier corresponding to lightweight concrete.

3.2.1.4 Modeling of Perimeter Walls

We modeled the perimeter shear walls as elastic wall elements with cracked stiffness equaling 50% of the gross stiffness. The elastic shear modulus was considered to be 40% of the gross elastic (Young's) modulus per ASCE 41, Supplement #1.

3.2.2 Selected Results from Non Linear Analysis

3.2.2.1 Story Drifts

We present the story drifts from the non linear analysis in Figures 12 and 13. Figure 12 shows the drift in the Y direction whereas Figure 13 shows the corresponding drift in the X direction. The maximum drift in the Y direction is around 2.13% while the maximum in the X direction is at 1.80%. As can be observed from the figures, the drifts are less than the permissible value of 3% in both directions and the mean peak drifts are generally on the order of 1.25% or less.

Figure 12: Peak Interstory Drifts in the Y Direction

Figure 13: Peak Interstory Drifts in the X Direction

3.2.2.2 Buckling Restrained Brace Core Strain

We also monitored strain in the cores of the buckling restrained braces and ensured that the mean strain is less than of 0.013 ($10\varepsilon_y$) obtained from the test results conducted at the University of Utah by Romero and Reavely. Figure 14 shows the buckling restrained brace core strain for lines 2, 3 and 4 respectively. The results are presented as D/C ratio with the capacity being 0.013. Similar information for line D is presented in Figure 15. The ratios are all less than unity implying acceptable performance.

Line 2 *Line 3* *Line 4*

Figure 14: BRBF Core Strain DCRs along Lines 2, 3 and 4

Figure 15: BRBF Core Strain DCR Along Line D

3.2.2.3 Column Axial Flexure Interaction Ratio

Figure 16 shows the axial load and flexure interaction ratio for the seismic frame columns along line E. As can be seen from the figure, the maximum mean interaction ratio is 0.54. The absolute maximum from the seven analysis is 0.73 signifying elastic behavior of the columns.

Figure 16: Seismic Frame Column Axial Flexure Interaction Ratio along Line E

3.2.2.4 Story Shears

We also monitored the story shears over the height of the building. Figure 17 and Figure 18 plot the story shears in the Y direction and X direction respectively. The effect of the stiff ground floor diaphragms is easily observable form the plots. We have proportioned the ground floor slab and the collectors so that it is capable of transferring this large reaction.

Figure 17: Accumulated Peak Story Shear in Steel Superstructure in Y Direction

Figure 18: Accumulated Peak Story Shear in Steel Superstructure in X Direction

4. ENHANCED PERFORMANCE BASED DESIGN

We based the seismic design for this alternate on the seismic design criteria provided to us by PEER. The following table shows summary of the criteria for this design.

Table 7 – Seismic Performance Objectives

Level of Earthquake	Earthquake Performance Objectives
Frequent/Service : 43 year return period, 2.5% damping	Serviceability: Drift limited to 0.5%. Demand capacity ratio for buckling restrained braces not to exceed 1.5.
Maximum Considered Earthquake (MCE): As defined by ASCE 7-05, Section 21.2, 2.5% damping.	Collapse Prevention: Extensive structural damage, repairs are required and may not be economically feasible. Drift limited to 3%

4.1 Service Level Earthquake Evaluation

We used a response spectrum provided to us by PEER for this evaluation. We observed that using the BRB sizes from the Performance Based Alternate caused overstress in some of the braces. This was particularly severe along the longitudinal direction of the building. As a result we had to upsize some of the braces. Additionally, we had to use an outrigger that projected out form the core on lines 2 and 7. This outrigger was provided at the roof, the 30th floor and the 20th floor. Figure 19 shows the response spectrum used for the evaluation and Figure 20 shows the 3D view of the computer model along with the outriggers.

Figure 19: Response Spectrum for Enhanced PBE

Figure 20: 3D Computer Model used for the Enhanced Performance Based Evaluation

Table 8 shows the drifts from the service level evaluation along the transverse and longitudinal directions of the building. As can be observed, the drifts are all less than the 0.5% limit.

Table 8 – Story Drifts for Service Level Earthquake

Story	Y Direction Drifts	X Direction Drifts
Story 40	0.0031	0.0022
Story 39	0.0042	0.0024
Story 38	0.0047	0.0026
Story 37	0.0048	0.0027
Story 36	0.0049	0.0028
Story 35	0.0049	0.0029
Story 34	0.0049	0.0029
Story 33	0.0049	0.0029
Story 32	0.0049	0.0029
Story 31	0.0046	0.0030
Story 30	0.0034	0.0029
Story 29	0.0045	0.0029
Story 28	0.0047	0.0029
Story 27	0.0046	0.0029
Story 26	0.0046	0.0029
Story 25	0.0045	0.0028
Story 24	0.0044	0.0028
Story 23	0.0043	0.0028
Story 22	0.0041	0.0027
Story 21	0.0037	0.0027
Story 20	0.0029	0.0027
Story 19	0.0035	0.0027
Story 18	0.0037	0.0026

Story	Y Direction Drifts	X Direction Drifts
Story 17	0.0037	0.0026
Story 16	0.0036	0.0026
Story 15	0.0036	0.0026
Story 14	0.0035	0.0025
Story 13	0.0034	0.0025
Story 12	0.0033	0.0025
Story 11	0.0032	0.0025
Story 10	0.0031	0.0025
Story 9	0.0030	0.0025
Story 8	0.0030	0.0025
Story 7	0.0029	0.0025
Story 6	0.0028	0.0025
Story 5	0.0027	0.0025
Story 4	0.0025	0.0024
Story 3	0.0024	0.0023
Story 2	0.0021	0.0021
Story 1	0.0014	0.0014

4.1 Maximum Considered Earthquake Evaluation

We used the same time histories and modeling assumptions as presented earlier in the Performance Based Evaluation section. Figure 21 shows the drift in the Y direction whereas Figure 22 shows the corresponding drift in the X direction. The maximum drift in the Y direction is around 1.33% while the maximum in the X direction is at 1.42%. As can be observed from the figures, the drifts are less than the permissible value of 3% in both directions and the mean peak drifts are generally on the order of 1.0% or less.

Figure 21: Peak Interstory Drifts in the Y Direction

Figure 22: Peak Interstory Drifts in the X Direction

We also examined the strains in the buckling restrained braces and the axial moment interaction in the columns. In general they followed the same trend as the earlier Performance Based Evaluation with the maximum strain demand capacity ratio of 0.58. The maximum demand capacity ratio for the column was around 0.75.

APPENDIX A

SIMPSON GUMPERTZ & HEGER
Engineering of Structures and Building Enclosures

SHEET NO. _____
PROJECT NO. 087237.00
DATE 11/26/08
BY AD
CHECKED BY ROH

CLIENT CSSC
SUBJECT LA BRBF Building, LA, CA

ROOF FLAT LOADS — ROOF

Level	Material	Slab (psf)	Beam (psf)	Cols (psf)	Seismic (psf)	Gr. Cols (psf)	Remarks
Roof	Roofing	5.0	5.0	5.0	5.0	5.0	
"	3-1/4" Ltwt. conc. over 3" mtl deck	48.5	48.5	48.5	48.5	48.5	
"	20 Ga. Metal deck	3.0	3.0	3.0	3.0	3.0	
"	Struct. Steel framing			5.0	5.0	5.0	*Beam weight calculated by RAM*
	Drop ceiling	2.0	2.0	2.0	2.0	2.0	
"	MEP	2.0	2.0	2.0	2.0	2.0	*Ceiling mounted*
"	Gravity columns				1.5	1.5	
"	Seismic Frame			8.0	8.0		
"	Partitions				5.0		
"	Miscellaneous	19.0	19.0	19.0	14.0	19.0	
	Sum of Dead Loads	**79.5**	**79.5**	**92.5**	**94.0**	**86.0**	
	Sum of Live Loads	**25.0**	**25.0**	**25.0**	**-**	**25.0**	
	Sum of Dead Plus Live Loads	**104.5**	**104.5**	**117.5**	**94.0**	**111.0**	

FLOOR FLAT LOADS — TYPICAL FLOORS 39th THROUGH 33rd

Level	Material	Slab (psf)	Beam (psf)	Cols (psf)	Seismic (psf)	Gr. Cols (psf)	Remarks
Floor	Partitions	20.0	20.0	20.0	10.0	20.0	
"	Carpet floor finish	2.0	2.0	2.0	2.0	2.0	
"	20 Ga. Metal deck	3.0	3.0	3.0	3.0	3.0	
"	3-1/4" Ltwt. conc. over 3" mtl deck	48.5	48.5	48.5	48.5	48.5	
"	Struct. Steel framing			5.0	5.0		*Beam weight calculated by RAM*
"	Drop ceiling	2.0	2.0	2.0	2.0	2.0	
"	MEP	3.0	3.0	3.0	3.0	3.0	*Ceiling mounted*
"	Gravity columns				2.0	2.0	
"	Seismic Frames			11.5	11.5		
"	Miscellaneous	1.0	1.0	1.0	1.0	1.0	```
	Sum of Dead Loads	**79.5**	**79.5**	**96.0**	**88.0**	**81.5**	
	Sum of Live Loads	**40.0**	**40.0**	**40.0**	**-**	**40.0**	
	Sum of Dead Plus Live Loads	**119.5**	**119.5**	**136.0**	**88.0**	**121.5**	

FLOOR FLAT LOADS — TYPICAL FLOORS 32nd THROUGH 28th

Level	Material	Slab (psf)	Beam (psf)	Cols (psf)	Seismic (psf)	Gr. Cols (psf)	Remarks
Floor	Partitions	20.0	20.0	20.0	10.0	20.0	
"	Carpet floor finish	2.0	2.0	2.0	2.0	2.0	
"	20 Ga. Metal deck	3.0	3.0	3.0	3.0	3.0	
"	3-1/4" Ltwt. conc. over 3" mtl deck	48.5	48.5	48.5	48.5	48.5	
"	Struct. Steel framing			5.0	5.0		*Beam weight calculated by RAM*
"	Drop ceiling	2.0	2.0	2.0	2.0	2.0	
"	MEP	3.0	3.0	3.0	3.0	3.0	*Ceiling mounted*
"	Gravity columns				2.5	2.5	
"	Seismic Frames			15.0	15.0		
"	Miscellaneous	1.0	1.0	1.0	1.0	1.0	```
	Sum of Dead Loads	**79.5**	**79.5**	**99.5**	**92.0**	**82.0**	
	Sum of Live Loads	**40.0**	**40.0**	**40.0**	**-**	**40.0**	
	Sum of Dead Plus Live Loads	**119.5**	**119.5**	**139.5**	**92.0**	**122.0**	

SIMPSON GUMPERTZ & HEGER
Engineering of Structures and Building Enclosures

SHEET NO. _____
PROJECT NO. 087237.00
DATE 11/26/08
BY AD
CHECKED BY ROH

CLIENT CSSC
SUBJECT LA BRBF Building, LA, CA

FLOOR FLAT LOADS — TYPICAL FLOORS 27th THROUGH 24th

Level	Material	Slab (psf)	Beam (psf)	Cols (psf)	Seismic (psf)	Gr. Cols (psf)	Remarks
Floor	Partitions	20.0	20.0	20.0	10.0	20.0	
"	Carpet floor finish	2.0	2.0	2.0	2.0	2.0	
"	20 Ga. Metal deck	3.0	3.0	3.0	3.0	3.0	
"	3-1/4" Ltwt. conc. over 3" mtl deck	48.5	48.5	48.5	48.5	48.5	
"	Struct. Steel framing			5.0	5.0		*Beam weight calculated by RAM*
"	Drop ceiling	2.0	2.0	2.0	2.0	2.0	
"	MEP	3.0	3.0	3.0	3.0	3.0	*Ceiling mounted*
"	Gravity columns				2.5	2.5	
"	Seismic Frames			19.0	19.0		
"	Miscellaneous	1.0	1.0	1.0	1.0	1.0	```
	Sum of Dead Loads	**79.5**	**79.5**	**103.5**	**96.0**	**82.0**	
	Sum of Live Loads	**40.0**	**40.0**	**40.0**	**-**	**40.0**	
	Sum of Dead Plus Live Loads	**119.5**	**119.5**	**143.5**	**96.0**	**122.0**	

FLOOR FLAT LOADS — TYPICAL FLOORS 23rd THROUGH 20th

Level	Material	Slab (psf)	Beam (psf)	Cols (psf)	Seismic (psf)	Gr. Cols (psf)	Remarks
Floor	Partitions	20.0	20.0	20.0	10.0	20.0	
"	Carpet floor finish	2.0	2.0	2.0	2.0	2.0	
"	20 Ga. Metal deck	3.0	3.0	3.0	3.0	3.0	
"	3-1/4" Ltwt. conc. over 3" mtl deck	48.5	48.5	48.5	48.5	48.5	
"	Struct. Steel framing			5.0	5.0		*Beam weight calculated by RAM*
"	Drop ceiling	2.0	2.0	2.0	2.0	2.0	
"	MEP	3.0	3.0	3.0	3.0	3.0	*Ceiling mounted*
"	Gravity columns				3.0		
"	Seismic Frames			24.5	24.5		
"	Miscellaneous	1.0	1.0	1.0	1.0	1.0	```
	Sum of Dead Loads	**79.5**	**79.5**	**109.0**	**102.0**	**79.5**	
	Sum of Live Loads	**40.0**	**40.0**	**40.0**	**-**	**40.0**	
	Sum of Dead Plus Live Loads	**119.5**	**119.5**	**149.0**	**102.0**	**119.5**	

FLOOR FLAT LOADS — TYPICAL FLOORS 19th THROUGH 15th

Level	Material	Slab (psf)	Beam (psf)	Cols (psf)	Seismic (psf)	Gr. Cols (psf)	Remarks
Floor	Partitions	20.0	20.0	20.0	10.0	20.0	
"	Carpet floor finish	2.0	2.0	2.0	2.0	2.0	
"	20 Ga. Metal deck	3.0	3.0	3.0	3.0	3.0	
"	3-1/4" Ltwt. conc. over 3" mtl deck	48.5	48.5	48.5	48.5	48.5	
"	Struct. Steel framing			5.0	5.0		*Beam weight calculated by RAM*
"	Drop ceiling	2.0	2.0	2.0	2.0	2.0	
"	MEP	3.0	3.0	3.0	3.0	3.0	*Ceiling mounted*
"	Gravity columns				2.5	2.5	
"	Seismic Frames			30.0	30.0		
"	Miscellaneous	1.0	1.0	1.0	1.0	1.0	```
	Sum of Dead Loads	**79.5**	**79.5**	**114.5**	**107.0**	**82.0**	
	Sum of Live Loads	**40.0**	**40.0**	**40.0**	**-**	**40.0**	
	Sum of Dead Plus Live Loads	**119.5**	**119.5**	**154.5**	**107.0**	**122.0**	

SIMPSON GUMPERTZ & HEGER
Engineering of Structures and Building Enclosures

SHEET NO. _____
PROJECT NO. 087237.00
DATE 11/26/08
BY AD
CHECKED BY ROH

CLIENT CSSC
SUBJECT LA BRBF Building, LA, CA

FLOOR FLAT LOADS — TYPICAL FLOORS 14th THROUGH 10th

Level	Material	Slab (psf)	Beam (psf)	Cols (psf)	Seismic (psf)	Gr. Cols (psf)	Remarks
Floor	Partitions	20.0	20.0	20.0	10.0	20.0	
"	Carpet floor finish	2.0	2.0	2.0	2.0	2.0	
"	20 Ga. Metal deck	3.0	3.0	3.0	3.0	3.0	
"	3-1/4" Ltwt. conc. over 3" mtl deck	48.5	48.5	48.5	48.5	48.5	
"	Struct. Steel framing			5.0	5.0		*Beam weight calculated by RAM*
"	Drop ceiling	2.0	2.0	2.0	2.0	2.0	
"	MEP	3.0	3.0	3.0	3.0	3.0	*Ceiling mounted*
"	Gravity columns				2.5	2.5	
"	Seismic Frames			38.0	38.0		
"	Miscellaneous	1.0	1.0	1.0	1.0	1.0	```
	Sum of Dead Loads	**79.5**	**79.5**	**122.5**	**115.0**	**82.0**	
	Sum of Live Loads	**40.0**	**40.0**	**40.0**	**-**	**40.0**	
	Sum of Dead Plus Live Loads	**119.5**	**119.5**	**162.5**	**115.0**	**122.0**	

FLOOR FLAT LOADS — TYPICAL FLOORS 9th THROUGH 5th

Level	Material	Slab (psf)	Beam (psf)	Cols (psf)	Seismic (psf)	Gr. Cols (psf)	Remarks
Floor	Partitions	20.0	20.0	20.0	10.0	20.0	
"	Carpet floor finish	2.0	2.0	2.0	2.0	2.0	
"	20 Ga. Metal deck	3.0	3.0	3.0	3.0	3.0	
"	3-1/4" Ltwt. conc. over 3" mtl deck	48.5	48.5	48.5	48.5	48.5	
"	Struct. Steel framing			5.0	5.0		*Beam weight calculated by RAM*
"	Drop ceiling	2.0	2.0	2.0	2.0	2.0	
"	MEP	3.0	3.0	3.0	3.0	3.0	*Ceiling mounted*
"	Gravity columns				2.5	2.5	
"	Seismic Frames			43.0	43.0		
"	Miscellaneous	1.0	1.0	1.0	1.0	1.0	```
	Sum of Dead Loads	**79.5**	**79.5**	**127.5**	**120.0**	**82.0**	
	Sum of Live Loads	**55.0**	**55.0**	**55.0**	**-**	**55.0**	*Includes 15 psf partition loading*
	Sum of Dead Plus Live Loads	**134.5**	**134.5**	**182.5**	**120.0**	**137.0**	

FLOOR FLAT LOADS — TYPICAL FLOORS 4th THROUGH 2nd

Level	Material	Slab (psf)	Beam (psf)	Cols (psf)	Seismic (psf)	Gr. Cols (psf)	Remarks
Floor	Partitions	20.0	20.0	20.0	10.0	20.0	
"	Carpet floor finish	2.0	2.0	2.0	2.0	2.0	
"	20 Ga. Metal deck	3.0	3.0	3.0	3.0	3.0	
"	3-1/4" Ltwt. conc. over 3" mtl deck	48.5	48.5	48.5	48.5	48.5	
"	Struct. Steel framing			5.0	5.0		*Beam weight calculated by RAM*
"	Drop ceiling	2.0	2.0	2.0	2.0	2.0	
"	MEP	3.0	3.0	3.0	3.0	3.0	*Ceiling mounted*
"	Gravity columns				2.5	2.5	
"	Seismic Frames			50.0	50.0		
"	Miscellaneous	1.0	1.0	1.0	1.0	1.0	```
	Sum of Dead Loads	**79.5**	**79.5**	**134.5**	**127.0**	**82.0**	
	Sum of Live Loads	**40.0**	**40.0**	**40.0**	**-**	**40.0**	
	Sum of Dead Plus Live Loads	**119.5**	**119.5**	**174.5**	**127.0**	**122.0**	

SIMPSON GUMPERTZ & HEGER
Engineering of Structures and Building Enclosures

SHEET NO. _____
PROJECT NO. 087237.00
DATE 11/26/08
BY AD
CHECKED BY ROH

CLIENT CSSC
SUBJECT LA BRBF Building, LA, CA

FLOOR FLAT LOADS — 1ST FLOOR

Level	Material	Slab (psf)	Beam (psf)	Cols (psf)	Seismic (psf)	Gr. Cols (psf)	Remarks
Floor	Partitions	20.0	20.0	20.0	10.0	20.0	
"	Carpet floor finish	2.0	2.0	2.0	2.0	2.0	
"	20 Ga. Metal deck	3.0	3.0	3.0	3.0	3.0	
"	3-1/4" Ltwt. conc. over 3" mtl deck	48.5	48.5	48.5	48.5	48.5	
"	Struct. Steel framing			5.0	5.0		*Beam weight calculated by RAM*
"	Drop ceiling	2.0	2.0	2.0	2.0	2.0	
"	MEP	3.0	3.0	3.0	3.0	3.0	*Ceiling mounted*
"	Gravity columns				2.5	2.5	
"	Seismic Frames			60.0	60.0		
"	Miscellaneous	1.0	1.0	1.0	1.0	1.0	```
	Sum of Dead Loads	**79.5**	**79.5**	**144.5**	**137.0**	**82.0**	
	Sum of Live Loads	**40.0**	**40.0**	**40.0**	**-**	**40.0**	
	Sum of Dead Plus Live Loads	**119.5**	**119.5**	**184.5**	**137.0**	**122.0**	

FLOOR FLAT LOADS — GROUND FLOOR INSIDE CORE

Level	Material	Slab (psf)	Beam (psf)	Cols (psf)	Seismic (psf)	Gr. Cols (psf)	Remarks
Floor	Partitions	20.0	20.0	20.0	10.0	20.0	
"	Carpet floor finish	2.0	2.0	2.0	2.0	2.0	
"	18 Ga. Metal deck	3.0	3.0	3.0	3.0	3.0	
"	9" Nwt. conc. over 3" mtl deck	127.0	127.0	127.0	127.0	127.0	
"	Struct. Steel framing			8.0	8.0		*Beam weight calculated by RAM*
"	Drop ceiling	2.0	2.0	2.0	2.0	2.0	
"	MEP	3.0	3.0	3.0	3.0	3.0	*Ceiling mounted*
"	Gravity columns				3.0	3.0	
"	Seismic Frames			27.5	27.5		
"	Miscellaneous	83.0	83.0	83.0	83.0	83.0	
	Sum of Dead Loads	**220.0**	**220.0**	**255.5**	**258.5**	**223.0**	
	Sum of Live Loads	**100.0**	**100.0**	**100.0**	**-**	**100.0**	
	Sum of Dead Plus Live Loads	**320.0**	**320.0**	**355.5**	**258.5**	**323.0**	

FLOOR FLAT LOADS — GROUND FLOOR PLAZA

Level	Material	Slab (psf)	Beam (psf)	Cols (psf)	Seismic (psf)	Gr. Cols (psf)	Remarks
Floor	Plant beds etc.	347.0	347.0	347.0	347.0	347.0	
"	18 Ga. Metal deck	3.0	3.0	3.0	3.0	3.0	
"	9" Nwt. conc. over 3" mtl deck	127.0	127.0	127.0	127.0	127.0	
"	Struct. Steel framing			8.0	8.0		*Beam weight calculated by RAM*
"	MEP	3.0	3.0	3.0	3.0	3.0	*Ceiling mounted*
"	Gravity columns				3.0	3.0	
"	Seismic Frames			27.5	27.5		
"	Miscellaneous	0.0	0.0	0.0	0.0	0.0	
	Sum of Dead Loads	**480.0**	**480.0**	**515.5**	**518.5**	**483.0**	
	Sum of Live Loads	**100.0**	**100.0**	**100.0**	**-**	**100.0**	
	Sum of Dead Plus Live Loads	**580.0**	**580.0**	**615.5**	**518.5**	**583.0**	

FLOOR FLAT LOADS — BASEMENT

Level	Material	Slab (psf)	Beam (psf)	Cols (psf)	Seismic (psf)	Gr. Cols (psf)	Remarks
Floor	18 Ga. Metal deck	3.0	3.0	3.0	3.0	3.0	
"	3-1/4" Ltwt. conc. over 3" mtl deck	48.5	48.5	48.5	48.5	48.5	
"	Struct. Steel framing			6.0	6.0		*Beam weight calculated by RAM*
"	MEP	3.0	3.0	3.0	3.0	3.0	*Ceiling mounted*
"	Gravity columns				2.5	2.5	
"	Seismic Frames			23.0	23.0		
"	Miscellaneous						
	Sum of Dead Loads	**54.5**	**54.5**	**83.5**	**86.0**	**57.0**	
	Sum of Live Loads	**40.0**	**40.0**	**40.0**	**-**	**40.0**	
	Sum of Dead Plus Live Loads	**94.5**	**94.5**	**123.5**	**86.0**	**97.0**	

SIMPSON GUMPERTZ & HEGER
Engineering of Structures and Building Enclosures

SHEET NO. _____
PROJECT NO. 087237.10
DATE 1/23/09
BY AD
CHECKED BY _____

CLIENT Pacific Earthquake Engineering Research Center
SUBJECT Gust Effect Factor in Short Normal Dir. for LA BRBF Bldg

Exposure =	B				
Basic Wind Speed (V) =	85.00	mph	Vz-bar =	99.51	ft/s (Eq. 6-14)
h (Mean Roof Height) =	544.50	ft	Lz-bar=	687.11	
z-bar =	326.70	ft	N1 =	1.73	
α-bar =	0.25	(Table 6-2)	η_h =	6.29	
b-bar =	0.45	(Table 6-2)	η_B =	1.24	
l =	320.00	ft (Table 6-2)	η_L =	6.58	
ε-bar =	0.33	(Table 6-2)	R_h =	0.15	
n1 =	0.25	Hz	R_B =	0.51	
B =	107.00	ft	R_L =	0.14	
L =	170.00	ft	R_n =	0.10	
β =	0.01	Damping	R =	0.65	
g_Q =	3.40	(Cl 6.5.8.2)	g_R =	3.84	
g_v =	3.40	(Cl 6.5.8.2)	Iz-bar=	0.20	
c =	0.30	(Table 6-2)	Q =	0.79	
			Gf =	**0.97**	

SIMPSON GUMPERTZ & HEGER
Engineering of Structures and Building Enclosures

SHEET NO. _____
PROJECT NO. 087237.10
DATE 1/23/09
BY AD
CHECKED BY _____

CLIENT Pacific Earthquake Engineering Research Center
SUBJECT Wind Pressures In Short Normal Direction for LA BRBF Bldg

Exposure :	B	
Basic Wind Speed (V):	85	mph (Fig 6-1)
Importance Factor (I) :	1	(Table 1-1, 6-1)
zg =	1200	ft (Table 6-2)
α =	7	(Table 6-2)
Kd =	0.85	(Table 6-4)
h (Mean roof Height) =	544.5	ft
Cp(windward) =	0.8	(Fig 6-6)
GCpi =	0.18	(Fig 6-5 for Encl. Bldg.)
	-0.18	(Fig 6-5 for Encl. Bldg.)
Parapet Tip Height =	551	ft
GCpn =	1.5	(6.5.12.2.4)

Topographic Factor		
K_1 =	0	(Fig 6-4)
K_2 =	0	(Fig 6-4)
K_3 =	0	(Fig 6-4)
K_{zt} =	1	
Gf =	0.97	
qh =	25.2	psf

Parapet Pressure		
Kz-parapet=	1.61	(Case 1 Table 6-3)
qz=qp =	25.3	
p_p =	37.9	psf

			Main Wind Force Resisting System					
Elevation (z)	B	L	Kz	qz	Windward Pr.	Internal Pressure		Leeward Pr.
						Positive	Negative	
0	107	170	0.5747	9.04	6.98	4.54	-4.54	-9.30
15	107	170	0.57	9.04	6.98	4.54	-4.54	-9.30
20	107	170	0.62	9.81	7.58	4.54	-4.54	-9.30
25	107	170	0.67	10.46	8.08	4.54	-4.54	-9.30
30	107	170	0.70	11.01	8.51	4.54	-4.54	-9.30
40	107	170	0.76	11.96	9.24	4.54	-4.54	-9.30
50	107	170	0.81	12.75	9.84	4.54	-4.54	-9.30
60	107	170	0.85	13.43	10.37	4.54	-4.54	-9.30
70	107	170	0.89	14.03	10.84	4.54	-4.54	-9.30
80	107	170	0.93	14.58	11.26	4.54	-4.54	-9.30
90	107	170	0.96	15.08	11.64	4.54	-4.54	-9.30
100	107	170	0.99	15.54	12.00	4.54	-4.54	-9.30
120	107	170	1.04	16.37	12.64	4.54	-4.54	-9.30
140	107	170	1.09	17.10	13.21	4.54	-4.54	-9.30
160	107	170	1.13	17.77	13.73	4.54	-4.54	-9.30
180	107	170	1.17	18.38	14.19	4.54	-4.54	-9.30
200	107	170	1.20	18.94	14.63	4.54	-4.54	-9.30
250	107	170	1.28	20.19	15.59	4.54	-4.54	-9.30
300	107	170	1.35	21.27	16.43	4.54	-4.54	-9.30
350	107	170	1.41	22.22	17.17	4.54	-4.54	-9.30
400	107	170	1.47	23.09	17.83	4.54	-4.54	-9.30
450	107	170	1.52	23.88	18.44	4.54	-4.54	-9.30
500	107	170	1.57	24.61	19.01	4.54	-4.54	-9.30
550	107	170	1.61	25.29	19.53	4.54	-4.54	-9.30

SIMPSON GUMPERTZ & HEGER
Engineering of Structures and Building Enclosures

SHEET NO. _____
PROJECT NO. 087237.10
DATE 1/23/09
BY AD
CHECKED BY _____

CLIENT Pacific Earthquake Engineering Research Center
SUBJECT Story Wind Forces in Short Normal Dir. for LA BRBF Bldg

B_Y = 107 ft
e_Y = 16.05 ft

Floor	Height	Cum Ht.	Wind Pressure Windward	Wind Pressure Leeward	Story Force	M_T
					(KIPS)	(KIP-IN)
Story40	13.5	544.5	19.47	-9.30	41.58	8008.31
Story39	13.5	531	19.33	-9.30	41.37	7967.87
Story38	13.5	517.5	19.19	-9.30	41.17	7929.35
Story37	13.5	504	19.05	-9.30	40.96	7888.90
Story36	13.5	490.5	18.90	-9.30	40.75	7848.45
Story35	13.5	477	18.75	-9.30	40.53	7806.08
Story34	13.5	463.5	18.60	-9.30	40.31	7763.71
Story33	13.5	450	18.44	-9.30	40.09	7721.34
Story32	13.5	436.5	18.28	-9.30	39.85	7675.11
Story31	13.5	423	18.11	-9.30	39.61	7628.89
Story30	13.5	409.5	17.95	-9.30	39.37	7582.67
Story29	13.5	396	17.78	-9.30	39.13	7536.44
Story28	13.5	382.5	17.60	-9.30	38.87	7486.37
Story27	13.5	369	17.42	-9.30	38.61	7436.29
Story26	13.5	355.5	17.24	-9.30	38.35	7386.21
Story25	13.5	342	17.05	-9.30	38.07	7332.29
Story24	13.5	328.5	16.85	-9.30	37.78	7276.43
Story23	13.5	315	16.65	-9.30	37.49	7220.58
Story22	13.5	301.5	16.45	-9.30	37.20	7164.72
Story21	13.5	288	16.23	-9.30	36.88	7103.09
Story20	13.5	274.5	16.00	-9.30	36.56	7041.46
Story19	13.5	261	15.78	-9.30	36.23	6977.90
Story18	13.5	247.5	15.54	-9.30	35.90	6914.34
Story17	13.5	234	15.28	-9.30	35.52	6841.16
Story16	13.5	220.5	15.02	-9.30	35.15	6769.89
Story15	13.5	207	14.76	-9.30	34.77	6696.71
Story14	13.5	193.5	14.49	-9.30	34.37	6619.67
Story13	13.5	180	14.19	-9.30	33.95	6538.77
Story12	13.5	166.5	13.88	-9.30	33.49	6450.18
Story11	13.5	153	13.55	-9.30	33.01	6357.73
Story10	13.5	139.5	13.20	-9.30	32.51	6261.43
Story9	13.5	126	12.81	-9.30	31.95	6153.57
Story8	13.5	112.5	12.40	-9.30	31.36	6039.94
Story7	13.5	99	11.96	-9.30	30.73	5918.60
Story6	13.5	85.5	11.47	-9.30	30.02	5781.86
Story5	13.5	72	10.92	-9.30	29.22	5627.78
Story4	13.5	58.5	10.29	-9.30	28.31	5452.51
Story3	13.5	45	9.54	-9.30	27.23	5244.50
Story2	13.5	31.5	8.62	-9.30	25.89	4986.42
Story1	18	18	7.34	-9.30	32.06	6174.76
Ground	12	0	6.98	-9.30	0.00	0.00
B1	12					
B2	12					
B3	12					
				Σ=	**1436.20**	

SIMPSON GUMPERTZ & HEGER
Engineering of Structures and Building Enclosures

SHEET NO. _____
PROJECT NO. 087237.10
DATE 1/23/09
BY AD
CHECKED BY _____

CLIENT Pacific Earthquake Engineering Research Center
SUBJECT Gust Effect Factor in Long Normal Dir. for LA BRBF Bldg

Exposure =	B				
Basic Wind Speed (V) =	85.00	mph	Vz-bar =	99.51	ft/s (Eq. 6-14)
h (Mean Roof Height) =	544.50	ft	Lz-bar=	687.11	
z-bar =	326.70	ft	N1 =	1.38	
α-bar =	0.25	(Table 6-2)	η_h =	5.03	
b-bar =	0.45	(Table 6-2)	η_B =	1.57	
l =	320.00	ft (Table 6-2)	η_L =	3.31	
ε-bar =	0.33	(Table 6-2)	R_h =	0.18	
n1 =	0.20	Hz	R_B =	0.44	
B =	170.00	ft	R_L =	0.26	
L =	107.00	ft	R_n =	0.11	
β =	0.01	Damping	R =	0.75	
g_Q =	3.40	(Cl 6.5.8.2)	g_R =	3.79	
g_v =	3.40	(Cl 6.5.8.2)	Iz-bar=	0.20	
c =	0.30	(Table 6-2)	Q =	0.78	
			Gf =	**1.00**	

SIMPSON GUMPERTZ & HEGER
Engineering of Structures and Building Enclosures

SHEET NO. _____
PROJECT NO. 087237.10
DATE 1/23/09
BY AD
CHECKED BY _____

CLIENT Pacific Earthquake Engineering Research Center
SUBJECT Wind Pressures In Long Normal Direction for LA BRBF Bldg

Exposure :	B	
Basic Wind Speed (V):	85	mph (Fig 6-1)
Importance Factor (I) :	1	(Table 1-1, 6-1)
zg =	1200	ft (Table 6-2)
α =	7	(Table 6-2)
Kd =	0.85	(Table 6-4)
h (Mean roof Height) =	544.4	ft
Cp(windward) =	0.8	(Fig 6-6)
GCpi =	0.18	(Fig 6-5 for Encl. Bldg.)
	-0.18	(Fig 6-5 for Encl. Bldg.)
Parapet Tip Height =	551	ft
GCpn =	1.5	(6.5.12.2.4)

Topographic Factor		
K_1 =	0	(Fig 6-4)
K_2 =	0	(Fig 6-4)
K_3 =	0	(Fig 6-4)
K_{zt} =	1	
Gf =	1.00	
qh =	25.2	psf

Parapet Pressure		
Kz-parapet=	1.61	(Case 1 Table 6-3)
qz=qp =	25.3	
p_p =	37.9	psf

			Main Wind Force Resisting System					
Elevation (z)	B	L	Kz	qz	Windward Pr.	Internal Pressure		Leeward Pr.
						Positive	Negative	
0	170	107	0.57	9.04	7.20	4.54	-4.54	-12.56
15	170	107	0.57	9.04	7.20	4.54	-4.54	-12.56
20	170	107	0.62	9.81	7.82	4.54	-4.54	-12.56
25	170	107	0.67	10.46	8.34	4.54	-4.54	-12.56
30	170	107	0.70	11.01	8.78	4.54	-4.54	-12.56
40	170	107	0.76	11.96	9.53	4.54	-4.54	-12.56
50	170	107	0.81	12.75	10.16	4.54	-4.54	-12.56
60	170	107	0.85	13.43	10.70	4.54	-4.54	-12.56
70	170	107	0.89	14.03	11.19	4.54	-4.54	-12.56
80	170	107	0.93	14.58	11.62	4.54	-4.54	-12.56
90	170	107	0.96	15.08	12.02	4.54	-4.54	-12.56
100	170	107	0.99	15.54	12.39	4.54	-4.54	-12.56
120	170	107	1.04	16.37	13.05	4.54	-4.54	-12.56
140	170	107	1.09	17.10	13.64	4.54	-4.54	-12.56
160	170	107	1.13	17.77	14.17	4.54	-4.54	-12.56
180	170	107	1.17	18.38	14.65	4.54	-4.54	-12.56
200	170	107	1.20	18.94	15.10	4.54	-4.54	-12.56
250	170	107	1.28	20.19	16.09	4.54	-4.54	-12.56
300	170	107	1.35	21.27	16.95	4.54	-4.54	-12.56
350	170	107	1.41	22.22	17.72	4.54	-4.54	-12.56
400	170	107	1.47	23.09	18.41	4.54	-4.54	-12.56
450	170	107	1.52	23.88	19.04	4.54	-4.54	-12.56
500	170	107	1.57	24.61	19.62	4.54	-4.54	-12.56
550	170	107	1.61	25.29	20.16	4.54	-4.54	-12.56

SIMPSON GUMPERTZ & HEGER
Engineering of Structures and Building Enclosures

SHEET NO. _____
PROJECT NO. 087237.10
DATE 1/23/09
BY AD
CHECKED BY _____

CLIENT Pacific Earthquake Engineering Research Center
SUBJECT Story Wind Forces in Long Normal Dir. for LA BRBF Bldg

B_Y = 170 ft
e_Y = 25.5 ft

Floor	Height	Cum Ht.	Wind Pressure Windward	Wind Pressure Leeward	Story Force	M_T
					(KIPS)	(KIP-IN)
Story40	13.5	544.5	20.10	-12.56	74.96	22937.76
Story39	13.5	531	19.95	-12.56	74.63	22836.78
Story38	13.5	517.5	19.81	-12.56	74.29	22732.74
Story37	13.5	504	19.66	-12.56	73.96	22631.76
Story36	13.5	490.5	19.51	-12.56	73.60	22521.60
Story35	13.5	477	19.35	-12.56	73.24	22411.44
Story34	13.5	463.5	19.19	-12.56	72.88	22301.28
Story33	13.5	450	19.04	-12.56	72.52	22191.12
Story32	13.5	436.5	18.87	-12.56	72.13	22071.78
Story31	13.5	423	18.70	-12.56	71.74	21952.44
Story30	13.5	409.5	18.53	-12.56	71.35	21833.10
Story29	13.5	396	18.35	-12.56	70.95	21710.70
Story28	13.5	382.5	18.16	-12.56	70.52	21579.12
Story27	13.5	369	17.98	-12.56	70.10	21450.60
Story26	13.5	355.5	17.79	-12.56	69.67	21319.02
Story25	13.5	342	17.60	-12.56	69.21	21178.26
Story24	13.5	328.5	17.39	-12.56	68.74	21034.44
Story23	13.5	315	17.18	-12.56	68.27	20890.62
Story22	13.5	301.5	16.98	-12.56	67.80	20746.80
Story21	13.5	288	16.75	-12.56	67.27	20584.62
Story20	13.5	274.5	16.51	-12.56	66.74	20422.44
Story19	13.5	261	16.28	-12.56	66.20	20257.20
Story18	13.5	247.5	16.04	-12.56	65.65	20088.90
Story17	13.5	234	15.78	-12.56	65.04	19902.24
Story16	13.5	220.5	15.51	-12.56	64.42	19712.52
Story15	13.5	207	15.24	-12.56	63.81	19525.86
Story14	13.5	193.5	14.95	-12.56	63.15	19323.90
Story13	13.5	180	14.65	-12.56	62.46	19112.76
Story12	13.5	166.5	14.32	-12.56	61.71	18883.26
Story11	13.5	153	13.98	-12.56	60.92	18641.52
Story10	13.5	139.5	13.62	-12.56	60.10	18390.60
Story9	13.5	126	13.23	-12.56	59.19	18112.14
Story8	13.5	112.5	12.80	-12.56	58.21	17812.26
Story7	13.5	99	12.35	-12.56	57.18	17497.08
Story6	13.5	85.5	11.84	-12.56	56.01	17139.06
Story5	13.5	72	11.27	-12.56	54.71	16741.26
Story4	13.5	58.5	10.62	-12.56	53.21	16282.26
Story3	13.5	45	9.85	-12.56	51.43	15737.58
Story2	13.5	31.5	8.89	-12.56	49.25	15070.50
Story1	18	18	7.57	-12.56	61.62	18855.72
Ground	12	0	7.20	-12.56	0.00	0.00
B1	12					
B2	12					
B3	12					
				Σ=	**2628.84**	

SIMPSON GUMPERTZ & HEGER
Engineering of Structures and Building Enclosures

SHEET NO.
PROJECT NO. 087237.10
DATE 1/23/09
BY AD
CHECKED BY

CLIENT Pacific Earthquake Engineering Research Center
SUBJECT Modal Information for Code Elastic Model of LA BRBF Bldg

Mode	Period	Perticipation Factor		Σ Participation Factor	
	(second)	Ux	Uy	Ux	Uy
1	5.05	0.00	34.40	0.00	34.40
2	3.62	43.98	0.00	43.98	34.40
3	3.53	0.00	0.00	43.98	34.40
4	1.38	0.00	15.06	43.98	49.46
5	1.19	10.99	0.00	54.96	49.46
6	1.15	0.00	0.00	54.96	49.46
7	0.72	0.00	6.71	54.96	56.17
8	0.65	3.32	0.00	58.28	56.17
9	0.64	0.00	0.00	58.28	56.17
10	0.47	0.00	2.90	58.28	59.07
11	0.44	1.71	0.00	59.99	59.07
12	0.44	0.00	0.00	59.99	59.07
13	0.35	0.00	1.51	59.99	60.58
14	0.34	1.19	0.00	61.18	60.58
15	0.33	0.00	0.00	61.18	60.58
16	0.27	0.89	0.00	62.06	60.58
17	0.27	0.00	1.11	62.06	61.70
18	0.26	0.00	0.00	62.06	61.70
19	0.23	0.79	0.00	62.85	61.70
20	0.23	0.00	1.17	62.85	62.86
21	0.21	0.00	0.00	62.85	62.86
22	0.19	0.74	0.00	63.59	62.86
23	0.19	0.00	1.16	63.59	64.02
24	0.18	0.00	0.00	63.59	64.02
25	0.17	0.85	0.00	64.44	64.02
26	0.17	0.00	1.15	64.44	65.17
27	0.16	0.00	0.00	64.44	65.17
28	0.15	0.00	1.36	64.44	66.53
29	0.15	1.00	0.00	65.45	66.53
30	0.14	0.00	0.00	65.45	66.53
31	0.13	1.43	0.00	66.88	66.53
32	0.13	0.00	1.41	66.88	67.95
33	0.13	0.00	0.00	66.88	67.95
34	0.12	2.55	0.00	69.43	67.95
35	0.12	0.00	3.32	69.43	71.26
36	0.12	0.00	0.00	69.43	71.26
37	0.11	6.45	0.00	75.88	71.26
38	0.11	0.00	7.95	75.88	79.21
39	0.11	0.00	0.00	75.88	79.21
40	0.11	10.94	0.00	86.82	79.21
41	0.11	0.00	9.10	86.82	88.32
42	0.10	5.31	0.00	92.13	88.32
43	0.10	0.00	3.88	92.13	92.20
44	0.10	0.00	0.00	92.13	92.20
45	0.09	1.74	0.00	93.87	92.20
46	0.09	0.00	1.65	93.87	93.85
47	0.09	0.00	0.00	93.87	93.85
48	0.09	0.57	0.00	94.44	93.85
49	0.09	0.00	0.68	94.44	94.53
50	0.08	0.00	0.00	94.44	94.53

SIMPSON GUMPERTZ & HEGER
Engineering of Structures and Building Enclosures

CLIENT Pacific Earthquake Engineering Research Center
SUBJECT Story Forces for Code Elastic Model of LA BRBF Bldg

SHEET NO.
PROJECT NO. 087237.10
DATE 1/23/09
BY AD
CHECKED BY

A12

V = 0.04335 W<-----(85% of Static Base Shear)
k = 2
S_{DS} = 1.145
S_{D1} = 0.52

											Equivalent Force		Diaphragm Design Force			
Floor	Height	Cumu Ht	Area	Perimeter	Seismic	Seismic	Addl.	Total Wt.	wi*hi^k	Cvx	Fx	Vx	Fpx	Fpx	Fpx	Fpx
					Flat Load	Line Load	Loading				(kips)	(kips)	(kips)	(kips)	(kips)	(kips)
					(psf)	(kip/ft)	(kips)						Eq(12.10-1)	Minimum	Maximum	Adopted
Story40	13.5	544.5	18190	554	94	0.203	100	1922.32	569930507.1	0.0753	**263.94**	263.94	263.94	440.21	880.42	**440.21**
Story39	13.5	531	18190	554	88	0.203		1713.18	483050509.9	0.0638	**223.71**	487.65	229.80	392.32	784.64	**392.32**
Story38	13.5	517.5	18190	554	88	0.203		1713.18	458800847	0.0606	**212.48**	700.13	224.25	392.32	784.64	**392.32**
Story37	13.5	504	18190	554	88	0.203		1713.18	435175638.9	0.0575	**201.54**	901.66	218.74	392.32	784.64	**392.32**
Story36	13.5	490.5	18190	554	88	0.203		1713.18	412174885.7	0.0545	**190.88**	1092.54	213.30	392.32	784.64	**392.32**
Story35	13.5	477	18190	554	88	0.203		1713.18	389798587.3	0.0515	**180.52**	1273.07	207.95	392.32	784.64	**392.32**
Story34	13.5	463.5	18190	554	88	0.203		1713.18	368046743.7	0.0486	**170.45**	1443.51	202.68	392.32	784.64	**392.32**
Story33	13.5	450	18190	554	88	0.203		1713.18	346919355	0.0459	**160.66**	1604.18	197.51	392.32	784.64	**392.32**
Story32	13.5	436.5	18190	554	92	0.203		1785.94	340279547.6	0.0450	**157.59**	1761.76	200.40	408.98	817.96	**408.98**
Story31	13.5	423	18190	554	92	0.203		1785.94	319556816.1	0.0422	**147.99**	1909.75	195.05	408.98	817.96	**408.98**
Story30	13.5	409.5	18190	554	92	0.203		1785.94	299485060.5	0.0396	**138.70**	2048.45	189.83	408.98	817.96	**408.98**
Story29	13.5	396	18190	554	92	0.203		1785.94	280064280.7	0.0370	**129.70**	2178.15	184.73	408.98	817.96	**408.98**
Story28	13.5	382.5	18190	554	92	0.203		1785.94	261294476.7	0.0345	**121.01**	2299.16	179.75	408.98	817.96	**408.98**
Story27	13.5	369	18190	554	96	0.203		1858.70	253082723	0.0334	**117.21**	2416.37	181.81	425.64	851.29	**425.64**
Story26	13.5	355.5	18190	554	96	0.203		1858.70	234903223.4	0.0310	**108.79**	2525.15	176.70	425.64	851.29	**425.64**
Story25	13.5	342	18190	554	96	0.203		1858.70	217401220.7	0.0287	**100.68**	2625.83	171.73	425.64	851.29	**425.64**
Story24	13.5	328.5	18190	554	96	0.203		1858.70	200576714.9	0.0265	**92.89**	2718.72	166.89	425.64	851.29	**425.64**
Story23	13.5	315	18190	554	102	0.203		1967.84	195259122.5	0.0258	**90.43**	2809.15	171.43	450.64	901.27	**450.64**
Story22	13.5	301.5	18190	554	102	0.203		1967.84	178881265.4	0.0236	**82.84**	2891.99	166.33	450.64	901.27	**450.64**
Story21	13.5	288	18190	554	102	0.203		1967.84	163220686.8	0.0216	**75.59**	2967.58	161.40	450.64	901.27	**450.64**
Story20	13.5	274.5	18190	554	102	0.203		1967.84	148277386.7	0.0196	**68.67**	3036.25	156.61	450.64	901.27	**450.64**
Story19	13.5	261	18190	554	107	0.203		2058.79	140246969.8	0.0185	**64.95**	3101.20	158.79	471.46	942.93	**471.46**
Story18	13.5	247.5	18190	554	107	0.203		2058.79	126113877.5	0.0167	**58.40**	3159.61	153.90	471.46	942.93	**471.46**
Story17	13.5	234	18190	554	107	0.203		2058.79	112731214.8	0.0149	**52.21**	3211.81	149.17	471.46	942.93	**471.46**
Story16	13.5	220.5	18190	554	107	0.203		2058.79	100098981.7	0.0132	**46.36**	3258.17	144.61	471.46	942.93	**471.46**
Story15	13.5	207	18190	554	107	0.203		2058.79	88217178.41	0.0117	**40.85**	3299.03	140.20	471.46	942.93	**471.46**
Story14	13.5	193.5	18190	554	115	0.203		2204.31	82534400.98	0.0109	**38.22**	3337.25	145.24	504.79	1009.57	**504.79**
Story13	13.5	180	18190	554	115	0.203		2204.31	71419708.8	0.0094	**33.08**	3370.32	140.56	504.79	1009.57	**504.79**
Story12	13.5	166.5	18190	554	115	0.203		2204.31	61108488.34	0.0081	**28.30**	3398.62	136.07	504.79	1009.57	**504.79**
Story11	13.5	153	18190	554	115	0.203		2204.31	51600739.61	0.0068	**23.90**	3422.52	131.75	504.79	1009.57	**504.79**
Story10	13.5	139.5	18190	554	115	0.203		2204.31	42896462.6	0.0057	**19.87**	3442.39	127.60	504.79	1009.57	**504.79**
Story9	13.5	126	18190	554	120	0.203		2295.26	36439579.51	0.0048	**16.88**	3459.26	128.56	525.61	1051.23	**525.61**
Story8	13.5	112.5	18190	554	120	0.203		2295.26	29049409.69	0.0038	**13.45**	3472.72	124.43	525.61	1051.23	**525.61**
Story7	13.5	99	18190	554	120	0.203		2295.26	22495862.86	0.0030	**10.42**	3483.13	120.49	525.61	1051.23	**525.61**
Story6	13.5	85.5	18190	554	120	0.203		2295.26	16778939.04	0.0022	**7.77**	3490.90	116.72	525.61	1051.23	**525.61**
Story5	13.5	72	18190	554	120	0.203		2295.26	11898638.21	0.0016	**5.51**	3496.41	113.12	525.61	1051.23	**525.61**
Story4	13.5	58.5	18190	554	127	0.203		2422.59	8290715.472	0.0011	**3.84**	3500.25	115.58	554.77	1109.55	**554.77**
Story3	13.5	45	18190	554	127	0.203		2422.59	4905748.8	0.0006	**2.27**	3502.53	111.96	554.77	1109.55	**554.77**
Story2	13.5	31.5	18190	554	127	0.203		2422.59	2403816.912	0.0003	**1.11**	3503.64	108.53	554.77	1109.55	**554.77**
Story1	18	18	18190	554	137	0.233		2621.11	849240.288	0.0001	**0.39**	3504.03	113.63	600.23	1200.47	**600.23**
Ground	0	0	49940		506.85			25312.09	0	0.0000	**0.00**					
B1	0	0	49940		86			4294.84	0	0.0000	**0.00**					
B2	0	0	49940		86			4294.84	0	0	**0.00**					
B3	0	0	49940		86			4294.84	0	0.0000	**0.00**					
								80831.20	7566259573.01		3504.03					

SIMPSON GUMPERTZ & HEGER
Engineering of Structures and Building Enclosures

CLIENT Pacific Earthquake Engineering Research Center
SUBJECT Redundancy Calculation for LA BRBF Bldg

SHEET NO.
PROJECT NO. 087237.10
DATE 1/23/09
BY AD
CHECKED BY

X Direction Motion

Model: 121908Model1Rddn_X

Case: **EQXPL**

Story	Height	Point	Disp	Drift	Point	Disp	Drift	Max/Avg-Drift	Verdict
Story40	13.5	52	18.981	0.372	54	23.401	0.580	1.218	Tor Irr
Story39	13.5	52	18.608	0.411	54	22.821	0.615	1.199	No Tor Irr
Story38	13.5	52	18.198	0.447	54	22.207	0.648	1.18	No Tor Irr
Story37	13.5	52	17.750	0.457	54	21.559	0.660	1.18	No Tor Irr
Story36	13.5	52	17.293	0.484	54	20.899	0.684	1.17	No Tor Irr
Story35	13.5	52	16.809	0.504	54	20.214	0.705	1.17	No Tor Irr
Story34	13.5	52	16.305	0.486	54	19.509	0.689	1.17	No Tor Irr
Story33	13.5	52	15.819	0.500	54	18.820	0.700	1.17	No Tor Irr
Story32	13.5	52	15.319	0.516	54	18.120	0.713	1.16	No Tor Irr
Story31	13.5	52	14.803	0.524	54	17.408	0.720	1.16	No Tor Irr
Story30	13.5	52	14.279	0.507	54	16.688	0.696	1.16	No Tor Irr
Story29	13.5	52	13.772	0.512	54	15.992	0.696	1.15	No Tor Irr
Story28	13.5	52	13.260	0.521	54	15.296	0.697	1.14	No Tor Irr
Story27	13.5	52	12.739	0.532	54	14.599	0.695	1.13	No Tor Irr
Story26	13.5	52	12.207	0.533	54	13.904	0.689	1.13	No Tor Irr
Story25	13.5	52	11.674	0.517	54	13.215	0.669	1.13	No Tor Irr
Story24	13.5	52	11.158	0.516	54	12.546	0.661	1.12	No Tor Irr
Story23	13.5	52	10.642	0.519	54	11.885	0.655	1.12	No Tor Irr
Story22	13.5	52	10.123	0.520	54	11.230	0.650	1.11	No Tor Irr
Story21	13.5	52	9.603	0.521	54	10.580	0.644	1.11	No Tor Irr
Story20	13.5	52	9.082	0.522	54	9.937	0.637	1.10	No Tor Irr
Story19	13.5	52	8.560	0.521	54	9.300	0.628	1.09	No Tor Irr
Story18	13.5	52	8.039	0.519	54	8.672	0.618	1.09	No Tor Irr
Story17	13.5	52	7.520	0.516	54	8.054	0.608	1.08	No Tor Irr
Story16	13.5	52	7.004	0.511	54	7.447	0.596	1.08	No Tor Irr
Story15	13.5	52	6.493	0.506	54	6.850	0.585	1.07	No Tor Irr
Story14	13.5	52	5.987	0.500	54	6.265	0.573	1.07	No Tor Irr
Story13	13.5	52	5.487	0.494	54	5.692	0.559	1.06	No Tor Irr
Story12	13.5	52	4.993	0.486	54	5.133	0.543	1.05	No Tor Irr
Story11	13.5	52	4.507	0.481	54	4.591	0.523	1.04	No Tor Irr
Story10	13.5	52	4.026	0.481	54	4.068	0.497	1.02	No Tor Irr
Story9	13.5	52	3.545	0.471	54	3.571	0.481	1.01	No Tor Irr
Story8	13.5	52	3.074	0.458	54	3.090	0.466	1.01	No Tor Irr
Story7	13.5	52	2.616	0.443	54	2.624	0.450	1.01	No Tor Irr
Story6	13.5	52	2.172	0.427	54	2.175	0.432	1.01	No Tor Irr
Story5	13.5	52	1.745	0.409	54	1.742	0.412	1.00	No Tor Irr
Story4	13.5	52	1.336	0.385	54	1.330	0.387	1.00	No Tor Irr
Story3	13.5	52	0.951	0.354	54	0.944	0.354	1.00	No Tor Irr
Story2	13.5	52	0.598	0.306	54	0.590	0.305	1.00	No Tor Irr
Story1	18	52	0.291	0.268	54	0.286	0.263	1.01	No Tor Irr
Ground	0	52	0.023	0.023	54	0.023	0.023	1.01	No Tor Irr

Case: **EQXMN**

Story	Height	Point	Disp	Drift	Point	Disp	Drift	Max/Avg-Drift	Verdict
Story40	13.5	52	15.793	0.270	54	28.202	0.740	1.465	Extr Tor Irr
Story39	13.5	52	15.522	0.303	54	27.461	0.781	1.441	Extr Tor Irr
Story38	13.5	52	15.219	0.336	54	26.680	0.820	1.418	Extr Tor Irr
Story37	13.5	52	14.883	0.342	54	25.860	0.837	1.419	Extr Tor Irr
Story36	13.5	52	14.540	0.364	54	25.023	0.866	1.408	Extr Tor Irr
Story35	13.5	52	14.176	0.385	54	24.157	0.887	1.395	Tor Irr
Story34	13.5	52	13.791	0.367	54	23.270	0.873	1.408	Extr Tor Irr
Story33	13.5	52	13.424	0.377	54	22.398	0.885	1.402	Extr Tor Irr
Story32	13.5	52	13.047	0.392	54	21.513	0.899	1.393	Tor Irr
Story31	13.5	52	12.655	0.401	54	20.613	0.904	1.386	Tor Irr
Story30	13.5	52	12.254	0.384	54	19.709	0.879	1.391	Tor Irr
Story29	13.5	52	11.870	0.389	54	18.830	0.877	1.385	Tor Irr
Story28	13.5	52	11.481	0.399	54	17.953	0.877	1.374	Tor Irr
Story27	13.5	52	11.081	0.416	54	17.076	0.867	1.351	Tor Irr
Story26	13.5	52	10.665	0.419	54	16.209	0.858	1.344	Tor Irr
Story25	13.5	52	10.246	0.405	54	15.351	0.835	1.347	Tor Irr
Story24	13.5	52	9.842	0.406	54	14.517	0.822	1.339	Tor Irr
Story23	13.5	52	9.436	0.413	54	13.694	0.811	1.325	Tor Irr
Story22	13.5	52	9.022	0.418	54	12.883	0.801	1.314	Tor Irr
Story21	13.5	52	8.604	0.421	54	12.083	0.790	1.305	Tor Irr
Story20	13.5	52	8.183	0.425	54	11.292	0.778	1.294	Tor Irr
Story19	13.5	52	7.758	0.431	54	10.514	0.761	1.277	Tor Irr
Story18	13.5	52	7.327	0.432	54	9.754	0.745	1.266	Tor Irr
Story17	13.5	52	6.895	0.432	54	9.009	0.729	1.256	Tor Irr
Story16	13.5	52	6.463	0.431	54	8.280	0.712	1.246	Tor Irr
Story15	13.5	52	6.032	0.429	54	7.568	0.695	1.236	Tor Irr
Story14	13.5	52	5.603	0.427	54	6.873	0.677	1.226	Tor Irr
Story13	13.5	52	5.176	0.425	54	6.196	0.657	1.215	Tor Irr
Story12	13.5	52	4.751	0.424	54	5.539	0.631	1.196	No Tor Irr
Story11	13.5	52	4.327	0.433	54	4.908	0.594	1.157	No Tor Irr
Story10	13.5	52	3.894	0.462	54	4.314	0.536	1.074	No Tor Irr
Story9	13.5	52	3.432	0.458	54	3.778	0.511	1.055	No Tor Irr
Story8	13.5	52	2.974	0.445	54	3.267	0.494	1.052	No Tor Irr
Story7	13.5	52	2.529	0.431	54	2.772	0.476	1.049	No Tor Irr
Story6	13.5	52	2.098	0.415	54	2.297	0.457	1.048	No Tor Irr
Story5	13.5	52	1.683	0.396	54	1.840	0.435	1.046	No Tor Irr
Story4	13.5	52	1.287	0.373	54	1.405	0.408	1.045	No Tor Irr
Story3	13.5	52	0.914	0.341	54	0.998	0.373	1.044	No Tor Irr
Story2	13.5	52	0.573	0.295	54	0.625	0.322	1.044	No Tor Irr
Story1	18	52	0.278	0.256	54	0.303	0.280	1.045	No Tor Irr
Ground	0	52	0.023	0.023	54	0.023	0.023	1.011	No Tor Irr

SIMPSON GUMPERTZ & HEGER
Engineering of Structures and Building Enclosures

CLIENT Pacific Earthquake Engineering Research Center
SUBJECT BRB Strength Check along Line 2 for LA BRBF Bldg

SHEET NO.
PROJECT NO. 087237.10
DATE 1/23/09
BY AD
CHECKED BY

V-target= 3626.26 kips(85% of Static Base Shear)
V-SPECX= 11595.55 kips Scale-X= 3.20
V-SPECY= 12103.43 kips Scale-Y= 3.34
SDS = 1.145
ρ-X dir = 1
ρ -Y dir = 1

Model: 121908Model1

| | | |

SIMPSON GUMPERTZ & HEGER
Engineering of Structures and Building Enclosures

CLIENT Pacific Earthquake Engineering Research Center
SUBJECT BRB Strength check along Line 2 for LA BRBF Bldg

SHEET NO. ____
PROJECT NO. 087237.10
DATE 1/23/09
BY AD
CHECKED BY ____

A15

V-target= 3626.26 kips(85% of Static Base Shear)
V-SPECX= 11995.55 kips Scale-X= 3.20
V-SPECY= 12103.43 kips Scale-Y= 3.34
SDS = 1.145
ρ-X dir = 1
ρ-Y dir = 1

Model: 121908Model1

| | | |

SIMPSON GUMPERTZ & HEGER
Engineering of Structures and Building Enclosures

CLIENT Pacific Earthquake Engineering Research Center
SUBJECT BRB Strength Check along Line 2 for LA BRBF Bldg

SHEET NO.
PROJECT NO. 087237.10
DATE 1/23/09
BY AD
CHECKED BY

V-target= 3626.26 kips(85% of Static Base Shear)
V-SPECX= 11595.55 kips Scale-X= 3.20
V-SPECY= 12103.43 kips Scale-Y= 3.34
SDS = 1.145
ρ-X dir = 1
ρ-Y dir = 1

Model: 121908Model1

0.671	0.671	0.671	0.671	0.671	0.671	0.671	0.671
1	0.3	-1	-0.3	0.3	1	-1	-0.3
0.3	1	0.3	1	-1	-0.3	-0.3	-1

Story	ETABS #	Section	Capacity	Dead	Live	WindFX	WindMTX	WindFY	WindMTY	SpecX	SpecY								Maximum Axial Loads Tension	Compression	DCR	Status
Story40	D21	A6	205	-2.48	0.00	0.00	5.15	6.82	14.84	74.07	408.13	58.2	127.6	11.9	113.7	-117.0	-15.2	-61.5	-130.9	127.56	-132.78	0.65	OK
Story39	D21	A6	205	-2.51	0.00	0.00	3.57	13.70	10.31	47.92	405.05	49.7	124.2	19.7	115.2	-118.5	-23.1	-53.1	-127.5	124.17	-129.44	0.63	OK
Story38	D21	A6	205	-2.54	0.00	0.00	2.42	19.54	7.00	28.59	439.71	46.8	132.7	28.9	127.4	-130.8	-32.3	-50.2	-136.1	132.72	-138.05	0.67	OK
Story37	D21	A6	205	-2.56	0.00	0.00	1.40	26.19	4.08	14.89	432.02	41.8	129.1	32.5	126.3	-129.8	-35.9	-45.2	-132.6	129.11	-134.49	0.66	OK
Story36	D21	A6	205	-2.59	0.00	0.00	-0.06	31.30	-0.10	8.41	429.79	39.5	127.8	34.3	126.2	-129.7	-37.7	-43.0	-131.3	127.82	-133.26	0.65	OK
Story35	D21	A9	308	-2.73	0.00	0.00	-0.87	40.30	-2.42	18.88	493.91	48.5	147.9	36.7	144.4	-148.0	-40.3	-52.1	-151.6	147.92	-153.65	0.50	OK
Story34	D21	A9	308	-2.76	0.00	0.00	-1.40	44.44	-3.94	27.33	479.36	49.8	144.3	32.7	139.2	-142.9	-36.4	-53.5	-148.0	144.33	-150.13	0.49	OK
Story33	D21	A9	308	-2.79	0.00	0.00	-3.00	50.40	-8.53	50.09	517.73	60.3	157.9	29.0	148.5	-152.3	-32.7	-64.1	-161.7	157.94	-163.80	0.53	OK
Story32	D21	A9	308	-2.82	0.00	0.00	-4.56	54.49	-13.02	73.38	542.35	69.8	167.5	23.9	153.7	-157.5	-27.7	-73.6	-171.3	167.48	-173.40	0.56	OK
Story31	D21	A9	308	-2.85	0.00	0.00	-4.81	52.05	-13.75	77.99	508.20	68.2	157.7	19.4	143.0	-146.9	-23.2	-72.0	-161.5	157.67	-163.64	0.53	OK
Story30	D21	A9	308	-2.87	0.00	0.00	-5.33	56.61	-15.25	84.31	524.27	71.6	163.1	18.8	147.2	-151.1	-22.7	-75.4	-166.9	163.06	-169.09	0.55	OK
Story29	D21	A9	308	-2.90	0.00	0.00	-6.83	62.85	-19.55	106.06	572.16	82.6	179.4	16.3	159.5	-163.4	-20.2	-86.5	-183.3	179.43	-185.52	0.60	OK
Story28	D21	A9	308	-2.93	0.00	0.00	-8.03	67.47	-23.01	123.81	601.21	90.8	189.8	13.4	166.5	-170.5	-17.3	-94.7	-193.7	189.78	-195.93	0.64	OK
Story27	D21	A15.5	530	-2.94	0.00	0.00	-12.25	110.39	-35.16	187.73	916.40	139.1	290.2	21.7	255.0	-258.9	-25.6	-143.0	-294.1	290.20	-296.37	0.56	OK
Story26	D21	A15.5	530	-2.96	0.00	0.00	-13.58	116.82	-38.99	206.87	939.73	147.2	299.0	17.8	260.2	-264.1	-21.8	-151.1	-302.9	298.97	-305.19	0.58	OK
Story25	D21	A15.5	530	-2.99	0.00	0.00	-14.75	126.40	-42.38	224.11	977.13	155.9	311.8	15.7	269.7	-273.7	-19.7	-159.9	-315.8	311.77	-318.06	0.60	OK
Story24	D21	A15.5	530	-3.02	0.00	0.00	-16.41	135.74	-47.16	248.37	1022.60	167.6	327.7	12.2	281.0	-285.1	-16.3	-171.6	-331.7	327.65	-333.99	0.63	OK
Story23	D21	A18.5	633	-2.99	0.00	0.00	-19.97	165.11	-57.42	301.79	1206.44	200.8	387.8	12.1	331.1	-335.1	-16.1	-204.8	-391.8	387.76	-394.04	0.62	OK
Story22	D21	A18.5	633	-3.02	0.00	0.00	-22.03	176.00	-63.39	333.64	1266.12	216.1	408.6	7.4	346.0	-350.1	-11.5	-220.2	-412.7	408.61	-414.95	0.66	OK
Story21	D21	A18.5	633	-2.93	0.00	0.00	-23.92	184.25	-68.85	362.35	1320.93	230.1	427.8	3.4	359.8	-363.7	-7.4	-234.0	-431.7	427.79	-433.94	0.69	OK
Story20	D21	A18.5	633	-2.95	0.00	0.00	-25.21	191.83	-72.60	382.17	1354.99	239.3	439.8	0.3	368.1	-372.1	-4.3	-243.3	-443.8	439.84	-446.04	0.70	OK
Story19	D21	A25	855	-2.95	0.00	0.00	-31.75	250.74	-91.48	482.88	1724.45	304.0	560.0	2.0	469.4	-473.3	-6.0	-308.0	-563.9	559.98	-566.17	0.66	OK
Story18	D21	A25	855	-2.98	0.00	0.00	-33.30	258.09	-96.00	508.21	1781.60	317.1	579.5	-0.8	484.1	-488.1	-3.2	-321.1	-583.5	579.46	-585.71	0.69	OK
Story17	D21	A25	855	-2.94	0.00	0.00	-35.55	269.41	-102.51	543.60	1875.35	336.6	610.9	-3.4	508.9	-512.8	-0.5	-340.5	-614.8	610.90	-617.06	0.72	OK
Story16	D21	A25	855	-2.96	0.00	0.00	-38.35	286.04	-110.63	587.66	1995.09	361.1	650.9	-6.4	540.6	-544.6	2.5	-365.1	-654.9	650.89	-657.10	0.77	OK
Story15	D21	A25	855	-2.89	0.00	0.00	-40.48	297.65	-116.84	621.36	2097.27	380.9	684.7	-7.8	568.1	-572.0	3.9	-384.8	-688.6	684.71	-690.78	0.81	OK
Story14	D21	A25	855	-2.92	0.00	0.00	-43.13	313.02	-124.55	663.87	2224.06	405.6	726.7	-9.7	602.1	-606.0	5.8	-409.5	-730.6	726.67	-732.79	0.86	OK
Story13	D21	A25	855	-2.94	0.00	0.00	-45.20	323.11	-130.58	698.01	2331.22	425.8	762.0	-10.7	631.0	-634.9	6.8	-429.8	-765.9	761.96	-768.14	0.90	OK
Story12	D21	A25	855	-2.97	0.00	0.00	-44.04	312.55	-127.31	682.78	2314.95	419.6	755.6	-7.4	627.5	-631.5	3.5	-423.6	-759.6	755.64	-761.87	0.89	OK
Story11	D21	A25	855	-2.93	0.00	0.00	-30.69	238.17	-88.89	478.83	1853.52	314.4	598.3	14.9	508.4	-512.4	-18.8	-318.3	-602.2	598.28	-604.44	0.71	OK
Story10	D21	A15.5	530	-2.88	0.00	0.00	-4.31	-33.28	-12.18	62.57	608.73	72.3	186.3	33.2	174.6	-178.4	-37.1	-76.2	-190.2	186.31	-192.37	0.36	OK
Story9	D21	A15.5	530	-2.84	0.00	0.00	-5.86	-17.60	-16.64	85.33	666.67	84.7	205.8	31.3	189.8	-193.6	-35.1	-88.5	-209.6	205.84	-211.80	0.40	OK
Story8	D21	A15.5	530	-2.86	0.00	0.00	-2.62	-33.18	-7.27	34.11	610.41	63.6	184.2	42.3	177.8	-181.6	-46.1	-67.5	-188.0	184.16	-190.17	0.36	OK
Story7	D21	A15.5	530	-2.82	0.00	0.00	-0.08	-46.56	0.06	6.15	586.59	52.8	174.4	48.9	173.3	-177.1	-52.7	-56.5	-178.2	174.43	-180.35	0.34	OK
Story6	D21	A15.5	530	-2.84	0.00	0.00	2.71	-62.17	8.14	50.60	686.70	75.6	208.6	44.0	199.1	-202.9	-47.8	-79.5	-212.4	208.58	-214.55	0.40	OK
Story5	D21	A15.5	530	-2.86	0.00	0.00	5.36	-76.94	15.82	92.92	782.03	97.4	241.1	39.3	223.7	-227.5	-43.2	-101.3	-244.9	241.10	-247.11	0.47	OK
Story4	D21	A15.5	530	-2.89	0.00	0.00	7.73	-89.32	22.67	130.69	862.58	116.5	268.8	34.7	244.2	-248.1	-38.6	-120.3	-272.6	268.76	-274.82	0.52	OK
Story3	D21	A15.5	530	-2.85	0.00	0.00	9.60	-97.13	28.08	160.69	917.31	130.8	288.0	30.3	257.8	-261.7	-34.1	-134.6	-291.8	288.00	-293.98	0.55	OK
Story2	D21	A15.5	530	-2.87	0.00	0.00	10.94	-98.63	31.97	182.24	931.67	138.8	294.3	24.8	260.1	-264.0	-28.7	-142.7	-298.2	294.31	-300.33	0.57	OK
Story1	D21	A15.5	530	-2.74	0.00	0.00	8.70	-70.14	25.44	145.17	703.64	106.8	222.6	16.0	195.4	-199.0	-19.7	-110.5	-226.3	222.60	-228.34	0.43	OK
Ground	D21	A15.5	530	-3.03	0.00	0.00	-4.98	32.99	-14.34	75.51	240.00	43.2	77.0	-4.1	62.8	-66.9	0.0	-47.2	-81.0	76.96	-83.32	0.16	OK
B1	D21	A15.5	530	-2.99	0.00	0.00	-3.32	22.92	-9.56	49.69	166.48	28.5	52.5	-2.6	43.2	-47.2	-1.4	-32.5	-56.5	52.54	-58.81	0.11	OK
B2	D21	A15.5	530	-3.01	0.00	0.00	-1.61	9.90	-4.64	23.49	89.54	13.4	27.0	-1.3	22.6	-26.6	-2.7	-17.4	-31.1	27.01	-33.34	0.06	OK
B3	D21	A15.5	530	-3.04	0.00	0.00	0.13	-4.43	0.37	3.48	43.53	3.0	11.3	0.8	10.7	-14.8	-4.9	-7.0	-15.4	11.33	-17.71	0.03	OK

Story	ETABS #	Section	Capacity	Dead	Live	WindFX	WindMTX	WindFY	WindMTY	SpecX	SpecY								Maximum Axial Loads Tension	Compression	DCR	Status
Story40	D22	A6	205	-2.48	0.00	0.00	-5.15	-6.82	-14.84	74.07	408.13	58.2	127.6	11.9	113.7	-117.0	-15.2	-61.5	-130.9	127.56	-132.78	0.65	OK
Story39	D22	A6	205	-2.51	0.00	0.00	-3.57	-13.70	-10.31	47.92	405.05	49.7	124.2	19.7	115.2	-118.5	-23.1	-53.1	-127.5	124.17	-129.44	0.63	OK
Story38	D22	A6	205	-2.54	0.00	0.00	-2.42	-19.54	-7.00	28.59	439.71	46.8	132.7	28.9	127.4	-130.8	-32.3	-50.2	-136.1	132.72	-138.05	0.67	OK
Story37	D22	A6	205	-2.56	0.00	0.00	-1.40	-26.19	-4.08	14.89	432.02	41.8	129.1	32.5	126.3	-129.8	-35.9	-45.2	-132.6	129.11	-134.49	0.66	OK
Story36	D22	A6	205	-2.59	0.00	0.00	0.06	-31.30	0.10	8.41	429.79	39.5	127.8	34.3	126.2	-129.7	-37.7	-43.0	-131.3	127.82	-133.26	0.65	OK
Story35	D22	A9	308	-2.73	0.00	0.00	0.87	-40.30	2.42	18.88	493.91	48.5	147.9	36.7	144.4	-148.0	-40.3	-52.1	-151.6	147.92	-153.65	0.50	OK
Story34	D22	A9	308	-2.76	0.00	0.00	1.40	-44.44	3.94	27.33	479.36	49.8	144.3	32.7	139.2	-142.9	-36.4	-53.5	-148.0	144.33	-150.13	0.49	OK
Story33	D22	A9	308	-2.79	0.00	0.00	3.00	-50.40	8.53	50.09	517.73	60.3	157.9	29.0	148.5	-152.3	-32.7	-64.1	-161.7	157.94	-163.80	0.53	OK
Story32	D22	A9	308	-2.82	0.00	0.00	4.56	-54.49	13.02	73.38	542.35	69.8	167.5	23.9	153.7	-157.5	-27.7	-73.6	-171.3	167.48	-173.40	0.56	OK
Story31	D22	A9	308	-2.85	0.00	0.00	4.81	-52.05	13.75	77.99	508.20	68.2	157.7	19.4	143.0	-146.9	-23.2	-72.0	-161.5	157.67	-163.64	0.53	OK
Story30	D22	A9	308	-2.87	0.00	0.00	5.33	-56.61	15.25	84.31	524.27	71.6	163.1	18.8	147.2	-151.1	-22.7	-75.4	-166.9	163.06	-169.09	0.55	OK
Story29	D22	A9	308	-2.90	0.00	0.00	6.83	-62.85	19.55	106.06	572.16	82.6	179.4	16.3	159.5	-163.4	-20.2	-86.5	-183.3	179.43	-185.52	0.60	OK
Story28	D22	A9	308	-2.93	0.00	0.00	8.03	-67.47	23.01	123.81	601.21	90.8	189.8	13.4	166.5	-170.5	-17.3	-94.7	-193.7	189.78	-195.93	0.64	OK
Story27	D22	A15.5	530	-2.94	0.00	0.00	12.25	-110.39	35.16	187.73	916.40	139.1	290.2	21.7	255.0	-258.9	-25.6	-143.0	-294.1	290.20	-296.37	0.56	OK
Story26	D22	A15.5	530	-2.96	0.00	0.00	13.58	-116.82	38.99	206.87	939.73	147.2	299.0	17.8	260.2	-264.1	-21.8	-151.1	-302.9	298.97	-305.19	0.58	OK
Story25	D22	A15.5	530	-2.99	0.00	0.00	14.75	-126.40	42.38	224.11	977.13	155.9	311.8	15.7	269.7	-273.7	-19.7	-159.9	-315.8	311.77	-318.06	0.60	OK
Story24	D22	A15.5	530	-3.02	0.00	0.00	16.41	-135.74	47.16	248.37	1022.60	167.6	327.7	12.2	281.0	-285.1	-16.3	-171.6	-331.7	327.65	-333.99	0.63	OK
Story23	D22	A18.5	633	-2.99	0.00	0.00	19.97	-165.11	57.42	301.79	1206.44	200.8	387.8	12.1	331.1	-335.1	-16.1	-204.8	-391.8	387.76	-394.04	0.62	OK
Story22	D22	A18.5	633	-3.02	0.00	0.00	22.03	-176.00	63.39	333.64	1266.12	216.1	408.6	7.4	346.0	-350.1	-11.5	-220.2	-412.7	408.61	-414.95	0.66	OK
Story21	D22	A18.5	633	-2.93	0.00	0.00	23.92	-184.25	68.85	362.35	1320.93	230.1	427.8	3.4	359.8	-363.7	-7.4	-234.0	-431.7	427.79	-433.94	0.69	OK
Story20	D22	A18.5	633	-2.95	0.00	0.00	25.21	-191.83	72.60	382.17	1354.99	239.3	439.8	0.3	368.1	-372.1	-4.3	-243.3	-443.8	439.84	-446.04	0.70	OK
Story19	D22	A25	855	-2.95	0.00	0.00	31.75	-250.74	91.48	482.88	1724.45	304.0	560.0	2.0	469.4	-473.3	-6.0	-308.0	-563.9	559.98	-566.17	0.66	OK
Story18	D22	A25	855	-2.98	0.00	0.00	33.30	-258.09	96.00	508.21	1781.60	317.1	579.5	-0.8	484.1	-488.1	-3.2	-321.1	-583.5	579.46	-585.71	0.69	OK
Story17	D22	A25	855	-2.94	0.00	0.00	35.55	-269.41	102.51	543.60	1875.35	336.6	610.9	-3.4	508.9	-512.8	-0.5	-340.5	-614.8	610.90	-617.06	0.72	OK
Story16	D22	A25	855	-2.96	0.00	0.00	38.35	-286.04	110.63	587.66	1995.09	361.1	650.9	-6.4	540.6	-544.6	2.5	-365.1	-654.9	650.89	-657.10	0.77	OK
Story15	D22	A25	855	-2.89	0.00	0.00	40.48	-297.65	116.84	621.36	2097.27	380.9	684.7	-7.8	568.1	-572.0	3.9	-384.8	-688.6	684.71	-690.78	0.81	OK
Story14	D22	A25	855	-2.92	0.00	0.00	43.13	-313.02	124.55	663.87	2224.06	405.6	726.7	-9.7	602.1	-606.0	5.8	-409.5	-730.6	726.67	-732.79	0.86	OK
Story13	D22	A25	855	-2.94	0.00	0.00	45.20	-323.11	130.58	698.01	2331.22	425.8	762.0	-10.7	631.0	-634.9	6.8	-429.8	-765.9	761.96	-768.14	0.90	OK
Story12	D22	A25	855	-2.97	0.00	0.00	44.04	-312.55	127.31	682.78	2314.95	419.6	755.6	-7.4	627.5	-631.5	3.5	-423.6	-759.6	755.64	-761.87	0.89	OK
Story11	D22	A25	855	-2.93	0.00	0.00	30.69	-238.17	88.89	478.83	1853.52	314.4	598.3	14.9	508.4	-512.4	-18.8	-318.3	-602.2	598.28	-604.44	0.71	OK
Story10	D22	A15.5	530	-2.88	0.00	0.00	-4.31	-33.28	-12.18	62.57	608.73	72.3	186.3	33.2	174.6	-178.4	-37.1	-76.2	-190.2	186.31	-192.37	0.36	OK
Story9	D22	A15.5	530	-2.84	0.00	0.00	-5.86	-17.60	-16.64	85.33	666.67	84.7	205.8	31.3	189.8	-193.6	-35.1	-88.5	-209.6	205.84	-211.80	0.40	OK
Story8	D22	A15.5	530	-2.86	0.00	0.00	-2.62	-33.18	-7.27	34.11	610.41	63.6	184.2	42.3	177.8	-181.6	-46.1	-67.5	-188.0	184.16	-190.17	0.36	OK
Story7	D22	A15.5	530	-2.82	0.00	0.00	-0.08	-46.56	0.06	6.15	586.59	52.8	174.4	48.9	173.3	-177.1	-52.7	-56.5	-178.2	174.43	-180.35	0.34	OK
Story6	D22	A15.5	530	-2.84	0.00	0.00	2.71	-62.17	8.14	50.60	686.70	75.6	208.6	44.0	199.1	-202.9	-47.8	-79.5	-212.4	208.58	-214.55	0.40	OK
Story5	D22	A15.5	530	-2.86	0.00	0.00	5.36	-76.94	15.82	92.92	782.03	97.4	241.1	39.3	223.7	-227.5	-43.2	-101.3	-244.9	241.10	-247.11	0.47	OK
Story4	D22	A15.5	530	-2.89	0.00	0.00	7.73	-89.32	22.67	130.69	862.58	116.5	268.8	34.7	244.2	-248.1	-38.6	-120.3	-272.6	268.76	-274.82	0.52	OK
Story3	D22	A15.5	530	-2.85	0.00	0.00	9.60	-97.13	28.08	160.69	917.31	130.8	288.0	30.3	257.8	-261.7	-34.1	-134.6	-291.8	288.00	-293.98	0.55	OK
Story2	D22	A15.5	530	-2.87	0.00	0.00	10.94	-98.63	31.97	182.24	931.67	138.8	294.3	24.8	260.1	-264.0	-28.7	-142.7	-298.2	294.31	-300.33	0.57	OK
Story1	D22	A15.5	530	-2.74	0.00	0.00	8.70	-70.14	25.44	145.17	703.64	106.8	222.6	16.0	195.4	-199.0	-19.7	-110.5	-226.3	222.60	-228.34	0.43	OK
Ground	D22	A15.5	530	-3.03	0.00	0.00	-4.98	32.99	-14.34	75.51	240.00	43.2	77.0	-4.1	62.8	-66.9	0.0	-47.2	-81.0	76.96	-83.32	0.16	OK
B1	D22	A15.5	530	-2.99	0.00	0.00	-3.32	22.92	-9.56	49.69	166.48	28.5	52.5	-2.6	43.2	-47.2	-1.4	-32.5	-56.5	52.54	-58.81	0.11	OK
B2	D22	A15.5	530	-3.01	0.00	0.00	-1.61	9.90	-4.64	23.49	89.54	13.4	27.0	-1.3	22.6	-26.6	-2.7	-17.4	-31.1	27.01	-33.34	0.06	OK
B3	D22	A15.5	530	-3.04	0.00	0.00	0.13	-4.43	0.37	3.48	43.53	3.0	11.3	0.8	10.7	-14.8	-4.9	-7.0	-15.4	11.33	-17.71	0.03	OK

Story	ETABS #	Section	Capacity	Dead	Live	WindFX	WindMTX	WindFY	WindMTY	SpecX	SpecY								Maximum Axial Loads Tension	Compression	DCR	Status
Story10	D25	A25	855	-24.39	0.00	0.00	-46.26	464.01	-133.49	716.18	2527.20	434.8	808.0	-13.2	673.6	-706.3	-19.5	-467.5	-840.7	807.99	-859.21	1.00	Say OK
Story9	D25	A25	855	-22.22	0.00	0.00	-35.54	371.82	-102.65	552.63	2010.14	338.6	639.2	-7.1	535.5	-565.3	-22.8	-368.4	-669.0	639.18	-685.86	0.80	OK
Story8	D25	A25	855	-20.54	0.00	0.00	-33.30	338.26	-96.23	519.73	1881.96	317.9	598.8	-7.2	501.3	-528.9	-20.4	-345.5	-626.4	598.83	-641.96	0.75	OK
Story7	D25	A27	923	-20.05	0.00	0.00	-33.78	336.90	-97.68	529.39	1925.81	325.2	613.2	-5.9	513.9	-540.8	-21.0	-352.1	-640.1	613.20	-655.30	0.71	OK
Story6	D25	A27	923	-18.72	0.00	0.00	-32.99	320.87	-95.45	519.43	1897.58	320.4	604.7	-4.4	507.2	-532.4	-20.7	-345.6	-629.8	604.70	-644.00	0.70	OK
Story5	D25	A27	923	-17.26	0.00	0.00	-32.46	307.38	-93.97	513.55	1887.89	318.7	602.2	-2.5	505.9	-529.0	-20.7	-341.9	-625.4	602.22	-638.46	0.69	OK
Story4	D25	A27	923	-16.06	0.00	0.00	-32.21	296.63	-93.32	512.03	1893.13	319.5	604.5	-0.7	508.4	-529.9	-20.8	-341.1	-626.0	604.46	-638.18	0.69	OK
Story3	D25	A27	923	-14.68	0.00	0.00	-31.74	282.65	-92.02	506.94	1877.38	317.4	600.2	0.4	505.1	-524.8	-20.1	-337.1	-619.9	600.19	-631.01	0.68	OK
Story2	D25	A27	923	-13.51	0.00	0.00	-30.96	263.12	-89.84	496.77	1825.15	310.3	584.4	-0.4	491.2	-509.3	-17.8	-328.5	-602.5	584.36	-612.74	0.66	OK
Story1	D25	A27	923	-10.82	0.00	0.00	-25.54	203.71	-74.20	411.69	1492.10	255.6	478.4	-1.9	401.2	-415.7	-12.6	-270.1	-492.9	478.41	-501.12	0.54	OK
Ground	D25	A18.5	633	-8.53	0.00	0.00	0.80	0.36	2.33	11.81	59.84	3.4	13.3	-4.0	11.1	-22.5	-7.4	-14.8	-24.8	13.32	-31.22	0.05	OK
B1	D25	A18.5	633	-7.48	0.00	0.00	0.54	-0.80	1.57	7.31	55.86	2.3	12.4	-2.3	11.0	-21.1	-7.8	-12.3	-22.4	12.41	-28.11	0.04	OK
B2	D25	A18.5	633	-6.51	0.00	0.00	0.19	1.49	0.56	1.83	39.45	-0.2	7.6	-1.4	7.3	-16.0	-7.3	-8.5	-16.4	7.63	-21.29	0.03	OK
B3	D25	A18.5	633	-5.55	0.00	0.00	-0.20	5.26	-0.57	4.65	48.45	2.1	11.2	-0.8	10.4	-17.8	-6.6	-9.5	-18.7	11.23	-22.89	0.04	OK

SIMPSON GUMPERTZ & HEGER
Engineering of Structures and Building Enclosures

CLIENT Pacific Earthquake Engineering Research Center
SUBJECT BRB Strength Check along Line 2 for LA BRBF Bldg

SHEET NO.
PROJECT NO. 087237.10
DATE 1/23/09
BY AD
CHECKED BY

Story	ETABS #	Section	Capacity	Dead	Live	WindFX	WindMTX	WindFY	WindMTY	SpecX	SpecY																													
Story10	D26	A25	855	13.78	0.00	0.00	46.04	-462.24	132.87	712.85	2516.92	16.5	16.5	-723.0	756.1	-538.1	571.2	-538.1	571.2	71.8	-38.7	71.8	-38.7	-378.7	-697.6	730.7	411.8	-238.7	-321.6	-238.7	-321.6	-478.1	594.1	354.7	271.8	354.7	271.8	-561.0	511.1	-561.0
Story9	D26	A25	855	11.63	0.00	0.00	35.36	-370.11	102.12	549.78	2000.87	14.0	14.0	-578.2	606.1	-430.2	458.1	-430.2	458.1	56.4	-28.5	56.4	-28.5	-307.6	-557.7	580.6	335.5	-195.6	-259.3	-195.6	-259.3	-379.6	471.2	287.2	223.5	287.2	223.5	-443.3	407.5	-443.3
Story8	D26	A25	855	9.91	0.00	0.00	33.10	-336.37	95.64	516.59	1871.75	11.9	11.9	-526.3	550.1	-391.8	415.5	-391.8	415.5	51.6	-27.8	51.6	-27.8	-277.0	-506.5	530.3	300.8	-175.1	-234.8	-175.1	-234.8	-347.5	430.9	258.6	198.9	258.6	198.9	-407.1	371.2	-407.1
Story7	D26	A27	923	9.48	0.00	0.00	33.60	-335.13	97.14	526.47	1916.35	11.4	11.4	-524.8	547.6	-390.8	413.5	-390.8	413.5	51.7	-28.9	51.7	-28.9	-274.2	-507.3	530.1	297.0	-172.7	-233.3	-172.7	-233.3	-347.7	431.0	256.0	195.5	256.0	195.5	-408.3	370.5	-408.3
Story6	D26	A27	923	8.12	0.00	0.00	32.79	-318.99	94.87	516.33	1887.55	9.7	9.7	-500.6	520.1	-373.0	392.5	-373.0	392.5	49.1	-29.6	49.1	-29.6	-259.2	-486.9	506.4	278.7	-162.6	-221.7	-162.6	-221.7	-333.5	412.1	241.2	182.1	241.2	182.1	-392.6	353.0	-392.6
Story5	D26	A27	923	6.69	0.00	0.00	32.27	-305.57	93.41	510.53	1878.25	8.0	8.0	-480.9	496.9	-358.6	374.7	-358.6	374.7	46.8	-30.7	46.8	-30.7	-246.6	-470.7	486.8	262.6	-154.0	-212.1	-154.0	-212.1	-322.3	396.5	228.2	170.1	228.2	170.1	-380.4	338.4	-380.4
Story4	D26	A27	923	5.47	0.00	0.00	32.01	-294.73	92.73	508.84	1882.96	6.6	6.6	-465.0	478.1	-347.1	360.2	-347.1	360.2	45.0	-31.8	45.0	-31.8	-235.8	-458.4	471.5	249.0	-146.6	-204.2	-146.6	-204.2	-313.6	384.4	217.3	159.7	217.3	159.7	-371.3	326.8	-371.3
Story3	D26	A27	923	4.18	0.00	0.00	31.55	-280.93	91.49	504.04	1868.15	5.0	5.0	-444.5	454.5	-332.1	342.1	-332.1	342.1	42.9	-32.8	42.9	-32.8	-222.3	-441.9	451.9	232.4	-137.2	-194.1	-137.2	-194.1	-302.0	368.9	204.1	147.2	204.1	147.2	-358.9	312.1	-358.9
Story2	D26	A27	923	2.99	0.00	0.00	30.76	-261.35	89.28	493.74	1815.51	3.6	3.6	-414.6	421.7	-310.0	317.2	-310.0	317.2	40.5	-33.3	40.5	-33.3	-202.9	-417.2	424.3	210.1	-123.7	-179.1	-123.7	-179.1	-284.5	347.1	186.3	130.9	186.3	130.9	-340.0	291.7	-340.0
Story1	D26	A27	923	1.96	0.00	0.00	25.36	-202.06	73.68	408.85	1483.35	2.4	2.4	-320.9	325.7	-240.1	244.8	-240.1	244.8	32.8	-28.1	32.8	-28.1	-151.7	-328.5	333.2	156.4	-90.4	-136.1	-90.4	-136.1	-223.2	273.6	140.9	95.2	140.9	95.2	-268.9	227.9	-268.9
Ground	D26	A18.5	633	-2.64	0.00	0.00	-0.95	1.03	-2.77	14.21	64.52	-3.2	-3.2	-1.5	-4.8	-1.9	-4.4	-1.9	-4.4	-4.3	-2.0	-4.3	-2.0	-5.3	1.4	-7.7	-1.1	-5.6	-3.9	-5.6	-3.9	-0.6	-7.5	-2.5	-0.7	-2.5	-0.7	1.1	-5.7	1.1
B1	D26	A18.5	633	-3.59	0.00	0.00	-0.66	1.94	-1.93	9.25	59.65	-4.3	-4.3	-1.2	-7.4	-2.0	-6.6	-2.0	-6.6	-5.1	-3.5	-5.1	-3.5	-4.3	0.3	-9.0	-4.3	-4.9	-3.7	-4.9	-3.7	-1.4	-8.4	-4.9	-3.7	-4.9	-3.7	-0.2	-7.2	-0.2
B2	D26	A18.5	633	-4.58	0.00	0.00	-0.32	-0.36	-0.92	3.74	42.45	-5.5	-5.5	-6.1	-4.9	-5.9	-5.1	-5.9	-5.1	-5.9	-5.1	-5.9	-5.1	-7.0	-4.8	-6.2	-4.0	-6.9	-6.4	-6.9	-6.4	-5.3	-6.3	-4.6	-4.1	-4.6	-4.1	-4.7	-5.7	-4.7
B3	D26	A18.5	633	-5.55	0.00	0.00	0.07	-4.13	0.22	2.73	43.91	-6.7	-6.7	-13.3	-0.1	-11.6	-1.7	-11.6	-1.7	-6.6	-6.7	-6.6	-6.7	-11.4	-11.9	-1.4	-2.0	-10.1	-10.3	-10.1	-10.3	-10.5	-2.7	-3.1	-3.2	-3.1	-3.2	-10.6	-2.8	-10.6

Story	ETABS #	Section	Capacity	Dead	Live	WindFX	WindMTX	WindFY	WindMTY	SpecX	SpecY																													
Story10	D27	A25	855	13.78	0.00	0.00	-46.04	462.24	-132.87	712.85	2516.92	16.5	16.5	756.1	-723.0	571.2	-538.1	571.2	-538.1	-38.7	71.8	-38.7	71.8	411.8	730.7	-697.6	-378.7	271.8	354.7	271.8	354.7	511.1	-561.0	-321.6	-238.7	-321.6	-238.7	594.1	-478.1	594.1
Story9	D27	A25	855	11.63	0.00	0.00	-35.36	370.11	-102.12	549.78	2000.87	14.0	14.0	606.1	-578.2	458.1	-430.2	458.1	-430.2	-28.5	56.4	-28.5	56.4	335.5	580.6	-552.7	-307.6	223.5	287.2	223.5	287.2	407.5	-443.3	-259.3	-195.6	-259.3	-195.6	471.2	-379.6	471.2
Story8	D27	A25	855	9.91	0.00	0.00	-33.10	336.37	-95.64	516.59	1871.75	11.9	11.9	550.1	-526.3	415.5	-391.8	415.5	-391.8	-27.8	51.6	-27.8	51.6	300.8	530.3	-506.5	-277.0	198.9	258.6	198.9	258.6	371.2	-407.1	-234.8	-175.1	-234.8	-175.1	430.9	-347.5	430.9
Story7	D27	A27	923	9.48	0.00	0.00	-33.60	335.13	-97.14	526.47	1916.35	11.4	11.4	547.6	-524.8	413.5	-390.8	413.5	-390.8	-28.9	51.7	-28.9	51.7	297.0	530.1	-507.3	-274.2	195.5	256.0	195.5	256.0	370.5	-408.3	-233.3	-172.7	-233.3	-172.7	431.0	-347.7	431.0
Story6	D27	A27	923	8.12	0.00	0.00	-32.79	318.99	-94.87	516.33	1887.55	9.7	9.7	520.1	-500.6	392.5	-373.0	392.5	-373.0	-29.6	49.1	-29.6	49.1	278.7	506.4	-486.9	-259.2	182.1	241.2	182.1	241.2	353.0	-392.6	-221.7	-162.6	-221.7	-162.6	412.1	-333.5	412.1
Story5	D27	A27	923	6.69	0.00	0.00	-32.27	305.57	-93.41	510.53	1878.25	8.0	8.0	496.9	-480.9	374.7	-358.6	374.7	-358.6	-30.7	46.8	-30.7	46.8	262.6	486.8	-470.7	-246.6	170.1	228.2	170.1	228.2	338.4	-380.4	-212.1	-154.0	-212.1	-154.0	396.5	-322.3	396.5
Story4	D27	A27	923	5.47	0.00	0.00	-32.01	294.73	-92.73	508.84	1882.96	6.6	6.6	478.1	-465.0	360.2	-347.1	360.2	-347.1	-31.8	45.0	-31.8	45.0	249.0	471.5	-458.4	-235.8	159.7	217.3	159.7	217.3	326.8	-371.3	-204.2	-146.6	-204.2	-146.6	384.4	-313.6	384.4
Story3	D27	A27	923	4.18	0.00	0.00	-31.55	280.93	-91.49	504.04	1868.15	5.0	5.0	454.5	-444.5	342.1	-332.1	342.1	-332.1	-32.8	42.9	-32.8	42.9	232.4	451.9	-441.9	-222.3	147.2	204.1	147.2	204.1	312.1	-358.9	-194.1	-137.2	-194.1	-137.2	368.9	-302.0	368.9
Story2	D27	A27	923	2.99	0.00	0.00	-30.76	261.35	-89.28	493.74	1815.51	3.6	3.6	421.7	-414.6	317.2	-310.0	317.2	-310.0	-33.3	40.5	-33.3	40.5	210.1	424.3	-417.2	-202.9	130.9	186.3	130.9	186.3	291.7	-340.0	-179.1	-123.7	-179.1	-123.7	347.1	-284.5	347.1
Story1	D27	A27	923	1.96	0.00	0.00	-25.36	202.06	-73.68	408.85	1483.35	2.4	2.4	325.7	-320.9	244.8	-240.1	244.8	-240.1	-28.1	32.8	-28.1	32.8	156.4	333.2	-328.5	-151.7	95.2	140.9	95.2	140.9	227.9	-268.9	-136.1	-90.4	-136.1	-90.4	273.6	-223.2	273.6
Ground	D27	A18.5	633	-2.64	0.00	0.00	0.95	-1.03	2.77	14.21	64.52	-3.2	-3.2	-4.8	-1.5	-4.4	-1.9	-4.4	-1.9	-2.0	-4.3	-2.0	-4.3	-1.1	-7.7	1.4	-5.3	-0.7	-2.5	-0.7	-2.5	-5.7	1.1	-3.9	-5.6	-3.9	-5.6	-7.5	-0.6	-7.5
B1	D27	A18.5	633	-3.59	0.00	0.00	0.66	-1.94	1.93	9.25	59.65	-4.3	-4.3	-7.4	-1.2	-6.6	-2.0	-6.6	-2.0	-3.5	-5.1	-3.5	-5.1	-4.3	-9.0	0.3	-4.3	-3.7	-4.9	-3.7	-4.9	-7.2	-0.2	-3.7	-4.9	-3.7	-4.9	-8.4	-1.4	-8.4
B2	D27	A18.5	633	-4.58	0.00	0.00	0.32	0.36	0.92	3.74	42.45	-5.5	-5.5	-4.9	-6.1	-5.1	-5.9	-5.1	-5.9	-5.1	-5.9	-5.1	-5.9	-4.0	-6.2	-4.8	-7.0	-4.1	-4.6	-4.1	-4.6	-5.7	-4.7	-6.4	-6.9	-6.4	-6.9	-6.3	-5.3	-6.3
B3	D27	A18.5	633	-5.55	0.00	0.00	-0.07	4.13	-0.22	2.73	43.91	-6.7	-6.7	-0.1	-13.3	-1.7	-11.6	-1.7	-11.6	-6.7	-6.6	-6.7	-6.6	-2.0	-1.4	-11.9	-11.4	-3.2	-3.1	-3.2	-3.1	-2.8	-10.6	-10.3	-10.1	-10.3	-10.1	-2.7	-10.5	-2.7

Story	ETABS #	Section	Capacity	Dead	Live	WindFX	WindMTX	WindFY	WindMTY	SpecX	SpecY																													
Story10	D28	A25	855	-24.39	0.00	0.00	46.26	-464.01	133.49	716.18	2527.20	-29.3	-29.3	-771.7	713.1	-586.1	527.5	-586.1	527.5	26.2	-84.8	26.2	-84.8	-425.9	-746.3	687.7	367.3	-285.3	-368.7	-285.3	-368.7	-525.8	550.6	310.1	226.8	310.1	226.8	-609.2	467.3	-609.2
Story9	D28	A25	855	-22.22	0.00	0.00	35.54	-371.82	102.65	552.63	2010.14	-26.7	-26.7	-621.6	568.2	-472.9	419.5	-472.9	419.5	16.0	-69.3	16.0	-69.3	-349.7	-596.0	542.7	296.3	-237.1	-301.2	-237.1	-301.2	-422.1	432.8	247.8	183.8	247.8	183.8	-486.1	368.7	-486.1
Story8	D28	A25	855	-20.54	0.00	0.00	33.30	-338.26	96.23	519.73	1881.96	-24.6	-24.6	-565.9	516.6	-430.6	381.3	-430.6	381.3	15.3	-64.6	15.3	-64.6	-315.1	-540.0	496.7	265.8	-212.7	-272.7	-212.7	-272.7	-386.0	396.7	223.4	163.4	223.4	163.4	-446.0	336.7	-446.0
Story7	D28	A27	923	-20.05	0.00	0.00	33.78	-336.90	97.68	529.39	1925.81	-24.1	-24.1	-563.1	515.0	-428.3	380.2	-428.3	380.2	16.5	-64.6	16.5	-64.6	-311.1	-545.5	497.4	263.0	-209.1	-270.0	-209.1	-270.0	-385.1	397.8	221.9	161.0	221.9	161.0	-446.0	337.0	-446.0
Story6	D28	A27	923	-18.72	0.00	0.00	32.99	-320.87	95.45	519.43	1897.58	-22.5	-22.5	-535.9	490.9	-407.5	362.6	-407.5	362.6	17.1	-62.1	17.1	-62.1	-293.0	-522.0	477.1	248.0	-195.8	-255.2	-195.8	-255.2	-367.8	382.3	210.3	150.9	210.3	150.9	-427.2	322.8	-427.2
Story5	D28	A27	923	-17.26	0.00	0.00	32.46	-307.38	93.97	513.55	1887.89	-20.7	-20.7	-512.5	471.1	-389.6	348.1	-389.6	348.1	18.2	-59.7	18.2	-59.7	-276.8	-502.3	460.9	235.4	-183.7	-242.2	-183.7	-242.2	-353.0	370.1	200.8	142.3	200.8	142.3	-411.5	311.6	-411.5
Story4	D28	A27	923	-16.06	0.00	0.00	32.21	-296.63	93.32	512.03	1893.13	-19.3	-19.3	-493.9	455.3	-375.2	336.7	-375.2	336.7	19.4	-57.9	19.4	-57.9	-263.2	-487.2	448.7	224.7	-173.4	-231.4	-173.4	-231.4	-341.5	361.0	192.9	134.9	192.9	134.9	-399.6	303.0	-399.6
Story3	D28	A27	923	-14.68	0.00	0.00	31.74	-282.65	92.02	506.94	1877.38	-17.6	-17.6	-469.8	434.6	-356.8	321.6	-356.8	321.6	20.5	-55.7	20.5	-55.7	-246.4	-467.2	432.0	211.1	-160.7	-217.9	-160.7	-217.9	-326.5	348.5	182.7	125.5	182.7	125.5	-383.7	291.3	-383.7
Story2	D28	A27	923	-13.51	0.00	0.00	30.96	-263.12	89.84	496.77	1825.15	-16.2	-16.2	-437.2	404.8	-332.0	299.5	-332.0	299.5	20.9	-53.4	20.9	-53.4	-224.2	-439.8	407.3	191.7	-144.4	-200.2	-144.4	-200.2	-306.3	329.6	167.8	112.0	167.8	112.0	-362.0	273.8	-362.0
Story1	D28	A27	923	-10.82	0.00	0.00	25.54	-203.71	74.20	411.69	1492.10	-13.0	-13.0	-338.9	313.0	-257.4	231.5	-257.4	231.5	17.7	-43.6	17.7	-43.6	-168.4	-346.5	320.5	142.4	-106.6	-152.7	-106.6	-152.7	-240.3	260.4	126.7	80.7	126.7	80.7	-286.3	214.4	-286.3
Ground	D28	A18.5	633	-8.53	0.00	0.00	-0.80	-0.36	-2.33	11.81	59.84	-10.2	-10.2	-10.8	-9.7	-10.7	-9.8	-10.7	-9.8	-11.2	-9.3	-11.2	-9.3	-13.5	-7.9	-12.6	-7.0	-13.4	-11.9	-13.4	-11.9	-9.2	-12.7	-8.5	-7.1	-8.5	-7.1	-7.7	-11.3	-7.7
B1	D28	A18.5	633	-7.48	0.00	0.00	-0.54	0.80	-1.57	7.31	55.86	-9.0	-9.0	-7.7	-10.2	-8.0	-9.9	-8.0	-9.9	-9.6	-8.3	-9.6	-8.3	-9.9	-6.1	-11.8	-8.0	-10.2	-9.2	-10.2	-9.2	-7.3	-11.6	-8.8	-7.8	-8.8	-7.8	-6.3	-10.6	-6.3
B2	D28	A18.5	633	-6.51	0.00	0.00	-0.19	-1.49	-0.56	1.83	39.45	-7.8	-7.8	-10.2	-5.4	-9.6	-6.0	-9.6	-6.0	-8.0	-7.6	-8.0	-7.6	-10.3	-8.9	-6.7	-5.3	-9.8	-9.5	-9.8	-9.5	-8.8	-7.2	-6.1	-5.8	-6.1	-5.8	-8.5	-6.8	-8.5
B3	D28	A18.5	633	-5.55	0.00	0.00	0.20	-5.26	0.57	4.65	48.45	-6.7	-6.7	-15.1	1.8	-13.0	-0.4	-13.0	-0.4	-6.4	-6.9	-6.4	-6.9	-12.3	-13.7	0.3	-1.0	-10.7	-11.1	-10.7	-11.1	-11.7	-1.2	-2.3	-2.6	-2.3	-2.6	-12.1	-1.6	-12.1

SIMPSON GUMPERTZ & HEGER
Engineering of Structures and Building Enclosures

CLIENT Pacific Earthquake Engineering Research Center
SUBJECT BRB Strength Check along Line 2 for LA BRBF Bldg

SHEET NO.
PROJECT NO. 087237.10
DATE 1/23/09
BY AD
CHECKED BY

Story	ETABS #	Section	Capacity	Dead	Live	WindFX	WindMTX	WindFY	WindMTY	SpecX	SpecY																																				
Story10	D26	A25	855	13.78	0.00	0.00	46.04	-462.24	132.87	712.85	2516.92	511.1	-478.1	594.1	12.4	12.4	-727.2	752.0	-542.3	567.1	-542.3	567.1	67.7	-42.8	67.7	-42.8	-382.8	-701.7	726.5	407.7	-242.8	-325.8	-242.8	-325.8	-482.2	590.0	350.6	267.6	350.6	267.6	-565.1	507.0	-565.1	507.0	-482.2	590.0	468.8	840.7	23.0	706.9	-667.5	16.4	-429.5	-801.3
Story9	D26	A25	855	11.63	0.00	0.00	35.36	-370.11	102.12	549.78	2000.87	407.5	-379.6	471.2	10.5	10.5	-581.7	602.6	-433.7	454.6	-433.7	454.6	52.9	-32.0	52.9	-32.0	-311.1	-556.2	577.1	332.1	-199.1	-262.8	-199.1	-262.8	-383.1	467.7	283.7	220.0	283.7	220.0	-446.8	404.0	-446.8	404.0	-383.1	467.7	368.4	667.7	24.5	564.5	-531.3	8.7	-335.2	-634.4
Story8	D26	A25	855	9.91	0.00	0.00	33.10	-336.37	95.64	516.59	1871.75	371.2	-347.5	430.9	8.9	8.9	-529.3	547.1	-394.7	412.6	-394.7	412.6	48.6	-30.8	48.6	-30.8	-280.0	-509.5	527.3	297.8	-178.1	-237.7	-178.1	-237.7	-350.4	427.9	255.6	196.0	255.6	196.0	-410.1	368.3	-410.1	368.3	-350.4	427.9	344.0	623.4	20.8	526.5	-498.2	7.5	-315.6	-595.1
Story7	D26	A27	923	9.48	0.00	0.00	33.60	-335.33	97.14	526.47	1916.35	370.5	-347.7	431.0	8.5	8.5	-527.7	544.7	-393.6	410.7	-393.6	410.7	48.8	-31.8	48.8	-31.8	-277.1	-510.2	527.3	294.1	-175.6	-236.1	-175.6	-236.1	-350.6	428.2	253.2	192.7	253.2	192.7	-411.1	367.7	-411.1	367.7	-350.6	428.2	350.4	637.1	21.2	538.3	-511.2	5.9	-323.3	-610.0
Story6	D26	A27	923	8.12	0.00	0.00	32.79	-318.99	94.87	516.33	1887.55	353.0	-333.5	412.1	7.3	7.3	-503.1	517.7	-375.5	390.1	-375.5	390.1	46.7	-32.0	46.7	-32.0	-261.6	-489.3	504.0	276.3	-165.0	-224.1	-165.0	-224.1	-336.0	409.7	238.7	179.7	238.7	179.7	-395.0	350.6	-395.0	350.6	-336.0	409.7	342.7	625.6	19.8	528.7	-505.5	3.4	-319.5	-602.4
Story5	D26	A27	923	6.69	0.00	0.00	32.27	-305.57	93.41	510.53	1878.25	338.4	-322.3	396.5	6.0	6.0	-482.9	494.9	-360.7	372.7	-360.7	372.7	44.7	-32.7	44.7	-32.7	-248.6	-472.8	484.8	260.6	-156.0	-214.1	-156.0	-214.1	-324.3	394.5	226.2	168.1	226.2	168.1	-382.4	336.4	-382.4	336.4	-324.3	394.5	338.0	620.2	18.7	524.4	-505.3	0.4	-318.9	-601.1
Story4	D26	A27	923	5.47	0.00	0.00	32.01	-294.73	92.73	508.84	1882.96	326.8	-313.6	384.4	4.9	4.9	-466.6	476.5	-348.8	358.6	-348.8	358.6	43.3	-33.5	43.3	-33.5	-237.5	-460.0	469.9	247.3	-148.2	-205.9	-148.2	-205.9	-315.3	382.8	215.7	158.0	215.7	158.0	-372.9	325.1	-372.9	325.1	-315.3	382.8	336.2	619.7	17.9	524.2	-508.6	-2.3	-320.6	-604.1
Story3	D26	A27	923	4.18	0.00	0.00	31.55	-280.93	91.49	504.04	1868.15	312.1	-302.0	368.9	3.8	3.8	-445.7	453.3	-333.4	340.9	-333.4	340.9	41.6	-34.1	41.6	-34.1	-223.4	-443.1	450.7	231.1	-138.5	-195.3	-138.5	-195.3	-303.3	367.7	202.8	146.0	202.8	146.0	-360.1	310.8	-360.1	310.8	-303.3	367.7	331.5	613.0	16.3	518.4	-506.5	-4.3	-319.6	-601.0
Story2	D26	A27	923	2.99	0.00	0.00	30.76	-261.35	89.28	493.74	1815.53	291.7	-284.5	347.1	2.7	2.7	-415.5	420.9	-310.9	316.3	-310.9	316.3	39.6	-34.2	39.6	-34.2	-203.8	-418.1	423.4	209.2	-124.6	-180.0	-124.6	-180.0	-285.4	346.3	185.4	130.0	185.4	130.0	-340.9	290.8	-340.9	290.8	-285.4	346.3	321.9	594.5	13.1	501.9	-493.3	-4.5	-313.3	-586.0
Story1	D26	A27	923	1.96	0.00	0.00	25.36	-202.06	73.68	408.85	1483.35	227.9	-223.2	273.6	1.8	1.8	-321.5	325.1	-240.7	244.2	-240.7	244.2	32.2	-28.7	32.2	-28.7	-152.3	-329.1	332.6	155.8	-91.0	-136.7	-91.0	-136.7	-223.8	273.0	140.3	94.6	140.3	94.6	-269.5	227.3	-269.5	227.3	-223.8	273.0	264.0	485.6	8.3	408.9	-403.3	-2.7	-258.4	-480.0
Ground	D26	A18.5	633	-2.64	0.00	0.00	-0.95	1.03	-2.77	14.21	64.52	-5.7	-0.6	-7.5	-2.4	-2.4	-0.7	-4.0	-1.1	-3.6	-1.1	-3.6	-3.5	-1.2	-3.5	-1.2	-4.5	2.2	-6.9	-0.3	-4.8	-3.1	-4.8	-3.1	0.2	-6.7	-1.7	0.0	-1.7	0.0	1.9	-4.9	1.9	-4.9	0.2	-6.7	6.5	16.9	-2.4	14.2	-21.8	-5.1	-14.0	-24.4
B1	D26	A18.5	633	-3.59	0.00	0.00	0.66	-1.94	1.93	9.25	59.65	-1.4	-7.2	-0.2	-3.2	-3.2	-6.3	-0.1	-5.6	-0.9	-5.6	-0.9	-2.6	-4.0	-2.6	-4.0	-3.2	-7.9	1.4	-3.2	-2.6	-3.8	-2.6	-3.8	-7.3	-0.3	-7.3	0.0	-7.3	0.0	-6.1	0.8	-6.1	0.8	-7.3	-0.3	3.1	13.6	-2.7	11.9	-22.1	-7.6	-13.4	-23.9
B2	D26	A18.5	633	-4.58	0.00	0.00	0.32	-0.36	0.92	3.74	42.45	-5.3	-5.7	-4.7	-4.1	-4.1	-3.5	-4.7	-3.7	-4.6	-3.7	-4.6	-3.7	-4.5	-3.7	-4.5	-2.6	-4.8	-3.5	-5.7	-2.7	-3.3	-2.7	-3.3	-4.3	-3.3	-5.0	-5.6	-5.0	-5.6	-4.9	-3.9	-4.9	-3.9	-4.3	-3.3	-1.6	6.5	-3.9	5.8	-18.9	-9.2	-11.5	-19.6
B3	D26	A18.5	633	-5.55	0.00	0.00	0.07	-4.13	0.22	2.73	43.91	-2.8	-10.5	-2.7	-5.0	-5.0	-11.6	1.6	-10.0	0.0	-10.0	0.0	-4.9	-5.1	-4.9	-5.1	-9.7	-10.2	0.2	-0.3	-8.5	-8.6	-8.5	-8.6	-8.8	-1.0	-1.4	-1.5	-1.4	-1.5	-9.0	-1.1	-9.0	-1.1	-8.8	-1.0	-3.1	5.5	-4.8	5.0	-20.8	-11.0	-12.7	-21.3

Story	ETABS #	Section	Capacity	Dead	Live	WindFX	WindMTX	WindFY	WindMTY	SpecX	SpecY																																				
Story10	D27	A25	855	13.78	0.00	0.00	-46.04	462.24	-132.87	712.85	2516.92	-478.1	511.1	-561.0	12.4	12.4	752.0	-727.2	567.1	-542.3	567.1	-542.3	-42.8	67.7	-42.8	67.7	407.7	726.5	-701.7	-382.8	267.6	350.6	267.6	350.6	507.0	-565.1	-325.8	-242.8	-325.8	-242.8	590.0	-482.2	590.0	-482.2	507.0	-565.1	468.8	840.7	23.0	706.9	-667.5	16.4	-429.5	-801.3
Story9	D27	A25	855	11.63	0.00	0.00	-35.36	370.11	-102.12	549.78	2000.87	-379.6	407.5	-443.3	10.5	10.5	602.6	-581.7	454.6	-433.7	454.6	-433.7	-32.0	52.9	-32.0	52.9	332.1	577.1	-556.2	-311.1	220.0	283.7	220.0	283.7	404.0	-446.8	-262.8	-199.1	-262.8	-199.1	467.7	-383.1	467.7	-383.1	404.0	-446.8	368.4	667.7	24.5	564.5	-531.3	8.7	-335.2	-634.4
Story8	D27	A25	855	9.91	0.00	0.00	-33.10	336.37	-95.64	516.59	1871.75	-347.5	371.2	-407.1	8.9	8.9	547.1	-529.3	412.6	-394.7	412.6	-394.7	-30.8	48.6	-30.8	48.6	297.8	527.3	-509.5	-280.0	196.0	255.6	196.0	255.6	368.3	-410.1	-237.7	-178.1	-237.7	-178.1	427.9	-350.4	427.9	-350.4	368.3	-410.1	344.0	623.4	20.8	526.5	-498.2	7.5	-315.6	-595.1
Story7	D27	A27	923	9.48	0.00	0.00	-33.60	335.13	-97.14	526.47	1916.35	-347.7	370.5	-408.3	8.5	8.5	544.7	-527.7	410.7	-393.6	410.7	-393.6	-31.8	48.8	-31.8	48.8	294.1	527.3	-510.2	-277.1	192.7	253.2	192.7	253.2	367.7	-411.1	-236.1	-175.6	-236.1	-175.6	428.2	-350.6	428.2	-350.6	367.7	-411.1	350.4	637.1	21.2	538.3	-511.2	5.9	-323.3	-610.0
Story6	D27	A27	923	8.12	0.00	0.00	-32.79	318.99	-94.87	516.33	1887.55	-333.5	353.0	-392.6	7.3	7.3	517.7	-503.1	390.1	-375.5	390.1	-375.5	-32.0	46.7	-32.0	46.7	276.3	504.0	-489.3	-261.6	179.7	238.7	179.7	238.7	350.6	-395.0	-224.1	-165.0	-224.1	-165.0	409.7	-336.0	409.7	-336.0	350.6	-395.0	342.7	625.6	19.8	528.7	-505.5	3.4	-319.5	-602.4
Story5	D27	A27	923	6.69	0.00	0.00	-32.27	305.57	-93.41	510.53	1878.25	-322.3	338.4	-380.4	6.0	6.0	494.9	-482.9	372.7	-360.7	372.7	-360.7	-32.7	44.7	-32.7	44.7	260.6	484.8	-472.8	-248.6	168.1	226.2	168.1	226.2	336.4	-382.4	-214.1	-156.0	-214.1	-156.0	394.5	-324.3	394.5	-324.3	336.4	-382.4	338.0	620.2	18.7	524.4	-505.3	0.4	-318.9	-601.1
Story4	D27	A27	923	5.47	0.00	0.00	-32.01	294.73	-92.73	508.84	1882.96	-313.6	326.8	-371.3	4.9	4.9	476.5	-466.6	358.6	-348.8	358.6	-348.8	-33.5	43.3	-33.5	43.3	247.3	469.9	-460.0	-237.5	158.0	215.7	158.0	215.7	325.1	-372.9	-205.9	-148.2	-205.9	-148.2	382.8	-315.3	382.8	-315.3	325.1	-372.9	336.2	619.7	17.9	524.2	-508.6	-2.3	-320.6	-604.1
Story3	D27	A27	923	4.18	0.00	0.00	-31.55	280.93	-91.49	504.04	1868.15	-302.0	312.1	-358.9	3.8	3.8	453.3	-445.7	340.9	-333.4	340.9	-333.4	-34.1	41.6	-34.1	41.6	231.1	450.7	-443.1	-223.6	146.0	202.8	146.0	202.8	310.8	-360.1	-195.3	-138.5	-195.3	-138.5	367.7	-303.3	367.7	-303.3	310.8	-360.1	331.5	613.0	16.3	518.4	-506.5	-4.3	-319.6	-601.0
Story2	D27	A27	923	2.99	0.00	0.00	-30.76	261.35	-89.28	493.74	1815.51	-284.5	291.7	-340.0	2.7	2.7	420.9	-415.5	316.3	-310.9	316.3	-310.9	-34.2	39.6	-34.2	39.6	209.2	423.4	-418.1	-203.8	130.0	185.4	130.0	185.4	290.8	-340.9	-180.0	-124.6	-180.0	-124.6	346.3	-285.4	346.3	-285.4	290.8	-340.9	321.9	594.5	13.1	501.9	-493.3	-4.5	-313.3	-586.0
Story1	D27	A27	923	1.96	0.00	0.00	-25.36	202.06	-73.68	408.85	1483.35	-223.2	227.9	-268.9	1.8	1.8	325.1	-321.5	244.2	-240.7	244.2	-240.7	-28.7	32.2	-28.7	32.2	155.8	332.6	-329.1	-152.3	94.6	140.3	94.6	140.3	227.3	-269.5	-136.7	-91.0	-136.7	-91.0	273.0	-223.8	273.0	-223.8	227.3	-269.5	264.0	485.6	8.3	408.9	-403.3	-2.7	-258.4	-480.0
Ground	D27	A18.5	633	-2.64	0.00	0.00	0.95	-1.03	2.77	14.21	64.52	-0.6	-5.7	1.1	-2.4	-2.4	-4.0	-0.7	-3.6	-1.1	-3.6	-1.1	-1.2	-3.5	-1.2	-3.5	-0.3	-6.9	2.2	-4.5	0.0	-1.7	0.0	-1.7	-4.9	1.9	-3.1	-4.8	-3.1	-4.8	-6.7	0.2	-6.7	0.2	-4.9	1.9	6.5	16.9	-2.4	14.2	-21.8	-5.1	-14.0	-24.4
B1	D27	A18.5	633	-3.59	0.00	0.00	0.66	-1.94	1.93	9.25	59.65	-1.4	-7.2	-0.2	-3.2	-3.2	-6.3	-0.1	-5.6	-0.9	-5.6	-0.9	-2.4	-4.0	-2.4	-4.0	-3.2	-7.9	1.4	-3.2	-2.6	-3.8	-2.6	-3.8	-6.1	0.8	-2.6	-3.8	-2.6	-3.8	-7.3	-0.3	-7.3	-0.3	-6.1	0.8	3.1	13.6	-2.7	11.9	-22.1	-7.6	-13.4	-23.9
B2	D27	A18.5	633	-4.58	0.00	0.00	0.32	0.36	0.92	3.74	42.45	-5.3	-5.7	-4.7	-4.1	-4.1	-3.5	-4.7	-3.7	-4.6	-3.7	-4.6	-3.7	-4.5	-3.7	-4.5	-2.6	-4.8	-3.5	-5.7	-2.7	-3.3	-2.7	-3.3	-4.3	-3.3	-5.0	-5.6	-5.0	-5.6	-4.9	-3.9	-4.9	-3.9	-4.3	-3.3	-1.6	6.5	-3.9	5.8	-18.9	-9.2	-11.5	-19.6
B3	D27	A18.5	633	-5.55	0.00	0.00	-0.07	4.13	-0.22	2.73	43.91	-10.5	-2.8	-10.6	-5.0	-5.0	1.6	-11.6	0.0	-10.0	0.0	-10.0	-5.1	-4.9	-5.1	-4.9	-0.3	0.2	-10.2	-9.7	-1.5	-1.4	-1.5	-1.4	-1.1	-9.0	-8.6	-8.5	-8.6	-8.5	-1.0	-8.8	-1.0	-8.8	-1.1	-9.0	-3.1	5.5	-4.8	5.0	-20.8	-11.0	-12.7	-21.3

Story	ETABS #	Section	Capacity	Dead	Live	WindFX	WindMTX	WindFY	WindMTY	SpecX	SpecY																																				
Story10	D28	A25	855	-24.39	0.00	0.00	46.26	-464.01	133.49	716.18	2527.20	467.3	-525.8	550.6	-22.0	-22.0	-764.4	720.5	-578.8	534.9	-578.8	534.9	33.6	-77.5	33.6	-77.5	-418.6	-739.0	695.0	374.7	-278.0	-361.4	-278.0	-361.4	-518.5	557.9	317.4	234.1	317.4	234.1	-601.8	474.6	-601.8	474.6	-518.5	557.9	416.3	789.5	-31.7	655.1	-724.8	-38.0	-486.0	-859.2
Story9	D28	A25	855	-22.22	0.00	0.00	35.54	-371.82	102.65	552.63	2010.14	368.7	-422.1	432.8	-20.0	-20.0	-614.9	574.9	-466.2	426.2	-466.2	426.2	22.7	-62.7	22.7	-62.7	-343.0	-589.4	549.4	303.0	-230.4	-294.5	-230.4	-294.5	-415.4	439.4	254.5	190.4	254.5	190.4	-479.4	375.4	-479.4	375.4	-415.4	439.4	321.7	622.3	-23.9	518.6	-582.2	-39.6	-385.3	-685.9
Story8	D28	A25	855	-20.54	0.00	0.00	33.30	-338.26	96.23	519.73	1881.96	336.7	-386.0	396.7	-18.5	-18.5	-559.7	522.7	-424.4	387.4	-424.4	387.4	21.5	-58.4	21.5	-58.4	-308.9	-539.9	502.9	272.0	-206.5	-266.5	-206.5	-266.5	-379.9	402.9	229.5	169.5	229.5	169.5	-439.9	342.9	-439.9	342.9	-379.9	402.9	302.3	583.3	-22.7	485.7	-544.4	-36.0	-361.0	-642.0
Story7	D28	A27	923	-20.05	0.00	0.00	33.78	-336.90	97.68	529.39	1925.81	337.0	-385.1	397.8	-18.0	-18.0	-557.1	521.0	-422.3	386.2	-422.3	386.2	22.5	-58.6	22.5	-58.6	-305.1	-539.5	503.4	269.0	-203.1	-264.0	-203.1	-264.0	-379.1	403.9	227.9	167.0	227.9	167.0	-439.9	343.0	-439.9	343.0	-379.1	403.9	310.0	598.0	-21.1	498.7	-556.0	-36.2	-367.3	-655.3
Story6	D28	A27	923	-18.72	0.00	0.00	32.99	-320.87	95.45	519.43	1897.58	322.8	-367.8	382.3	-16.8	-16.8	-530.2	496.5	-401.9	368.2	-401.9	368.2	22.7	-56.4	22.7	-56.4	-287.3	-516.4	482.7	253.7	-190.2	-249.6	-190.2	-249.6	-362.1	387.9	215.9	156.5	215.9	156.5	-421.6	328.5	-421.6	328.5	-362.1	387.9	306.3	590.5	-18.6	493.0	-546.5	-34.9	-359.7	-644.0
Story5	D28	A27	923	-17.26	0.00	0.00	32.46	-307.38	93.97	513.55	1887.89	311.6	-353.0	370.1	-15.5	-15.5	-507.3	476.3	-384.4	353.3	-384.4	353.3	23.4	-54.5	23.4	-54.5	-271.6	-497.1	466.1	240.6	-178.5	-237.0	-178.5	-237.0	-347.8	375.2	205.9	147.5	205.9	147.5	-406.3	316.8	-406.3	316.8	-347.8	375.2	305.6	589.1	-15.6	492.8	-542.1	-33.7	-354.9	-638.5
Story4	D28	A27	923	-16.06	0.00	0.00	32.21	-296.63	93.32	512.03	1893.13	303.0	-341.5	361.0	-14.5	-14.5	-489.1	460.2	-370.4	341.5	-370.4	341.5	24.2	-53.1	24.2	-53.1	-258.4	-482.4	453.5	229.5	-168.6	-226.6	-168.6	-226.6	-336.7	365.8	197.7	139.7	197.7	139.7	-394.7	307.8	-394.7	307.8	-336.7	365.8	307.3	592.3	-12.9	496.2	-542.1	-33.0	-353.2	-638.2
Story3	D28	A27	923	-14.68	0.00	0.00	31.74	-282.65	92.02	506.94	1877.38	291.3	-326.5	348.5	-13.2	-13.2	-465.4	439.0	-352.4	326.0	-352.4	326.0	24.9	-51.3	24.9	-51.3	-242.0	-462.8	436.4	215.5	-156.3	-213.5	-156.3	-213.5	-322.1	352.9	187.1	129.9	187.1	129.9	-379.3	295.7	-379.3	295.7	-322.1	352.9	306.3	589.1	-10.8	493.9	-535.9	-31.2	-348.2	-631.0
Story2	D28	A27	923	-13.51	0.00	0.00	30.96	-263.12	89.84	496.77	1825.15	273.8	-306.3	329.6	-12.2	-12.2	-433.2	408.8	-327.9	303.6	-327.9	303.6	25.0	-49.3	25.0	-49.3	-220.1	-435.7	411.4	195.8	-140.4	-196.1	-140.4	-196.1	-302.2	333.7	171.8	116.0	171.8	116.0	-358.0	277.9	-358.0	277.9	-302.2	333.7	300.1	574.1	-10.6	480.9	-519.5	-28.0	-338.7	-612.7
Story1	D28	A27	923	-10.82	0.00	0.00	25.54	-203.71	74.20	411.69	1492.10	214.4	-240.3	260.4	-9.7	-9.7	-335.7	316.2	-254.2	234.7	-254.2	234.7	20.9	-40.4	20.9	-40.4	-165.2	-343.2	323.8	145.7	-103.4	-149.4	-103.4	-149.4	-237.1	263.6	129.9	83.9	129.9	83.9	-283.1	217.6	-283.1	217.6	-237.1	263.6	247.4	470.2	-10.1	393.0	-423.9	-20.8	-278.3	-501.1
Ground	D28	A18.5	633	-8.53	0.00	0.00	-0.80	-0.36	-2.33	11.81	59.84	-11.3	-9.2	-12.7	-7.7	-7.7	-8.2	-7.1	-8.1	-7.2	-8.1	-7.2	-8.6	-6.7	-8.6	-6.7	-10.9	-5.3	-10.0	-4.5	-10.8	-9.4	-10.8	-9.4	-6.6	-10.2	-6.0	-4.5	-6.0	-4.5	-5.2	-8.7	-5.2	-8.7	-6.6	-10.2	-3.1	6.9	-10.5	4.6	-29.0	-13.9	-21.3	-31.2
B1	D28	A18.5	633	-7.48	0.00	0.00	-0.54	0.80	-1.57	7.31	55.86	-10.6	-7.3	-11.6	-6.7	-6.7	-5.5	-8.0	-5.8	-7.7	-5.8	-7.7	-7.4	-6.1	-7.4	-6.1	-7.7	-3.9	-9.6	-5.8	-7.9	-6.9	-7.9	-6.9	-5.1	-9.4	-6.5	-5.5	-6.5	-5.5	-4.1	-8.4	-4.1	-8.4	-5.1	-9.4	-3.4	6.7	-7.9	5.4	-26.7	-13.4	-18.0	-28.1
B2	D28	A18.5	633	-6.51	0.00	0.00	-0.19	-1.49	-0.56	1.83	39.45	-6.8	-8.8	-7.2	-5.9	-5.9	-8.2	-3.5	-7.6	-4.1	-7.6	-4.1	-6.1	-5.6	-6.1	-5.6	-8.3	-7.0	-4.7	-3.4	-7.9	-7.5	-7.9	-7.5	-6.9	-5.2	-4.2	-3.8	-4.2	-3.8	-6.5	-4.9	-6.5	-4.9	-6.9	-5.2	-5.2	2.7	-6.3	2.4	-20.9	-12.3	-13.4	-21.3
B3	D28	A18.5	633	-5.55	0.00	0.00	0.20	-5.26	0.57	4.65	48.45	-1.6	-11.7	-1.2	-5.0	-5.0	-13.4	3.4	-11.3	1.3	-11.3	1.3	-4.8	-5.2	-4.8	-5.2	-10.6	-12.0	2.0	0.6	-9.0	-9.4	-9.0	-9.4	-10.1	0.4	-0.6	-1.0	-0.6	-1.0	-10.4	0.1	-10.4	0.1	-10.1	0.4	-2.1	7.0	-5.0	6.1	-22.0	-10.8	-13.7	-22.9

SIMPSON GUMPERTZ & HEGER
Engineering of Structures and Building Enclosures

CLIENT Pacific Earthquake Engineering Research Center
SUBJECT BRB Strength Check along Line 2 for LA BRBF Bldg

SHEET NO.
PROJECT NO. 087237.10
DATE 1/23/09
BY AD
CHECKED BY

Story	ETABS #	Section	Capacity	Dead	Live	WindFX	WindMTX	WindFY	WindMTY	SpecX	SpecY									Maximum Axial Loads Tension	Compression	DCR	Status
Story10	D26	A25	855	13.78	0.00	0.00	46.04	-462.24	132.87	712.85	2516.92	458.4	830.2	12.5	696.5	-678.0	6.0	-439.9	-811.7	840.66	-811.71	0.98	OK
Story9	D26	A25	855	11.63	0.00	0.00	35.36	-370.11	102.12	549.78	2000.87	359.6	658.9	15.7	555.7	-540.1	-0.1	-344.0	-643.2	667.67	-643.25	0.78	OK
Story8	D26	A25	855	9.91	0.00	0.00	33.10	-336.37	95.64	516.59	1871.75	336.4	615.9	13.3	519.0	-505.7	0.0	-323.1	-602.6	623.42	-602.60	0.73	OK
Story7	D26	A27	923	9.48	0.00	0.00	33.60	-335.13	97.14	526.47	1916.35	343.2	629.9	14.0	531.1	-518.4	-1.2	-330.5	-617.2	637.09	-617.18	0.69	OK
Story6	D26	A27	923	8.12	0.00	0.00	32.79	-318.99	94.87	516.33	1887.55	336.6	619.4	13.6	522.5	-511.6	-2.7	-325.7	-608.5	625.57	-608.51	0.68	OK
Story5	D26	A27	923	6.69	0.00	0.00	32.27	-305.57	93.41	510.53	1878.25	333.0	615.1	13.7	519.3	-510.3	-4.7	-324.0	-606.1	620.20	-606.14	0.67	OK
Story4	D26	A27	923	5.47	0.00	0.00	32.01	-294.73	92.73	508.84	1882.96	332.0	615.6	13.8	520.1	-512.7	-6.4	-324.7	-608.2	619.70	-608.21	0.67	OK
Story3	D26	A27	923	4.18	0.00	0.00	31.55	-280.93	91.49	504.04	1868.15	328.3	609.8	13.1	515.2	-509.6	-7.5	-322.7	-604.2	612.97	-604.19	0.66	OK
Story2	D26	A27	923	2.99	0.00	0.00	30.76	-261.35	89.28	493.74	1815.51	319.6	592.3	10.8	499.6	-495.6	-6.8	-315.6	-588.3	594.54	-588.25	0.64	OK
Story1	D26	A27	923	1.96	0.00	0.00	25.36	-202.06	73.68	408.85	1483.35	262.5	484.1	6.8	407.4	-404.7	-4.2	-259.9	-481.5	485.59	-481.46	0.53	OK
Ground	D26	A18.5	633	-2.64	0.00	0.00	-0.95	1.03	-2.77	14.21	64.52	8.5	18.9	-0.4	16.2	-19.8	-3.1	-12.0	-22.4	18.89	-24.44	0.04	OK
B1	D26	A18.5	633	-3.59	0.00	0.00	-0.66	1.94	-1.93	9.25	59.65	5.8	16.3	0.1	14.6	-19.4	-4.9	-10.7	-21.2	16.33	-23.87	0.04	OK
B2	D26	A18.5	633	-4.58	0.00	0.00	-0.32	-0.36	-0.92	3.74	42.45	1.9	10.0	-0.4	9.3	-15.4	-5.7	-8.1	-16.1	10.00	-19.62	0.03	OK
B3	D26	A18.5	633	-5.55	0.00	0.00	0.07	-4.13	0.22	2.73	43.91	1.1	9.7	-0.6	9.2	-16.6	-6.8	-8.5	-17.1	9.69	-21.34	0.03	OK

Story	ETABS #	Section	Capacity	Dead	Live	WindFX	WindMTX	WindFY	WindMTY	SpecX	SpecY									Maximum Axial Loads Tension	Compression	DCR	Status
Story10	D27	A25	855	13.78	0.00	0.00	-46.04	462.24	-132.87	712.85	2516.92	458.4	830.2	12.5	696.5	-678.0	6.0	-439.9	-811.7	840.66	-811.71	0.98	OK
Story9	D27	A25	855	11.63	0.00	0.00	-35.36	370.11	-102.12	549.78	2000.87	359.6	658.9	15.7	555.7	-540.1	-0.1	-344.0	-643.2	667.67	-643.25	0.78	OK
Story8	D27	A25	855	9.91	0.00	0.00	-33.10	336.37	-95.64	516.59	1871.75	336.4	615.9	13.3	519.0	-505.7	0.0	-323.1	-602.6	623.42	-602.60	0.73	OK
Story7	D27	A27	923	9.48	0.00	0.00	-33.60	335.13	-97.14	526.47	1916.35	343.2	629.9	14.0	531.1	-518.4	-1.2	-330.5	-617.2	637.09	-617.18	0.69	OK
Story6	D27	A27	923	8.12	0.00	0.00	-32.79	318.99	-94.87	516.33	1887.55	336.6	619.4	13.6	522.5	-511.6	-2.7	-325.7	-608.5	625.57	-608.51	0.68	OK
Story5	D27	A27	923	6.69	0.00	0.00	-32.27	305.57	-93.41	510.53	1878.25	333.0	615.1	13.7	519.3	-510.3	-4.7	-324.0	-606.1	620.20	-606.14	0.67	OK
Story4	D27	A27	923	5.47	0.00	0.00	-32.01	294.73	-92.73	508.84	1882.96	332.0	615.6	13.8	520.1	-512.7	-6.4	-324.7	-608.2	619.70	-608.21	0.67	OK
Story3	D27	A27	923	4.18	0.00	0.00	-31.55	280.93	-91.49	504.04	1868.15	328.3	609.8	13.1	515.2	-509.6	-7.5	-322.7	-604.2	612.97	-604.19	0.66	OK
Story2	D27	A27	923	2.99	0.00	0.00	-30.76	261.35	-89.28	493.74	1815.51	319.6	592.3	10.8	499.6	-495.6	-6.8	-315.6	-588.3	594.54	-588.25	0.64	OK
Story1	D27	A27	923	1.96	0.00	0.00	-25.36	202.06	-73.68	408.85	1483.35	262.5	484.1	6.8	407.4	-404.7	-4.2	-259.9	-481.5	485.59	-481.46	0.53	OK
Ground	D27	A18.5	633	-2.64	0.00	0.00	0.95	-1.03	2.77	14.21	64.52	8.5	18.9	-0.4	16.2	-19.8	-3.1	-12.0	-22.4	18.89	-24.44	0.04	OK
B1	D27	A18.5	633	-3.59	0.00	0.00	0.66	-1.94	1.93	9.25	59.65	5.8	16.3	0.1	14.6	-19.4	-4.9	-10.7	-21.2	16.33	-23.87	0.04	OK
B2	D27	A18.5	633	-4.58	0.00	0.00	0.32	0.36	0.92	3.74	42.45	1.9	10.0	-0.4	9.3	-15.4	-5.7	-8.1	-16.1	10.00	-19.62	0.03	OK
B3	D27	A18.5	633	-5.55	0.00	0.00	-0.07	4.13	-0.22	2.73	43.91	1.1	9.7	-0.6	9.2	-16.6	-6.8	-8.5	-17.1	9.69	-21.34	0.03	OK

Story	ETABS #	Section	Capacity	Dead	Live	WindFX	WindMTX	WindFY	WindMTY	SpecX	SpecY									Maximum Axial Loads Tension	Compression	DCR	Status
Story10	D28	A25	855	-24.39	0.00	0.00	46.26	-464.01	133.49	716.18	2527.20	434.8	808.0	-13.2	673.6	-706.3	-19.5	-467.5	-840.7	807.99	-859.21	1.00	Say OK
Story9	D28	A25	855	-22.22	0.00	0.00	35.54	-371.82	102.65	552.63	2010.14	338.6	639.2	-7.1	535.5	-565.3	-22.8	-368.4	-669.0	639.18	-685.86	0.80	OK
Story8	D28	A25	855	-20.54	0.00	0.00	33.30	-338.26	96.23	519.73	1881.96	317.9	598.8	-7.2	501.3	-528.9	-20.4	-345.5	-626.4	598.83	-641.96	0.75	OK
Story7	D28	A27	923	-20.05	0.00	0.00	33.78	-336.90	97.68	529.39	1925.81	325.2	613.2	-5.9	513.9	-540.8	-21.0	-352.1	-640.1	613.20	-655.30	0.71	OK
Story6	D28	A27	923	-18.72	0.00	0.00	32.99	-320.87	95.45	519.43	1897.58	320.4	604.7	-4.4	507.2	-532.4	-20.7	-345.6	-629.8	604.70	-644.00	0.70	OK
Story5	D28	A27	923	-17.26	0.00	0.00	32.46	-307.38	93.97	513.55	1887.89	318.7	602.2	-2.5	505.9	-529.0	-20.7	-341.9	-625.4	602.22	-638.46	0.69	OK
Story4	D28	A27	923	-16.06	0.00	0.00	32.21	-296.63	93.32	512.03	1893.13	319.5	604.5	-0.7	508.4	-529.9	-20.8	-341.1	-626.0	604.46	-638.18	0.69	OK
Story3	D28	A27	923	-14.68	0.00	0.00	31.74	-282.65	92.02	506.94	1877.38	317.4	600.2	0.4	505.1	-524.8	-20.1	-337.1	-619.9	600.19	-631.01	0.68	OK
Story2	D28	A27	923	-13.51	0.00	0.00	30.96	-263.12	89.84	496.77	1825.15	310.3	584.4	-0.4	491.2	-509.3	-17.8	-328.5	-602.5	584.36	-612.74	0.66	OK
Story1	D28	A27	923	-10.82	0.00	0.00	25.54	-203.71	74.20	411.69	1492.10	255.6	478.4	-1.9	401.2	-415.7	-12.6	-270.1	-492.9	478.41	-501.12	0.54	OK
Ground	D28	A18.5	633	-8.53	0.00	0.00	-0.80	-0.36	-2.33	11.81	59.84	3.4	13.3	-4.0	11.1	-22.5	-7.4	-14.8	-24.8	13.32	-31.22	0.05	OK
B1	D28	A18.5	633	-7.48	0.00	0.00	-0.54	0.80	-1.57	7.31	55.86	2.3	12.4	-2.3	11.0	-21.1	-7.8	-12.3	-22.4	12.41	-28.11	0.04	OK
B2	D28	A18.5	633	-6.51	0.00	0.00	-0.19	-1.49	-0.56	1.83	39.45	-0.2	7.6	-1.4	7.3	-16.0	-7.3	-8.5	-16.4	7.63	-21.29	0.03	OK
B3	D28	A18.5	633	-5.55	0.00	0.00	0.20	-5.26	0.57	4.65	48.45	2.1	11.2	-0.8	10.4	-17.8	-6.6	-9.5	-18.7	11.23	-22.89	0.04	OK

SIMPSON GUMPERTZ & HEGER
Engineering of Structures and Building Enclosures

CLIENT Pacific Earthquake Engineering Research Center
SUBJECT BRB Strength Check along Line 3 for LA BRBF Bldg

SHEET NO. ____
PROJECT NO. 087237.10
DATE 1/23/09
BY AD
CHECKED BY ____

V-target= 3626.26 kips(85% of Static Base Shear)
V-SPECX= 11595.55 kips Scale-X= 3.20
V-SPECY= 12103.43 kips Scale-Y= 3.34
SDS = 1.145
ρ-X dir = 1
ρ -Y dir = 1

Model: 121908Model1

| | | |

SIMPSON GUMPERTZ & HEGER
Engineering of Structures and Building Enclosures

CLIENT Pacific Earthquake Engineering Research Center
SUBJECT BRB Strength Check along Line 3 for LA BRBF Bldg

SHEET NO. ____
PROJECT NO. 087237.10
DATE 1/23/09
BY AD
CHECKED BY ____

V-target= 3626.26 kips(85% of Static Base Shear) Model: 121908Model1
V-SPECX= 11595.55 kips Scale-X= 3.20
V-SPECY= 12103.43 kips Scale-Y= 3.34
SDS = 1.145
ρ-X dir = 1
ρ -Y dir = 1

1.2	1.2	1.2	1.2	1.2	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9
1	1	1	1	1																																											
-0.9008	-0.9008	0.9008	-0.9008	-0.9008	1.6	-1.6				1.2	1.2	-1.2	-1.2	1.2	1.2	-1.2	-1.2													0.9008	0.9008	-0.9008	-0.9008	0.9008	0.9008	0.9008	-0.9008	-0.9008	0.9008	0.9008	-0.9008	-0.9008	0.9008	-0.9008
-0.9008	-0.9008	-0.9008	0.9008	0.9008										1.2	-1.2	1.2	-1.2													0.9008	-0.9008	0.9008	-0.9008	0.9008	0.9008	0.9008	-0.9008	-0.9008	0.9008	-0.9008	-0.9008	-0.9008	-0.9008	0.9008
-0.9008	0.9008	-0.9008	0.9008	-0.9008			1.6	-1.6	1.2	-1.2	1.2	-1.2						1.2	1.2	-1.2	-1.2	0.9008	0.9008	0.9008	-0.9008	0.9008	-0.9008	-0.9008	-0.9008	-0.9008	-0.9008	0.9008	-0.9008	0.9008	-0.9008	-0.9008	-0.9008	0.9008	-0.9008	0.9008	-0.9008	0.9008	-0.9008	0.9008	-0.9008	0.9008
0.9008	-0.9008	0.9008	-0.9008	0.9008																1.2	-1.2	0.9008	0.9008	0.9008	-0.9008	0.9008	-0.9008	-0.9008	-0.9008	-0.9008	-0.9008	0.9008	-0.9008	0.9008	-0.9008	-0.9008	-0.9008	0.9008	-0.9008	0.9008	-0.9008	0.9008	-0.9008	0.9008	-0.9008	0.9008
							Figure 6-9 Case 1				Figure 6-9 Case 2						Figure 6-9 Case 3												Figure 6-9 Case 4																

Story	ETABS #	Section	Capacity	Dead	Live	WindFX	WindMTX	WindFY	WindMTY																																						
Story40	D13	A7	239	-2.57	0.00	0.00	-5.98	10.93	-17.19	-23.0	27.6	-23.0	16.9	-33.8	-2.3	-2.3	15.2	-19.8	10.8	-15.4	10.8	-15.4	-9.5	4.9	-9.5	4.9	-9.8	31.4	-36.1	5.2	-13.3	-2.6	-13.3	-2.6	17.6	-33.0	-2.1	8.7	-2.1	8.7	28.4	-22.3	28.4	-22.3	17.6
Story39	D13	A7	239	-2.62	0.00	0.01	-6.95	19.09	-19.96	-32.1	38.3	-32.1	25.8	-44.6	-2.3	-2.4	28.2	-32.9	20.6	-25.3	20.5	-25.3	-10.7	6.0	-10.7	6.0	-3.4	44.5	-49.2	-1.3	-9.4	3.1	-9.4	3.1	26.6	-43.8	-7.8	4.7	-7.9	4.7	39.1	-31.3	39.1	-31.3	26.6
Story38	D13	A9	308	-2.74	0.00	0.03	-9.82	33.74	-28.19	-50.3	61.3	-50.2	43.6	-67.9	-2.4	-2.5	51.5	-56.5	38.1	-42.9	38.0	-43.0	-14.2	9.4	-14.3	9.3	4.2	71.9	-76.8	-9.1	-6.3	11.4	-6.3	11.3	44.5	-67.1	-16.3	1.3	-16.3	1.4	62.2	-49.4	62.1	-49.4	44.4
Story37	D13	A9	308	-2.79	0.00	0.07	-10.65	44.73	-30.56	-61.6	74.0	-61.5	54.8	-80.8	-2.4	-2.6	69.0	-74.1	51.2	-56.1	51.1	-56.3	-15.2	10.3	-15.4	10.2	14.5	87.8	-92.9	-19.5	0.7	19.9	0.6	19.8	55.8	-79.9	-24.8	-5.7	-24.9	-5.6	75.0	-60.8	74.8	-60.7	55.7
Story36	D13	A9	308	-2.85	0.00	0.11	-11.83	54.14	-33.97	-72.2	86.5	-72.0	65.2	-93.5	-2.4	-2.7	84.1	-89.2	62.5	-67.4	62.3	-67.7	-16.6	11.8	-16.9	11.5	21.6	103.2	-108.3	-26.8	5.0	26.4	4.9	26.2	66.2	-92.5	-31.3	-10.2	-31.5	-10.0	87.6	-71.4	87.4	-71.2	66.0
Story35	D13	A11	376	-2.95	0.00	0.16	-15.02	61.30	-43.15	-84.2	103.9	-83.9	76.9	-111.3	-2.4	-2.9	95.4	-100.7	71.1	-76.0	70.7	-76.4	-20.5	15.6	-20.9	15.2	19.1	122.7	-128.0	-24.4	0.3	27.4	0.0	27.1	78.0	-110.1	-32.4	-5.6	-32.7	-5.3	105.1	-83.4	104.8	-83.1	77.8
Story34	D13	A11	376	-3.00	0.00	0.22	-15.54	70.77	-44.63	-93.8	114.2	-93.4	86.2	-121.8	-2.3	-3.1	110.5	-115.9	82.5	-87.4	82.0	-87.9	-21.1	16.2	-21.6	15.7	28.7	135.8	-141.2	-34.1	7.0	35.0	6.6	34.6	87.5	-120.5	-40.0	-12.4	-40.5	-12.0	115.5	-92.9	115.1	-92.5	87.1
Story33	D13	A11	376	-2.96	0.00	0.24	-16.77	81.57	-48.16	-105.5	128.2	-105.1	98.0	-135.7	-2.3	-3.0	127.8	-133.2	95.5	-100.3	94.9	-100.8	-22.5	17.8	-23.1	17.2	37.4	153.0	-158.3	-42.8	12.6	42.8	12.1	42.3	99.3	-134.4	-47.6	-17.9	-48.1	-17.4	129.5	-104.6	129.1	-104.2	98.9
Story32	D13	A11	376	-3.01	0.00	0.31	-17.98	91.08	-51.65	-116.3	140.9	-115.7	108.5	-148.6	-2.2	-3.2	143.0	-148.4	107.0	-111.6	106.2	-112.4	-23.9	19.2	-24.7	18.5	44.6	168.6	-174.0	-50.0	16.9	49.3	16.3	48.7	109.9	-147.2	-54.1	-22.3	-54.7	-21.8	142.3	-115.4	141.8	-114.8	109.4
Story31	D13	A13.5	462	-2.95	0.00	0.28	-22.47	109.86	-64.54	-140.7	173.6	-140.2	133.1	-181.1	-2.2	-3.1	173.1	-178.4	129.5	-134.2	128.8	-134.8	-29.3	24.6	-30.0	24.0	51.7	206.6	-211.9	-57.0	18.2	58.7	17.7	58.2	134.5	-179.7	-63.5	-23.5	-64.0	-23.0	174.9	-139.8	174.4	-139.3	134.0
Story30	D13	A13.5	462	-2.99	0.00	0.34	-23.20	119.52	-66.64	-150.7	184.7	-150.1	142.9	-192.5	-2.1	-3.2	188.5	-193.9	141.1	-145.7	140.3	-146.5	-30.1	25.6	-30.9	24.7	60.8	220.7	-226.1	-66.1	24.3	66.1	23.7	65.5	144.4	-191.0	-70.9	-29.7	-71.5	-29.1	186.2	-149.8	185.6	-149.2	143.8
Story29	D13	A13.5	462	-2.95	0.00	0.36	-24.60	129.82	-70.70	-162.3	198.9	-161.7	154.6	-206.7	-2.1	-3.2	205.1	-210.4	153.6	-158.0	152.7	-158.9	-31.7	27.3	-32.6	26.4	68.3	238.0	-243.3	-73.6	28.8	73.1	28.1	72.4	156.1	-205.1	-77.8	-34.1	-78.4	-33.4	200.5	-161.4	199.8	-160.8	155.5
Story28	D13	A13.5	462	-2.99	0.00	0.43	-25.74	138.37	-73.99	-172.1	210.5	-171.3	164.1	-218.5	-2.0	-3.4	218.7	-224.1	163.9	-168.2	162.8	-169.2	-33.1	28.7	-34.1	27.7	74.6	252.1	-257.5	-79.9	32.5	78.9	31.7	78.1	165.8	-216.8	-83.5	-37.9	-84.3	-37.1	212.2	-171.2	211.4	-170.4	165.0
Story27	D13	A13.5	462	-2.91	0.00	0.40	-25.16	136.19	-72.34	-169.0	206.7	-168.3	161.3	-214.4	-2.0	-3.3	215.3	-220.5	161.3	-165.6	160.3	-166.5	-32.3	28.0	-33.3	27.1	74.0	247.6	-252.9	-79.2	32.6	77.9	31.9	77.2	162.9	-212.8	-82.4	-37.8	-83.2	-37.1	208.2	-168.2	207.5	-167.4	162.2
Story26	D13	A13.5	462	-2.95	0.00	0.46	-25.84	144.19	-74.30	-177.5	216.1	-176.7	169.6	-224.0	-1.9	-3.4	228.0	-233.4	170.9	-175.1	169.8	-176.2	-33.1	28.9	-34.2	27.8	81.2	259.5	-264.8	-86.5	37.4	84.0	36.6	83.2	171.3	-222.3	-88.5	-42.7	-89.3	-41.9	217.8	-176.6	217.0	-175.8	170.5
Story25	D13	A13.5	462	-2.91	0.00	0.47	-26.28	151.63	-75.58	-184.9	224.4	-184.1	177.1	-232.3	-1.9	-3.4	240.0	-245.2	179.9	-184.0	178.8	-185.1	-33.6	29.5	-34.7	28.3	88.6	270.0	-275.3	-93.9	42.6	90.0	41.8	89.1	178.8	-230.5	-94.4	-47.9	-95.2	-47.0	226.1	-184.1	225.3	-183.2	178.0
Story24	D13	A13.5	462	-2.95	0.00	0.54	-26.79	157.93	-77.09	-191.6	231.8	-190.6	183.5	-239.9	-1.8	-3.5	250.0	-255.3	187.5	-191.5	186.2	-192.8	-34.2	30.1	-35.4	28.9	94.4	279.4	-284.7	-99.7	46.5	94.8	45.5	93.8	185.4	-238.0	-99.1	-51.8	-100.1	-50.9	233.7	-190.7	232.7	-189.7	184.4
Story23	D13	A13.5	462	-2.91	0.00	0.54	-26.63	158.59	-76.64	-191.9	231.9	-190.9	183.9	-239.9	-1.8	-3.5	251.1	-256.4	188.3	-192.3	187.0	-193.6	-33.9	30.0	-35.2	28.7	95.7	279.7	-284.9	-101.0	47.7	95.7	46.7	94.7	185.8	-238.0	-99.9	-52.9	-100.9	-52.0	233.8	-191.0	232.8	-190.0	184.8
Story22	D13	A13.5	462	-2.95	0.00	0.61	-26.95	163.47	-77.58	-196.9	237.3	-195.9	188.8	-245.5	-1.7	-3.6	258.9	-264.2	194.2	-198.1	192.8	-199.6	-34.3	30.4	-35.7	29.0	100.4	286.6	-291.9	-105.7	51.0	99.5	49.9	98.5	190.8	-243.5	-103.8	-56.3	-104.9	-55.2	239.3	-196.1	238.2	-195.0	189.7
Story21	D13	A13.5	462	-2.87	0.00	0.56	-27.21	167.15	-78.36	-200.6	241.7	-199.6	192.7	-249.6	-1.7	-3.5	264.9	-270.0	198.7	-202.5	197.3	-203.8	-34.6	30.7	-35.9	29.4	104.0	292.0	-297.2	-109.1	53.4	102.4	52.4	101.4	194.6	-247.7	-106.6	-58.6	-107.6	-57.6	243.6	-199.7	242.6	-198.7	193.5
Story20	D13	A13.5	462	-2.91	0.00	0.62	-27.10	169.08	-78.05	-202.3	243.0	-201.1	194.2	-251.1	-1.6	-3.6	267.9	-273.1	201.0	-204.8	199.5	-206.3	-34.4	30.7	-35.9	29.2	106.6	293.9	-299.2	-111.9	55.5	104.4	54.4	103.2	196.2	-249.1	-108.5	-60.8	-109.6	-59.6	245.0	-201.4	243.9	-200.3	195.0
Story19	D13	A13.5	462	-2.94	0.00	0.69	-25.87	163.29	-74.52	-195.1	233.4	-193.8	186.8	-241.7	-1.5	-3.7	258.6	-263.9	194.1	-197.8	192.5	-199.4	-32.9	29.2	-34.5	27.6	103.9	282.7	-288.0	-109.2	54.6	101.2	53.4	100.0	188.9	-239.5	-105.3	-59.9	-106.5	-58.7	235.5	-194.2	234.3	-192.9	187.6
Story18	D13	A13.5	462	-2.97	0.00	0.75	-25.56	164.13	-73.66	-195.4	233.0	-194.1	186.9	-241.5	-1.5	-3.9	259.9	-265.3	195.2	-198.7	193.4	-200.5	-32.4	28.9	-34.3	27.1	105.9	282.7	-288.0	-111.2	56.5	102.5	55.1	101.2	189.2	-239.2	-106.5	-61.8	-107.9	-60.5	235.2	-194.5	233.9	-193.2	187.8
Story17	D13	A13.5	462	-2.93	0.00	0.75	-25.40	166.22	-73.20	-197.0	234.4	-195.6	188.6	-242.7	-1.4	-3.8	263.3	-268.6	197.7	-201.2	195.9	-203.0	-32.2	28.7	-34.0	26.9	109.0	284.7	-289.9	-114.3	59.0	104.7	57.6	103.4	190.8	-240.5	-108.6	-64.2	-110.0	-62.9	236.6	-196.1	235.2	-194.8	189.5
Story16	D13	A13.5	462	-2.96	0.00	0.82	-25.22	169.30	-72.69	-199.6	236.4	-198.1	191.0	-245.0	-1.4	-4.0	268.2	-273.5	201.5	-204.8	199.5	-206.8	-31.9	28.6	-33.9	26.6	113.3	287.7	-293.1	-118.6	62.4	107.8	60.9	106.3	193.3	-242.6	-111.7	-67.7	-113.1	-66.2	238.8	-198.7	237.3	-197.2	191.9
Story15	D13	A13.5	462	-2.92	0.00	0.82	-24.95	171.59	-71.96	-201.1	237.6	-199.7	192.7	-246.1	-1.3	-3.9	271.9	-277.2	204.3	-207.5	202.3	-209.5	-31.6	28.3	-33.6	26.3	116.9	289.6	-294.9	-122.2	65.4	110.3	63.9	108.9	195.0	-243.8	-114.1	-70.6	-115.6	-69.2	240.0	-200.3	238.5	-198.8	193.5
Story14	D13	A13.5	462	-2.95	0.00	0.88	-24.68	174.25	-71.20	-203.2	239.0	-201.6	194.5	-247.7	-1.2	-4.1	276.2	-281.5	207.5	-210.7	205.4	-212.8	-31.2	28.0	-33.3	25.9	121.0	291.9	-297.2	-126.3	68.7	113.2	67.1	111.6	197.0	-245.2	-116.9	-74.0	-118.5	-72.5	241.5	-202.3	239.9	-200.7	195.4
Story13	D13	A13.5	462	-2.98	0.00	0.95	-24.07	172.28	-69.46	-200.5	235.0	-198.8	191.6	-243.9	-1.2	-4.2	273.0	-278.3	205.2	-208.3	202.9	-210.6	-30.4	27.3	-32.7	25.1	120.7	287.4	-292.8	-126.1	69.1	112.5	67.4	110.8	194.3	-241.3	-116.1	-74.5	-117.8	-72.8	237.6	-199.6	235.9	-197.9	192.5
Story12	D13	A13.5	462	-3.01	0.00	1.02	-22.36	157.24	-64.55	-184.2	215.4	-182.3	175.1	-224.5	-1.1	-4.3	248.9	-254.3	187.2	-190.2	184.8	-192.6	-28.3	25.3	-30.8	22.9	108.5	263.4	-268.9	-113.9	61.6	101.8	59.7	100.0	177.9	-221.7	-105.4	-67.0	-107.3	-65.1	218.1	-183.3	216.3	-181.4	176.0
Story11	D13	A13.5	462	-2.96	0.00	1.01	-17.16	107.38	-49.58	-120.4	152.4	-128.6	121.5	-161.3	-1.0	-4.3	169.1	-174.5	127.4	-130.3	125.0	-132.7	-22.0	19.1	-24.5	16.7	66.7	185.7	-191.0	-72.0	34.9	65.8	33.0	63.9	124.2	-158.6	-69.3	-40.2	-71.1	-38.4	155.1	-129.5	153.3	-127.7	122.4
Story10	D13	A13.5	462	-2.99	0.00	1.08	-4.90	-3.32	-14.24	-10.0	9.7	-8.0	0.9	-18.8	-1.0	-4.4	-8.0	2.6	-5.4	2.6	-8.0	0.0	-7.3	4.5	-9.9	1.9	-23.8	10.4	-15.8	18.4	-21.9	-13.1	-23.9	-15.1	3.7	-16.0	9.7	16.6	7.7	18.5	12.5	-9.1	10.6	-7.1	1.8
Story9	D13	A13.5	462	-2.96	0.00	1.08	-3.02	-23.82	-8.81	11.7	-15.3	-7.2	3.3	-30.4	-1.0	-4.4	-40.8	35.5	-29.9	27.2	-32.5	24.6	-5.0	2.3	-7.6	-0.3	-41.8	-20.7	15.4	36.5	-33.8	-28.4	-35.7	-30.3	-17.9	9.1	25.0	28.5	23.0	30.4	-12.5	12.6	-14.4	14.6	-19.9
Story8	D13	A13.5	462	-2.98	0.00	1.15	3.47	14.92	10.12	-12.1	-3.4	-10.0	2.8	-5.8	-0.8	-4.5	21.2	-26.5	16.6	-19.2	13.8	-22.0	2.9	-5.5	0.1	-8.2	27.4	3.1	-8.4	-32.7	24.0	17.8	22.0	15.7	5.8	-2.8	-21.1	-29.4	-23.1	-27.3	-0.5	-11.2	-2.5	-9.1	3.7
Story7	D13	A13.5	462	-3.00	0.00	1.22	3.88	3.29	11.32	-1.0	-15.4	1.2	-8.4	6.0	-0.8	-4.7	2.6	-8.0	2.7	-5.2	-0.2	-8.1	3.4	-5.9	0.5	-8.8	14.8	-12.3	6.9	-20.2	15.0	8.1	12.9	5.9	-5.3	9.1	-11.3	-20.5	-13.5	-18.3	-12.3	-0.1	-14.5	2.1	-7.5
Story6	D13	A13.5	462	-3.03	0.00	1.29	4.51	-11.94	13.13	13.7	-31.4	16.0	-23.3	21.8	-0.7	-4.8	-21.8	16.4	-15.5	13.1	-18.6	10.0	4.2	-6.6	1.1	-9.7	-1.3	-32.8	27.4	-4.2	3.6	-4.6	1.2	-6.9	-20.1	25.1	1.4	-9.0	-0.9	-6.7	-28.2	14.6	-30.5	17.0	-22.4
Story5	D13	A13.5	462	-3.00	0.00	1.29	5.08	-25.72	14.80	27.2	-45.8	29.5	-36.7	36.3	-0.6	-4.7	-43.8	38.5	-32.0	29.7	-35.1	26.6	5.0	-7.2	1.9	-10.3	-15.8	-51.3	45.9	10.4	-6.8	-15.9	-9.1	-18.3	-33.5	39.5	12.9	1.4	10.6	3.7	-42.6	28.1	-44.9	30.4	-35.8
Story4	D13	A13.5	462	-3.01	0.00	1.36	5.60	-38.86	16.32	39.8	-59.6	42.3	-49.5	49.9	-0.5	-4.9	-64.9	59.5	-47.7	45.5	-51.0	42.3	5.6	-7.8	2.4	-11.1	-29.8	-68.9	63.5	24.3	-16.7	-26.8	-19.2	-29.3	-46.1	53.3	23.9	11.3	21.4	13.8	-56.2	40.7	-58.7	43.2	-48.6
Story3	D13	A13.5	462	-2.97	0.00	1.35	6.02	-49.24	17.54	49.9	-70.4	52.4	-59.5	60.8	-0.5	-4.8	-81.4	76.1	-60.1	58.0	-63.4	54.8	6.2	-8.3	2.9	-11.5	-40.7	-82.8	77.5	35.4	-24.6	-35.4	-27.0	-37.9	-56.2	64.1	32.5	19.2	30.1	21.7	-67.0	50.8	-69.5	53.3	-58.6
Story2	D13	A13.5	462	-3.00	0.00	1.41	6.27	-55.26	18.26	55.7	-76.7	58.3	-65.4	67.0	-0.4	-5.0	-91.1	85.7	-67.3	65.3	-70.7	61.9	6.5	-8.5	3.1	-11.9	-47.1	-90.9	85.5	41.7	-29.1	-40.4	-31.7	-42.9	-62.0	70.4	37.6	23.7	35.0	26.3	-73.3	56.6	-75.8	59.2	-64.5
Story1	D13	A13.5	462	-2.92	0.00	1.75	4.79	-39.08	13.95	38.4	-57.2	41.5	-48.5	47.0	0.2	-5.4	-65.1	59.9	-47.4	46.4	-51.6	42.2	5.2	-6.3	1.0	-10.5	-32.8	-66.3	61.0	27.5	-19.4	-28.0	-22.5	-31.1	-44.5	51.0	25.9	14.1	22.7	17.3	-53.1	39.3	-56.3	42.4	-47.7
Ground	D13	A13.5	462	-3.14	0.00	1.43	-1.72	45.49	-4.95	-48.9	41.9	-46.4	38.8	-52.0	-0.5	-5.1	70.0	-75.6	53.5	-55.7	50.0	-59.1	-3.2	0.9	-6.6	-2.5	45.8	57.7	-63.4	-51.5	33.4	36.5	30.9	34.0	42.4	-48.5	-39.6	-39.1	-42.2	-36.5	45.4	-48.0	42.9	-45.4	39.8
B1	D13	A13.5	462	-3.09	0.00	1.35	-1.14	31.11	-3.30	-34.9	27.1	-32.5	25.0	-37.0	-0.6	-4.9	47.0	-52.6	36.2	-38.5	32.9	-41.7	-2.5	0.2	-5.8	-3.0	30.6	38.5	-44.1	-36.2	22.5	24.5	20.0	22.1	28.4	-33.6	-27.6	-28.0	-30.1	-25.6	30.5	-34.0	28.0	-31.5	26.0
B2	D13	A13.5	462	-3.11	0.00	1.35	0.55	-14.19	1.59	8.8	-19.7	11.2	-18.7	9.8	-0.6	-5.0	-25.5	19.9	-18.2	15.9	-21.5	12.6	-0.5	-1.8	-3.8	-5.1	-17.9	-21.7	16.1	12.3	-12.4	-13.4	-14.9	-15.9	-15.3	13.1	10.3	6.8	7.8	9.3	-16.3	9.7	-18.7	12.1	-17.7
B3	D13	A13.5	462	-3.13	0.00	1.35	0.06	-3.86	0.17	-1.4	-8.7	1.0	-8.5	-1.3	-0.7	-5.0	3.3	-9.0	3.4	-5.8	0.2	-9.1	-1.3	-1.1	-4.5	-4.4	1.6	2.0	-7.7	-7.2	1.7	1.8	-0.8	-0.7	2.0	-5.3	-5.0	-7.3	-7.4	-4.9	2.1	-7.6	-0.4	-5.2	-0.5

Story	ETABS #	Section	Capacity	Dead	Live	WindFX	WindMTX	WindFY	WindMTY																																						
Story40	D14	A7	239	-2.57	0.00	0.00	5.98	-10.93	17.19	16.9	-33.8	16.9	-23.0	27.6	-2.3	-2.3	-19.8	15.2	-15.4	10.8	-15.4	10.8	4.9	-9.5	4.9	-9.5	5.2	-36.1	31.4	-9.8	8.7	-2.1	8.7	-2.1	-22.3	28.4	-2.6	-13.3	-2.6	-13.3	-33.0	17.6	-33.0	17.6	-22.3
Story39	D14	A7	239	-2.62	0.00	0.01	6.95	-19.09	19.96	25.8	-44.6	25.8	-32.1	38.3	-2.3	-2.4	-32.9	28.2	-25.3	20.6	-25.3	20.5	6.0	-10.7	6.0	-10.7	-1.3	-49.2	44.5	-3.4	4.7	-7.8	4.7	-7.9	-31.3	39.1	3.1	-9.4	3.1	-9.4	-43.8	26.6	-43.8	26.6	-31.3
Story38	D14	A9	308	-2.74	0.00	0.03	9.82	-33.74	28.19	43.6	-67.9	43.7	-50.3	61.3	-2.4	-2.5	-56.5	51.5	-42.9	38.1	-43.0	38.0	9.4	-14.2	9.3	-14.3	-9.1	-76.8	71.9	4.2	1.4	-16.3	1.3	-16.3	-49.4	62.2	11.4	-6.3	11.3	-6.3	-67.1	44.4	-67.1	44.5	-49.4
Story37	D14	A9	308	-2.79	0.00	0.07	10.65	-44.73	30.56	54.8	-80.8	54.9	-61.6	74.0	-2.4	-2.6	-74.1	69.0	-56.1	51.2	-56.3	51.1	10.3	-15.2	10.2	-15.4	-19.5	-92.9	87.8	14.5	-5.6	-24.8	-5.7	-24.9	-60.7	75.0	19.9	0.6	19.8	0.7	-79.9	55.7	-80.0	55.8	-60.8
Story36	D14	A9	308	-2.85	0.00	0.11	11.83	-54.14	33.97	65.2	-93.5	65.4	-72.2	86.5	-2.4	-2.7	-89.2	84.1	-67.4	62.5	-67.7	62.3	11.8	-16.6	11.5	-16.9	-26.8	-108.3	103.2	21.6	-10.0	-31.3	-10.2	-31.5	-71.2	87.6	26.4	4.9	26.2	5.0	-92.5	66.0	-92.7	66.2	-71.4
Story35	D14	A11	376	-2.95	0.00	0.16	15.02	-61.30	43.15	76.9	-111.3	77.2	-84.2	103.9	-2.4	-2.9	-100.7	95.4	-76.0	71.1	-76.4	70.7	15.6	-20.5	15.2	-20.9	-24.4	-128.0	122.7	19.1	-5.3	-32.4	-5.6	-32.7	-83.1	105.1	27.4	0.0	27.1	0.3	-110.1	77.8	-110.4	78.0	-83.4
Story34	D14	A11	376	-3.00	0.00	0.22	15.54	-70.77	44.63	86.2	-121.8	86.6	-93.8	114.2	-2.3	-3.1	-115.9	110.5	-87.4	82.5	-87.9	82.0	16.2	-21.1	15.7	-21.6	-34.1	-141.2	135.8	28.7	-12.0	-40.0	-12.4	-40.5	-

SIMPSON GUMPERTZ & HEGER
Engineering of Structures and Building Enclosures

CLIENT Pacific Earthquake Engineering Research Center
SUBJECT BRB Strength Check along Line 3 for LA BRBF Bldg

SHEET NO.
PROJECT NO. 087237.10
DATE 1/23/09
BY AD
CHECKED BY

V-target= 3626.26 kips(85% of Static Base Shear)
V-SPECX= 11595.55 kips Scale-X= 3.20
V-SPECY= 12103.43 kips Scale-Y= 3.34
SDS = 1.145
ρ-X dir = 1
ρ -Y dir = 1

Model: 121908Model1

0.9	1.429	1.429	1.429	1.429	1.429	1.429	1.429	1.429	0.671	0.671	0.671	0.671	0.671	0.671	0.671	0.671											
	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5																			
-0.9008																											
0.9008																											
-0.9008																											
0.9008																											
	1	0.3	-1	-0.3	0.3	1	-1	-0.3	1	0.3	-1	-0.3	0.3	1	-1	-0.3											
	0.3	1	0.3	1	-1	-0.3	-0.3	-1	0.3	1	0.3	1	-1	-0.3	-0.3	-1											

Story	ETABS #	Section	Capacity	Dead	Live	WindFX	WindMTX	WindFY	WindMTY																						
																												Maximum Axial Loads			
																												Tension	Compression	DCR	Status
Story40	D13	A7	239	-2.57	0.00	0.00	-5.98	10.93	-17.19	-33.0	68.8	144.8	7.4	126.4	-133.7	-14.8	-76.1	-152.1	70.7	146.7	9.4	128.3	-131.8	-12.8	-74.2	-150.2	146.72	-152.12	0.64	OK
Story39	D13	A7	239	-2.62	0.00	0.01	-6.95	19.09	-19.96	-43.8	79.9	166.3	8.2	144.8	-152.3	-15.7	-87.4	-173.8	81.9	168.3	10.1	146.8	-150.3	-13.7	-85.4	-171.8	168.29	-173.80	0.73	OK
Story38	D13	A9	308	-2.74	0.00	0.03	-9.82	33.74	-28.19	-67.1	119.2	252.2	17.5	221.7	-229.5	-25.3	-127.1	-260.1	121.3	254.3	19.5	223.8	-227.5	-23.2	-125.0	-258.0	254.31	-260.06	0.84	OK
Story37	D13	A9	308	-2.79	0.00	0.07	-10.65	44.73	-30.56	-80.0	127.4	268.4	18.2	235.7	-243.7	-26.2	-135.4	-276.4	129.5	270.6	20.3	237.8	-241.5	-24.1	-133.3	-274.3	270.56	-276.43	0.90	OK
Story36	D13	A9	308	-2.85	0.00	0.11	-11.83	54.14	-33.97	-92.7	139.4	289.6	17.7	253.1	-261.2	-25.9	-147.5	-297.7	141.5	291.7	19.9	255.2	-259.1	-23.7	-145.3	-295.5	291.72	-297.70	0.97	OK
Story35	D13	A11	376	-2.95	0.00	0.16	-15.02	61.30	-43.15	-110.4	158.4	307.3	6.4	261.7	-270.1	-14.8	-166.8	-315.7	160.6	309.5	8.6	264.0	-267.9	-12.6	-164.6	-313.5	309.55	-315.74	0.84	OK
Story34	D13	A11	376	-3.00	0.00	0.22	-15.54	70.77	-44.63	-120.9	162.4	312.1	4.6	264.8	-273.4	-13.2	-171.0	-320.7	164.7	314.4	6.9	267.1	-271.1	-10.9	-168.7	-318.4	314.40	-320.71	0.85	OK
Story33	D13	A11	376	-2.96	0.00	0.24	-16.77	81.57	-48.16	-134.8	172.2	327.8	3.4	277.1	-285.6	-11.9	-180.6	-336.2	174.4	330.0	5.6	279.4	-283.3	-9.6	-178.4	-334.0	330.00	-336.21	0.89	OK
Story32	D13	A11	376	-3.01	0.00	0.31	-17.98	91.08	-51.65	-147.7	180.7	338.4	0.1	284.2	-292.8	-8.7	-189.3	-347.0	183.0	340.7	2.4	286.5	-290.5	-6.4	-187.0	-344.7	340.69	-347.00	0.92	OK
Story31	D13	A13.5	462	-2.95	0.00	0.28	-22.47	109.86	-64.54	-180.3	218.8	399.0	-5.4	331.8	-340.2	-3.0	-227.2	-407.5	221.0	401.3	-3.2	334.0	-338.0	-0.8	-225.0	-405.2	401.26	-407.45	0.88	OK
Story30	D13	A13.5	462	-2.99	0.00	0.34	-23.20	119.52	-66.64	-191.6	224.0	407.1	-6.5	338.0	-346.5	-2.1	-232.6	-415.7	226.3	409.4	-4.2	340.2	-344.3	0.2	-230.3	-413.4	409.40	-415.68	0.90	OK
Story29	D13	A13.5	462	-2.95	0.00	0.36	-24.60	129.82	-70.70	-205.8	234.7	423.5	-8.4	350.6	-359.0	-0.1	-243.1	-431.9	236.9	425.7	-6.1	352.8	-356.8	2.2	-240.9	-429.7	425.71	-431.91	0.94	OK
Story28	D13	A13.5	462	-2.99	0.00	0.43	-25.74	138.37	-73.99	-217.6	243.0	435.2	-10.7	359.1	-367.6	2.2	-251.6	-443.8	245.3	437.5	-8.4	361.4	-365.4	4.4	-249.3	-441.5	437.47	-443.76	0.96	OK
Story27	D13	A13.5	462	-2.91	0.00	0.40	-25.16	136.19	-72.34	-213.5	234.0	415.1	-13.0	341.1	-349.4	4.6	-242.3	-423.5	236.2	417.4	-10.8	343.3	-347.2	6.9	-240.1	-421.3	417.36	-423.47	0.92	OK
Story26	D13	A13.5	462	-2.95	0.00	0.46	-25.84	144.19	-74.30	-223.2	239.2	423.1	-14.0	347.1	-355.5	5.6	-247.6	-431.5	241.4	425.3	-11.8	349.4	-353.3	7.8	-245.4	-429.3	425.32	-431.51	0.93	OK
Story25	D13	A13.5	462	-2.91	0.00	0.47	-26.28	151.63	-75.58	-231.4	243.1	430.4	-13.8	353.4	-361.7	5.5	-251.4	-438.8	245.3	432.6	-11.6	355.6	-359.5	7.7	-249.2	-436.6	432.64	-438.76	0.95	OK
Story24	D13	A13.5	462	-2.95	0.00	0.54	-26.79	157.93	-77.09	-239.0	247.1	436.9	-14.5	358.4	-366.8	6.0	-255.6	-445.3	249.4	439.1	-12.2	360.7	-364.6	8.3	-253.3	-443.1	439.13	-445.32	0.96	OK
Story23	D13	A13.5	462	-2.91	0.00	0.54	-26.63	158.59	-76.64	-239.0	244.8	432.1	-14.8	354.2	-362.5	6.4	-253.1	-440.4	247.0	434.3	-12.6	356.4	-360.3	8.7	-250.9	-438.2	434.28	-440.39	0.95	OK
Story22	D13	A13.5	462	-2.95	0.00	0.61	-26.95	163.47	-77.58	-244.6	247.9	437.4	-15.0	358.6	-367.0	6.5	-256.3	-445.8	250.1	439.6	-12.7	360.8	-364.7	8.8	-254.0	-443.6	439.63	-445.81	0.97	OK
Story21	D13	A13.5	462	-2.87	0.00	0.56	-27.21	167.15	-78.36	-248.8	250.4	442.9	-14.3	363.5	-371.7	6.1	-258.6	-451.1	252.6	445.1	-12.1	365.7	-369.5	8.2	-256.5	-448.9	445.06	-451.10	0.98	OK
Story20	D13	A13.5	462	-2.91	0.00	0.62	-27.10	169.08	-78.05	-250.2	249.8	442.4	-14.0	363.2	-371.5	5.7	-258.1	-450.7	252.0	444.6	-11.8	365.4	-369.3	7.9	-255.9	-448.5	444.56	-450.66	0.98	OK
Story19	D13	A13.5	462	-2.94	0.00	0.69	-25.87	163.29	-74.52	-240.8	239.4	424.8	-13.1	349.1	-357.5	4.7	-247.8	-433.2	241.6	427.1	-10.9	351.3	-355.3	6.9	-245.6	-431.0	427.07	-433.24	0.94	OK
Story18	D13	A13.5	462	-2.97	0.00	0.75	-25.56	164.13	-73.66	-240.6	238.0	423.9	-12.1	348.9	-357.4	3.6	-246.4	-432.4	240.2	426.1	-9.8	351.1	-355.1	5.8	-244.2	-430.1	426.12	-432.36	0.94	OK
Story17	D13	A13.5	462	-2.93	0.00	0.75	-25.40	166.22	-73.20	-241.9	237.9	425.9	-10.6	351.4	-359.7	2.2	-246.3	-434.3	240.1	428.1	-8.3	353.6	-357.5	4.4	-244.0	-432.0	428.11	-434.26	0.94	OK
Story16	D13	A13.5	462	-2.96	0.00	0.82	-25.22	169.30	-72.69	-244.1	237.7	427.5	-9.4	353.4	-361.9	0.9	-246.2	-436.0	240.0	429.8	-7.1	355.7	-359.6	3.1	-243.9	-433.8	429.79	-436.01	0.94	OK
Story15	D13	A13.5	462	-2.92	0.00	0.82	-24.95	171.59	-71.96	-245.2	237.0	428.6	-7.6	355.2	-363.6	-0.7	-245.3	-436.9	239.2	430.8	-5.4	357.4	-361.4	1.5	-243.1	-434.7	430.82	-436.95	0.95	OK
Story14	D13	A13.5	462	-2.95	0.00	0.88	-24.68	174.25	-71.20	-246.8	236.2	429.3	-6.3	356.6	-365.0	-2.1	-244.6	-437.7	238.4	431.5	-4.1	358.8	-362.8	0.1	-242.4	-435.5	431.55	-437.74	0.95	OK
Story13	D13	A13.5	462	-2.98	0.00	0.95	-24.07	172.28	-69.46	-243.0	232.3	424.3	-5.0	353.1	-361.6	-3.5	-240.8	-432.8	234.5	426.5	-2.8	355.4	-359.4	-1.2	-238.5	-430.5	426.54	-432.79	0.94	OK
Story12	D13	A13.5	462	-3.01	0.00	1.02	-22.36	157.24	-64.55	-223.6	218.0	400.9	-3.4	334.5	-343.1	-5.2	-226.6	-409.5	220.3	403.2	-1.2	336.8	-340.8	-2.9	-224.4	-407.2	403.21	-409.53	0.89	OK
Story11	D13	A13.5	462	-2.96	0.00	1.01	-17.16	107.38	-49.58	-160.4	172.8	325.6	1.2	274.2	-282.6	-9.7	-181.3	-334.1	175.0	327.9	3.5	276.4	-280.4	-7.5	-179.0	-331.9	327.89	-334.11	0.72	OK
Story10	D13	A13.5	462	-2.99	0.00	1.08	-4.90	-3.32	-14.24	-17.9	73.6	173.9	19.9	157.8	-166.3	-28.5	-82.2	-182.4	75.9	176.2	22.2	160.1	-164.1	-26.2	-79.9	-180.2	176.16	-182.44	0.40	OK
Story9	D13	A13.5	462	-2.95	0.00	1.08	-3.02	-23.82	8.81	7.2	60.9	158.7	25.2	148.0	-156.4	-33.6	-69.3	-167.1	63.1	160.9	27.4	150.2	-154.2	-31.4	-67.1	-164.9	160.94	-167.13	0.36	OK
Story8	D13	A13.5	462	-2.98	0.00	1.15	-3.47	-14.92	-10.12	-2.5	64.9	164.8	24.3	152.6	-161.1	-32.8	-73.5	-173.3	67.2	167.1	26.6	154.9	-158.9	-30.6	-71.2	-171.1	167.07	-173.32	0.38	OK
Story7	D13	A13.5	462	-3.00	0.00	1.22	-3.88	-3.29	-11.32	-14.5	68.4	169.6	23.3	156.1	-164.7	-31.9	-77.0	-178.2	70.7	171.9	25.6	158.4	-162.4	-29.6	-74.7	-175.9	171.91	-178.22	0.39	OK
Story6	D13	A13.5	462	-3.03	0.00	1.29	-4.51	11.94	-13.13	-30.5	74.0	178.2	22.2	162.7	-171.4	-30.9	-82.7	-186.9	76.3	180.5	24.5	165.0	-169.1	-28.6	-80.4	-184.6	180.54	-186.91	0.40	OK
Story5	D13	A13.5	462	-2.99	0.00	1.29	-5.08	25.72	-14.80	-44.9	79.6	187.8	21.9	170.5	-179.0	-30.5	-88.1	-196.3	81.8	190.0	24.2	172.8	-176.8	-28.2	-85.8	-194.1	190.05	-196.32	0.43	OK
Story4	D13	A13.5	462	-3.01	0.00	1.36	-5.60	38.86	-16.32	-58.7	84.7	196.4	21.4	177.4	-186.1	-30.0	-93.3	-205.0	87.0	198.7	23.7	179.7	-183.8	-27.8	-91.0	-202.8	198.72	-205.05	0.44	OK
Story3	D13	A13.5	462	-2.97	0.00	1.35	-6.02	49.24	-17.54	-69.5	88.5	202.5	20.9	182.2	-190.7	-29.4	-97.0	-210.9	90.8	204.7	23.2	184.4	-188.4	-27.2	-94.8	-208.7	204.71	-210.95	0.46	OK
Story2	D13	A13.5	462	-3.00	0.00	1.41	-6.27	55.26	-18.26	-75.8	89.5	201.4	19.0	180.3	-188.8	-27.6	-98.0	-210.0	91.8	203.7	21.3	182.5	-186.6	-25.3	-95.8	-207.7	203.68	-209.97	0.45	OK
Story1	D13	A13.5	462	-2.92	0.00	1.75	-4.79	39.08	-13.95	-56.3	68.0	149.9	11.0	132.8	-141.2	-19.4	-76.3	-158.3	70.2	152.1	13.2	135.0	-139.0	-17.1	-74.1	-156.0	152.13	-158.25	0.34	OK
Ground	D13	A13.5	462	-3.14	0.00	1.43	1.72	-45.49	4.95	42.9	22.4	50.6	-0.3	43.8	-52.8	-8.6	-31.3	-59.6	24.7	53.0	2.0	46.2	-50.4	-6.3	-29.0	-57.2	69.96	-76.55	0.17	OK
B1	D13	A13.5	462	-3.09	0.00	1.35	1.14	31.11	-3.30	-28.0	14.8	34.2	-2.0	29.2	-38.0	-6.9	-23.6	-43.0	17.1	36.5	0.4	31.5	-35.7	-4.5	-21.3	-40.7	47.00	-53.49	0.12	OK
B2	D13	A13.5	462	-3.11	0.00	1.35	0.55	-14.19	1.59	10.7	6.7	16.2	-4.2	12.9	-21.8	-4.6	-15.6	-25.1	9.1	18.5	-1.9	15.2	-19.4	-2.3	-13.3	-22.7	19.91	-26.44	0.06	OK
B3	D13	A13.5	462	-3.13	0.00	1.35	-0.06	3.86	-0.17	-7.7	2.3	7.3	-4.7	5.2	-14.2	-4.2	-11.2	-16.3	4.6	9.7	-2.4	7.6	-11.8	-1.8	-8.8	-13.9	9.72	-16.30	0.04	OK

Story	ETABS #	Section	Capacity	Dead	Live	WindFX	WindMTX	WindFY	WindMTY																						
																												Maximum Axial Loads			
																												Tension	Compression	DCR	Status
Story40	D14	A7	239	-2.57	0.00	0.00	5.98	-10.93	17.19	28.4	68.8	144.8	7.4	126.4	-133.7	-14.8	-76.1	-152.1	70.7	146.7	9.4	128.3	-131.8	-12.8	-74.2	-150.2	146.72	-152.12	0.64	OK
Story39	D14	A7	239	-2.62	0.00	0.01	6.95	-19.09	19.96	39.1	79.9	166.3	8.2	144.8	-152.3	-15.7	-87.4	-173.8	81.9	168.3	10.2	146.8	-150.3	-13.7	-85.4	-171.8	168.29	-173.80	0.73	OK
Story38	D14	A9	308	-2.74	0.00	0.03	9.82	-33.74	28.19	62.1	119.2	252.2	17.5	221.7	-229.5	-25.3	-127.1	-260.1	121.3	254.3	19.5	223.8	-227.5	-23.2	-125.0	-258.0	254.30	-260.06	0.84	OK
Story37	D14	A9	308	-2.79	0.00	0.07	10.65	-44.73	30.56	74.8	127.4	268.4	18.2	235.7	-243.7	-26.2	-135.4	-276.4	129.5	270.6	20.3	237.8	-241.5	-24.1	-133.3	-274.3	270.56	-276.43	0.90	OK
Story36	D14	A9	308	-2.85	0.00	0.11	11.83	-54.14	33.97	87.4	139.4	289.6	17.7	253.1	-261.2	-25.9	-147.5	-297.7	141.5	291.7	19.9	255.2	-259.1	-23.7	-145.3	-295.5	291.72	-297.70	0.97	OK
Story35	D14	A11	376	-2.95	0.00	0.16	15.02	-61.30	43.15	104.8	158.4	307.3	6.4	261.7	-270.1	-14.8	-166.8	-315.7	160.6	309.5	8.6	264.0	-267.9	-12.6	-164.6	-313.5	309.55	-315.74	0.84	OK
Story34	D14	A11	376	-3.00	0.00	0.22	15.54	-70.77	44.63	115.1	162.4	312.1	4.6	264.8	-273.4	-13.2	-171.0	-320.7	164.7	314.4	6.9	267.1	-271.1	-10.9	-168.7	-318.4	314.40	-320.71	0.85	OK
Story33	D14	A11	376	-2.96	0.00	0.24	16.77	-81.57	48.16	129.1	172.2	327.8	3.4	277.1	-285.6	-11.9	-180.6	-336.2	174.4	330.0	5.6	279.4	-283.3	-9.6	-178.4	-334.0	330.00	-336.21	0.89	OK
Story32	D14	A11	376	-3.01	0.00	0.31	17.98	-91.08	51.65	141.8	180.7	338.4	0.1	284.2	-292.8	-8.7	-189.3	-347.0	183.0	340.7	2.4	286.5	-290.5	-6.4	-187.0	-344.7	340.69	-347.00	0.92	OK
Story31	D14	A13.5	462	-2.95	0.00	0.28	22.47	-109.86	64.54	174.4	218.8	399.0	-5.4	331.8	-340.2	-3.0	-227.2	-407.5	221.0	401.3	-3.2	334.0	-338.0	-0.8	-225.0	-405.2	401.26	-407.45	0.88	OK
Story30	D14	A13.5	462	-2.99	0.00	0.34	23.20	-119.52	66.64	185.6	224.0	407.1	-6.5	338.0	-346.5	-2.1	-232.6	-415.7	226.3	409.4	-4.2	340.2	-344.3	0.2	-230.3	-413.4	409.40	-415.68	0.90	OK
Story29	D14	A13.5	462	-2.95	0.00	0.36	24.60	-129.82	70.70	199.8	234.7	423.5	-8.4	350.6	-359.0	-0.1	-243.1	-431.9	236.9	425.7	-6.1	352.8	-356.8	2.2	-240.9	-429.7	425.71	-431.91	0.94	OK
Story28	D14	A13.5	462	-2.99	0.00	0.43	25.74	-138.37	73.99	211.4	243.0	435.2	-10.7	359.1	-367.6	2.2	-251.6	-443.8	245.3	437.5	-8.4	361.4	-365.4	4.4	-249.3	-441.5	437.47	-443.76	0.96	OK
Story27	D14	A13.5	462	-2.91	0.00	0.40	25.16	-136.19	72.34	207.5	234.0	415.1	-13.0	341.1	-349.4	4.6	-242.3	-423.5	236.2	417.4	-10.8	343.3	-347.2	6.9	-240.1	-421.3	417.36	-423.47	0.92	OK
Story26	D14	A13.5	462	-2.95	0.00	0.46	25.84	-144.19	74.30	217.0	239.2	423.1	-14.0	347.1	-355.5	5.6	-247.6	-431.5	241.4	425.3	-11.8	349.4	-353.3	7.8	-245.4	-429.3	425.32	-431.51	0.93	OK
Story25	D14	A13.5	462	-2.91	0.00	0.47	26.28	-151.63	75.58	225.3	243.1	430.4	-13.8	353.4	-361.7	5.5	-251.4	-438.8	245.3	432.6	-11.6	355.6	-359.5	7.7	-249.2	-436.6	432.64	-438.76	0.95	OK
Story24	D14	A13.5	462	-2.95	0.00	0.54	26.79	-157.93	77.09	232.7	247.1	436.9	-14.5	358.4	-366.8	6.0	-255.6	-445.3	249.4	439.1	-12.2	360.7	-364.6	8.3	-253.3	-443.1	439.13	-445.32	0.96	OK
Story23	D14	A13.5	462	-2.91	0.00	0.54	26.63	-158.59	76.64	232.8	244.8	432.1	-14.8	354.2	-362.5	6.4	-253.1	-440.4	247.0	434.3	-12.6	356.4	-360.3	8.7	-250.9	-438.2	434.28	-440.39	0.95	OK
Story22	D14	A13.5	462	-2.95	0.00	0.61	26.95	-163.47	77.58	238.2	247.9	437.4	-15.0	358.6	-367.0	6.5	-256.3	-445.8	250.1	439.6	-12.7	360.8	-364.7	8.8	-254.0	-443.6	439.63	-445.81	0.97	OK
Story21	D14	A13.5	462	-2.87	0.00	0.56	27.21	-167.15	78.36	242.6	250.4	442.9	-14.3	363.5	-371.7	6.1	-258.6	-451.1	252.6	445.1	-12.1	365.7	-369.5	8.2	-256.5	-448.9	445.06	-451.10	0.98	OK
Story20	D14	A13.5	462	-2.91	0.00	0.62	27.10	-169.08	78.05	243.9	249.8	442.4	-14.0	363.2	-371.5	5.7	-258.1	-450.7	252.0	444.6	-11.8	365.4	-369.3	7.9	-255.9	-448.5	444.56	-450.66	0.98	OK
Story19	D14	A13.5	462	-2.94	0.00	0.69	25.87	-163.29	74.52	234.3	239.4	424.8	-13.1	349.1	-357.5	4.7	-247.8	-433.2	241.6	427.1	-10.9	351.3	-355.3	6.9	-245.6	-431.0	427.07	-433.24	0.94	OK
Story18	D14	A13.5	462	-2.97	0.00	0.75	25.56	-164.13	73.66	233.9	238.0	423.9	-12.1	348.9	-357.4	3.6	-246.4	-432.4	240.2	426.1	-9.8	351.1	-355.1	5.8	-244.2	-430.1	426.12	-432.36	0.94	OK
Story17	D14	A13.5	462	-2.93	0.00	0.75	25.40	-166.22	73.20	235.2	237.9	425.9	-10.6	351.4	-359.7	2.2	-246.3	-434.3	240.1	428.1	-8.3	353.6	-357.5	4.4	-244.0	-432.0	428.11	-434.26	0.94	OK
Story16	D14	A13.5	462	-2.96	0.00	0.82	25.22	-169.30	72.69	237.3	237.7	427.5	-9.4	353.4	-361.9	0.9	-246.2	-436.0	240.0	429.8	-7.1	355.7	-359.6	3.1	-243.9	-433.8	429.79	-436.01	0.94	OK
Story15	D14	A13.5	462	-2.92	0.00	0.82	24.95	-171.59	71.96	238.5	237.0	428.6	-7.6	355.2	-363.6	-0.7	-245.3	-436.9	239.2	430.8	-5.4	357.4	-361.4	1.5	-243.1	-434.7	430.82	-436.95	0.95	OK
Story14	D14	A13.5	462	-2.95	0.00	0.88	24.68	-174.25	71.20	239.9	236.2	429.3	-6.3	356.6	-365.0	-2.1	-244.6	-437.7	238.4	431.5	-4.1	358.8	-362.8	0.1	-242.4	-435.5	431.55	-437.74	0.95	OK
Story13	D14	A13.5	462	-2.98	0.00	0.95	24.07	-172.28	69.46	235.9	232.3	424.3	-5.0	353.1	-361.6	-3.5	-240.8	-432.8	234.5	426.5	-2.8	355.4	-359.4	-1.2	-238.5	-430.5	426.54	-432.79	0.94	OK
Story12	D14	A13.5	462	-3.01	0.00	1.02	22.36	-157.24	64.55	216.3	218.0	400.9	-3.4	334.5	-343.1	-5.2	-226.6	-409.5	220.3	403.2	-1.2	336.8	-340.8	-2.9	-224.4	-407.2	403.21	-409.53	0.89	OK
Story11	D14	A13.5	462	-2.96	0.00	1.01	17.16	-107.38	49.58	153.3	172.8	325.6	1.2	274.2	-282.6	-9.7	-181.3	-334.1	175.0	327.9	3.5	276.4	-280.4	-7.5	-179.0	-331.9	327.89	-334.11	0.72	OK
Story10	D14	A13.5	462	-2.99	0.00	1.08	4.90	3.32	14.24	10.6	73.6	173.9	19.9	157.8	-166.3	-28.5	-82.2	-182.4	75.9	176.2	22.2	160.1	-164.1	-26.2	-79.9	-180.2	176.16	-182.44	0.40	OK
Story9	D14	A13.5	462	-2.95	0.00	1.08	3.02	23.82	8.81	-14.4	60.9	158.7	25.2	148.0	-156.4	-33.6	-69.3	-167.1	63.1	160.9	27.4	150.2	-154.2	-31.4	-67.1	-164.9	160.94	-167.13	0.36	OK
Story8	D14	A13.5	462	-2.98	0.00	1.15	3.47	14.92	10.12	-4.9	64.9	164.8	24.3	152.6	-161.1	-32.8	-73.5	-173.3	67.2	167.1	26.6	154.9	-158.9	-30.6	-71.2	-171.1	167.07	-173.32	0.38	OK
Story7	D14	A13.5	462	-3.00	0.00	1.22	3.88	3.29	11.32	6.9	68.4	169.6	23.3	156.1	-164.7	-31.9	-77.0	-178.2	70.7	171.9	25.6	158.4	-162.4	-29.6	-74.7	-175.9	171.91	-178.22	0.39	OK
Story6	D14	A13.5	462	-3.03	0.00	1.29	4.51	-11.94	13.13	22.7	74.0	178.2	22.2	162.7	-171.4	-30.9	-82.7	-186.9	76.3	180.5	24.5	165.0	-169.1	-28.6	-80.4	-184.6	180.54	-186.91	0.40	OK
Story5	D14	A13.5	462	-2.99	0.00	1.29	5.08	-25.72	14.80	37.2	79.6	187.8	21.9	170.5	-179.0	-30.5	-88.1	-196.3	81.8	190.0	24.2	172.8	-176.8	-28.2	-85.8	-194.1	190.05	-196.32	0.43	OK
Story4	D14	A13.5	462	-3.01	0.00	1.36	5.60	-38.86	16.32	50.8	84.7	196.4	21.4	177.4	-186.1	-30.0	-93.3	-205.0	87.0	198.7	23.7	179.7	-183.8	-27.8	-91.0	-202.8	198.72	-205.05	0.44	OK
Story3	D14	A13.5	462	-2.97	0.00	1.35	6.02	-49.24	17.54	61.7	88.5	202.5	20.9	182.2	-190.7	-29.4	-97.0	-210.9	90.8	204.7

SIMPSON GUMPERTZ & HEGER
Engineering of Structures and Building Enclosures

CLIENT Pacific Earthquake Engineering Research Center
SUBJECT BRB Strength Check along Line 4 for LA BRBF Bldg

SHEET NO.
PROJECT NO. 087237.10
DATE 1/23/09
BY AD
CHECKED BY

V-target= 3626.26 kips(85% of Static Base Shear)
V-SPECX= 11595.55 kips Scale-X= 3.20
V-SPECY= 12103.43 kips Scale-Y= 3.34
SDS = 1.145
ρ-X dir = 1
ρ -Y dir = 1
Model: 121908Model1

| | | |

SIMPSON GUMPERTZ & HEGER
Engineering of Structures and Building Enclosures

CLIENT Pacific Earthquake Engineering Research Center
SUBJECT BRB Strength Check along Line 4 for LA BRBF Bldg

SHEET NO.
PROJECT NO. 087237.10
DATE 1/23/09
BY AD
CHECKED BY

V-target= 3626.26 kips(85% of Static Base Shear)
V-SPECX= 11595.55 kips Scale-X= 3.20
V-SPECY= 12103.43 kips Scale-Y= 3.34
SDS = 1.145
ρ-X dir = 1
ρ -Y dir = 1

Model: 121908Model1

0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9
		1.2	1.2	-1.2	-1.2	1.2	1.2	-1.2	-1.2									0.9008	0.9008	-0.9008	-0.9008	0.9008	0.9008	0.9008	-0.9008	-0.9008	0.9008	0.9008	-0.9008	-0.9008	0.9008
						1.2	-1.2	1.2	-1.2									0.9008	-0.9008	0.9008	-0.9008	0.9008	0.9008	0.9008	-0.9008	0.9008	-0.9008	-0.9008	-0.9008	-0.9008	-0.9008
1.6	-1.6	1.2	-1.2	1.2	-1.2					1.2	1.2	-1.2	-1.2					0.9008	0.9008	0.9008	0.9008	-0.9008	0.9008	-0.9008	-0.9008	-0.9008	0.9008	0.9008	-0.9008	0.9008	0.9008
										1.2	-1.2	1.2	-1.2					0.9008	0.9008	0.9008	0.9008	-0.9008	0.9008	-0.9008	-0.9008	-0.9008	-0.9008	-0.9008	0.9008	-0.9008	0.9008
9 Case 1		Figure 6-9 Case 2				Figure 6-9 Case 3												Figure 6-9 Case 4																	

Story	ETABS #	Section	Capacity	Dead	Live	WindFX	WindMTX	WindFY	WindMTY																										
Story40	D15	A7	239	-2.58	0.00	0.00	-1.24	10.92	-3.56	15.1	-19.8	10.8	-15.4	10.8	-15.4	-3.8	-0.8	-3.8	-0.8	6.5	15.0	-19.7	-11.1	3.2	5.4	3.2	5.4	9.6	-16.5	-10.1	-7.8	-10.1	-7.8	11.8	-14.2	11.8	-14.2
Story39	D15	A7	239	-2.63	0.00	0.01	-1.59	19.08	-4.56	28.2	-32.9	20.5	-25.3	20.5	-25.3	-4.3	-0.4	-4.3	-0.5	15.1	26.0	-30.7	-19.8	9.3	12.1	9.3	12.1	17.5	-25.1	-16.9	-14.0	-16.9	-14.0	20.4	-22.2	20.4	-22.2
Story38	D15	A7	239	-2.68	0.00	0.01	-1.88	26.23	-5.40	39.6	-44.4	29.1	-33.9	29.0	-33.9	-4.7	-0.1	-4.7	-0.2	22.6	35.5	-40.4	-27.4	14.7	18.1	14.6	18.0	24.4	-32.6	-22.9	-19.5	-22.9	-19.5	27.8	-29.2	27.8	-29.2
Story37	D15	A7	239	-2.73	0.00	0.02	-2.18	34.59	-6.25	52.9	-57.8	39.1	-43.9	39.0	-44.0	-5.0	0.2	-5.1	0.1	31.5	46.5	-51.5	-36.5	21.1	25.0	21.1	25.0	32.4	-41.2	-29.9	-26.0	-30.0	-26.0	36.3	-37.3	36.3	-37.3
Story36	D15	A7	239	-2.78	0.00	0.04	-2.53	41.46	-7.26	63.8	-68.8	47.3	-52.2	47.2	-52.3	-5.5	0.6	-5.6	0.5	38.5	56.0	-61.0	-43.5	28.1	30.6	26.0	30.5	39.1	-48.6	-35.6	-31.1	-35.6	-31.0	43.7	-44.2	43.6	-44.1
Story35	D15	A11	376	-2.95	0.00	0.07	-4.18	59.07	-12.00	91.9	-97.2	68.3	-73.5	68.1	-73.6	-7.6	2.4	-7.8	2.3	53.8	82.6	-87.9	-59.1	36.0	43.6	35.9	43.5	57.7	-70.4	-48.8	-41.4	-48.9	-41.2	65.2	-63.0	65.1	-62.8
Story34	D15	A11	376	-3.01	0.00	0.09	-4.33	67.19	-12.44	104.8	-110.2	78.0	-83.2	77.8	-83.4	-7.8	2.6	-8.0	2.4	63.0	92.8	-98.3	-68.4	42.8	50.6	42.6	50.4	65.2	-78.3	-55.8	-48.2	-56.0	-48.0	73.0	-70.6	72.8	-70.4
Story33	D15	A11	376	-2.95	0.00	0.11	-4.65	76.71	-13.36	120.1	-125.4	89.5	-94.6	89.3	-94.8	-8.1	3.1	-8.4	2.8	73.4	105.4	-110.7	-78.7	50.3	58.7	50.1	58.5	74.4	-87.9	-63.8	-55.6	-64.0	-55.4	82.8	-79.7	82.6	-79.5
Story32	D15	A11	376	-3.00	0.00	0.15	-4.89	84.68	-14.04	132.8	-138.2	99.1	-104.1	98.7	-104.5	-8.4	3.3	-8.7	3.0	82.1	115.8	-121.2	-87.5	56.7	65.5	56.4	65.2	82.0	-95.9	-70.6	-62.1	-70.9	-61.8	90.8	-87.3	90.5	-87.1
Story31	D15	A13.5	462	-2.94	0.00	0.14	-5.91	100.37	-16.96	157.9	-163.2	118.0	-122.9	117.6	-123.3	-9.6	4.6	-9.9	4.3	97.4	138.2	-143.4	-102.7	67.3	77.9	67.0	77.7	97.9	-113.5	-83.0	-72.6	-83.2	-72.3	108.5	-103.1	108.2	-102.9
Story30	D15	A13.5	462	-2.98	0.00	0.18	-5.82	107.97	-16.72	170.1	-175.4	127.1	-132.0	126.7	-132.5	-9.5	4.5	-9.9	4.1	106.8	147.0	-152.3	-112.2	74.4	84.9	74.1	84.6	104.6	-120.1	-90.0	-79.8	-90.3	-79.5	115.0	-109.9	114.7	-109.6
Story29	D15	A13.5	462	-2.93	0.00	0.16	-6.07	116.09	-17.42	183.1	-188.4	136.9	-141.7	136.5	-142.1	-9.7	4.8	-10.1	4.4	115.8	157.6	-162.9	-121.0	80.9	91.8	80.6	91.6	112.3	-128.2	-96.8	-86.2	-97.1	-85.9	123.2	-117.6	122.9	-117.3
Story28	D15	A13.5	462	-2.97	0.00	0.18	-6.26	121.87	-17.99	192.3	-197.7	143.8	-148.7	143.4	-149.1	-10.0	5.1	-10.4	4.6	122.0	165.2	-170.5	-127.3	85.4	96.7	85.1	96.4	117.8	-134.1	-101.7	-90.8	-102.0	-90.4	129.1	-123.2	128.8	-122.9
Story27	D15	A13.5	462	-2.88	0.00	0.15	-5.95	117.07	-17.11	184.7	-189.9	138.1	-142.9	137.7	-143.3	-9.6	4.7	-9.9	4.4	117.4	158.4	-163.6	-122.5	82.2	92.9	81.9	92.7	113.0	-128.7	-97.9	-87.4	-98.1	-87.1	123.8	-118.2	123.5	-118.0
Story26	D15	A13.5	462	-2.91	0.00	0.17	-6.08	121.84	-17.48	192.3	-197.6	143.8	-148.6	143.4	-149.0	-9.7	4.9	-10.1	4.5	122.6	164.6	-169.8	-127.9	86.1	97.0	85.8	96.7	117.6	-133.4	-102.0	-91.3	-102.3	-91.0	128.5	-122.8	128.2	-122.5
Story25	D15	A13.5	462	-2.95	0.00	0.18	-6.17	128.17	-17.73	202.4	-207.7	151.4	-156.2	150.9	-156.7	-9.8	5.0	-10.3	4.5	129.9	172.4	-177.7	-135.2	91.4	102.5	91.1	102.2	123.4	-139.5	-107.5	-96.7	-107.8	-96.4	134.5	-128.7	134.2	-128.4
Story24	D15	A13.5	462	-2.98	0.00	0.20	-6.30	132.91	-18.12	210.0	-215.3	157.1	-161.9	156.6	-162.4	-10.0	5.1	-10.5	4.6	135.1	178.6	-183.9	-140.4	95.2	106.6	94.9	106.2	127.9	-144.2	-111.6	-100.6	-111.9	-100.2	139.2	-133.2	138.9	-132.9
Story23	D15	A13.5	462	-3.01	0.00	0.21	-6.25	134.54	-17.99	212.6	-218.0	159.0	-163.9	158.5	-164.4	-10.0	5.1	-10.5	4.5	137.2	180.3	-185.7	-142.6	96.8	108.1	96.5	107.7	129.3	-145.5	-113.1	-102.3	-113.5	-101.9	140.5	-134.7	140.1	-134.3
Story22	D15	A13.5	462	-3.04	0.00	0.23	-6.38	140.27	-18.37	221.7	-227.2	165.9	-170.8	165.3	-171.3	-10.1	5.2	-10.7	4.6	143.5	187.6	-193.1	-149.0	101.5	113.0	101.1	112.6	134.6	-151.2	-118.1	-107.0	-118.5	-106.6	146.1	-140.1	145.7	-139.7
Story21	D15	A13.5	462	-2.99	0.00	0.22	-6.52	146.15	-18.78	231.2	-236.5	173.0	-177.8	172.4	-178.3	-10.2	5.4	-10.8	4.9	150.2	195.2	-200.6	-155.5	106.4	118.1	106.0	117.7	140.2	-156.9	-123.1	-111.7	-123.5	-111.3	152.0	-145.6	151.6	-145.2
Story20	D15	A13.5	462	-3.02	0.00	0.24	-6.56	150.43	-18.89	238.0	-243.4	178.1	-182.9	177.5	-183.5	-10.3	5.4	-10.9	4.9	155.1	200.5	-205.9	-160.6	110.1	121.9	109.7	121.5	144.1	-160.9	-126.9	-115.5	-127.3	-115.1	155.9	-149.5	155.5	-149.1
Story19	D15	A13.5	462	-3.05	0.00	0.26	-6.24	147.20	-17.97	232.8	-238.3	174.2	-179.1	173.6	-179.7	-9.9	5.1	-10.5	4.4	152.3	195.5	-201.0	-157.8	108.3	119.5	107.8	119.1	140.7	-156.9	-124.5	-113.8	-125.0	-113.3	151.9	-146.1	151.4	-145.7
Story18	D15	A13.5	462	-3.08	0.00	0.28	-6.25	150.88	-18.00	238.6	-244.2	178.6	-183.5	177.9	-184.2	-9.9	5.1	-10.6	4.4	156.7	199.9	-205.4	-162.2	111.6	122.8	111.1	122.3	144.0	-160.3	-127.8	-117.1	-128.3	-116.6	155.2	-149.5	154.7	-149.0
Story17	D15	A13.5	462	-3.02	0.00	0.27	-6.30	155.26	-18.15	245.7	-251.1	183.9	-188.7	183.3	-189.4	-10.0	5.2	-10.6	4.5	161.8	205.4	-210.8	-167.2	115.4	126.7	114.9	126.2	148.1	-164.4	-131.7	-120.8	-132.1	-120.3	159.4	-153.5	158.9	-153.0
Story16	D15	A13.5	462	-3.05	0.00	0.29	-6.36	160.95	-18.34	254.8	-260.3	190.7	-195.5	190.0	-196.2	-10.0	5.2	-10.7	4.5	168.4	212.4	-217.9	-173.9	120.2	131.7	119.7	131.2	153.3	-169.7	-136.7	-125.7	-137.2	-125.2	164.7	-158.8	164.2	-158.3
Story15	D15	A13.5	462	-2.96	0.00	0.26	-6.37	163.20	-18.36	263.8	258.5	-198.2	193.5	-198.8	192.9	5.3	-10.0	5.3	-10.6	4.7	171.1	215.2	-220.5	-176.5	122.3	133.8	121.8	133.3	155.4	-171.7	-138.6	-137.6	-139.1	-127.2	166.8	-160.7	166.4	-160.2
Story14	D15	A13.5	462	-2.99	0.00	0.27	-6.38	166.02	-18.41	262.9	-268.3	196.9	-201.6	196.2	-202.2	-10.0	5.3	-10.7	4.6	174.4	218.6	-224.0	-179.8	124.8	136.3	124.3	135.8	157.9	-174.3	-141.2	-130.2	-141.7	-129.7	169.4	-163.3	168.9	-162.8
Story13	D15	A13.5	462	-3.02	0.00	0.29	-6.30	164.39	-18.18	260.3	-265.7	194.9	-199.6	194.2	-200.3	-9.9	5.2	-10.6	4.5	172.7	216.4	-221.8	-178.2	123.6	134.9	123.1	134.4	156.3	-172.6	-139.8	-129.0	-140.4	-128.5	167.7	-161.8	167.2	-161.2
Story12	D15	A13.5	462	-3.05	0.00	0.31	-5.86	149.91	-16.93	237.1	-242.6	177.5	-182.3	176.8	-183.0	-9.4	4.7	-10.2	3.9	156.8	197.5	-203.0	-162.3	112.0	122.6	111.5	122.0	142.5	-158.0	-127.5	-117.5	-128.1	-117.0	153.1	-148.0	152.6	-147.5
Story11	D15	A13.5	462	-3.00	0.00	0.30	-4.26	100.33	-12.33	157.8	-163.2	118.1	-122.7	117.3	-123.5	-7.5	2.8	-8.2	2.1	102.9	132.5	-137.9	-108.3	73.0	80.7	72.5	80.2	95.2	-107.8	-85.6	-78.4	-86.1	-77.9	102.9	-100.6	102.4	-100.1
Story10	D15	A13.5	462	-3.03	0.00	0.31	-0.32	-10.02	-0.95	-18.8	13.3	-14.4	9.7	-15.1	8.9	-2.7	-2.0	-3.5	-2.7	-15.9	-13.6	8.2	10.4	-12.6	-12.0	-13.2	-12.6	-10.9	5.4	7.1	7.2	6.6	7.7	-10.3	5.4	-10.9	6.0
Story9	D15	A13.5	462	-3.06	0.00	0.32	0.15	-27.67	0.40	-47.0	41.5	-35.6	30.8	-36.3	30.1	-2.2	-2.5	-3.0	-3.3	-35.5	-36.4	30.9	30.0	-26.9	-27.2	-27.5	-27.7	-27.6	23.0	22.2	21.4	21.7	22.0	-27.9	22.1	-28.5	22.7
Story8	D15	A13.5	462	-3.09	0.00	0.34	-0.15	-16.04	-0.48	-28.4	22.9	-21.6	16.9	-22.4	16.1	-2.6	-2.2	-3.4	-3.0	-22.6	-21.5	15.9	17.0	-17.5	-17.2	-18.1	-17.8	-16.6	11.4	12.3	11.9	11.7	12.5	-16.4	11.1	-17.0	11.7
Story7	D15	A13.5	462	-3.04	0.00	0.33	-0.39	-4.65	-1.17	-10.2	4.7	-7.9	3.2	-8.7	2.5	-2.8	-1.9	-3.6	-2.7	-9.7	-6.9	1.4	4.3	-8.0	-7.3	-8.6	-7.9	-5.9	0.3	2.4	2.6	1.9	3.2	-5.2	0.5	-5.8	1.0
Story6	D15	A13.5	462	-3.07	0.00	0.34	-0.70	10.32	-2.06	13.7	-19.3	10.0	-14.7	9.2	-15.5	-3.2	-1.5	-4.0	-2.3	7.1	12.1	-17.6	-12.7	4.3	5.6	3.7	5.0	8.1	-14.2	-10.5	-9.9	-11.1	-9.3	9.3	-13.6	8.7	-13.0
Story5	D15	A13.5	462	-3.10	0.00	0.35	-1.01	26.09	-2.97	39.0	-44.5	28.9	-33.7	28.1	-34.5	-3.6	-1.2	-4.4	-2.0	25.0	32.1	-37.7	-30.5	17.4	19.3	16.8	18.6	22.8	-29.6	-24.2	-23.0	-24.8	-22.4	24.6	-28.4	24.0	-27.7
Story4	D15	A13.5	462	-3.13	0.00	0.36	-1.31	41.28	-3.83	63.2	-68.9	47.1	-51.9	46.3	-52.8	-4.0	-0.8	-4.8	-1.7	42.1	51.3	-56.9	-47.8	30.1	32.4	29.4	31.8	37.0	-44.3	-37.4	-35.7	-38.1	-35.0	39.3	-42.6	38.7	-41.9
Story3	D15	A13.5	462	-3.08	0.00	0.34	-1.56	53.29	-4.55	82.5	-88.0	61.6	-66.3	60.8	-67.1	-4.2	-0.5	-5.1	-1.3	55.7	66.6	-72.2	-61.3	40.0	42.8	39.4	42.2	48.2	-56.0	-47.8	-45.6	-48.4	-45.0	51.0	-53.8	50.4	-53.2
Story2	D15	A13.5	462	-3.11	0.00	0.35	-1.75	61.10	-5.12	95.0	-100.6	70.9	-75.7	70.1	-76.5	-4.5	-0.3	-5.3	-1.1	64.4	76.7	-82.3	-70.0	46.4	49.5	45.7	48.9	55.6	-63.7	-54.5	-52.0	-55.1	-51.3	58.7	-61.2	58.1	-60.6
Story1	D15	A13.5	462	-2.94	0.00	0.40	-1.38	44.32	-4.04	68.3	-73.6	51.0	-55.3	50.1	-56.3	-3.8	-0.5	-4.8	-1.5	45.7	55.4	-60.7	-51.0	32.7	35.2	32.0	34.5	40.0	-47.1	-39.8	-38.0	-40.5	-37.3	42.5	-45.3	41.8	-44.6
Ground	D15	A13.5	462	-3.19	0.00	0.32	0.71	-40.21	2.05	-67.2	61.5	-50.7	45.8	-51.5	45.0	-1.6	-3.3	-2.4	-4.1	-48.7	-53.6	47.8	42.9	-36.3	-37.6	-36.9	-38.2	-40.0	36.1	32.4	30.6	31.8	31.1	-41.3	34.3	-41.9	34.8
B1	D15	A13.5	462	-3.07	0.00	0.29	0.47	-27.61	1.37	-46.9	41.4	-35.5	30.7	-36.2	30.0	-1.8	-3.0	-2.5	-3.7	-34.2	-37.5	32.0	28.7	-25.7	-26.6	-26.2	-27.1	-28.2	24.0	21.6	20.2	21.0	20.7	-29.0	22.7	-29.5	23.2
B2	D15	A13.5	462	-3.09	0.00	0.29	0.23	-12.45	0.66	-22.7	17.1	-17.4	12.5	-18.1	11.8	-2.2	-2.7	-2.9	-3.4	-16.9	-18.5	12.9	11.4	-12.9	-13.3	-13.5	-13.9	-14.1	9.5	8.3	7.4	7.8	7.9	-14.5	8.6	-15.1	9.1
B3	D15	A13.5	462	-3.12	0.00	0.29	-0.02	3.86	-0.06	3.4	-9.0	2.2	-7.1	1.5	-7.8	-2.5	-2.4	-3.2	-3.1	1.8	1.9	-7.5	-7.4	0.9	0.9	0.3	0.4	1.0	-6.1	-6.0	-6.5	-6.5	-5.9	1.0	-6.6	0.5	-6.0

Story	ETABS #	Section	Capacity	Dead	Live	WindFX	WindMTX	WindFY	WindMTY																										
Story40	D16	A7	239	-2.58	0.00	0.00	1.24	-10.92	3.56	-19.8	15.1	-15.4	10.8	-15.4	10.8	-0.8	-3.8	-0.8	-3.8	-11.1	-19.7	15.0	6.5	-7.8	-10.1	-7.8	-10.1	-14.2	11.8	5.4	3.2	5.4	3.2	-16.5	9.6	-16.5	9.6
Story39	D16	A7	239	-2.63	0.00	0.01	1.59	-19.08	4.56	-32.9	28.2	-25.3	20.5	-25.3	20.5	-0.4	-4.3	-0.5	-4.3	-19.8	-30.7	26.0	15.1	-14.0	-16.9	-14.0	-16.9	-22.2	20.4	12.1	9.3	12.1	9.3	-25.1	17.5	-25.1	17.5
Story38	D16	A7	239	-2.68	0.00	0.01	1.88	-26.23	5.40	-44.4	39.6	-33.9	29.1	-33.9	29.0	-0.1	-4.7	-0.2	-4.7	-27.4	-40.4	35.5	22.6	-19.5	-22.9	-19.5	-22.9	-29.2	27.8	18.1	14.6	18.0	14.7	-32.6	24.4	-32.6	24.4
Story37	D16	A7	239	-2.73	0.00	0.02	2.18	-34.59	6.25	-57.8	52.9	-43.9	39.1	-44.0	39.0	0.2	-5.0	0.1	-5.1	-36.5	-51.5	46.5	31.5	-26.0	-29.9	-26.0	-30.0	-37.3	36.3	25.0	21.1	25.0	21.1	-41.2	32.3	-41.2	32.4
Story36	D16	A7	239	-2.78	0.00	0.04	2.53	-41.46	7.26	-68.8	63.8	-52.2	47.3	-52.3	47.2	0.6	-5.5	0.5	-5.6	-43.5	-61.0	56.0	38.5	-31.0	-35.6	-31.1	-35.6	-44.1	43.7	30.6	26.0	30.5	26.1	-48.6	39.1	-48.7	39.1
Story35	D16	A11	376	-2.95	0.00	0.07	4.18	-59.07	12.00	-97.2	91.9	-73.5	68.3	-73.6	68.1	2.4	-7.6	2.3	-7.8	-59.1	-87.9	82.6	53.8	-41.2	-48.8	-41.4	-48.9	-62.8	65.2	43.6	35.9	43.5	36.0	-70.4	57.5	-70.5	57.7
Story34	D16	A11	376	-3.01	0.00	0.09	4.33	-67.19	12.44	-110.2	104.8	-83.2	78.0	-83.4	77.8	2.6	-7.8	2.4	-8.0	-68.4	-98.3	92.8	63.0	-48.0	-55.8	-48.2	-56.0	-70.4	73.0	50.6	42.6	50.4	42.8	-78.3	65.0	-78.4	65.2
Story33	D16	A11	376	-2.95	0.00	0.11	4.65	-76.71	13.36	-125.4	120.1	-94.6	89.5	-94.8	89.3	3.1	-8.1	2.8	-8.4	-78.7	-110.7	105.4	73.4	-55.4	-63.8	-55.6	-64.0	-79.5	82.8	58.7	50.1	58.5	50.3	-87.9	74.2	-88.1	74.4
Story32	D16	A11	376	-3.00	0.00	0.15	4.89	-84.68	14.04	-138.2	132.8	-104.1	99.1	-104.5	98.7	3.3	-8.4	3.0	-8.7	-87.5	-121.2	115.8	82.1	-61.8	-70.6	-62.1	-70.9	-87.1	90.8	65.5	56.4	65.2	56.7	-95.9	81.7	-96.2	82.0
Story31	D16	A13.5	462	-2.94	0.00	0.14	5.91	-100.37	16.96	-163.2	157.9	-122.9	118.0	-123.3	117.6	4.6	-9.6	4.3	-9.9	-102.7	-143.4	138.2	97.4	-72.3	-83.0	-72.6	-83.2	-102.9	108.5	77.9	67.0	77.7	67.3	-113.5	97.6	-113.8	97.9
Story30	D16	A13.5	462	-2.98	0.00	0.18	5.82	-107.97	16.72	-175.4	170.1	-132.0	127.1	-132.5	126.7	4.5	-9.5	4.1	-9.9	-112.2	-152.3	147.0	106.8	-79.5	-90.0	-79.8	-90.3	-109.6	115.0	84.9	74.1	84.6	74.4	-120.1	104.2	-120.4	104.6
Story29	D16	A13.5	462	-2.93	0.00	0.16	6.07	-116.09	17.42	-188.4	183.1	-141.7	136.9	-142.1	136.5	4.8	-9.7	4.4	-10.1	-121.0	-162.9	157.6	115.8	-85.9	-96.8	-86.2	-97.1	-117.3	123.2	91.8	80.6	91.6	80.9	-128.2	112.0	-128.5	112.3
Story28	D16	A13.5	462	-2.97	0.00	0.18	6.26	-121.87	17.99	-197.7	192.3	-148.7	143.8	-149.1	143.4	5.1	-10.0	4.6	-10.4	-127.3	-170.5	165.2	122.0	-90.4	-101.7	-90.8	-102.0	-122.9	129.1	96.7	85.1	96.4	85.4	-134.1	117.5	-134.5	117.8
Story27	D16	A13.5	462	-2.88	0.00	0.15	5.95	-117.07	17.11	-189.9	184.7	-142.9	138.1	-143.3	137.7	4.7	-9.6	4.4	-9.9	-122.5	-163.6	158.4	117.4	-87.1	-97.9	-87.4	-98.1	-118.0	123.8	92.9	81.9	92.7	82.2	-128.7	112.8	-129.0	113.0
Story26	D16	A13.5	462	-2.91	0.00	0.17	6.08	-121.84	17.48	-197.6	192.3	-148.6	143.8	-149.0	143.4	4.9	-9.7	4.5	-10.1	-127.9	-169.8	164.6	122.6	-91.0	-102.0	-91.3	-102.3	-122.5	128.5	97.0	85.8	96.7	86.1	-133.4	117.3	-133.7	117.6
Story25	D16	A13.5	462	-2.95	0.00	0.18	6.17	-128.17	17.73	-207.7	202.4	-156.2	151.4	-156.7	150.9	5.0	-9.8	4.5	-10.3	-135.2	-177.7	172.4	129.9	-96.4	-107.5	-96.7	-107.8	-128.4	134.5	102.5	91.1	102.2	91.4	-139.5	123.1	-139.8	123.4
Story24	D16	A13.5	462	-2.98	0.00	0.20	6.30	-132.91	18.12	-215.3	210.0	-161.9	157.1	-162.4	156.6	5.1	-10.0	4.6	-10.5	-140.4	-183.9	178.6	135.1	-100.2	-111.6	-100.6	-111.9	-132.9	139.2	106.6	94.9	106.2	95.2	-144.2	127.5	-144.6	127.9
Story23	D16	A13.5	462	-3.01	0.00	0.21	6.25	-134.54	17.99	-218.0	212.6	-163.9	159.0	-164.4	158.5	5.1	-10.0	4.5	-10.5	-142.6	-185.7	180.3	137.2	-101.9	-113.1	-102.3	-113.5	-134.3	140.5	108.1	96.5	107.7	96.8	-145.5	128.9	-145.9	129.3
Story22	D16	A13.5	462	-3.04	0.00	0.23	6.38	-140.27	18.37	-227.2	221.7	-170.8	165.9	-171.3	165.3	5.2	-10.1	4.6	-10.7	-149.0	-193.1	187.6	143.5	-106.6	-118.1	-107.0	-118.5	-139.7	146.1	113.0	101.1	112.6	101.5	-151.2	134.2	-151.6	134.6
Story21	D16	A13.5	462	-2.99	0.00	0.22	6.52	-146.15	18.78	-236.5	231.2	-177.8	173.0	-178.3	172.4	5.4	-10.2	4.9	-10.8	-155.5	-200.6	195.2	150.2	-111.3	-123.

SIMPSON GUMPERTZ & HEGER
Engineering of Structures and Building Enclosures

CLIENT Pacific Earthquake Engineering Research Center
SUBJECT BRB Strength Check along Line 4 for LA BRBF Bldg

SHEET NO.
PROJECT NO. 087237.10
DATE 1/23/09
BY AD
CHECKED BY

V-target= 3626.26 kips(85% of Static Base Shear)
V-SPECX= 11595.55 kips Scale-X= 3.20
V-SPECY= 12103.43 kips Scale-Y= 3.34
SDS = 1.145
ρ-X dir = 1
ρ -Y dir = 1

Model: 121908Model1

0.9	0.9	1.429	1.429	1.429	1.429	1.429	1.429	1.429	1.429	0.671	0.671	0.671	0.671	0.671	0.671	0.671	0.671
		0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5								
-0.9008	-0.9008																
0.9008	0.9008																
0.9008	-0.9008																
-0.9008	0.9008																
		1	0.3	-1	-0.3	0.3	1	-1	-0.3	1	0.3	-1	-0.3	0.3	1	-1	-0.3
		0.3	1	0.3	1	-1	-0.3	-0.3	-1	0.3	1	0.3	1	-1	-0.3	-0.3	-1

Story	ETABS #	Section	Capacity	Dead	Live	WindFX	WindMTX	WindFY	WindMTY																					Maximum Axial Loads			
																														Tension	Compression	DCR	Status
Story40	D15	A7	239	-2.58	0.00	0.00	-1.24	10.92	-3.56	9.6	-16.5	33.6	100.9	20.6	97.0	-104.4	-28.0	-41.0	-108.3	35.6	102.9	22.6	99.0	-102.4	-26.0	-39.0	-106.3	102.87	-108.28	0.45	OK
Story39	D15	A7	239	-2.63	0.00	0.01	-1.59	19.08	-4.56	17.5	-25.1	40.4	118.0	23.7	113.0	-120.6	-31.2	-47.9	-125.6	42.4	120.0	25.7	115.0	-118.6	-29.2	-45.9	-123.6	120.03	-125.55	0.52	OK
Story38	D15	A7	239	-2.68	0.00	0.01	-1.88	26.23	-5.40	24.4	-32.6	49.6	144.4	29.9	138.5	-146.1	-37.5	-57.3	-152.1	51.7	146.4	31.9	140.5	-144.1	-35.5	-55.3	-150.0	146.44	-152.07	0.64	OK
Story37	D15	A7	239	-2.73	0.00	0.02	-2.18	34.59	-6.25	32.3	-41.2	53.7	154.2	31.3	147.5	-155.3	-39.1	-61.6	-162.0	55.8	156.3	33.4	149.6	-153.2	-37.0	-59.5	-160.0	156.30	-162.04	0.68	OK
Story36	D15	A7	239	-2.78	0.00	0.04	-2.53	41.46	-7.26	39.1	-48.7	58.3	163.9	32.1	156.0	-164.0	-40.1	-66.3	-171.8	60.4	166.0	34.2	158.1	-161.9	-38.0	-64.1	-169.7	166.00	-171.85	0.72	OK
Story35	D15	A11	376	-2.95	0.00	0.07	-4.18	59.07	-12.00	57.5	-70.5	78.5	207.1	36.1	194.4	-202.9	-44.5	-86.9	-215.6	80.7	209.4	38.3	196.7	-200.6	-42.3	-84.7	-213.3	209.37	-215.57	0.57	OK
Story34	D15	A11	376	-3.01	0.00	0.09	-4.33	67.19	-12.44	65.0	-78.4	78.9	205.9	34.7	192.7	-201.3	-43.3	-87.5	-214.5	81.1	208.2	37.0	195.0	-199.0	-41.0	-85.2	-212.2	208.21	-214.52	0.57	OK
Story33	D15	A11	376	-2.95	0.00	0.11	-4.65	76.71	-13.36	74.2	-88.1	82.0	211.6	34.9	197.5	-205.9	-43.3	-90.4	-220.1	84.2	213.9	37.1	199.7	-203.7	-41.1	-88.2	-217.8	213.87	-220.07	0.58	OK
Story32	D15	A11	376	-3.00	0.00	0.15	-4.89	84.68	-14.04	81.7	-96.2	82.8	211.0	33.3	196.2	-204.8	-41.9	-91.4	-219.6	85.1	213.3	35.6	198.5	-202.5	-39.6	-89.1	-217.3	213.32	-219.62	0.58	OK
Story31	D15	A13.5	462	-2.94	0.00	0.14	-5.91	100.37	-16.96	97.6	-113.8	95.0	236.3	35.5	218.4	-226.8	-43.9	-103.4	-244.7	97.2	238.5	37.8	220.7	-224.6	-41.7	-101.2	-242.4	238.49	-244.66	0.53	OK
Story30	D15	A13.5	462	-2.98	0.00	0.18	-5.82	107.97	-16.72	104.2	-120.4	94.2	235.2	35.7	217.6	-226.2	-44.2	-102.7	-243.7	96.4	237.4	38.0	219.9	-223.9	-42.0	-100.4	-241.4	237.44	-243.69	0.53	OK
Story29	D15	A13.5	462	-2.93	0.00	0.16	-6.07	116.09	-17.42	112.0	-128.5	96.3	239.2	35.9	221.1	-229.5	-44.3	-104.6	-247.6	98.5	241.4	38.2	223.3	-227.2	-42.1	-102.4	-245.3	241.41	-247.57	0.54	OK
Story28	D15	A13.5	462	-2.97	0.00	0.18	-6.26	121.87	-17.99	117.5	-134.5	97.4	240.4	35.3	221.8	-230.3	-43.8	-105.9	-248.9	99.6	242.7	37.6	224.0	-228.0	-41.6	-103.6	-246.6	242.66	-248.89	0.54	OK
Story27	D15	A13.5	462	-2.88	0.00	0.15	-5.95	117.07	-17.11	112.8	-129.0	90.3	221.6	31.7	204.0	-212.2	-39.9	-98.5	-229.8	92.4	223.8	33.8	206.2	-210.1	-37.7	-96.3	-227.6	223.78	-229.83	0.50	OK
Story26	D15	A13.5	462	-2.91	0.00	0.17	-6.08	121.84	-17.48	117.3	-133.7	91.1	222.9	31.4	205.0	-213.4	-39.8	-99.4	-231.3	93.3	225.1	33.6	207.2	-211.1	-37.6	-97.2	-229.0	225.14	-231.26	0.50	OK
Story25	D15	A13.5	462	-2.95	0.00	0.18	-6.17	128.17	-17.73	123.1	-139.8	92.8	227.5	32.4	209.4	-217.8	-40.8	-101.2	-235.9	95.0	229.7	34.6	211.6	-215.6	-38.6	-99.0	-233.7	229.75	-235.93	0.51	OK
Story24	D15	A13.5	462	-2.98	0.00	0.20	-6.30	132.91	-18.12	127.5	-144.6	94.2	230.6	32.6	212.1	-220.6	-41.1	-102.7	-239.1	96.5	232.8	34.9	214.4	-218.4	-38.9	-100.5	-236.8	232.85	-239.10	0.52	OK
Story23	D15	A13.5	462	-3.01	0.00	0.21	-6.25	134.54	-17.99	128.9	-145.9	93.3	228.2	32.2	209.9	-218.5	-40.7	-101.9	-236.8	95.5	230.5	34.4	212.2	-216.2	-38.5	-99.6	-234.5	230.49	-236.80	0.51	OK
Story22	D15	A13.5	462	-3.04	0.00	0.23	-6.38	140.27	-18.37	134.2	-151.6	95.2	232.8	32.8	214.0	-222.7	-41.5	-103.9	-241.4	97.5	235.1	35.1	216.3	-220.4	-39.2	-101.6	-239.1	235.05	-241.43	0.52	OK
Story21	D15	A13.5	462	-2.99	0.00	0.22	-6.52	146.15	-18.78	139.8	-157.3	97.6	238.6	33.9	219.6	-228.1	-42.5	-106.1	-247.2	99.8	240.9	36.2	221.8	-225.8	-40.2	-103.8	-244.9	240.91	-247.18	0.54	OK
Story20	D15	A13.5	462	-3.02	0.00	0.24	-6.56	150.43	-18.89	143.7	-161.4	98.3	240.5	34.3	221.3	-229.9	-42.9	-106.9	-249.1	100.6	242.8	36.5	223.6	-227.7	-40.6	-104.6	-246.9	242.81	-249.14	0.54	OK
Story19	D15	A13.5	462	-3.05	0.00	0.26	-6.24	147.20	-17.97	140.2	-157.4	94.4	232.2	33.3	213.9	-222.6	-42.0	-103.1	-240.9	96.7	234.5	35.6	216.2	-220.3	-39.7	-100.8	-238.6	234.52	-240.92	0.52	OK
Story18	D15	A13.5	462	-3.08	0.00	0.28	-6.25	150.88	-18.00	143.5	-160.8	95.3	235.0	34.0	216.6	-225.4	-42.8	-104.1	-243.8	97.7	237.3	36.3	218.9	-223.0	-40.4	-101.8	-241.4	238.63	-245.10	0.53	OK
Story17	D15	A13.5	462	-3.02	0.00	0.27	-6.30	155.26	-18.15	147.6	-164.8	97.0	239.6	35.2	221.1	-229.7	-43.8	-105.6	-248.3	99.3	241.9	37.5	223.4	-227.4	-41.5	-103.3	-246.0	245.69	-252.04	0.55	OK
Story16	D15	A13.5	462	-3.05	0.00	0.29	-6.36	160.95	-18.34	152.8	-170.2	98.7	244.2	36.1	225.5	-234.2	-44.8	-107.4	-253.0	101.0	246.5	38.4	227.8	-231.9	-42.5	-105.1	-250.6	254.77	-261.18	0.57	OK
Story15	D15	A13.5	462	-2.96	0.00	0.26	-6.37	163.20	-18.36	154.9	-172.2	99.7	247.5	37.3	228.8	-237.2	-45.7	-108.2	-256.0	101.9	249.7	39.5	231.0	-235.0	-43.5	-105.9	-253.7	258.45	-264.67	0.57	OK
Story14	D15	A13.5	462	-2.99	0.00	0.27	-6.38	166.02	-18.41	157.4	-174.8	100.8	250.6	38.0	231.8	-240.3	-46.5	-109.3	-259.2	103.0	252.9	40.3	234.1	-238.1	-44.3	-107.0	-256.9	262.94	-269.22	0.58	OK
Story13	D15	A13.5	462	-3.02	0.00	0.29	-6.30	164.39	-18.18	155.8	-173.1	100.4	250.3	38.2	231.7	-240.3	-46.8	-109.0	-258.9	102.6	252.6	40.5	234.0	-238.0	-44.5	-106.7	-256.7	260.31	-266.66	0.58	OK
Story12	D15	A13.5	462	-3.05	0.00	0.31	-5.86	149.91	-16.93	142.0	-158.6	95.0	238.7	36.8	221.2	-230.0	-45.6	-103.8	-247.4	97.3	241.0	39.2	223.6	-227.7	-43.3	-101.4	-245.1	241.01	-247.42	0.54	OK
Story11	D15	A13.5	462	-3.00	0.00	0.30	-4.26	100.33	-12.33	94.7	-108.3	75.5	196.7	32.7	183.9	-192.5	-41.3	-84.1	-205.3	77.8	199.0	35.0	186.2	-190.2	-39.0	-81.8	-203.1	199.02	-205.33	0.44	OK
Story10	D15	A13.5	462	-3.03	0.00	0.31	-0.32	-10.02	-0.95	-11.5	4.9	36.4	124.1	31.6	122.7	-131.3	-40.2	-45.1	-132.8	38.7	126.4	33.9	125.0	-129.0	-37.9	-42.8	-130.5	126.41	-132.77	0.29	OK
Story9	D15	A13.5	462	-3.06	0.00	0.32	0.15	-27.67	0.40	-28.2	22.4	35.4	124.1	32.7	123.3	-132.0	-41.5	-44.1	-132.8	37.7	126.4	35.0	125.6	-129.7	-39.1	-41.8	-130.5	126.39	-132.82	0.29	OK
Story8	D15	A13.5	462	-3.09	0.00	0.34	-0.15	-16.04	-0.48	-17.2	10.8	36.3	126.1	32.8	125.0	-133.8	-41.6	-45.2	-134.9	38.7	128.4	35.1	127.3	-131.5	-39.3	-42.8	-132.6	128.41	-134.91	0.29	OK
Story7	D15	A13.5	462	-3.04	0.00	0.33	-0.39	-4.65	-1.17	-6.5	-0.3	38.5	129.6	32.6	127.8	-136.5	-41.3	-47.2	-138.3	40.8	131.9	34.9	130.1	-134.2	-39.0	-44.9	-136.0	131.88	-138.27	0.30	OK
Story6	D15	A13.5	462	-3.07	0.00	0.34	-0.70	10.32	-2.06	7.4	-14.9	41.7	135.4	32.6	132.7	-141.5	-41.4	-50.4	-144.2	44.0	137.8	35.0	135.1	-139.2	-39.1	-48.1	-141.9	137.76	-144.21	0.31	OK
Story5	D15	A13.5	462	-3.10	0.00	0.35	-1.01	26.09	-2.97	22.2	-30.2	45.3	142.8	33.1	139.1	-148.0	-41.9	-54.2	-151.7	47.6	145.1	35.4	141.5	-145.6	-39.6	-51.8	-149.3	145.14	-151.65	0.33	OK
Story4	D15	A13.5	462	-3.13	0.00	0.36	-1.31	41.28	-3.83	36.3	-45.0	48.8	150.0	33.6	145.4	-154.4	-42.5	-57.8	-159.0	51.2	152.4	35.9	147.8	-152.0	-40.1	-55.4	-156.6	152.38	-158.96	0.34	OK
Story3	D15	A13.5	462	-3.08	0.00	0.34	-1.56	53.29	-4.55	47.6	-56.6	51.6	155.4	33.9	150.1	-158.9	-42.7	-60.4	-164.2	53.9	157.7	36.2	152.4	-156.5	-40.4	-58.1	-161.8	157.71	-164.18	0.36	OK
Story2	D15	A13.5	462	-3.11	0.00	0.35	-1.75	61.10	-5.12	55.0	-64.3	52.4	155.0	32.7	149.1	-158.0	-41.5	-61.3	-163.9	54.7	157.4	35.0	151.5	-155.6	-39.2	-58.9	-161.6	157.38	-163.92	0.36	OK
Story1	D15	A13.5	462	-2.94	0.00	0.40	-1.38	44.32	-4.04	39.3	-47.8	38.9	115.0	22.8	110.1	-118.6	-31.2	-47.3	-123.4	41.1	117.2	25.0	112.4	-116.3	-28.9	-45.1	-121.2	117.22	-123.40	0.27	OK
Ground	D15	A13.5	462	-3.19	0.00	0.32	0.71	-40.21	2.05	-40.6	35.5	11.5	36.4	3.2	33.9	-43.0	-12.3	-20.6	-45.5	13.9	38.8	5.6	36.3	-40.6	-9.9	-18.2	-43.1	61.46	-68.16	0.15	OK
B1	D15	A13.5	462	-3.07	0.00	0.29	0.47	-27.61	1.37	-28.7	23.5	7.0	24.8	1.2	23.1	-31.8	-10.0	-15.8	-33.6	9.3	27.1	3.5	25.4	-29.5	-7.6	-13.5	-31.2	41.41	-47.85	0.10	OK
B2	D15	A13.5	462	-3.09	0.00	0.29	0.23	-12.45	0.66	-14.6	9.0	1.9	11.5	-1.5	10.5	-19.3	-7.3	-10.8	-20.3	4.3	13.8	0.8	12.8	-17.0	-5.0	-8.4	-18.0	17.13	-23.62	0.05	OK
B3	D15	A13.5	462	-3.12	0.00	0.29	-0.02	3.86	-0.06	0.4	-6.6	-0.5	6.1	-2.2	5.6	-14.5	-6.7	-8.4	-15.0	1.8	8.5	0.2	8.0	-12.2	-4.4	-6.0	-12.7	8.49	-15.03	0.03	OK

Story	ETABS #	Section	Capacity	Dead	Live	WindFX	WindMTX	WindFY	WindMTY																					Maximum Axial Loads			
																														Tension	Compression	DCR	Status
Story40	D16	A7	239	-2.58	0.00	0.00	1.24	-10.92	3.56	-14.2	11.8	33.6	100.9	20.6	97.0	-104.4	-28.0	-41.0	-108.3	35.6	102.9	22.6	99.0	-102.4	-26.0	-39.0	-106.3	102.87	-108.28	0.45	OK
Story39	D16	A7	239	-2.63	0.00	0.01	1.59	-19.08	4.56	-22.2	20.4	40.4	118.0	23.7	113.0	-120.6	-31.2	-47.9	-125.6	42.4	120.0	25.7	115.0	-118.6	-29.2	-45.9	-123.6	120.03	-125.55	0.52	OK
Story38	D16	A7	239	-2.68	0.00	0.01	1.88	-26.23	5.40	-29.2	27.8	49.6	144.4	29.9	138.5	-146.1	-37.5	-57.3	-152.1	51.7	146.4	31.9	140.5	-144.1	-35.5	-55.3	-150.0	146.44	-152.07	0.64	OK
Story37	D16	A7	239	-2.73	0.00	0.02	2.18	-34.59	6.25	-37.3	36.3	53.7	154.2	31.3	147.5	-155.3	-39.1	-61.6	-162.0	55.8	156.3	33.4	149.6	-153.2	-37.0	-59.5	-160.0	156.30	-162.04	0.68	OK
Story36	D16	A7	239	-2.78	0.00	0.04	2.53	-41.46	7.26	-44.2	43.6	58.3	163.9	32.1	156.0	-164.0	-40.1	-66.3	-171.8	60.4	166.0	34.2	158.1	-161.9	-38.0	-64.1	-169.7	166.00	-171.85	0.72	OK
Story35	D16	A11	376	-2.95	0.00	0.07	4.18	-59.07	12.00	-63.0	65.1	78.5	207.1	36.1	194.4	-202.9	-44.5	-86.9	-215.6	80.7	209.4	38.3	196.7	-200.6	-42.3	-84.7	-213.3	209.37	-215.57	0.57	OK
Story34	D16	A11	376	-3.01	0.00	0.09	4.33	-67.19	12.44	-70.6	72.8	78.9	205.9	34.7	192.7	-201.3	-43.3	-87.5	-214.5	81.1	208.2	37.0	195.0	-199.0	-41.0	-85.2	-212.2	208.21	-214.52	0.57	OK
Story33	D16	A11	376	-2.95	0.00	0.11	4.65	-76.71	13.36	-79.7	82.6	82.0	211.6	34.9	197.5	-205.9	-43.3	-90.4	-220.1	84.2	213.9	37.1	199.7	-203.7	-41.1	-88.2	-217.8	213.87	-220.07	0.58	OK
Story32	D16	A11	376	-3.00	0.00	0.15	4.89	-84.68	14.04	-87.3	90.5	82.8	211.0	33.3	196.2	-204.8	-41.9	-91.4	-219.6	85.1	213.3	35.6	198.5	-202.5	-39.6	-89.1	-217.3	213.32	-219.62	0.58	OK
Story31	D16	A13.5	462	-2.94	0.00	0.14	5.91	-100.37	16.96	-103.1	108.2	95.0	236.3	35.5	218.4	-226.8	-43.9	-103.4	-244.7	97.2	238.5	37.8	220.7	-224.6	-41.7	-101.2	-242.4	238.49	-244.66	0.53	OK
Story30	D16	A13.5	462	-2.98	0.00	0.18	5.82	-107.97	16.72	-109.9	114.7	94.2	235.2	35.7	217.6	-226.2	-44.2	-102.7	-243.7	96.4	237.4	38.0	219.9	-223.9	-42.0	-100.4	-241.4	237.44	-243.69	0.53	OK
Story29	D16	A13.5	462	-2.93	0.00	0.16	6.07	-116.09	17.42	-117.6	122.9	96.3	239.2	35.9	221.1	-229.5	-44.3	-104.6	-247.6	98.5	241.4	38.2	223.3	-227.2	-42.1	-102.4	-245.3	241.41	-247.57	0.54	OK
Story28	D16	A13.5	462	-2.97	0.00	0.18	6.26	-121.87	17.99	-123.2	128.8	97.4	240.4	35.3	221.8	-230.3	-43.8	-105.9	-248.9	99.6	242.7	37.6	224.0	-228.0	-41.6	-103.6	-246.6	242.66	-248.89	0.54	OK
Story27	D16	A13.5	462	-2.88	0.00	0.15	5.95	-117.07	17.11	-118.2	123.5	90.3	221.6	31.7	204.0	-212.2	-39.9	-98.5	-229.8	92.4	223.8	33.8	206.2	-210.1	-37.7	-96.3	-227.6	223.78	-229.83	0.50	OK
Story26	D16	A13.5	462	-2.91	0.00	0.17	6.08	-121.84	17.48	-122.8	128.2	91.1	222.9	31.4	205.0	-213.4	-39.8	-99.4	-231.3	93.3	225.1	33.6	207.2	-211.1	-37.6	-97.2	-229.0	225.14	-231.26	0.50	OK
Story25	D16	A13.5	462	-2.95	0.00	0.18	6.17	-128.17	17.73	-128.7	134.2	92.8	227.5	32.4	209.4	-217.8	-40.8	-101.2	-235.9	95.0	229.7	34.6	211.6	-215.6	-38.6	-99.0	-233.7	229.75	-235.93	0.51	OK
Story24	D16	A13.5	462	-2.98	0.00	0.20	6.30	-132.91	18.12	-133.2	138.9	94.2	230.6	32.6	212.1	-220.6	-41.1	-102.7	-239.1	96.5	232.8	34.9	214.4	-218.4	-38.9	-100.5	-236.8	232.85	-239.10	0.52	OK
Story23	D16	A13.5	462	-3.01	0.00	0.21	6.25	-134.54	17.99	-134.7	140.1	93.3	228.2	32.2	209.9	-218.5	-40.7	-101.9	-236.8	95.5	230.5	34.4	212.2	-216.2	-38.5	-99.6	-234.5	230.49	-236.80	0.51	OK
Story22	D16	A13.5	462	-3.04	0.00	0.23	6.38	-140.27	18.37	-140.1	145.7	95.2	232.8	32.8	214.0	-222.7	-41.5	-103.9	-241.4	97.5	235.1	35.1	216.3	-220.4	-39.2	-101.6	-239.1	235.05	-241.43	0.52	OK
Story21	D16	A13.5	462	-2.99	0.00	0.22	6.52	-146.15	18.78	-145.6	151.6	97.6	238.6	33.9	219.6	-228.1	-42.5	-106.1	-247.2	99.8	240.9	36.2	221.8	-225.8	-40.2	-103.8	-244.9	240.91	-247.18	0.54	OK
Story20	D16	A13.5	462	-3.02	0.00	0.24	6.56	-150.43	18.89	-149.5	155.5	98.3	240.5	34.3	221.3	-229.9	-42.9	-106.9	-249.1	100.6	242.8	36.5	223.6	-227.7	-40.6	-104.6	-246.9	242.81	-249.14	0.54	OK
Story19	D16	A13.5	462	-3.05	0.00	0.26	6.24	-147.20	17.97	-146.1	151.4	94.4	232.2	33.3	213.9	-222.6	-42.0	-103.1	-240.9	96.7	234.5	35.6	216.2	-220.3	-39.7	-100.8	-238.6	234.52	-240.92	0.52	OK
Story18	D16	A13.5	462	-3.08	0.00	0.28	6.25	-150.88	18.00	-149.5	154.7	95.3	235.0	34.0	216.6	-225.4	-42.8	-104.1	-243.8	97.7	237.3	36.3	218.9	-223.0	-40.4	-101.8	-241.4	238.63	-245.10	0.53	OK
Story17	D16	A13.5	462	-3.02	0.00	0.27	6.30	-155.26	18.15	-153.5	158.9	97.0	239.6	35.2	221.1	-229.7	-43.8	-105.6	-248.3	99.3	241.9	37.5	223.4	-227.4	-41.5	-103.3	-246.0	245.69	-252.04	0.55	OK
Story16	D16	A13.5	462	-3.05	0.00	0.29	6.36	-160.95	18.34	-158.8	164.2	98.7	244.2	36.1	225.5	-234.2	-44.8	-107.4	-253.0	101.0	246.5	38.4	227.8	-231.9	-42.5	-105.1	-250.6	254.77	-261.18	0.57	OK
Story15	D16	A13.5	462	-2.96	0.00	0.26	6.37	-163.20	18.36	-160.7	166.4	99.7	247.5	37.3	228.8	-237.2	-45.7	-108.2	-256.0	101.9	249.7	39.5	231.0	-235.0	-43.5	-105.9	-253.7	258.45	-264.67	0.57	OK
Story14	D16	A13.5	462	-2.99	0.00	0.27	6.38	-166.02	18.41	-163.3	168.9	100.8	250.6	38.0	231.8	-240.3	-46.5	-109.3	-259.2	103.0	252.9	40.3	234.1	-238.1	-44.3	-107.0	-256.9	262.94	-269.22	0.58	OK
Story13	D16	A13.5	462	-3.02	0.00	0.29	6.30	-164.39	18.18	-161.8	167.2	100.4	250.3	38.2	231.7	-240.3	-46.8	-109.0	-258.9	102.6	252.6	40.5	234.0	-238.0	-44.5	-106.7	-256.7	260.31	-266.66	0.58	OK
Story12	D16	A13.5	462	-3.05	0.00	0.31	5.86	-149.91	16.93	-148.0	152.6	95.0	238.7	36.8	221.2	-230.0	-45.6	-103.8	-247.4	97.3	241.0	39.2	223.6	-227.7	-43.3	-101.4	-245.1	241.01	-247.42	0.54	OK
Story11	D16	A13.5	462	-3.00	0.00	0.30	4.26	-100.33	12.33	-100.6	102.4	75.5	196.7	32.7	183.9	-192.5	-41.3	-84.1	-205.3	77.8	199.0	35.0	186.2	-190.2	-39.0	-81.8	-203.1	199.02	-205.33	0.44	OK
Story10	D16	A13.5	462	-3.03	0.00	0.31	0.32	10.02	0.95	5.4	-10.9	36.4	124.1	31.6	122.7	-131.3	-40.2	-45.1	-132.8	38.7	126.4	33.9	125.0	-129.0	-37.9	-42.8	-130.5	126.41	-132.77	0.29	OK
Story9	D16	A13.5	462	-3.06	0.00	0.32	-0.15	27.67	-0.40	22.1	-28.5	35.4	124.1	32.7	123.3	-132.0	-41.5	-44.1	-132.8	37.7	126.4	35.0	125.6	-129.7	-39.1	-41.8	-130.5	126.39	-132.82	0.29	OK
Story8	D16	A13.5	462	-3.09	0.00	0.34	0.15	16.04	0.48	11.1	-17.0	36.3	126.1	32.8	125.0	-133.8	-41.6	-45.2	-134.9	38.7	128.4	35.1	127.3	-131.5	-39.3	-42.8	-132.6	128.41	-134.91	0.29	OK
Story7	D16	A13.5	462	-3.04	0.00	0.33	0.39	4.65	1.17	0.5	-5.8	38.5	129.6	32.6	127.8	-136.5	-41.3	-47.2	-138.3	40.8	131.9	34.9	130.1	-134.2	-39.0	-44.9	-136.0	131.88	-138.27	0.30	OK
Story6	D16	A13.5	462	-3.07	0.00	0.34	0.70	-10.32	2.06	-13.6	8.7	41.7	135.4	32.6	132.7	-141.5	-41.4	-50.4	-144.2	44.0	137.8	35.0	135.1	-139.2	-39.1	-48.1	-141.9	137.76	-144.21	0.31	OK
Story5	D16	A13.5	462	-3.10	0.00	0.35	1.01	-26.09	2.97	-28.4	24.0	45.3	142.8	33.1	139.1	-148.0	-41.9	-54.2	-

SIMPSON GUMPERTZ & HEGER
Engineering of Structures and Building Enclosures

CLIENT Pacific Earthquake Engineering Research Center
SUBJECT BRB Strength Check along Line D for LA BRBF Bldg

SHEET NO. ____
PROJECT NO. 087237.10
DATE 1/23/09
BY AD
CHECKED BY ____

V-target= 3626.26 kips(85% of Static Base Shear)
V-SPECX= 11595.55 kips Scale-X= 3.20
V-SPECY= 12103.43 kips Scale-Y= 3.34
SDS = 1.145
ρ-X dir = 1
ρ -Y dir = 1

Model: 121908Model1

| | | |

SIMPSON GUMPERTZ & HEGER
Engineering of Structures
Cost Building Processes

CLIENT Pacific Earthquake Engineering Research Center
SUBJECT BRB Strength Check along Line D for LA BRBF Bldg

SHEET NO.
PROJECT NO. 087237.10
DATE 1/23/09
BY AD
CHECKED BY

V-target= 3626.26 kips(85% of Static Base Shear)
V-SPECX= 11595.55 kips Scale-X= 3.20
V-SPECY= 12103.43 kips Scale-Y= 3.34
SDS = 1.145
ρ-X dir = 1
ρ- Y dir = 1

Model: 121908Model1

0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9
		1.2	1.2	-1.2	-1.2	1.2	-1.2			1.2	-1.2	-1.2	-1.2							0.9008	0.9008	-0.9008	-0.9008	0.9008	0.9008	-0.9008	-0.9008	0.9008	0.9008	-0.9008	-0.9008
								1.2	-1.2	1.2	-1.2									0.9008	-0.9008	0.9008	-0.9008	0.9008	0.9008	0.9008	-0.9008	-0.9008	-0.9008	-0.9008	-0.9008
1.6	-1.6	1.2	-1.2	1.2	-1.2							1.2	1.2	-1.2	-1.2					0.9008	0.9008	-0.9008	-0.9008	0.9008	0.9008	-0.9008	-0.9008	0.9008	0.9008	-0.9008	-0.9008
												1.2	-1.2	1.2	-1.2					0.9008	0.9008	0.9008	0.9008	-0.9008	-0.9008	-0.9008	-0.9008	0.9008	0.9008	-0.9008	0.9008
9 Case 1		Figure 6-9 Case 2						Figure 6-9 Case 3										Figure 6-9 Case 4													

Story	ETABS #	Section	Capacity	Dead	Live	WindFX	WindMTX	WindFY	WindMTY																						
Story40	D1	A7	239	-5.97	0.00	4.11	9.15	0.01	26.30	-5.4	-5.4	-0.4	-0.5	-10.3	-10.3	10.5	-11.4	0.7	-21.3	26.2	-36.9	26.2	-36.9	30.3	13.8	22.9	6.4	-17.1	30.3	-17.1	-41.0	-24.5	-33.6	-33.6	6.4	-41.0	13.8
Story39	D1	A7	239	-5.98	0.00	8.39	9.50	0.03	27.29	-5.3	-5.4	4.7	4.7	-15.4	-15.5	16.1	-6.7	-4.1	-26.8	27.4	-38.1	27.3	-38.2	35.3	18.2	20.2	3.1	-13.8	35.3	-13.9	-46.1	-29.0	-31.0	-30.9	3.1	-46.1	18.2
Story38	D1	A7	239	-6.00	0.00	12.67	9.80	0.07	28.16	-5.3	-5.5	9.9	9.7	-20.5	-20.7	21.6	-1.9	-8.8	-32.4	28.5	-39.1	28.3	-39.3	40.3	22.6	17.4	-0.2	-10.5	40.1	-10.6	-51.1	-33.4	-28.2	-28.1	-0.3	-50.9	22.5
Story37	D1	A8	274	-6.45	0.00	16.14	11.52	0.23	33.11	-5.4	-6.2	13.8	13.3	-24.9	-25.4	27.4	-0.3	-11.3	-39.0	34.2	-45.2	33.6	-45.8	49.1	28.4	20.1	-0.7	-10.5	48.7	-10.9	-60.8	-40.0	-31.7	-31.3	-1.1	-60.3	28.0
Story36	D1	A8	274	-6.46	0.00	20.14	11.93	0.54	34.29	-4.9	-6.7	19.0	17.7	-29.3	-30.6	32.7	4.0	-15.7	-44.3	36.0	-46.3	34.7	-47.6	54.4	32.9	18.2	-3.3	-7.3	53.5	-8.3	-66.1	-44.6	-29.8	-28.8	-4.3	-65.1	32.0
Story35	D1	A8	274	-6.49	0.00	23.72	12.13	1.04	34.85	-4.2	-7.5	23.9	21.4	-33.1	-35.5	37.2	8.1	-19.8	-48.9	37.2	-46.4	34.7	-48.9	58.8	36.9	16.0	-5.8	-4.0	56.9	-5.9	-70.5	-48.6	-27.7	-25.9	-7.7	-68.6	35.1
Story34	D1	A10	342	-7.37	0.00	27.57	15.30	1.90	43.98	-3.6	-9.7	28.7	24.2	-37.4	-42.0	44.8	8.1	-21.4	-58.1	48.4	-57.1	43.9	-61.7	73.3	45.7	23.6	-3.9	-5.9	69.9	-9.3	-86.6	-59.0	-36.9	-33.5	-7.4	-83.2	42.3
Story33	D1	A10	342	-7.34	0.00	30.84	15.59	2.46	44.80	-2.7	-10.5	33.4	27.4	-40.7	-46.6	49.1	11.7	-24.9	-62.3	50.1	-57.4	44.2	-63.3	77.8	49.7	22.2	-5.9	-2.9	73.4	-7.4	-91.0	-62.9	-35.4	-31.0	-10.3	-88.6	45.3
Story32	D1	A10	342	-7.42	0.00	34.77	15.80	3.23	45.42	-1.5	-11.8	38.9	31.2	-44.5	-52.3	54.0	16.1	-29.4	-67.4	51.7	-57.3	43.9	-65.1	82.7	54.2	20.1	-8.4	0.9	76.9	-4.9	-96.1	-67.6	-33.4	-27.6	-14.2	-90.2	48.4
Story31	D1	A10	342	-7.39	0.00	37.56	15.75	3.71	45.26	-0.7	-12.6	42.9	34.0	-47.3	-56.2	57.3	19.5	-32.8	-70.6	52.1	-56.5	43.2	-65.4	85.5	57.1	17.8	-10.5	3.9	78.8	-2.7	-98.8	-70.4	-31.1	-24.4	-17.2	-92.1	50.4
Story30	D1	A13.5	462	-8.99	0.00	47.70	21.10	5.87	60.67	1.3	-17.5	56.2	42.1	-58.3	-72.4	74.5	23.8	-40.0	-90.7	71.8	-73.8	57.7	-87.9	113.8	75.8	27.9	-10.1	4.5	103.2	-6.1	-130.0	-92.0	-44.1	-33.5	-20.7	-119.4	65.2
Story29	D1	A13.5	462	-9.08	0.00	50.80	21.20	6.88	60.95	2.8	-19.2	61.1	44.5	-60.9	-77.4	78.2	27.4	-43.7	-94.6	73.2	-73.0	56.7	-89.6	117.8	79.6	26.3	-11.9	8.0	106.4	-4.4	-134.1	-95.9	-42.6	-30.2	-24.3	-121.7	67.2
Story28	D1	A13.5	462	-9.29	0.00	55.11	21.17	8.26	60.88	4.8	-21.6	67.7	47.9	-64.6	-84.4	83.2	32.4	-49.1	-99.9	74.6	-71.5	54.8	-91.3	122.6	84.5	23.3	-14.8	13.0	107.8	-1.9	-139.3	-101.2	-40.1	-25.2	-29.7	-124.5	69.6
Story27	D1	A13.5	462	-9.40	0.00	59.17	20.67	9.35	59.45	6.5	-23.4	73.8	51.3	-68.2	-90.7	87.4	37.7	-54.7	-104.3	74.1	-68.6	51.7	-91.0	125.4	88.2	18.8	-18.4	18.3	108.6	1.5	-142.4	-105.1	-35.8	-18.9	-35.3	-125.5	71.4
Story26	D1	A13.5	462	-9.65	0.00	61.86	20.49	10.90	58.96	8.8	-26.1	78.6	52.5	-69.8	-96.0	90.1	40.9	-58.3	-107.5	75.1	-66.4	49.0	-92.5	128.4	91.5	17.0	-19.9	22.2	108.8	2.6	-145.8	-108.9	-34.4	-14.7	-39.6	-126.2	71.9
Story25	D1	A15.5	530	-10.51	0.00	68.28	23.25	13.02	66.90	11.4	-30.3	88.1	56.8	-75.8	-107.0	100.4	44.6	-63.5	-119.3	86.4	-74.1	55.2	-105.4	145.0	103.1	22.0	-19.9	24.5	121.5	1.0	-163.9	-122.0	-40.9	-17.4	-43.4	-140.4	79.6
Story24	D1	A15.5	530	-10.49	0.00	71.02	22.97	13.93	66.09	12.8	-31.7	92.5	59.1	-77.9	-111.4	103.3	48.2	-67.1	-122.2	86.6	-72.0	53.2	-105.5	147.3	105.9	19.4	-22.0	28.2	122.2	3.1	-166.2	-124.8	-38.3	-13.2	-47.1	-141.1	80.8
Story23	D1	A15.5	530	-10.07	0.00	74.79	22.48	13.49	64.71	12.5	-30.6	96.9	64.5	-82.6	-115.0	107.7	53.7	-71.8	-125.8	84.8	-70.5	52.4	-102.9	149.0	108.5	14.3	-26.2	32.4	124.7	8.1	-167.1	-126.6	-32.4	-8.1	-50.5	-142.8	84.2
Story22	D1	A15.5	530	-9.70	0.00	78.81	22.13	13.17	63.69	12.3	-29.8	101.6	70.0	-87.5	-119.1	112.4	59.3	-76.7	-129.9	83.5	-69.4	51.9	-101.0	151.4	111.6	9.4	-30.4	36.7	127.7	13.0	-168.9	-129.0	-26.9	-3.2	-54.1	-145.2	87.8
Story21	D1	A15.5	530	-9.10	0.00	82.48	21.82	11.97	62.81	11.0	-27.3	105.1	76.4	-92.8	-121.5	117.0	64.6	-81.0	-133.3	81.5	-69.2	52.8	-97.9	153.1	113.8	4.5	-34.8	40.0	131.6	18.4	-169.5	-130.2	-20.9	0.7	-56.3	-147.9	92.3
Story20	D1	A15.5	530	-8.60	0.00	86.20	21.34	10.86	61.44	9.6	-25.1	108.7	82.7	-98.1	-124.2	121.3	70.1	-85.6	-136.8	79.0	-68.4	53.0	-94.5	154.3	115.8	-1.0	-39.5	43.6	134.7	24.0	-169.7	-131.3	-14.4	5.1	-59.0	-150.2	96.3
Story19	D1	A15.5	530	-8.09	0.00	89.97	20.43	9.65	58.85	8.2	-22.7	112.3	89.1	-103.7	-126.8	125.2	76.2	-90.7	-139.8	74.9	-66.3	51.7	-89.5	153.9	117.1	-8.2	-45.0	47.9	136.5	30.5	-168.4	-131.6	-6.3	11.0	-62.4	-151.0	99.7
Story18	D1	A15.5	530	-7.58	0.00	93.80	19.81	8.31	57.06	6.5	-20.1	115.7	95.8	-109.4	-129.3	129.5	82.0	-95.6	-143.2	71.6	-65.3	51.7	-85.3	154.4	118.7	-14.6	-50.3	51.6	139.4	36.6	-168.0	-132.4	0.9	15.9	-65.2	-153.1	103.7
Story17	D1	A15.5	530	-7.12	0.00	97.46	19.25	7.09	55.47	4.9	-17.8	119.0	102.0	-114.9	-131.9	133.6	87.4	-100.3	-146.5	68.7	-64.5	51.6	-81.5	155.1	120.4	-20.5	-55.2	55.1	142.3	42.4	-167.9	-133.2	7.7	20.5	-68.0	-155.1	107.6
Story16	D1	A15.5	530	-6.72	0.00	101.25	18.65	5.85	53.75	3.3	-15.4	122.5	108.4	-120.5	-134.6	137.8	93.1	-105.2	-149.9	66.5	-63.5	51.4	-77.6	155.6	122.0	-26.8	-60.4	58.8	145.1	48.3	-167.7	-134.1	14.7	25.2	-70.9	-157.2	111.5
Story15	D1	A15.5	530	-6.62	0.00	105.01	18.03	5.76	51.95	3.3	-15.2	127.0	113.1	-125.1	-138.9	141.7	98.4	-110.3	-153.6	63.3	-61.4	49.5	-75.2	156.9	124.4	-32.3	-64.8	63.3	146.5	52.9	-168.8	-136.3	20.4	30.8	-75.2	-158.4	114.0
Story14	D1	A15.5	530	-6.59	0.00	108.88	17.35	5.77	50.03	3.3	-15.2	131.7	117.8	-129.7	-143.5	145.6	103.9	-115.8	-157.4	61.0	-59.0	47.2	-72.9	158.0	126.8	-38.1	-69.4	67.9	147.7	57.5	-169.9	-138.6	26.3	36.6	-79.8	-159.5	116.4
Story13	D1	A15.5	530	-6.54	0.00	112.79	16.53	5.68	47.66	3.2	-15.0	136.3	122.6	-134.4	-148.0	149.3	109.6	-121.4	-161.1	58.1	-56.3	44.5	-69.9	158.7	128.9	-44.5	-74.3	72.8	148.4	62.6	-170.4	-140.6	32.8	43.0	-84.6	-160.2	118.6
Story12	D1	A15.5	530	-6.47	0.00	116.75	15.28	5.49	44.08	3.0	-14.6	140.9	127.7	-139.3	-152.5	152.6	115.9	-127.6	-164.3	53.7	-52.1	40.5	-65.3	157.8	130.2	-52.6	-80.1	78.4	147.9	68.5	-169.4	-141.9	40.9	50.8	-90.0	-159.5	120.3
Story11	D1	A15.5	530	-6.36	0.00	120.48	12.87	5.29	37.15	2.7	-14.2	145.2	132.5	-144.0	-156.6	154.3	123.4	-134.9	-165.7	45.2	-44.0	32.5	-56.6	152.6	129.4	-64.4	-87.6	85.7	143.1	76.2	-164.1	-140.9	53.0	62.5	-97.2	-154.5	119.9
Story10	D1	A15.5	530	-6.31	0.00	124.41	8.02	5.16	23.16	2.6	-13.9	149.8	137.4	-148.8	-161.2	153.2	134.0	-145.3	-164.6	28.3	-27.3	15.9	-39.7	139.1	124.7	-85.0	-99.5	97.4	129.8	88.1	-150.5	-136.0	73.6	82.9	-108.8	-141.2	115.4
Story9	D1	A15.5	530	-5.83	0.00	127.81	6.82	3.64	19.69	0.6	-11.1	152.5	143.8	-154.3	-163.0	156.3	139.9	-150.4	-166.8	22.7	-24.5	14.0	-33.2	137.0	124.8	-93.2	-105.5	101.6	130.5	95.0	-147.5	-135.2	82.7	88.9	-112.1	-141.0	118.2
Story8	D1	A15.5	530	-5.35	0.00	131.29	6.42	2.22	18.56	-1.3	-8.4	155.4	150.1	-159.7	-165.0	160.4	145.0	-154.6	-170.1	20.1	-24.4	14.8	-29.8	138.0	126.4	-98.6	-110.1	104.5	134.0	100.5	-147.6	-136.0	88.9	92.9	-114.1	-143.6	122.4
Story7	D1	A15.5	530	-5.26	0.00	134.96	6.00	2.27	17.38	-1.1	-8.4	159.9	154.5	-164.0	-169.4	164.4	150.0	-159.5	-173.9	18.8	-22.8	13.4	-28.3	139.9	129.1	-103.2	-114.0	108.7	135.8	104.6	-149.4	-138.6	93.7	97.8	-118.1	-145.3	125.0
Story6	D1	A15.5	530	-5.19	0.00	138.39	5.66	2.40	16.38	-0.8	-8.5	164.3	158.5	-167.8	-173.6	168.2	154.6	-163.9	-177.5	17.9	-21.4	12.1	-27.2	142.0	131.8	-107.3	-117.5	112.5	137.7	108.2	-151.3	-141.1	98.0	102.3	-121.8	-147.0	127.5
Story5	D1	A15.5	530	-4.67	0.00	140.41	5.37	1.34	15.54	-2.1	-6.3	165.9	162.7	-171.1	-174.3	170.7	157.8	-166.3	-179.1	16.1	-21.2	12.8	-24.5	142.3	132.6	-110.6	-120.3	114.3	139.9	111.9	-150.7	-141.1	102.2	104.7	-122.7	-148.3	130.2
Story4	D1	A15.5	530	-4.15	0.00	140.67	5.06	0.30	14.65	-3.3	-4.2	165.4	164.7	-172.2	-172.9	171.2	159.0	-166.5	-178.6	14.2	-21.0	13.5	-21.7	141.0	131.9	-112.4	-121.5	114.6	140.5	114.1	-148.5	-139.4	106.0	105.5	-122.1	-147.9	131.4
Story3	D1	A15.5	530	-3.62	0.00	136.87	4.75	-0.62	13.77	-4.3	-2.3	160.2	161.7	-168.3	-166.8	166.7	155.3	-161.8	-173.2	12.5	-20.5	14.0	-19.0	136.2	127.6	-110.4	-119.0	111.3	137.3	112.5	-142.7	-134.1	103.9	102.8	-117.9	-143.8	128.7
Story2	D1	A15.5	530	-3.13	0.00	125.09	4.38	-1.52	12.70	-5.2	-0.4	145.5	149.1	-154.8	-151.1	152.6	142.0	-147.7	-158.2	10.6	-19.9	14.2	-16.2	123.9	116.0	-101.5	-109.4	101.0	126.6	103.7	-129.5	-121.6	95.9	93.1	-106.6	-132.3	118.7
Story1	D1	A15.5	530	-2.72	0.00	83.92	3.26	-1.07	9.46	-4.2	-0.7	97.0	99.5	-104.4	-101.9	102.2	94.3	-99.2	-107.1	7.6	-15.1	10.2	-12.5	83.6	77.8	-67.6	-73.4	66.6	85.6	68.5	-88.5	-82.7	62.7	60.7	-71.5	-90.5	79.7
Ground	D1	A14	479	-3.05	0.00	-8.19	0.51	-1.04	1.46	-4.4	-1.1	-13.8	-11.3	5.8	8.3	-12.0	-13.2	7.7	6.5	-2.2	-5.7	0.2	-3.3	-9.3	-10.2	5.5	4.6	-11.9	-7.4	-10.0	3.8	4.7	-11.0	-12.8	6.4	1.9	-8.3
B1	D1	A14	479	-3.15	0.00	-6.43	0.33	-0.35	0.84	-3.4	-2.3	-11.0	-10.1	4.5	5.3	-10.2	-10.9	5.3	4.5	-2.1	-4.4	-1.3	-3.5	-7.8	-8.4	3.8	3.2	-9.5	-7.2	-8.9	2.1	2.7	-9.5	-10.1	3.8	1.5	-7.8
B2	D1	A14	479	-3.33	0.00	-2.17	0.15	0.44	0.44	-2.3	-3.7	-5.1	-6.1	0.1	-0.9	-5.4	-5.8	-0.2	-0.6	-1.9	-1.9	-3.0	-3.0	-4.1	-4.0	-4.3	-0.1	-0.4	-4.8	-4.8	-5.6	-2.0	-1.7	-5.9	-5.1	-1.2	-5.1
B3	D1	A14	479	-3.50	0.00	2.71	-0.01	1.24	-0.04	-1.2	-5.1	1.6	-1.4	-4.9	-7.9	0.1	0.1	-6.4	-6.4	-1.7	-1.6	-4.7	-4.6	0.4	0.4	-4.5	-4.5	0.4	-1.9	-1.8	-6.7	-6.7	-1.8	0.5	-6.7	-4.4	-1.8

SIMPSON GUMPERTZ & HEGER
Engineering of Structures and Building Enclosures

CLIENT Pacific Earthquake Engineering Research Center
SUBJECT BRB Strength Check along Line D for LA BRBF Bldg

SHEET NO.
PROJECT NO. 087237.10
DATE 1/23/09
BY AD
CHECKED BY

V-target= 3626.26 kips(85% of Static Base Shear)
V-SPECX= 11595.55 kips Scale-X= 3.20
V-SPECY= 12103.43 kips Scale-Y= 3.34
SDS = 1.145
ρ-X dir = 1
ρ -Y dir = 1

Model: 121908Model1

0.9	0.9	1.429	1.429	1.429	1.429	1.429	1.429	1.429	1.429	0.671	0.671	0.671	0.671	0.671	0.671	0.671	0.671				
		0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5												
-0.9008	-0.9008																				
0.9008	0.9008																				
0.9008	-0.9008																				
-0.9008	0.9008																				
		1	0.3	-1	-0.3	0.3	1	-1	-0.3	1	0.3	-1	-0.3	0.3	1	-1	-0.3				
		0.3	1	0.3	1	-1	-0.3	-0.3	-1	0.3	1	0.3	1	-1	-0.3	-0.3	-1				

Story	ETABS #	Section	Capacity	Dead	Live	WindFX	WindMTX	WindFY	WindMTY																					Maximum Axial Loads			
																														Tension	Compression	DCR	Status
Story40	D1	A7	239	-5.97	0.00	4.11	9.15	0.01	26.30	-24.5	22.9	140.5	104.8	-112.3	29.0	-46.1	95.2	-157.5	-121.9	145.0	109.3	-107.7	33.5	-41.5	99.7	-153.0	-117.3	144.98	-157.52	0.66	OK
Story39	D1	A7	239	-5.98	0.00	8.39	9.50	0.03	27.29	-28.9	20.2	151.2	110.6	-121.3	28.9	-46.0	104.2	-168.3	-127.7	155.7	115.2	-116.8	33.4	-41.5	108.7	-163.8	-123.2	155.73	-168.29	0.70	OK
Story38	D1	A7	239	-6.00	0.00	12.67	9.80	0.07	28.16	-33.3	17.3	184.5	122.7	-153.3	21.4	-38.5	136.1	-201.6	-139.8	189.1	127.3	-148.7	25.9	-34.0	140.7	-197.1	-135.3	189.05	-201.64	0.84	OK
Story37	D1	A8	274	-6.45	0.00	16.14	11.52	0.23	33.11	-39.6	19.6	202.9	140.1	-164.8	29.8	-48.2	146.4	-221.3	-158.5	207.8	145.0	-159.9	34.6	-43.3	151.3	-216.4	-153.6	207.75	-221.29	0.81	OK
Story36	D1	A8	274	-6.46	0.00	20.14	11.93	0.54	34.29	-43.6	17.2	218.5	147.1	-179.0	27.9	-46.4	160.5	-237.0	-165.6	223.4	152.0	-174.1	32.8	-41.5	165.4	-232.1	-160.7	223.44	-237.01	0.87	OK
Story35	D1	A8	274	-6.49	0.00	23.72	12.13	1.04	34.85	-46.7	14.2	226.9	150.2	-187.1	26.0	-44.5	168.5	-245.5	-168.7	231.9	155.1	-182.2	30.9	-39.6	173.5	-240.6	-163.8	231.87	-245.50	0.90	OK
Story34	D1	A10	342	-7.37	0.00	27.57	15.30	1.90	43.98	-55.6	20.2	256.4	181.6	-203.6	43.5	-64.6	182.5	-277.5	-202.6	262.0	187.1	-198.0	49.1	-59.0	188.1	-271.9	-197.0	261.98	-277.47	0.81	OK
Story33	D1	A10	342	-7.34	0.00	30.84	15.59	2.46	44.80	-58.5	17.8	265.1	186.5	-210.7	43.8	-64.7	189.7	-286.1	-207.5	270.7	192.1	-205.2	49.3	-59.2	195.3	-280.5	-201.9	270.69	-286.11	0.84	OK
Story32	D1	A10	342	-7.42	0.00	34.77	15.80	3.23	45.42	-61.8	14.2	270.8	190.4	-215.1	44.6	-65.8	193.9	-292.0	-211.6	276.4	196.0	-209.5	50.2	-60.2	199.5	-286.4	-206.0	276.41	-292.00	0.85	OK
Story31	D1	A10	342	-7.39	0.00	37.56	15.75	3.71	45.26	-63.7	11.1	272.6	190.8	-216.9	44.0	-65.1	195.8	-293.7	-211.9	278.2	196.4	-211.3	49.6	-59.5	201.4	-288.1	-206.3	278.15	-293.67	0.86	OK
Story30	D1	A13.5	462	-8.99	0.00	47.70	21.10	5.87	60.67	-81.4	17.3	342.3	250.2	-264.8	68.1	-93.8	239.1	-368.0	-275.9	349.1	257.0	-258.0	74.9	-86.9	245.9	-361.2	-269.1	349.13	-368.01	0.80	OK
Story29	D1	A13.5	462	-9.08	0.00	50.80	21.20	6.88	60.95	-83.5	13.9	343.3	251.8	-265.2	69.2	-95.2	239.2	-369.3	-277.7	350.2	258.7	-258.3	76.1	-88.3	246.1	-362.4	-270.8	350.21	-369.28	0.80	OK
Story28	D1	A13.5	462	-9.29	0.00	55.11	21.17	8.26	60.88	-86.3	8.5	348.7	254.0	-270.6	68.3	-94.8	244.0	-375.2	-280.6	355.7	261.1	-263.5	75.3	-87.8	251.1	-368.2	-273.6	355.71	-375.23	0.81	OK
Story27	D1	A13.5	462	-9.40	0.00	59.17	20.67	9.35	59.45	-88.3	2.0	350.4	251.7	-274.5	64.2	-91.1	247.6	-377.3	-278.6	357.6	258.8	-267.3	71.3	-84.0	254.7	-370.2	-271.4	357.56	-377.30	0.82	OK
Story26	D1	A13.5	462	-9.65	0.00	61.86	20.49	10.90	58.96	-89.2	-2.7	349.1	251.1	-273.8	64.2	-91.8	246.2	-376.7	-278.7	356.4	258.4	-266.5	71.5	-84.5	253.6	-369.4	-271.3	356.41	-376.69	0.82	OK
Story25	D1	A15.5	530	-10.51	0.00	68.28	23.25	13.02	66.90	-98.6	-1.5	380.8	280.6	-294.2	78.1	-108.2	264.2	-410.9	-310.7	388.8	288.6	-286.3	86.1	-100.2	272.2	-402.9	-302.7	388.80	-410.88	0.78	OK
Story24	D1	A15.5	530	-10.49	0.00	71.02	22.97	13.93	66.09	-99.7	-5.7	379.2	278.4	-293.7	76.6	-106.6	263.7	-409.2	-308.4	387.1	286.4	-285.7	84.5	-98.6	271.6	-401.2	-300.5	387.14	-409.17	0.77	OK
Story23	D1	A15.5	530	-10.07	0.00	74.79	22.48	13.49	64.71	-102.3	-10.0	379.3	274.4	-295.6	71.9	-100.7	266.8	-408.1	-303.2	386.9	282.0	-287.9	79.5	-93.1	274.4	-400.4	-295.5	386.94	-408.08	0.77	OK
Story22	D1	A15.5	530	-9.70	0.00	78.81	22.13	13.17	63.69	-105.3	-14.3	380.8	271.8	-298.2	68.1	-95.8	270.5	-408.5	-299.6	388.2	279.2	-290.9	75.5	-88.5	277.9	-401.2	-292.2	388.18	-408.54	0.77	OK
Story21	D1	A15.5	530	-9.10	0.00	82.48	21.82	11.97	62.81	-108.6	-17.0	383.0	269.4	-301.1	64.1	-90.1	275.1	-409.0	-295.4	389.9	276.3	-294.2	71.0	-83.2	282.0	-402.1	-288.5	389.88	-408.99	0.77	OK
Story20	D1	A15.5	530	-8.60	0.00	86.20	21.34	10.86	61.44	-111.7	-20.6	384.0	265.6	-303.7	59.3	-83.9	279.1	-408.5	-290.1	390.5	272.1	-297.2	65.8	-77.3	285.6	-402.0	-283.6	390.47	-408.52	0.77	OK
Story19	D1	A15.5	530	-8.09	0.00	89.97	20.43	9.65	58.85	-114.2	-25.6	382.5	258.3	-305.7	51.8	-74.9	282.6	-405.7	-281.4	388.7	264.4	-299.6	58.0	-68.8	288.7	-399.5	-275.3	388.68	-405.64	0.77	OK
Story18	D1	A15.5	530	-7.58	0.00	93.80	19.81	8.31	57.06	-117.4	-29.6	383.7	253.8	-308.9	46.0	-67.7	287.3	-405.4	-275.5	389.5	259.6	-303.2	51.8	-61.9	293.0	-399.6	-269.7	389.47	-405.39	0.76	OK
Story17	D1	A15.5	530	-7.12	0.00	97.46	19.25	7.09	55.47	-120.4	-33.3	385.3	250.2	-312.2	40.9	-61.2	291.9	-405.7	-270.5	390.7	255.6	-306.8	46.3	-55.8	297.3	-400.3	-265.1	390.70	-405.66	0.77	OK
Story16	D1	A15.5	530	-6.72	0.00	101.25	18.65	5.85	53.75	-123.6	-37.3	386.8	246.3	-315.7	35.5	-54.7	296.5	-406.0	-265.5	391.9	251.3	-310.6	40.6	-49.6	301.6	-400.9	-260.4	391.88	-406.00	0.77	OK
Story15	D1	A15.5	530	-6.62	0.00	105.01	18.03	5.76	51.95	-125.9	-42.7	388.6	242.5	-320.1	29.9	-48.8	301.2	-407.6	-261.5	393.6	247.6	-315.1	34.9	-43.8	306.2	-402.5	-256.4	393.64	-407.55	0.77	OK
Story14	D1	A15.5	530	-6.59	0.00	108.88	17.35	5.77	50.03	-128.3	-48.5	390.6	238.5	-325.1	23.8	-42.7	306.2	-409.4	-257.4	395.6	243.5	-320.1	28.8	-37.7	311.2	-404.4	-252.4	395.60	-409.44	0.77	OK
Story13	D1	A15.5	530	-6.54	0.00	112.79	16.53	5.68	47.66	-130.4	-54.8	391.8	233.2	-329.9	16.6	-35.3	311.3	-410.5	-251.9	396.8	238.1	-325.0	21.6	-30.4	316.2	-405.5	-246.9	396.76	-410.49	0.77	OK
Story12	D1	A15.5	530	-6.47	0.00	116.75	15.28	5.49	44.08	-132.0	-62.5	390.4	224.1	-334.1	6.7	-25.2	315.6	-408.9	-242.5	395.3	229.0	-329.2	11.6	-20.3	320.5	-404.0	-237.6	395.31	-408.89	0.77	OK
Story11	D1	A15.5	530	-6.36	0.00	120.48	12.87	5.29	37.15	-131.4	-74.0	380.6	204.1	-335.2	-10.6	-7.6	317.0	-398.7	-222.3	385.4	209.0	-330.4	-5.8	-2.8	321.9	-393.9	-217.5	385.38	-398.74	0.75	OK
Story10	D1	A15.5	530	-6.31	0.00	124.41	8.02	5.16	23.16	-128.7	-94.3	353.5	161.7	-330.7	-43.6	25.5	312.7	-371.6	-179.7	358.3	166.5	-325.9	-38.8	30.3	317.5	-366.8	-175.0	358.31	-371.56	0.70	OK
Story9	D1	A15.5	530	-5.83	0.00	127.81	6.82	3.64	19.69	-128.7	-99.8	353.1	152.8	-335.0	-53.6	36.9	318.4	-369.8	-169.5	357.5	157.3	-330.6	-49.2	41.4	322.8	-365.4	-165.1	357.55	-369.78	0.70	OK
Story8	D1	A15.5	530	-5.35	0.00	131.29	6.42	2.22	18.56	-132.0	-102.6	359.6	152.0	-342.3	-58.6	43.3	327.0	-374.9	-167.3	363.6	156.0	-338.2	-54.5	47.4	331.0	-370.8	-163.2	363.63	-374.86	0.71	OK
Story7	D1	A15.5	530	-5.26	0.00	134.96	6.00	2.27	17.36	-134.5	-107.3	366.5	151.1	-350.9	-64.1	49.1	335.9	-381.5	-166.1	370.4	155.1	-346.9	-60.1	53.1	339.8	-377.5	-162.1	370.44	-381.49	0.72	OK
Story6	D1	A15.5	530	-5.19	0.00	138.39	5.66	2.40	16.38	-136.8	-111.6	374.0	150.9	-359.8	-69.2	54.4	345.0	-388.8	-166.8	377.9	154.9	-355.9	-65.3	58.3	348.9	-384.8	-161.8	377.89	-388.78	0.73	OK
Story5	D1	A15.5	530	-4.67	0.00	140.41	5.37	1.34	15.54	-138.6	-113.1	380.2	150.8	-366.2	-73.1	59.8	352.9	-393.6	-164.2	383.8	154.4	-362.7	-69.6	63.3	356.4	-390.0	-160.6	383.76	-393.57	0.74	OK
Story4	D1	A15.5	530	-4.15	0.00	140.67	5.06	0.30	14.65	-138.8	-113.0	382.1	149.4	-368.3	-75.7	63.9	356.5	-394.0	-161.3	385.3	152.6	-365.2	-72.6	67.0	359.6	-390.8	-158.1	385.28	-393.98	0.74	OK
Story3	D1	A15.5	530	-3.62	0.00	136.87	4.75	-0.62	13.77	-135.2	-109.3	373.9	145.1	-360.2	-75.1	64.7	349.8	-384.3	-155.5	376.7	147.9	-357.4	-72.4	67.5	352.6	-381.5	-152.7	376.68	-384.30	0.72	OK
Story2	D1	A15.5	530	-3.13	0.00	125.09	4.38	-1.52	12.70	-124.4	-98.8	344.9	134.2	-331.5	-68.7	59.7	322.6	-353.9	-143.2	347.3	136.6	-329.1	-66.3	62.1	324.9	-351.5	-140.8	347.28	-353.86	0.67	OK
Story1	D1	A15.5	530	-2.72	0.00	83.92	3.26	-1.07	9.46	-84.6	-65.6	236.8	93.5	-227.9	-45.9	38.1	220.1	-244.6	-101.3	238.8	95.6	-225.9	-43.8	40.2	222.2	-242.5	-99.3	238.85	-244.56	0.46	OK
Ground	D1	A14	479	-3.05	0.00	-8.19	0.51	-1.04	1.46	2.8	7.3	23.2	8.7	-28.8	-6.9	-1.8	20.0	-31.9	-17.4	25.5	11.0	-26.4	-4.6	0.5	22.4	-29.6	-15.1	25.49	-31.90	0.07	OK
B1	D1	A14	479	-3.15	0.00	-6.43	0.33	-0.35	0.94	2.1	4.4	17.3	5.0	-24.3	-7.4	-1.6	15.3	-26.3	-14.0	19.7	7.4	-21.9	-5.1	0.8	17.7	-23.9	-11.7	19.68	-26.30	0.05	OK
B2	D1	A14	479	-3.33	0.00	-2.17	0.15	0.44	0.44	-0.9	-0.9	7.9	0.7	-16.4	-6.7	-2.9	6.9	-17.5	-10.2	10.5	3.2	-13.9	-4.1	-0.3	9.4	-14.9	-7.7	10.47	-17.47	0.04	OK
B3	D1	A14	479	-3.50	0.00	2.71	-0.01	1.24	-0.04	-4.5	-6.8	6.8	-0.5	-16.1	-7.4	-2.6	6.1	-16.8	-9.5	9.4	2.1	-13.5	-4.8	0.1	8.8	-14.1	-6.8	9.41	-16.75	0.03	OK

SIMPSON GUMPERTZ & HEGER
Engineering of Structures and Building Enclosures

CLIENT Pacific Earthquake Engineering Research Center
SUBJECT BRB Strength Check along Line D for LA BRBF Bldg

SHEET NO. ___
PROJECT NO. 087237.10
DATE 1/23/09
BY AD
CHECKED BY ___

Story	ETABS #	Section	Capacity	Dead	Live	WindFX	WindMTX	WindFY	WindMTY	SpecX	SpecY
Story40	D2	A7	239	-0.20	0.00	-4.11	-9.15	-0.01	-26.30	404.04	251.77
Story39	D2	A7	239	-0.27	0.00	-8.38	-9.49	0.02	-27.27	435.18	261.89
Story38	D2	A7	239	-0.33	0.00	-12.63	-9.79	0.05	-28.13	539.20	270.69
Story37	D2	A8	274	-0.04	0.00	-16.08	-11.52	0.02	-33.09	586.27	317.70
Story36	D2	A8	274	-0.11	0.00	-20.02	-11.93	-0.12	-34.27	633.00	328.13
Story35	D2	A8	274	-0.16	0.00	-23.55	-12.12	-0.42	-34.82	658.47	330.17
Story34	D2	A10	342	0.53	0.00	-27.33	-15.30	-1.01	-43.97	731.14	413.93
Story33	D2	A10	342	0.59	0.00	-30.57	-15.58	-1.49	-44.79	756.52	419.08
Story32	D2	A10	342	0.60	0.00	-34.42	-15.80	-1.98	-45.41	771.67	424.23
Story31	D2	A10	342	0.73	0.00	-37.24	-15.75	-2.59	-45.26	778.20	422.68
Story30	D2	A13.5	462	2.15	0.00	-47.30	-21.11	-4.46	-60.69	965.79	567.69
Story29	D2	A13.5	462	2.32	0.00	-50.40	-21.21	-5.41	-60.98	968.38	572.21
Story28	D2	A13.5	462	2.48	0.00	-54.64	-21.19	-6.51	-60.94	985.20	574.25
Story27	D2	A13.5	462	2.73	0.00	-58.75	-20.69	-7.76	-59.52	995.12	564.98
Story26	D2	A13.5	462	2.93	0.00	-61.38	-20.53	-9.10	-59.05	991.70	564.42
Story25	D2	A15.5	530	3.75	0.00	-67.81	-23.30	-11.09	-67.04	1075.70	641.45
Story24	D2	A15.5	530	3.68	0.00	-70.49	-23.02	-11.77	-66.25	1071.89	634.76
Story23	D2	A15.5	530	3.28	0.00	-74.29	-22.55	-11.22	-64.89	1075.78	618.74
Story22	D2	A15.5	530	2.85	0.00	-78.25	-22.20	-10.68	-63.90	1082.29	606.41
Story21	D2	A15.5	530	2.37	0.00	-81.96	-21.89	-9.61	-63.01	1090.94	594.03
Story20	D2	A15.5	530	1.82	0.00	-85.63	-21.41	-8.30	-61.65	1096.38	577.66
Story19	D2	A15.5	530	1.26	0.00	-89.34	-20.51	-6.87	-59.08	1097.14	551.42
Story18	D2	A15.5	530	0.71	0.00	-93.11	-19.90	-5.31	-57.31	1104.10	533.28
Story17	D2	A15.5	530	0.34	0.00	-96.78	-19.34	-4.18	-55.72	1112.20	518.14
Story16	D2	A15.5	530	-0.11	0.00	-100.52	-18.74	-2.74	-54.01	1119.99	502.62
Story15	D2	A15.5	530	-0.08	0.00	-104.31	-18.11	-2.86	-52.21	1130.33	486.37
Story14	D2	A15.5	530	-0.16	0.00	-108.12	-17.45	-2.69	-50.30	1141.24	469.12
Story13	D2	A15.5	530	-0.26	0.00	-111.97	-16.63	-2.42	-47.95	1150.80	447.77
Story12	D2	A15.5	530	-0.38	0.00	-115.87	-15.39	-2.05	-44.39	1155.12	415.50
Story11	D2	A15.5	530	-0.39	0.00	-119.62	-12.98	-1.96	-37.44	1141.33	352.66
Story10	D2	A15.5	530	-0.49	0.00	-123.49	-8.12	-1.73	-23.46	1090.67	226.24
Story9	D2	A15.5	530	-0.95	0.00	-126.97	-6.91	-0.32	-19.97	1097.52	194.35
Story8	D2	A15.5	530	-1.48	0.00	-130.39	-6.52	1.07	-18.83	1119.18	184.46
Story7	D2	A15.5	530	-1.54	0.00	-133.95	-6.09	0.87	-17.60	1143.18	172.54
Story6	D2	A15.5	530	-1.65	0.00	-137.32	-5.75	0.74	-16.62	1169.20	162.77
Story5	D2	A15.5	530	-2.15	0.00	-139.44	-5.45	1.72	-15.78	1190.26	155.35
Story4	D2	A15.5	530	-2.72	0.00	-139.64	-5.14	2.78	-14.89	1196.42	148.08
Story3	D2	A15.5	530	-3.15	0.00	-135.86	-4.83	3.54	-14.00	1170.43	140.68
Story2	D2	A15.5	530	-3.69	0.00	-124.02	-4.46	4.48	-12.92	1077.83	132.32
Story1	D2	A15.5	530	-3.57	0.00	-82.47	-3.35	4.48	-9.71	737.40	101.98
Ground	D2	A14	479	-4.05	0.00	9.44	-0.58	3.81	-1.66	92.12	25.61
B1	D2	A14	479	-3.78	0.00	7.65	-0.39	2.86	-1.12	74.65	18.10
B2	D2	A14	479	-3.63	0.00	3.39	-0.21	2.05	-0.62	44.93	11.27
B3	D2	A14	479	-3.50	0.00	-1.49	-0.05	1.24	-0.14	34.45	4.78

Story	ETABS #	Section	Capacity	Dead	Live	WindFX	WindMTX	WindFY	WindMTY	SpecX	SpecY
Story40	D3	A7	239	-3.09	0.00	6.79	10.17	0.00	29.22	450.35	271.59
Story39	D3	A7	239	-3.13	0.00	11.11	10.47	0.02	30.08	488.64	280.71
Story38	D3	A7	239	-3.17	0.00	15.41	10.69	0.06	30.71	586.69	286.68
Story37	D3	A10	342	-3.30	0.00	24.09	15.53	0.12	44.62	795.14	415.46
Story36	D3	A10	342	-3.34	0.00	29.16	15.95	0.19	45.85	848.55	427.41
Story35	D3	A10	342	-3.38	0.00	33.81	16.18	0.28	46.49	877.65	431.89
Story34	D3	A13.5	462	-3.49	0.00	43.20	22.04	0.41	63.36	1056.41	586.98
Story33	D3	A13.5	462	-3.44	0.00	48.24	22.57	0.46	64.88	1093.33	599.00
Story32	D3	A13.5	462	-3.47	0.00	54.47	23.14	0.59	66.51	1126.34	613.63
Story31	D3	A13.5	462	-3.39	0.00	59.24	23.37	0.53	67.19	1149.34	617.75
Story30	D3	A13.5	462	-3.42	0.00	57.57	23.67	0.66	68.05	1085.40	624.61
Story29	D3	A13.5	462	-3.37	0.00	61.60	24.07	0.68	69.21	1101.55	633.54
Story28	D3	A13.5	462	-3.40	0.00	66.64	24.29	0.80	69.86	1127.73	638.57
Story27	D3	A13.5	462	-3.32	0.00	71.16	23.95	0.73	68.89	1142.13	627.87
Story26	D3	A13.5	462	-3.35	0.00	74.10	23.91	0.82	68.79	1141.76	626.17
Story25	D3	A15.5	530	-3.40	0.00	83.01	27.27	0.93	78.47	1252.97	712.72
Story24	D3	A15.5	530	-3.42	0.00	86.23	27.05	1.03	77.85	1252.77	706.29
Story23	D3	A15.5	530	-3.44	0.00	90.97	26.56	1.13	76.45	1262.66	693.27
Story22	D3	A15.5	530	-3.47	0.00	95.85	26.17	1.24	75.34	1274.30	682.82
Story21	D3	A15.5	530	-3.42	0.00	100.55	25.78	1.21	74.22	1287.88	671.82
Story20	D3	A15.5	530	-3.44	0.00	105.24	25.19	1.32	72.54	1297.89	656.59
Story19	D3	A15.5	530	-3.47	0.00	109.95	24.15	1.43	69.55	1302.42	630.08
Story18	D3	A15.5	530	-3.49	0.00	114.69	23.36	1.54	67.29	1312.37	609.97
Story17	D3	A15.5	530	-3.44	0.00	119.06	22.64	1.48	65.22	1321.79	590.97
Story16	D3	A15.5	530	-3.46	0.00	123.51	21.85	1.59	62.95	1330.55	570.74
Story15	D3	A15.5	530	-3.38	0.00	127.28	21.08	1.41	60.76	1337.80	550.31
Story14	D3	A15.5	530	-3.40	0.00	131.03	20.25	1.51	58.37	1345.21	529.28
Story13	D3	A15.5	530	-3.43	0.00	134.71	19.24	1.60	55.47	1350.36	503.77
Story12	D3	A15.5	530	-3.45	0.00	138.33	17.78	1.70	51.30	1349.21	466.90
Story11	D3	A15.5	530	-3.40	0.00	141.58	15.17	1.63	43.77	1328.90	399.42
Story10	D3	A15.5	530	-3.43	0.00	144.84	10.10	1.68	29.17	1270.98	268.49
Story9	D3	A15.5	530	-3.45	0.00	148.13	8.65	1.68	24.97	1272.08	230.90
Story8	D3	A15.5	530	-3.47	0.00	151.30	8.02	1.66	23.15	1287.36	214.66
Story7	D3	A15.5	530	-3.42	0.00	153.73	7.43	1.53	21.48	1301.13	199.43
Story6	D3	A15.5	530	-3.45	0.00	155.74	6.94	1.52	20.06	1315.22	186.82
Story5	D3	A15.5	530	-3.47	0.00	156.91	6.46	1.53	18.68	1325.44	174.57
Story4	D3	A15.5	530	-3.49	0.00	156.02	5.96	1.54	17.25	1319.55	161.85
Story3	D3	A15.5	530	-3.44	0.00	150.87	5.48	1.45	15.88	1280.17	149.37
Story2	D3	A15.5	530	-3.47	0.00	137.49	4.93	1.48	14.30	1172.67	135.28
Story1	D3	A15.5	530	-3.16	0.00	92.81	3.64	1.64	10.56	807.01	101.49
Ground	D3	A14	479	-3.58	0.00	-2.23	0.73	1.34	2.12	66.13	22.95
B1	D3	A14	479	-3.46	0.00	-2.68	0.48	1.18	1.40	55.07	16.03
B2	D3	A14	479	-3.48	0.00	-0.61	0.25	1.17	0.72	38.35	9.80
B3	D3	A14	479	-3.50	0.00	2.10	0.02	1.16	0.05	35.29	3.79

Story											
Story40	-6.8	6.3	-0.3	-0.2	-5.2	-5.2	4.7	4.7	-16.2	5.8	-6.3
Story39	-13.7	13.1	-0.3	-0.3	-10.4	-10.4	9.8	9.7	-21.8	1.0	-1.7
Story38	-20.6	19.8	-0.3	-0.5	-15.5	-15.6	14.8	14.7	-27.3	-3.8	3.0
Story37	-25.8	25.7	0.0	-0.1	-19.3	-19.4	19.3	19.2	-33.2	-5.5	5.4
Story36	-32.2	31.9	-0.3	0.1	-24.3	-24.0	23.8	24.0	-38.5	-9.8	9.6
Story35	-37.9	37.5	-0.9	0.5	-28.9	-28.0	27.6	28.6	-43.0	-13.9	13.5
Story34	-43.1	44.4	-1.0	2.3	-33.4	-30.9	32.2	34.6	-50.5	-13.8	15.1
Story33	-48.2	49.6	-1.7	3.1	-37.8	-34.2	35.6	39.2	-54.7	-17.3	18.7
Story32	-54.4	55.8	-2.5	3.9	-43.0	-38.2	39.6	44.4	-59.5	-21.6	23.1
Story31	-58.7	60.5	-3.3	5.0	-46.9	-40.7	42.5	48.7	-62.7	-24.9	26.7
Story30	-73.1	78.3	-4.5	9.7	-59.5	-48.8	54.0	64.7	-79.5	-28.8	34.0
Story29	-77.9	83.4	-5.9	11.4	-64.2	-51.2	56.8	69.8	-83.1	-32.2	37.8
Story28	-84.5	90.4	-7.4	13.4	-70.4	-54.8	60.7	76.4	-88.0	-37.2	43.1
Story27	-90.7	97.3	-9.1	15.7	-76.5	-57.9	64.5	83.1	-92.1	-42.4	48.9
Story26	-94.7	101.7	-11.0	18.1	-81.1	-59.2	66.3	88.1	-94.8	-45.5	52.5
Story25	-104.0	113.0	-13.2	22.3	-90.2	-63.6	72.6	99.2	-104.8	-48.9	57.9
Story24	-108.4	117.2	-14.4	23.3	-94.3	-66.0	74.9	103.1	-107.8	-52.5	61.4
Story23	-114.9	122.8	-14.0	21.9	-98.7	-71.7	79.6	106.5	-112.3	-58.2	66.0
Story22	-121.8	128.6	-13.7	20.5	-103.3	-77.7	84.5	110.1	-117.1	-63.8	70.7
Story21	-128.3	134.0	-12.5	18.2	-107.0	-84.0	89.7	112.7	-121.8	-69.2	74.9
Story20	-134.8	139.2	-11.1	15.5	-110.5	-90.6	95.0	114.9	-126.3	-74.9	79.2
Story19	-141.4	144.5	-9.5	12.5	-113.9	-97.4	100.5	117.0	-130.3	-81.1	84.1
Story18	-148.1	149.8	-7.7	9.3	-117.3	-104.5	106.2	118.9	-134.8	-87.0	88.7
Story17	-154.4	155.3	-6.3	7.1	-120.7	-110.7	111.5	121.6	-138.9	-92.5	93.3
Story16	-161.0	160.7	-4.5	4.3	-124.0	-117.5	117.2	123.8	-143.2	-98.3	98.0
Story15	-167.0	166.8	-4.7	4.5	-128.7	-121.8	121.6	128.5	-147.0	-103.5	103.3
Story14	-173.2	172.8	-4.5	4.1	-133.2	-126.7	126.3	132.8	-150.9	-109.0	108.6
Story13	-179.5	178.8	-4.2	3.6	-137.6	-131.8	131.1	137.0	-154.6	-114.7	114.1
Story12	-185.8	184.9	-3.7	2.8	-142.0	-137.0	136.1	141.0	-158.0	-121.0	120.1
Story11	-191.9	190.9	-3.6	2.7	-146.4	-141.7	140.7	145.4	-159.6	-128.4	127.5
Story10	-198.2	197.0	-3.4	2.2	-150.9	-146.7	145.5	149.7	-158.5	-139.0	137.9
Story9	-204.3	202.0	-1.7	-0.6	-153.9	-153.1	150.8	151.6	-161.8	-145.2	142.9
Story8	-210.4	206.9	-0.1	-3.5	-157.0	-159.5	156.0	153.4	-166.1	-150.4	146.9
Story7	-216.2	212.5	-0.4	-3.2	-161.5	-163.6	159.9	157.0	-169.9	-155.3	151.6
Story6	-221.7	217.7	-0.8	-3.2	-165.9	-167.7	163.7	161.9	-173.7	-159.9	155.9
Story5	-225.7	220.5	0.2	-5.3	-167.8	-172.0	166.8	162.7	-176.5	-163.4	158.2
Story4	-226.7	220.2	1.2	-7.7	-167.5	-174.2	167.6	161.0	-177.0	-164.7	158.1
Story3	-221.2	213.6	1.9	-9.4	-162.6	-171.7	163.5	155.0	-172.6	-161.0	153.5
Story2	-202.8	194.0	2.8	-11.6	-147.9	-158.6	149.8	139.0	-158.6	-147.9	139.0
Story1	-136.2	127.7	2.9	-11.4	-97.9	-108.6	100.1	89.3	-107.3	-99.2	90.7
Ground	10.3	-20.0	1.2	-10.9	11.0	1.9	-13.8	-20.2	5.8	7.2	-16.9
B1	7.7	-16.8	0.0	-9.1	8.1	1.2	-10.3	-17.1	4.2	5.1	-14.2
B2	1.1	-9.8	-1.1	-7.6	2.2	-2.7	-6.0	-10.9	-0.5	0.0	-8.7
B3	-6.6	-1.8	-2.2	-6.2	-4.5	-7.5	-0.9	-3.9	-6.0	-5.9	-2.5

Story											
Story40	7.2	-14.6	-3.7	-3.7	4.4	4.4	-11.9	-11.9	16.6	-7.8	0.3
Story39	14.0	-21.5	-3.7	-3.8	8.6	8.6	-17.1	-17.1	22.1	-3.0	4.5
Story38	20.9	-28.5	-3.7	-3.9	14.8	14.6	-22.2	-22.4	27.5	1.9	-9.5
Story37	34.6	-42.5	-3.8	-4.2	25.1	24.8	-32.7	-33.0	43.6	6.3	-14.2
Story36	42.6	-50.7	-3.7	-4.3	31.2	30.7	-38.8	-39.2	50.1	11.8	-19.9
Story35	50.0	-58.2	-3.6	-4.5	36.9	36.2	-44.3	-45.0	55.9	17.1	-25.2
Story34	64.9	-73.3	-3.5	-4.8	48.2	47.2	-55.5	-56.5	74.1	21.2	-29.6
Story33	73.1	-81.3	-3.4	-4.9	54.3	53.2	-61.5	-62.6	80.8	26.7	-34.9
Story32	83.0	-91.3	-3.2	-5.1	61.9	60.5	-68.8	-70.2	88.0	33.4	-41.8
Story31	90.7	-98.9	-3.2	-4.9	67.7	66.4	-74.5	-75.8	95.1	39.0	-47.1
Story30	88.0	-96.2	-3.0	-5.2	65.8	64.2	-72.4	-74.0	93.4	36.6	-44.8
Story29	94.5	-102.6	-3.0	-5.3	70.7	69.1	-77.2	-78.8	98.8	41.0	-49.1
Story28	102.5	-110.7	-2.8	-5.4	76.9	74.9	-83.1	-85.0	105.0	46.7	-54.9
Story27	109.9	-117.9	-2.8	-5.2	82.3	80.5	-88.5	-90.3	110.2	52.7	-60.6
Story26	114.5	-122.6	-2.7	-5.3	85.9	83.9	-91.9	-93.9	113.6	56.2	-64.2
Story25	128.7	-136.9	-2.6	-5.6	96.6	94.4	-102.6	-104.8	128.3	62.8	-71.0
Story24	133.9	-142.1	-2.5	-5.8	100.6	98.1	-106.4	-108.8	131.8	66.9	-75.1
Story23	141.4	-149.7	-2.3	-5.9	106.4	103.7	-111.9	-114.7	136.9	73.2	-81.4
Story22	149.2	-157.5	-2.2	-6.1	112.4	109.4	-117.7	-120.7	142.3	79.5	-87.8
Story21	156.8	-165.0	-2.2	-6.0	118.0	115.1	-123.3	-126.2	147.5	85.6	-93.8
Story20	164.3	-172.5	-2.0	-6.2	123.7	120.6	-128.8	-132.0	152.4	91.9	-100.2
Story19	171.8	-180.1	-1.9	-6.4	129.5	126.1	-134.4	-137.8	156.8	98.8	-107.1
Story18	179.3	-187.7	-1.7	-6.6	135.3	131.6	-140.0	-143.7	161.5	105.4	-113.8
Story17	186.4	-194.6	-1.8	-6.5	140.5	137.0	-145.2	-148.8	165.9	111.6	-119.8
Story16	193.5	-201.8	-1.6	-6.7	146.0	142.1	-150.5	-154.3	170.3	117.8	-126.1
Story15	199.6	-207.7	-1.8	-6.3	150.4	147.0	-155.1	-158.5	174.0	123.4	-131.5
Story14	205.6	-213.7	-1.7	-6.5	155.0	151.3	-159.5	-163.1	177.4	128.8	-137.0
Story13	211.4	-219.6	-1.6	-6.7	159.5	155.6	-163.8	-167.7	180.6	134.5	-142.7
Story12	217.2	-225.5	-1.4	-6.9	163.9	159.8	-168.1	-172.2	183.2	140.5	-148.8
Story11	222.4	-230.6	-1.5	-6.7	167.8	163.8	-172.0	-175.9	184.0	147.6	-155.8
Story10	227.6	-235.9	-1.4	-6.8	171.7	167.7	-175.9	-179.9	181.8	157.6	-165.8
Story9	232.9	-241.2	-1.5	-6.8	175.6	171.6	-179.9	-183.9	184.0	163.2	-171.5
Story8	237.9	-246.2	-1.5	-6.8	179.4	175.4	-183.7	-187.7	187.0	167.8	-176.1
Story7	241.9	-250.1	-1.7	-6.6	182.2	178.5	-186.8	-190.4	189.3	171.5	-179.7
Story6	245.1	-253.3	-1.7	-6.6	184.6	180.9	-189.2	-192.9	191.1	174.4	-182.7
Story5	246.9	-255.2	-1.7	-6.6	186.0	182.3	-190.6	-194.3	191.9	176.4	-184.7
Story4	245.4	-253.8	-1.7	-6.7	184.9	181.2	-189.6	-193.3	190.2	175.9	-184.3
Story3	237.3	-245.5	-1.8	-6.5	178.7	175.2	-183.4	-186.9	183.5	170.3	-178.6
Story2	215.8	-224.1	-1.8	-6.5	162.6	159.1	-167.4	-170.9	166.8	154.9	-163.2
Story1	144.7	-152.3	-1.2	-6.4	109.5	105.6	-113.2	-117.1	111.9	103.2	-110.8
Ground	-7.9	-0.7	-2.1	-6.4	-5.4	-8.6	0.0	-3.2	-6.1	-7.8	-0.7
B1	-8.4	0.1	-2.3	-6.0	-6.0	-8.8	0.5	-2.3	-6.8	-8.0	-0.4
B2	-5.2	-3.2	-2.3	-6.0	-3.5	-6.3	-2.0	-4.8	-4.6	-5.2	-3.1
B3	-0.8	-7.6	-2.3	-6.1	-0.3	-3.1	-5.3	-8.1	-1.7	-1.7	-6.7

Story											
Story40	-24.1	31.4	-38.8	31.4	-38.8	31.4	-35.9	-19.4	-28.5	-12.0	11.5
Story39	-33.0	32.4	-33.1	32.4	-41.0	-23.9	-25.9	-8.8	8.2	-41.0	8.3
Story38	-34.1	33.4	-34.2	33.3	-45.9	-28.3	-23.1	-5.5	4.8	-46.0	4.7
Story37	-39.7	-39.8	-39.6	-54.7	-33.9	-25.7	-5.0	4.9	-54.7	4.9	54.6
Story36	-41.1	41.1	-59.9	-38.4	-23.8	-2.3	1.9	0.1	-59.6	38.1	23.6
Story35	-42.5	42.1	-64.1	-42.2	-21.6	0.2	-1.3	-63.3	-0.6	63.7	41.8
Story34	-53.4	52.2	-50.9	54.6	-78.3	-50.7	-29.1	-1.5	0.9	-76.5	2.8
Story33	-54.8	52.7	-51.2	56.2	-82.6	-54.5	-27.5	0.6	-1.9	-79.9	0.8
Story32	-56.2	52.8	-51.4	57.6	-87.2	-58.7	-25.2	3.3	-5.4	-83.6	-1.8
Story31	-56.5	52.1	-50.3	58.3	-90.0	-61.6	-22.9	5.5	-8.4	-85.3	-3.7
Story30	-75.6	70.1	-64.9	60.0	-117.7	-79.7	-32.5	5.5	-8.4	-109.7	-0.4
Story29	-76.9	69.5	-63.9	82.5	-121.5	-83.3	-30.7	7.5	-11.7	-111.8	-1.9
Story28	-78.0	68.3	-62.3	83.9	-126.1	-87.9	-27.7	10.3	-16.1	-114.4	-4.6
Story27	-79.7	65.4	-58.8	84.0	-128.9	-91.6	-23.1	14.2	-21.7	-114.9	-7.9
Story26	-78.3	63.5	-56.4	85.3	-131.6	-94.7	-21.1	15.9	-25.3	-115.3	-8.9
Story25	-89.2	71.6	-62.6	98.3	-147.9	-106.0	-25.8	16.2	-27.2	-128.0	-7.2
Story24	-89.2	69.8	-60.9	98.0	-150.1	-108.6	-23.1	18.4	-30.7	-128.9	-9.5
Story23	-87.4	68.3	-60.5	96.3	-151.9	-111.2	-18.0	22.6	-34.9	-131.6	-14.7
Story22	-86.1	67.3	-60.4	92.9	-154.2	-114.2	-13.3	26.7	-39.1	-135.0	-19.9
Story21	-84.3	66.9	-61.2	90.0	-156.1	-116.7	-8.5	31.0	-42.6	-138.8	-25.3
Story20	-81.8	66.2	-61.8	86.1	-157.3	-118.7	-3.0	35.6	-46.2	-142.3	-31.2
Story19	-78.6	64.2	-61.1	80.7	-158.6	-119.9	4.1	41.1	-50.4	-144.5	-38.0
Story18	-74.3	63.2	-61.5	76.0	-157.4	-121.5	10.4	46.2	-54.1	-147.8	-44.5
Story17	-71.1	62.2	-61.4	72.3	-158.1	-123.3	16.2	51.1	-57.8	-150.6	-50.2
Story16	-68.1	61.4	-61.7	68.0	-158.7	-124.9	22.4	56.2	-61.4	-153.7	-56.4
Story15	-59.3	66.0	-160.0	-127.4	27.9	60.6	-65.9	-154.8	-60.8	159.8	127.2
Story14	-53.7	63.4	-161.0	-129.6	33.7	65.2	-70.4	-156.2	-65.6	-160.7	129.2
Story13	-48.9	60.8	-161.1	-131.6	40.2	70.2	-75.1	-157.2	-70.8	160.9	130.9
Story12	-51.3	55.3	-160.5	-132.8	48.2	76.0	-80.6	-156.8	-76.9	159.6	131.9
Story11	-43.0	46.8	-155.4	-132.0	60.1	83.5	-87.9	-151.9	-84.4	154.5	131.1
Story10	-26.7	29.6	-141.8	-127.2	80.7	95.3	-99.6	-138.7	-96.5	140.7	126.0
Story9	-24.7	23.2	-140.0	-127.6	88.7	101.2	-104.0	-139.4	-103.5	137.7	125.3
Story8	-22.1	-25.7	19.5	-141.1	-129.4	93.8	105.6	-107.2	-143.0	-109.1	133.6
Story7	-21.9	20.0	-24.0	18.2	-143.1	-132.1	98.3	109.2	-111.3	-144.6	-112.9
Story6	-21.0	18.8	-22.8	17.1	-145.2	-134.8	102.2	112.6	-115.2	-146.5	-116.6
Story5	-19.5	18.4	-23.6	14.3	-145.8	-135.9	105.4	115.3	-117.3	-148.9	-120.4
Story4	-19.5	17.3	-24.8	11.4	-146.3	-137.0	108.2	117.8	-149.6	-122.8	-138.1
Story3	-16.5	16.3	-24.8	8.8	-139.9	-131.2	104.8	113.5	-114.7	-146.3	-121.1
Story2	-25.3	5.7	-127.8	-119.7	95.7	103.7	-104.5	-135.8	-112.6	118.9	110.9
Story1	-21.3	2.0	-86.3	-80.3	62.3	68.3	-68.8	-94.4	-76.9	77.7	71.7
Ground	-11.4	-5.4	5.1	6.1	-11.9	-10.9	8.1	-1.8	1.2	-14.8	-15.8
B1	-14.2	-13.2	-2.4	0.2	-9.3	-6.6	3.6	4.3	-10.2	-

SIMPSON GUMPERTZ & HEGER
Engineering of Structures and Building Envelopes

CLIENT: Pacific Earthquake Engineering Research Center
SUBJECT: BRB Strength Check along Line D for LA BRBF Bldg

SHEET NO. ____
PROJECT NO. 087237.10
DATE 1/23/09
BY AD
CHECKED BY ____

Story	ETABS #	Section	Capacity	Dead	Live	WindFX	WindMTX	WindFY	WindMTY
Story40	D2	A7	239	-0.20	0.00	-4.11	-9.15	-0.01	-26.30
Story39	D2	A7	239	-0.27	0.00	-8.38	-9.49	0.02	-27.27
Story38	D2	A7	239	-0.33	0.00	-12.63	-9.79	0.05	-28.13
Story37	D2	A8	274	-0.04	0.00	-16.08	-11.52	0.02	-33.09
Story36	D2	A8	274	-0.11	0.00	-20.02	-11.93	-0.12	-34.27
Story35	D2	A8	274	-0.16	0.00	-23.55	-12.12	-0.42	-34.82
Story34	D2	A10	342	0.53	0.00	-27.38	-15.30	-1.01	-43.97
Story33	D2	A10	342	0.59	0.00	-30.57	-15.58	-1.49	-44.79
Story32	D2	A10	342	0.60	0.00	-34.42	-15.80	-1.98	-45.41
Story31	D2	A10	342	0.73	0.00	-37.24	-15.75	-2.59	-45.26
Story30	D2	A13.5	462	2.15	0.00	-47.30	-21.11	-4.46	-60.69
Story29	D2	A13.5	462	2.32	0.00	-50.40	-21.21	-5.41	-60.98
Story28	D2	A13.5	462	2.48	0.00	-54.66	-21.19	-6.51	-60.94
Story27	D2	A13.5	462	2.73	0.00	-58.75	-20.69	-7.76	-59.52
Story26	D2	A13.5	462	2.93	0.00	-61.38	-20.53	-9.10	-59.05
Story25	D2	A15.5	530	3.75	0.00	-67.81	-23.30	-11.09	-67.04
Story24	D2	A15.5	530	3.68	0.00	-70.49	-23.02	-11.77	-66.25
Story23	D2	A15.5	530	3.28	0.00	-74.29	-22.55	-11.22	-64.89
Story22	D2	A15.5	530	2.85	0.00	-78.25	-22.20	-10.68	-63.90
Story21	D2	A15.5	530	2.37	0.00	-81.96	-21.89	-9.61	-63.01
Story20	D2	A15.5	530	1.82	0.00	-85.63	-21.41	-8.30	-61.65
Story19	D2	A15.5	530	1.26	0.00	-89.34	-20.51	-6.87	-59.08
Story18	D2	A15.5	530	0.71	0.00	-93.11	-19.90	-5.31	-57.31
Story17	D2	A15.5	530	0.34	0.00	-96.78	-19.34	-4.18	-55.72
Story16	D2	A15.5	530	-0.11	0.00	-100.52	-18.74	-2.74	-54.01
Story15	D2	A15.5	530	-0.08	0.00	-104.31	-18.11	-2.86	-52.21
Story14	D2	A15.5	530	-0.16	0.00	-108.12	-17.45	-2.69	-50.30
Story13	D2	A15.5	530	-0.26	0.00	-111.97	-16.63	-2.42	-47.95
Story12	D2	A15.5	530	-0.38	0.00	-115.87	-15.39	-2.05	-44.39
Story11	D2	A15.5	530	-0.39	0.00	-119.62	-12.98	-1.96	-37.44
Story10	D2	A15.5	530	-0.49	0.00	-123.49	-8.12	-1.73	-23.46
Story9	D2	A15.5	530	-0.95	0.00	-126.97	-6.91	-0.32	-19.97
Story8	D2	A15.5	530	-1.48	0.00	-130.39	-6.52	1.07	-18.83
Story7	D2	A15.5	530	-1.54	0.00	-133.95	-6.09	0.87	-17.60
Story6	D2	A15.5	530	-1.65	0.00	-137.32	-5.75	0.74	-16.62
Story5	D2	A15.5	530	-2.15	0.00	-139.44	-5.45	1.72	-15.78
Story4	D2	A15.5	530	-2.72	0.00	-139.64	-5.14	2.78	-14.89
Story3	D2	A15.5	530	-3.15	0.00	-135.86	-4.83	3.54	-14.00
Story2	D2	A15.5	530	-3.69	0.00	-124.02	-4.46	4.48	-12.92
Story1	D2	A15.5	530	-3.57	0.00	-82.47	-3.35	4.48	-9.71
Ground	D2	A14	479	-3.48	0.00	9.44	-0.58	3.81	-1.66
B1	D2	A14	479	-3.78	0.00	7.65	-0.39	2.86	-1.12
B2	D2	A14	479	-3.63	0.00	3.39	-0.21	2.05	-0.62
B3	D2	A14	479	-3.50	0.00	-1.49	-0.05	1.24	-0.14

Story	WindFX	WindMTX	WindFY	WindMTY																												
Story40	-0.2	-0.2	-5.1	-5.1	4.7	4.8	-16.1	5.9	-6.2	15.7	-31.8	31.4	-31.7	31.4	-35.8	-19.3	-28.4	-11.9	11.6	-35.8	11.6	35.5	19.0	28.1	28.1	-11.9	35.5	-19.3
Story39	-0.2	-0.3	-10.3	-10.3	9.8	9.8	-21.7	1.1	-1.6	21.2	-32.9	32.5	-33.0	32.5	-40.9	-23.8	-25.8	-8.7	8.2	-40.9	8.2	40.4	23.3	25.3	25.3	-8.7	40.4	-23.8
Story38	-0.2	-0.4	-15.4	-15.5	14.9	14.8	-27.2	-3.7	3.1	26.6	-34.0	33.5	-34.1	33.4	-45.8	-28.2	-23.0	-5.4	4.9	-45.9	4.8	45.2	27.6	22.4	22.5	-5.5	45.3	-28.3
Story37	-0.2	-0.1	-19.3	-19.4	19.3	19.2	-33.1	-5.5	5.4	33.1	-39.7	39.7	-39.8	39.6	-54.7	-33.9	-25.7	-5.0	4.9	-54.7	4.9	54.6	33.9	25.6	25.7	-5.0	54.6	-34.0
Story36	-0.2	0.1	-24.3	-24.0	23.8	24.1	-38.4	-9.8	9.6	38.2	-41.4	40.9	-41.1	41.2	-59.9	-38.4	-23.8	-2.3	1.9	-59.6	2.1	59.7	38.2	23.6	23.4	-2.1	59.4	-38.1
Story35	-0.2	0.5	-28.9	-27.9	27.6	28.6	-42.9	-13.9	13.6	42.6	-42.4	41.1	-41.4	42.1	-64.0	-42.2	-21.6	0.2	-1.3	-63.3	-0.5	63.7	41.9	21.3	20.5	1.0	63.0	-41.4
Story34	-0.2	1.2	-33.5	-31.1	32.1	34.5	-50.7	-14.0	14.9	51.6	-53.5	52.0	-51.1	54.5	-78.5	-50.9	-29.2	-1.6	0.8	-76.6	2.6	79.4	51.8	30.2	28.3	0.2	77.6	-49.1
Story33	-0.2	2.1	-37.9	-34.4	35.4	39.0	-54.9	-17.5	18.5	55.9	-55.0	52.5	-51.4	56.1	-82.7	-54.7	-27.7	0.4	-2.0	-80.0	0.6	83.8	55.7	28.7	26.0	3.1	81.1	-52.0
Story32	-0.2	3.7	-43.1	-38.4	39.5	44.2	-59.7	-21.8	22.9	60.8	-56.3	52.6	-51.6	57.4	-87.4	-58.9	-25.4	3.1	-5.6	-83.8	-2.0	88.5	60.0	26.5	22.9	6.7	84.9	-55.4
Story31	-0.2	5.3	-47.1	-40.9	42.2	48.5	-62.9	-25.1	26.5	64.2	-56.8	51.9	-50.5	58.1	-90.2	-61.8	-23.1	5.3	-8.6	-85.5	-4.0	91.5	63.1	24.4	19.7	9.9	86.8	-57.1
Story30	-0.2	9.1	-60.2	-49.5	53.3	64.0	-80.2	-29.5	33.4	64.0	-76.2	69.4	-65.5	80.1	-118.4	-80.3	-33.2	4.9	-9.0	-110.3	-1.0	122.2	84.2	37.0	29.0	12.9	114.2	-72.3
Story29	-0.2	9.4	-61.9	-51.9	56.1	69.1	-83.8	-32.9	37.1	88.0	-77.6	68.8	-64.6	81.8	-122.2	-84.0	-31.4	6.8	-12.4	-112.5	-2.6	126.4	88.2	35.6	25.9	16.5	116.7	-74.3
Story28	-0.2	9.8	-64.6	-54.5	60.0	75.6	-88.8	-37.9	42.4	93.2	-78.7	67.5	-63.1	83.2	-126.8	-88.7	-28.4	9.8	-17.1	-115.1	-5.3	131.3	93.1	32.9	21.1	21.5	119.6	-76.9
Story27	-0.2	10.1	-67.5	-57.1	63.6	82.3	-92.9	-43.2	48.1	97.8	-78.3	64.6	-59.7	83.2	-129.7	-92.4	-23.9	13.4	-22.5	-115.7	-8.5	134.6	97.4	28.8	14.8	27.4	120.6	-78.5
Story26	-0.2	10.3	-69.1	-59.9	67.1	87.2	-95.7	-46.4	51.7	100.9	-79.1	62.6	-57.3	84.4	-132.5	-95.5	-21.9	15.0	-26.1	-116.1	-9.8	137.8	100.8	27.2	10.8	31.4	121.4	-79.2
Story25	-0.2	10.5	-70.5	-63.8	70.5	93.8	-106.0	-50.0	56.8	112.7	-90.4	70.5	-63.8	97.1	-149.1	-107.1	-26.9	15.1	-28.3	-129.1	-8.3	155.8	113.9	33.7	13.7	35.1	135.8	-87.1
Story24	-0.2	10.7	-72.1	-66.7	73.8	102.0	-108.9	-53.6	60.3	115.5	-90.3	68.7	-62.1	96.9	-151.2	-109.7	-24.2	17.3	-31.8	-130.0	-10.6	157.8	116.4	30.8	9.6	38.5	136.6	-88.5
Story23	-0.2	10.9	-73.6	-69.2	76.8	105.6	-113.3	-59.1	65.0	119.1	-88.4	67.4	-61.5	94.3	-152.8	-112.2	-19.0	21.6	-35.9	-132.6	-15.7	158.7	118.1	24.9	4.7	41.8	138.5	-92.0
Story22	-0.2	11.0	-75.1	-70.5	79.5	109.3	-118.0	-64.7	69.8	123.1	-86.9	66.4	-61.3	92.1	-155.1	-115.1	-14.1	25.9	-40.0	-135.9	-20.7	160.2	120.2	19.3	0.0	45.1	141.0	-95.9
Story21	-0.2	11.2	-76.6	-71.9	82.1	112.0	-122.5	-70.0	74.2	126.7	-85.0	66.2	-61.9	89.3	-156.8	-117.4	-9.2	30.3	-43.3	-139.5	-26.0	161.1	121.7	13.4	-3.9	47.6	143.8	-100.1
Story20	-0.2	11.4	-78.1	-73.3	84.7	114.3	-126.8	-75.4	78.7	130.1	-82.3	65.7	-62.4	85.6	-157.8	-119.2	-3.5	35.0	-46.7	-142.8	-31.8	161.1	122.5	6.8	-8.1	50.0	146.1	-104.3
Story19	-0.2	11.6	-79.6	-74.6	87.3	116.6	-130.7	-81.5	83.7	133.0	-78.0	63.8	-61.5	80.3	-157.2	-120.3	3.7	40.7	-50.8	-144.8	-38.4	159.5	122.5	-1.5	-13.8	53.1	147.1	-107.9
Story18	-0.2	11.8	-81.0	-75.8	89.9	118.7	-135.0	-87.2	88.5	136.2	-74.5	63.0	-61.8	75.8	-157.6	-121.7	10.2	46.0	-54.3	-148.0	-44.7	158.8	123.0	-8.9	-18.5	55.6	149.3	-112.2
Story17	-0.2	12.0	-82.4	-77.0	92.6	121.5	-139.0	-92.6	93.2	139.6	-71.6	62.1	-61.5	72.2	-158.2	-123.4	16.1	50.9	-57.9	-150.7	-50.3	158.9	124.0	-15.5	-23.0	58.5	151.3	-115.9
Story16	-0.2	12.2	-83.7	-78.3	95.3	123.8	-143.2	-98.2	98.0	143.0	-68.2	61.4	-61.6	68.0	-158.6	-124.9	22.4	56.2	-61.3	-153.7	-56.4	158.4	124.7	-22.6	-27.6	61.1	153.5	-119.9
Story15	-0.2	12.4	-85.1	-79.1	98.1	126.5	-147.0	-103.5	103.4	146.8	-66.2	59.1	-59.3	66.0	-160.0	-127.3	28.0	60.6	-65.9	-154.8	-60.7	159.8	127.2	-28.1	-33.3	65.8	154.7	-122.2
Story14	-0.2	12.6	-86.4	-80.0	101.0	129.1	-150.8	-109.0	108.7	150.5	-63.7	57.0	-57.3	63.4	-161.0	-129.6	33.8	65.2	-70.4	-156.1	-65.5	160.7	129.3	-34.1	-38.9	70.1	155.9	-124.7
Story13	-0.2	12.8	-87.8	-80.9	104.0	131.7	-154.5	-114.6	114.2	154.1	-60.7	54.4	-54.9	60.2	-161.4	-131.5	40.3	70.2	-75.1	-157.1	-70.7	161.0	131.0	-40.7	-45.1	74.6	156.6	-127.1
Story12	-0.2	13.0	-89.2	-81.7	107.2	134.2	-157.9	-120.9	120.2	157.2	-56.1	50.5	-51.1	55.4	-160.4	-132.7	48.3	76.1	-80.4	-156.7	-76.8	159.7	132.0	-49.0	-52.7	79.8	156.0	-129.0
Story11	-0.2	13.2	-90.7	-72.1	110.4	136.7	-161.3	-127.6	126.8	160.2	-47.6	42.2	-42.9	46.9	-155.3	-131.9	60.2	83.6	-87.8	-151.8	-84.3	154.6	131.2	-60.9	-64.5	87.1	151.1	-128.4
Story10	-0.2	13.4	-92.0	-62.4	113.6	139.3	-164.7	-134.2	133.4	162.8	-38.9	33.9	-36.1	38.0	-141.7	-127.0	80.8	95.4	-99.4	-138.6	-96.3	140.8	126.2	-81.7	-84.8	98.5	137.7	-123.9
Story9	-0.2	13.6	-93.2	-52.5	116.7	141.5	-167.5	-140.9	140.1	165.2	-25.2	22.7	-24.4	23.5	-139.7	-127.3	89.0	101.5	-103.8	-139.2	-103.2	138.0	125.6	-90.7	-91.3	102.0	137.4	-126.7
Story8	-0.2	13.8	-94.3	-43.7	120.0	143.7	-170.2	-147.3	146.8	167.5	-12.5	12.0	-14.0	14.7	-140.7	-128.9	94.3	106.0	-106.7	-142.6	-108.7	138.0	126.3	-96.9	-95.0	104.1	139.9	-130.8
Story7	-0.2	14.0	-95.4	-35.0	123.2	145.9	-172.8	-154.8	152.0	166.7	-2.5	20.8	-23.6	18.7	-142.6	-131.6	98.7	109.7	-110.9	-144.2	-112.5	139.8	128.9	-101.5	-99.9	108.1	141.4	-133.2
Story6	-0.2	14.2	-96.5	-26.0	125.5	148.1	-175.2	-159.4	156.4	170.2	-20.5	19.3	-22.3	17.6	-144.7	-134.3	102.7	113.1	-114.7	-146.0	-116.1	141.7	131.3	-105.7	-104.4	111.8	143.0	-135.6
Story5	-0.2	14.4	-97.6	-16.7	128.7	150.5	-177.6	-163.7	161.3	172.8	-11.9	18.8	-22.9	14.9	-145.1	-135.3	106.1	115.9	-116.7	-148.2	-119.8	141.2	131.4	-110.0	-106.9	112.8	144.3	-138.4
Story4	-0.2	14.6	-98.7	-7.5	131.2	152.7	-179.1	-168.5	165.8	175.3	-17.0	18.8	-23.7	12.1	-143.8	-134.5	107.8	117.1	-117.0	-148.8	-122.0	138.9	129.6	-112.7	-107.7	112.1	143.9	-139.5
Story3	-0.2	14.8	-99.8	1.9	133.4	155.9	-171.7	-160.1	154.4	166.0	-15.4	18.2	-23.9	9.7	-139.0	-130.3	105.8	114.5	-113.8	-145.4	-120.2	133.3	124.6	-111.4	-105.1	108.1	139.7	-136.7
Story2	-0.2	15.1	-100.5	10.5	-146.8	-157.5	150.9	140.1	-157.5	-146.8	140.2	150.9	-13.4	17.6	-24.2	6.8	-126.6	-118.6	96.8	104.8	-103.4	-134.7	-111.4	120.0	112.0	-103.4	-95.3	96.7	128.1	-126.7
Story1	-0.2	15.3	-101.1	90.4	-106.2	-98.2	91.7	99.8	-9.5	13.8	-20.2	3.1	-85.2	-79.2	63.4	69.4	-67.7	-93.3	-75.8	78.8	72.8	-69.8	-61.7	61.3	86.9	-87.3			
Ground	-0.2	7.6	-101.7	7.0	8.4	-15.7	-14.3	-1.1	2.9	-10.2	-6.2	6.3	7.3	-10.7	-9.7	9.3	-0.6	7.4	-13.6	-14.6	3.4	10.3	-16.6	-6.7	0.5				
B1	-0.2	3.9	-102.2	-19.5	-16.0	5.3	6.2	-13.0	-12.1	-1.3	1.4	-8.2	-5.5	4.7	5.4	-9.1	-8.4	6.7	-0.4	1.6	-11.5	-12.2	2.3	7.4	-13.5	-6.4	0.2		
B2	-0.2	1.1	-102.4	-9.8	0.5	1.1	-7.6	-7.1	-1.6	-0.1	-6.5	-5.0	0.9	1.3	-5.2	-4.8	2.0	-2.8	-1.7	-7.4	-7.8	-1.3	2.4	-8.5	-3.7	-2.4			
B3	-0.2	0.8	-102.5	-2.9	-5.0	-4.9	-1.4	-1.3	-1.8	-1.5	-4.8	-4.5	-3.5	-3.5	-0.9	-0.8	-3.3	-5.8	-5.5	-2.8	-2.8	-5.4	-3.2	-3.0	-0.5	-5.7			

Story	ETABS #	Section	Capacity	Dead	Live	WindFX	WindMTX	WindFY	WindMTY																							
Story40	D3	A7	239	-3.09	0.00	6.79	10.17	0.00	29.22	-2.8	-2.8	5.4	5.4	-10.9	-10.9	17.6	-6.8	1.3	-23.1	32.3	-37.8	32.3	-37.8	38.8	20.5	26.6	8.3	-13.8	38.8	-13.8	-44.4	-26.1	-32.1	-32.1	8.3	-44.4	20.5
Story39	D3	A7	239	-3.13	0.00	11.11	10.47	0.02	30.08	-2.8	-2.9	10.5	10.5	-16.1	-16.2	23.1	-2.0	-3.6	-28.7	33.3	-38.9	33.3	-38.9	43.7	24.9	23.7	4.9	-10.5	43.7	-10.5	-49.4	-30.5	-29.4	-29.3	4.8	-49.3	24.8
Story38	D3	A7	239	-3.17	0.00	15.41	10.69	0.06	30.71	-2.8	-3.0	15.7	15.6	-21.3	-21.4	28.5	2.8	-8.5	-34.2	34.1	-39.6	33.9	-39.8	48.4	29.1	20.6	1.4	-6.9	48.3	-7.1	-54.1	-34.8	-26.3	-26.2	1.2	-54.0	29.0
Story37	D3	A10	342	-3.30	0.00	24.09	15.53	0.12	44.62	-2.8	-3.2	26.1	25.8	-31.7	-32.0	44.6	7.3	-13.2	-50.5	50.7	-56.4	50.4	-56.7	73.0	45.0	29.6	1.6	-7.4	72.8	-7.6	-79.0	-51.0	-35.6	-35.3	1.4	-78.7	44.8
Story36	D3	A10	342	-3.34	0.00	29.16	15.95	0.19	45.85	-2.7	-3.3	32.2	31.7	-37.8	-38.2	51.1	12.8	-18.9	-57.1	52.2	-57.8	51.8	-58.3	79.1	50.4	28.6	-2.2	-3.5	78.8	-3.8	-85.1	-56.4	-32.6	-32.2	-2.5	-84.8	50.0
Story35	D3	A10	342	-3.38	0.00	33.81	16.18	0.28	46.49	-2.6	-3.5	37.9	37.2	-43.3	-44.0	56.9	18.1	-24.7	-63.0	53.1	-58.5	52.4	-58.9	84.1	55.0	23.2	-5.9	6.4	83.6	6.1	-90.2	-61.1	-29.3	-28.8	6.4	-89.7	54.5
Story34	D3	A13.5	462	-3.49	0.00	43.20	22.04	0.41	63.36	-2.5	-3.8	49.2	48.2	-54.5	-55.5	75.2	22.2	-28.5	-81.4	73.4	-78.7	72.4	-79.7	113.1	73.4	35.3	-4.5	-1.1	112.3	-1.8	-119.4	-79.6	-41.5	-40.8	-5.2	-118.6	72.6
Story33	D3	A13.5	462	-3.44	0.00	48.24	22.57	0.46	64.88	-2.4	-3.8	55.3	54.2	-60.4	-61.5	81.9	27.7	-33.9	-88.1	75.3	-80.4	74.2	-81.5	119.5	78.9	32.6	-8.0	2.7	118.7	1.8	-125.7	-85.1	-38.8	-38.0	-8.8	-124.9	78.1
Story32	D3	A13.5	462	-3.47	0.00	54.47	23.14	0.59	66.51	-2.2	-4.1	63.0	61.5	-67.8	-69.2	90.0	34.5	-40.7	-96.3	77.4	-82.7	76.0	-84.6	127.2	85.5	29.1	-12.6	7.4	126.2	6.3	-133.5	-91.8	-35.3	-34.3	-13.7	-132.4	84.5
Story31	D3	A13.5	462	-3.39	0.00	59.24	23.37	0.53	67.19	-2.2	-3.9	68.7	67.4	-73.5	-74.8	96.1	40.0	-46.1	-102.2	78.2	-83.0	76.9	-84.3	132.4	90.3	25.6	-16.5	11.3	131.4	10.4	-138.5	-96.4	-31.7	-30.8	-17.4	-137.5	89.3
Story30	D3	A13.5	462	-3.42	0.00	57.57	23.67	0.66	68.05	-2.0	-4.1	66.8	65.2	-71.4	-73.0	94.4	37.6	-43.8	-100.6	79.4	-84.0	77.8	-85.5	132.0	89.4	28.3	-14.4	9.4	130.8	8.2	-138.2	-95.5	-34.4	-33.2	-15.5	-137.0	88.2
Story29	D3	A13.5	462	-3.37	0.00	61.60	24.07	0.68	69.23	-1.9	-4.1	71.7	70.1	-76.1	-77.8	99.8	42.0	-48.1	-105.8	80.8	-85.3	79.2	-86.9	137.1	93.7	26.1	-17.2	12.4	135.9	11.2	-143.2	-99.8	-32.2	-31.0	-18.5	-141.9	92.5
Story28	D3	A13.5	462	-3.40	0.00	66.64	24.29	0.80	69.86	-1.8	-4.3	77.9	75.9	-82.1	-84.0	106.1	47.8	-53.9	-112.2	81.7	-85.9	79.8	-87.9	142.5	98.7	22.5	-21.3	16.6	141.1	15.2	-148.6	-104.9	-28.6	-27.1	-22.8	-147.2	97.3
Story27	D3	A13.5	462	-3.32	0.00	71.16	23.95	0.73	68.89	-1.8	-4.2	83.3	81.5	-87.5	-89.3	111.1	53.7	-59.6	-117.1	80.6	-84.8	78.8	-86.5	145.4	102.3	17.2	-26.0	21.3	144.1	20.0	-151.4	-108.2	-23.2	-21.9	-27.3	-150.1	100.9
Story26	D3	A13.5	462	-3.35	0.00	74.10	23.91	0.82	68.79	-1.7	-4.3	86.9	84.9	-90.9	-92.9	114.6	57.2	-63.2	-120.6	80.5	-84.6	78.6	-86.6	148.0	104.9	14.5	-28.6	24.0	146.5	22.6	-154.0	-110.9	-20.5	-19.0	-30.1	-152.5	103.4
Story25	D3	A15.5	530	-3.40	0.00	83.01	27.27	0.93	78.47	-1.6	-4.5	97.7	95.4	-101.6	-103.8	129.3	63.8	-69.9	-135.4	92.2	-96.1	90.0	-98.3	167.8	118.7	18.3	-30.9	26.4	166.1	24.8	-173.9	-124.8	-24.4	-22.7	-32.6	-172.3	117.0
Story24	D3	A15.5	530	-3.42	0.00	86.23	27.05	1.03	77.85	-1.4	-4.7	101.6	99.2	-105.3	-107.8	132.9	67.9	-74.1	-139.0	91.6	-95.3	89.1	-97.7	170.0	121.3	14.7	-34.1	29.8	168.2	27.9	-176.2	-127.4	-20.8	-19.0	-35.9	-174.3	119.4
Story23	D3	A15.5	530	-3.44	0.00	90.97	26.56	1.13	76.45	-1.3	-4.9	107.4	104.7	-110.9	-113.6	137.9	74.2	-80.4	-144.1	90.0	-93.5	87.3	-96.2	172.7	124.8	8.8	-39.1	34.9	170.6	32.9	-178.9	-131.0	-15.0	-12.9	-41.1	-176.8	122.8
Story22	D3	A15.5	530	-3.47	0.00	95.85	26.17	1.24	75.34	-1.1	-5.1	113.4	110.4	-116.7	-119.6	143.3	80.5	-86.7	-149.6	88.8	-92.0	85.8	-95.0	175.8	128.6	3.1	-44.1	40.1	173.5	37.8	-182.0	-134.9	-9.3	-7.1	-46.3	-179.8	126.4
Story21	D3	A15.5	530	-3.42	0.00	100.55	25.78	1.21	74.22	-1.1	-5.0	119.0	116.1	-122.3	-125.2	148.5	86.7	-92.8	-154.7	87.4	-90.7	84.5	-93.6	178.7	132.2	-2.5	-48.9	45.0	176.5	42.8	-184.8	-138.4	-3.7	-1.5	-51.1	-182.6	130.0
Story20	D3	A15.5	530	-3.44	0.00	105.24	25.19	1.32	72.54	-1.0	-5.2	124.8	121.6	-127.8	-131.0	153.4	93.0	-99.2	-159.6	85.5	-88.6	82.4	-91.7	180.9	135.5	-8.7	-54.1	50.2	178.5	47.9	-187.1	-141.7	2.5	4.9	-56.4	-184.7	133.2
Story19	D3	A15.5	530	-3.47	0.00	109.95	24.15	1.43	69.55	-0.8	-5.4	130.5	127.1	-133.3	-136.8	157.8	99.8	-106.1	-164.0	82.1	-84.9	78.6	-88.3	181.6	138.1	-16.5	-60.0	56.3	179.0	53.7	-187.9	-144.3	10.2	12.8	-62.5	-185.3	135.5
Story18	D3	A15.5	530	-3.49	0.00	114.69	23.36	1.54	67.29	-0.7	-5.6	136.3	132.6	-138.9	-142.6	162.5	106.5	-112.7	-168.8	79.5	-82.0	75.8	-85.7	183.2	141.1	-23.4	-65.5	62.0	180.4	59.2	-189.5	-147.4	17.1	19.9	-68.3	-186.7	138.4
Story17	D3	A15.5	530	-3.44	0.00	119.06	22.64	1.48	65.22	-0.7	-5.5	141.6	138.0	-144.2	-147.7	166.9	112.6	-118.8	-173.1	77.0	-79.6	73.4	-83.1	184.6	143.9	-29.9	-70.6	67.1	182.0	64.5	-190.8	-150.0	23.7

SIMPSON GUMPERTZ & HEGER
Engineering of Structures and Building Enclosures

CLIENT Pacific Earthquake Engineering Research Center
SUBJECT BRB Strength Check along Line D for LA BRBF Bldg

SHEET NO.
PROJECT NO. 087237.10
DATE 1/23/09
BY AD
CHECKED BY

Story	ETABS #	Section	Capacity	Dead	Live	WindFX	WindMTX	WindFY	WindMTY																					Maximum Axial Loads Tension	Compression	DCR	Status
Story40	D2	A7	239	-0.20	0.00	-4.11	-9.15	-0.01	-26.30	19.0	-28.4	148.7	113.1	-104.0	37.2	-37.8	103.4	-149.3	-113.6	148.9	113.2	-103.9	37.4	-37.7	103.6	-149.1	-113.5	148.85	-149.27	0.62	OK
Story39	D2	A7	239	-0.27	0.00	-8.38	-9.49	0.02	-27.27	23.3	-25.8	159.3	118.9	-112.9	37.3	-38.0	112.2	-160.0	-119.7	159.5	119.1	-112.7	37.5	-37.8	112.4	-159.8	-119.5	159.45	-160.01	0.67	OK
Story38	D2	A7	239	-0.33	0.00	-12.63	-9.79	0.05	-28.13	27.7	-23.1	192.5	131.2	-144.8	30.0	-31.0	143.8	-193.4	-132.2	192.7	131.5	-144.5	30.3	-30.7	144.1	-193.2	-131.9	192.73	-193.43	0.81	OK
Story37	D2	A8	274	-0.04	0.00	-16.08	-11.52	0.02	-33.09	33.9	-25.9	211.8	150.1	-154.8	40.1	-40.2	154.7	-212.0	-150.2	211.9	150.2	-154.8	40.2	-40.2	154.8	-211.9	-150.2	211.87	-211.96	0.77	OK
Story36	D2	A8	274	-0.11	0.00	-20.02	-11.93	-0.12	-34.27	38.0	-23.6	227.3	157.5	-168.6	38.8	-39.1	168.3	-227.6	-157.9	227.4	157.6	-168.5	38.9	-39.0	168.4	-227.5	-157.8	227.38	-227.60	0.83	OK
Story35	D2	A8	274	-0.16	0.00	-23.55	-12.12	-0.42	-34.82	41.1	-20.8	235.4	160.5	-176.5	36.9	-37.4	176.0	-235.8	-160.9	235.5	160.6	-176.4	37.0	-37.3	176.1	-235.7	-160.8	235.49	-235.83	0.86	OK
Story34	D2	A10	342	0.53	0.00	-27.33	-15.30	-1.01	-43.97	50.0	-27.4	266.6	193.4	-190.7	56.2	-54.7	192.2	-265.1	-191.9	266.2	193.0	-191.1	55.8	-55.1	191.8	-265.5	-192.3	266.60	-265.50	0.78	OK
Story33	D2	A10	342	0.59	0.00	-30.57	-15.58	-1.49	-44.79	53.0	-25.0	275.1	197.4	-198.1	55.4	-53.7	199.8	-273.4	-195.7	274.6	196.9	-198.5	55.0	-54.2	199.3	-273.9	-196.1	275.10	-273.86	0.80	OK
Story32	D2	A10	342	0.60	0.00	-34.42	-15.80	-1.98	-45.41	56.4	-21.8	280.3	200.4	-202.3	55.6	-53.9	204.0	-278.6	-198.6	279.9	199.9	-202.8	55.1	-54.3	203.6	-279.1	-199.1	280.31	-279.05	0.82	OK
Story31	D2	A10	342	0.73	0.00	-37.24	-15.75	-2.59	-45.26	58.5	-18.4	282.4	200.7	-204.3	54.7	-52.6	206.4	-280.3	-198.6	281.8	200.1	-204.9	54.1	-53.1	205.9	-280.9	-199.2	282.40	-280.86	0.83	OK
Story30	D2	A13.5	462	2.15	0.00	-47.30	-21.11	-4.46	-60.69	76.2	-25.1	356.1	263.8	-247.9	82.5	-76.4	254.1	-350.0	-257.6	354.5	262.1	-249.6	80.9	-78.0	252.4	-351.6	-259.2	356.13	-351.61	0.77	OK
Story29	D2	A13.5	462	2.32	0.00	-50.40	-21.21	-5.41	-60.98	78.4	-21.7	357.6	265.6	-248.1	83.9	-77.3	254.7	-351.0	-259.0	355.8	263.8	-249.9	82.1	-79.0	253.0	-352.7	-260.7	357.59	-352.71	0.77	OK
Story28	D2	A13.5	462	2.48	0.00	-54.64	-21.19	-6.51	-60.94	81.4	-16.7	363.3	268.0	-252.9	83.2	-76.1	260.0	-356.2	-260.9	361.4	266.1	-254.8	81.3	-78.0	258.1	-358.1	-262.8	363.26	-358.05	0.79	OK
Story27	D2	A13.5	462	2.73	0.00	-58.75	-20.69	-7.76	-59.52	83.4	-9.9	365.9	266.5	-256.5	79.8	-72.0	264.3	-358.1	-258.7	363.8	264.5	-258.6	77.7	-74.1	262.3	-360.2	-260.8	365.89	-360.15	0.79	OK
Story26	D2	A13.5	462	2.93	0.00	-61.38	-20.53	-9.10	-59.05	84.4	-5.6	365.1	266.3	-255.2	80.3	-71.9	263.6	-356.7	-258.0	362.8	264.1	-257.4	78.0	-74.1	261.4	-358.9	-260.2	365.05	-358.90	0.79	OK
Story25	D2	A15.5	530	3.75	0.00	-67.81	-23.30	-11.09	-67.04	93.9	-6.9	399.4	298.5	-273.4	96.6	-85.9	284.1	-388.7	-287.7	396.6	295.6	-276.2	93.8	-88.7	281.3	-391.5	-290.6	399.42	-391.54	0.75	OK
Story24	D2	A15.5	530	3.68	0.00	-70.49	-23.02	-11.77	-66.25	95.1	-3.0	397.5	296.0	-272.9	94.9	-84.4	283.4	-387.0	-285.5	394.7	293.2	-275.7	92.1	-87.1	280.6	-389.8	-288.3	397.53	-389.79	0.75	OK
Story23	D2	A15.5	530	3.28	0.00	-74.29	-22.55	-11.22	-64.89	97.9	1.2	396.7	291.0	-276.1	89.1	-79.8	285.5	-387.4	-281.6	394.2	288.5	-278.6	86.6	-82.3	283.0	-389.8	-284.1	396.72	-389.84	0.75	OK
Story22	D2	A15.5	530	2.85	0.00	-78.25	-22.20	-10.68	-63.90	101.0	5.1	397.0	287.3	-279.9	84.2	-76.1	288.0	-388.9	-279.1	394.9	285.1	-282.0	82.1	-78.2	285.9	-391.1	-281.3	397.04	-391.05	0.75	OK
Story21	D2	A15.5	530	2.37	0.00	-81.96	-21.89	-9.61	-63.01	104.3	8.1	397.9	283.7	-284.4	79.0	-72.2	291.2	-391.2	-276.9	396.2	281.9	-286.2	77.2	-74.0	289.4	-393.0	-278.7	397.95	-392.97	0.75	OK
Story20	D2	A15.5	530	1.82	0.00	-85.63	-21.41	-8.30	-61.65	107.5	11.4	397.4	278.5	-288.3	72.8	-67.6	293.5	-392.2	-273.3	396.0	277.1	-289.7	71.4	-69.0	292.2	-393.6	-274.7	397.39	-393.57	0.75	OK
Story19	D2	A15.5	530	1.26	0.00	-89.34	-20.51	-6.87	-59.08	110.2	16.1	394.5	269.9	-291.7	64.1	-60.5	295.4	-390.9	-266.3	393.5	269.0	-292.7	63.1	-61.4	294.4	-391.8	-267.3	394.48	-391.82	0.74	OK
Story18	D2	A15.5	530	0.71	0.00	-93.11	-19.90	-5.31	-57.31	113.4	19.7	394.2	264.4	-296.3	57.2	-55.2	298.4	-392.2	-262.4	393.7	263.8	-296.9	56.7	-55.7	297.8	-392.7	-262.9	394.22	-392.74	0.74	OK
Story17	D2	A15.5	530	0.34	0.00	-96.79	-19.34	-4.18	-55.72	116.5	23.6	394.9	260.1	-300.8	51.4	-50.4	301.7	-393.9	-259.1	394.6	259.8	-301.0	51.1	-50.7	301.5	-394.2	-259.4	394.88	-394.16	0.74	OK
Story16	D2	A15.5	530	-0.11	0.00	-100.52	-18.74	-2.74	-54.01	119.7	27.4	395.3	255.5	-305.2	45.4	-45.7	304.9	-395.6	-255.8	395.4	255.6	-305.1	45.4	-45.6	305.0	-395.5	-255.7	395.36	-395.58	0.75	OK
Story15	D2	A15.5	530	-0.08	0.00	-104.31	-18.11	-2.86	-52.21	122.0	33.1	397.1	251.6	-309.9	39.6	-39.8	309.7	-397.3	-251.9	397.1	251.7	-309.8	39.6	-39.7	309.7	-397.3	-251.8	397.15	-397.32	0.75	OK
Story14	D2	A15.5	530	-0.16	0.00	-108.12	-17.45	-2.69	-50.30	124.4	38.6	398.8	247.4	-315.0	33.3	-33.7	314.5	-399.3	-247.9	399.0	247.5	-314.8	33.4	-33.6	314.6	-399.2	-247.7	398.96	-399.30	0.75	OK
Story13	D2	A15.5	530	-0.26	0.00	-111.97	-16.63	-2.42	-47.95	126.7	44.6	399.8	241.8	-320.0	25.8	-26.6	319.3	-400.5	-242.5	400.0	241.9	-319.8	26.0	-26.4	319.5	-400.3	-242.3	399.96	-400.51	0.76	OK
Story12	D2	A15.5	530	-0.38	0.00	-115.87	-15.39	-2.05	-44.39	128.3	52.0	398.0	232.3	-324.4	15.6	-16.7	323.3	-399.1	-233.4	398.3	232.6	-324.1	15.9	-16.4	323.6	-398.8	-233.1	398.33	-399.13	0.75	OK
Story11	D2	A15.5	530	-0.39	0.00	-119.62	-12.98	-1.96	-37.44	127.7	63.7	388.1	212.2	-325.8	-2.0	0.9	324.7	-389.2	-213.3	388.4	212.5	-325.5	-1.7	1.2	325.0	-388.9	-213.0	388.36	-389.18	0.73	OK
Story10	D2	A15.5	530	-0.49	0.00	-123.49	-8.12	-1.73	-23.49	123.1	83.9	360.7	169.4	-321.4	-35.2	33.8	320.0	-362.1	-170.8	361.1	169.8	-321.1	34.9	34.2	320.4	-361.7	-170.4	361.09	-362.12	0.68	OK
Story9	D2	A15.5	530	-0.95	0.00	-126.97	-6.91	-0.32	-19.97	125.0	89.6	359.3	159.8	-327.1	-46.1	43.4	324.4	-362.1	-162.6	360.1	160.6	-326.4	-45.4	44.1	325.1	-361.3	-161.8	360.05	-362.05	0.68	OK
Story8	D2	A15.5	530	-1.48	0.00	-130.39	-6.52	1.07	-18.83	128.2	92.3	364.5	158.2	-335.5	-51.8	47.6	331.3	-368.7	-162.4	365.6	159.3	-334.4	-50.7	48.7	332.4	-367.6	-161.3	365.59	-368.69	0.70	OK
Story7	D2	A15.5	530	-1.54	0.00	-133.95	-6.09	0.87	-17.60	130.4	97.1	370.8	156.8	-344.2	-57.8	53.4	339.8	-375.2	-161.1	372.0	157.9	-343.0	-56.6	54.5	341.0	-374.0	-160.0	371.98	-375.21	0.71	OK
Story6	D2	A15.5	530	-1.65	0.00	-137.32	-5.75	0.74	-16.62	132.7	101.4	377.9	156.1	-353.4	-63.3	58.6	348.6	-382.6	-160.8	379.2	157.3	-352.1	-62.0	59.8	349.9	-381.4	-159.6	379.16	-382.63	0.72	OK
Story5	D2	A15.5	530	-2.15	0.00	-139.44	-5.45	1.72	-15.78	134.5	103.0	383.1	155.1	-361.3	-68.2	62.0	355.2	-389.3	-161.3	384.7	156.8	-359.7	-66.6	63.7	356.8	-387.6	-159.7	384.75	-389.27	0.73	OK
Story4	D2	A15.5	530	-2.72	0.00	-139.64	-5.14	2.78	-14.89	134.6	102.8	383.6	152.7	-364.7	-71.8	64.0	357.0	-391.4	-160.5	385.6	154.8	-362.7	-69.7	66.1	359.0	-389.3	-158.4	385.64	-391.35	0.74	OK
Story3	D2	A15.5	530	-3.15	0.00	-135.86	-4.83	3.54	-14.00	131.0	99.4	374.2	147.5	-357.9	-72.2	63.2	348.9	-383.2	-156.5	376.6	149.8	-355.5	-69.8	65.5	351.3	-380.8	-154.1	376.58	-383.17	0.72	OK
Story2	D2	A15.5	530	-3.69	0.00	-124.02	-4.46	4.48	-12.92	120.1	88.7	343.7	135.5	-330.4	-66.7	56.2	319.9	-354.2	-146.0	346.5	138.3	-327.6	-64.0	59.0	322.7	-351.4	-143.2	346.49	-354.23	0.67	OK
Story1	D2	A15.5	530	-3.57	0.00	-82.47	-3.35	4.48	-9.71	80.8	55.3	234.7	94.6	-226.5	-43.7	33.5	216.3	-244.9	-104.8	237.4	97.3	-223.8	-41.0	36.2	219.0	-242.2	-102.1	237.38	-244.87	0.46	OK
Ground	D2	A14	479	-4.05	0.00	9.44	-0.58	3.81	-1.66	-7.7	-17.6	25.3	10.5	-32.3	-4.8	-4.8	20.7	-36.9	-22.1	28.4	13.6	-29.2	-3.7	-1.7	22.8	-33.8	-19.0	28.40	-36.89	0.08	OK
B1	D2	A14	479	-3.78	0.00	7.65	-0.39	2.86	-1.12	-7.0	-14.2	19.6	7.0	-27.1	-7.0	-3.8	16.3	-30.4	-17.8	22.4	9.9	-24.3	-4.1	-1.0	19.2	-27.5	-15.0	22.44	-30.37	0.08	OK
B2	D2	A14	479	-3.63	0.00	3.39	-0.21	2.05	-0.62	-4.1	-8.9	9.9	2.4	-18.2	-6.0	-4.3	7.9	-20.3	-12.8	12.6	5.2	-15.5	-3.3	-1.6	10.6	-17.5	-10.0	12.63	-20.25	0.04	OK
B3	D2	A14	479	-3.50	0.00	-1.49	-0.05	1.24	-0.14	-0.6	-3.1	6.2	-0.3	-15.3	-6.8	-3.2	5.3	-16.2	-9.7	8.9	2.3	-12.7	-4.1	-0.5	8.0	-13.6	-7.0	8.86	-16.21	0.03	OK

Story	ETABS #	Section	Capacity	Dead	Live	WindFX	WindMTX	WindFY	WindMTY																					Maximum Axial Loads Tension	Compression	DCR	Status
Story40	D3	A7	239	-3.09	0.00	6.79	10.17	0.00	29.22	-26.1	26.6	160.8	119.2	-120.8	34.7	-43.5	112.0	-169.7	-128.0	163.2	121.6	-118.5	37.0	-41.2	114.4	-167.3	-125.7	163.18	-169.66	0.71	OK
Story39	D3	A7	239	-3.13	0.00	11.11	10.47	0.02	30.08	-30.5	23.7	173.6	125.5	-132.1	33.8	-42.7	123.1	-182.5	-134.4	175.9	127.8	-129.7	36.2	-40.4	125.5	-180.1	-132.0	175.96	-182.51	0.76	OK
Story38	D3	A7	239	-3.17	0.00	15.41	10.69	0.06	30.71	-34.7	20.5	204.7	136.4	-162.2	26.3	-35.4	153.2	-213.8	-145.5	207.1	138.8	-159.8	28.7	-33.0	155.6	-211.4	-143.1	207.12	-213.77	0.89	OK
Story37	D3	A10	342	-3.30	0.00	24.09	15.53	0.12	44.62	-50.8	29.4	281.3	194.4	-216.0	45.2	-54.6	206.6	-290.7	-203.8	283.8	196.9	-213.5	47.7	-52.1	209.1	-288.2	-201.3	283.79	-290.72	0.85	OK
Story36	D3	A10	342	-3.34	0.00	29.16	15.95	0.19	45.85	-56.0	26.2	299.0	202.9	-231.7	43.7	-53.2	222.2	-308.6	-212.4	301.5	205.4	-229.2	46.2	-50.7	224.7	-306.0	-209.9	301.54	-308.56	0.90	OK
Story35	D3	A10	342	-3.38	0.00	33.81	16.18	0.28	46.49	-60.6	22.7	308.5	206.9	-240.5	42.2	-51.9	230.8	-318.1	-216.6	311.0	209.5	-237.9	44.8	-49.3	233.4	-315.6	-214.0	311.02	-318.12	0.93	OK
Story34	D3	A13.5	462	-3.49	0.00	43.20	22.04	0.41	63.36	-78.9	34.5	378.1	270.0	-282.6	71.8	-81.7	272.6	-388.1	-280.0	380.8	272.6	-280.0	74.4	-79.1	275.3	-385.5	-277.3	380.79	-388.11	0.84	OK
Story33	D3	A13.5	462	-3.44	0.00	48.24	22.57	0.46	64.88	-84.2	31.8	390.8	277.1	-293.0	72.0	-81.8	283.2	-400.7	-286.9	393.4	279.7	-290.4	74.6	-79.2	285.8	-398.1	-284.3	393.45	-400.67	0.87	OK
Story32	D3	A13.5	462	-3.47	0.00	54.47	23.14	0.59	66.51	-90.7	28.0	402.4	284.6	-302.0	73.2	-83.1	292.1	-412.4	-294.5	405.1	287.2	-299.4	75.8	-80.5	294.8	-409.7	-291.8	405.06	-412.36	0.89	OK
Story31	D3	A13.5	462	-3.39	0.00	59.24	23.37	0.53	67.19	-95.4	24.7	410.1	288.1	-308.7	72.4	-82.1	299.1	-419.8	-297.7	412.7	290.6	-306.2	75.0	-79.5	301.6	-417.2	-295.2	412.68	-419.79	0.91	OK
Story30	D3	A13.5	462	-3.42	0.00	57.57	23.67	0.66	68.05	-94.3	27.1	390.7	284.1	-288.2	80.4	-90.2	278.4	-400.5	-293.8	393.3	286.7	-285.6	83.0	-87.6	281.0	-397.9	-291.3	393.28	-400.46	0.87	OK
Story29	D3	A13.5	462	-3.37	0.00	61.60	24.07	0.68	69.21	-98.6	24.9	396.6	288.3	-292.4	81.7	-91.3	282.7	-406.2	-298.0	399.2	290.9	-289.8	84.2	-88.7	285.3	-403.7	-295.4	399.17	-406.25	0.88	OK
Story28	D3	A13.5	462	-3.40	0.00	66.64	24.29	0.80	69.86	-103.4	21.0	405.2	292.3	-300.1	80.7	-90.4	290.4	-414.9	-302.0	407.8	294.8	-297.6	83.2	-87.8	293.0	-412.3	-299.4	407.79	-414.92	0.90	OK
Story27	D3	A13.5	462	-3.32	0.00	71.16	23.95	0.73	68.89	-106.9	15.9	408.9	290.5	-305.5	76.2	-85.7	296.0	-418.4	-300.0	411.4	293.0	-303.0	78.7	-83.2	298.5	-415.8	-297.5	411.38	-418.36	0.91	OK
Story26	D3	A13.5	462	-3.35	0.00	74.10	23.91	0.82	68.79	-109.4	13.0	408.6	289.9	-305.6	75.7	-85.3	296.0	-418.1	-299.5	411.1	292.5	-303.0	78.2	-82.7	298.5	-415.6	-297.0	411.10	-418.13	0.91	OK
Story25	D3	A15.5	530	-3.40	0.00	83.01	27.27	0.93	78.47	-123.1	16.6	451.0	326.2	-332.6	91.1	-100.8	322.9	-460.8	-335.9	453.6	328.8	-330.1	93.7	-98.3	325.5	-458.2	-333.4	453.62	-460.75	0.87	OK
Story24	D3	A15.5	530	-3.42	0.00	86.23	27.05	1.03	77.85	-125.6	12.8	450.4	324.3	-333.2	89.2	-99.0	323.4	-460.1	-334.0	453.0	326.8	-330.6	91.8	-96.4	326.0	-457.6	-331.4	452.96	-460.15	0.87	OK
Story23	D3	A15.5	530	-3.44	0.00	90.97	26.56	1.13	76.45	-129.0	6.7	452.3	321.2	-337.5	84.3	-94.2	327.6	-462.1	-331.1	454.9	323.9	-334.9	86.9	-91.6	330.2	-459.5	-328.5	454.87	-462.10	0.87	OK
Story22	D3	A15.5	530	-3.47	0.00	95.85	26.17	1.24	75.34	-132.6	0.9	454.9	319.2	-342.1	80.1	-90.0	332.2	-464.8	-329.1	457.6	321.8	-339.5	82.7	-87.4	334.8	-462.2	-326.5	457.56	-464.84	0.88	OK
Story21	D3	A15.5	530	-3.42	0.00	100.55	25.78	1.21	74.22	-136.2	-4.7	458.3	317.2	-347.3	75.6	-85.3	337.5	-468.0	-327.0	460.8	319.8	-344.7	78.2	-82.7	340.1	-465.4	-324.4	460.85	-468.03	0.88	OK
Story20	D3	A15.5	530	-3.44	0.00	105.24	25.19	1.32	72.54	-139.4	-11.1	460.0	313.6	-351.8	70.0	-79.9	342.0	-469.8	-323.4	462.6	316.2	-349.2	72.6	-77.3	344.6	-467.2	-320.8	462.59	-469.82	0.89	OK
Story19	D3	A15.5	530	-3.47	0.00	109.95	24.15	1.43	69.55	-141.8	-19.0	459.0	306.0	-355.6	61.6	-71.5	345.7	-468.9	-315.9	461.6	308.6	-353.0	64.3	-68.9	348.3	-466.3	-313.3	461.61	-468.89	0.88	OK
Story18	D3	A15.5	530	-3.49	0.00	114.69	23.36	1.54	67.29	-144.6	-26.2	460.3	300.9	-360.6	54.6	-64.6	350.6	-470.2	-310.9	462.9	303.5	-357.9	57.3	-62.0	353.2	-467.6	-308.2	462.90	-470.23	0.89	OK
Story17	D3	A15.5	530	-3.44	0.00	119.06	22.64	1.48	65.22	-147.4	-32.5	461.6	296.2	-365.2	48.1	-58.0	355.3	-471.4	-306.0	464.2	298.8	-362.6	50.7	-55.4	357.9	-468.8	-303.4	464.17	-471.39	0.89	OK
Story16	D3	A15.5	530	-3.46	0.00	123.51	21.85	1.59	62.95	-150.0	-39.4	462.5	290.9	-369.7	41.2	-51.1	359.9	-472.3	-300.8	465.1	293.5	-367.1	43.8	-48.5	362.5	-469.7	-298.2	465.08	-472.35	0.89	OK
Story15	D3	A15.5	530	-3.38	0.00	127.28	21.08	1.41	60.76	-152.2	-45.2	463.0	285.6	-373.7	34.5	-44.2	364.1	-472.7	-295.2	465.6	288.1	-371.2	37.1	-41.6	366.6	-470.1	-292.7	465.56	-472.66	0.89	OK
Story14	D3	A15.5	530	-3.40	0.00	131.03	20.25	1.51	58.37	-154.1	-51.6	463.4	279.9	-378.0	27.5	-37.2	368.2	-473.1	-289.6	466.0	282.5	-375.4	30.1	-34.7	370.8	-470.5	-287.1	465.98	-473.12	0.89	OK
Story13	D3	A15.5	530	-3.43	0.00	134.71	19.24	1.60	55.47	-155.6	-58.6	462.7	272.7	-381.9	19.3	-29.1	372.1	-472.5	-282.5	465.3	275.3	-379.3	21.9	-26.5	374.7	-469.9	-279.9	465.28	-472.47	0.89	OK
Story12	D3	A15.5	530	-3.45	0.00	138.33	17.78	1.70	51.30	-156.4	-67.0	459.0	261.5	-384.9	8.4	-18.2	375.0	-468.8	-271.4	461.6	264.2	-382.3	11.0	-15.6	377.7	-466.2	-268.8	461.59	-468.83	0.88	OK
Story11	D3	A15.5	530	-3.40	0.00	141.58	15.17	1.63	43.77	-154.9	-79.0	446.6	239.5	-384.5	-9.9	0.1	374.8	-456.3	-249.2	449.2	242.1	-382.0	-7.3	2.7	377.4	-453.8	-246.6	449.20	-456.35	0.86	OK
Story10	D3	A15.5	530	-3.43	0.00	144.84	10.10	1.68	29.17	-149.2	-99.7	416.7	194.8	-378.2	-43.7	33.9	368.4	-426.5	-204.6	419.3	197.4	-375.5	-41.1	36.5	371.0	-423.9	-202.0	419.30	-426.50	0.80	OK
Story9	D3	A15.5	530	-3.45	0.00	148.13	8.65	1.68	24.97	-149.7	-107.8	413.6	183.6	-382.0	-55.1	45.2	372.1	-423.5	-193.5	416.3	186.2	-379.4	-52.5	47.9	374.7	-420.9	-190.8	416.25	-423.50	0.80	OK
Story8	D3	A15.5	530	-3.47	0.00	151.30	8.02	1.66	23.15	-151.6	-112.8	416.9	180.1	-388.3	-61.4	51.5	378.3	-426.9	-190.1	419.6	182.8	-385.6	-58.8	54.1	381.0	-424.2	-187.4	419.56	-426.85	0.81	OK
Story7	D3	A15.5	530	-3.42	0.00	153.73	7.43	1.53	21.48	-152.8	-116.9	419.9	176.9	-393.9	-67.2	57.4	384.1	-429.7	-186.7	422.5	179.5	-391.3	-64.6	60.0	386.7	-427.1	-184.1	422.53	-429.72	0.81	OK
Story6	D3	A15.5	530	-3.45	0.00	155.74	6.94	1.52	20.06	-153.8	-120.4	423.2	174.4	-399.4	-72.3	62.5	389.6	-433.0	-184.3	425.8	177.1	-396.8	-69.7	65.1	392.2	-430.4	-181.7	425.79	-433.03	0.82	OK
Story5	D3	A15.5	530	-3.47	0.00	156.91	6.46	1.53	18.68	-154.1	-123.2	425.2	171.7	-403.8	-77.0	67.1	393.9	-435.2	-181.6	427.9	174.3	-401.1	-74.4	69.7	396.5	-432.5	-179.0	427.87	-435.15	0.82	OK
Story4	D3	A15.5	530	-3.49	0.00	156.02	5.96	1.54	17.25	-152.5	-124.2	422.2	167.3	-403.1	-80.3	70.3	393.1	-432.2	-177.3	424.9	169.9	-400.5	-77.7	73.0	395.8	-429.6	-174.6	424.87	-432.20	0.82	OK
Story3	D3	A15.5	530	-3.44	0.00	150.87	5.48	1.45	15.88	-147.1	-122.1	408.8	159.9	-391.8	-80.3	70.4	382.0	-418.7	-169.8	411.5	162.5	-389.2	-77.7	73.0	384.6	-416.1	-167.2	411.46	-418.69	0.79	OK
Story2	D3	A15.5	530	-3.47	0.00	137.49	4.93	1.48	14.30	-134.1	-111.0	373.9	145.6	-359.5	-74.4	64.5	349.6	-383.8	-155.5	376.6	148.2	-356.9	-71.8	67.2	352.2	-381.2	-152.9	376.56	-383.84	0.72	OK
Story1	D3	A15.5	530	-3.16	0.00	92.81	3.64	1.64	10.56	-91.2	-75.1	257.0	101.6	-247.8	-49.8	40.8	238.7	-266.0	-110.6	259.

SIMPSON GUMPERTZ & HEGER
Engineering of Structures and Building Enclosures

CLIENT Pacific Earthquake Engineering Research Center
SUBJECT BRB Strength Check along Line D for LA BRBF Bldg

SHEET NO. ___
PROJECT NO. 087237.10
DATE 1/23/09
BY AD
CHECKED BY ___

Story	ETABS #	Section	Capacity	Dead	Live	WindFX	WindMTX	WindFY	WindMTY	SpecX	SpecY																														
Story40	D41	A7	239	-3.09	0.00	-6.79	-10.17	0.00	-29.22	450.35	271.59	-14.6	7.2	-3.7	-3.7	-11.9	-11.9	4.4	4.4	-24.1	0.3	-7.8	16.6	-38.8	31.4	-38.8	31.4	-45.3	-27.0	-33.1	-14.7	7.3	-45.3	7.3	37.9	19.6	25.7	25.7	-14.7	37.9	-27.0	19.6	-33.1	-13.6	8.1
Story39	D41	A7	239	-3.13	0.00	-11.11	-10.47	0.02	-30.08	488.64	280.70	-21.5	14.0	-3.7	-3.8	-17.1	-17.1	9.6	9.6	-29.6	-4.5	-3.0	22.1	-39.8	32.4	-39.9	32.3	-50.3	-31.4	-30.3	-11.4	3.9	-50.3	3.9	42.8	23.9	22.7	22.8	-11.4	42.8	-31.4	23.9	-30.3	-20.6	15.0
Story38	D41	A7	239	-3.17	0.00	-15.41	-10.69	0.06	-30.71	586.69	286.68	-28.5	20.9	-3.7	-3.9	-22.2	-22.4	14.8	14.6	-35.1	-9.5	1.9	27.5	-40.6	33.1	-40.7	33.0	-54.9	-35.7	-27.2	-7.9	0.4	-55.0	0.3	47.3	28.1	19.5	19.7	-8.0	47.4	-35.8	28.2	-27.3	-27.5	21.8
Story37	D41	A10	342	-3.30	0.00	-24.09	-15.53	0.12	-44.62	795.14	415.46	-42.5	34.6	-3.8	-4.2	-32.7	-33.0	25.1	24.8	-51.5	-14.2	6.3	43.6	-57.4	49.7	-57.6	49.4	-79.7	-51.8	-36.3	-8.4	0.7	-79.9	0.4	71.8	43.8	28.4	28.6	-8.6	72.0	-52.0	44.0	-36.6	-41.5	35.6
Story36	D41	A10	342	-3.34	0.00	-29.16	-15.95	0.19	-45.85	848.55	427.41	-50.7	42.6	-3.7	-4.3	-38.8	-39.2	31.2	30.7	-58.1	-19.9	11.8	50.1	-58.8	51.2	-59.3	50.8	-85.8	-57.0	-33.2	-4.5	-3.2	-86.1	-3.5	77.7	49.0	25.2	25.6	-4.8	78.1	-57.4	49.4	-33.6	-49.7	43.6
Story35	D41	A10	342	-3.38	0.00	-33.81	-16.18	0.26	-46.49	877.65	431.89	-58.2	50.0	-3.6	-4.5	-44.3	-45.0	36.9	36.2	-64.0	-25.2	17.1	55.9	-59.5	52.1	-60.2	51.4	-90.7	-61.6	-29.8	-0.7	-7.0	-91.2	-7.5	82.6	53.4	21.7	22.2	-1.2	83.1	-62.1	54.0	-30.3	-57.1	51.1
Story34	D41	A13.5	462	-3.49	0.00	-43.20	-22.04	0.41	-53.36	1056.41	586.98	-73.3	64.9	-3.5	-4.8	-55.5	-56.5	48.2	47.2	-82.5	-29.6	21.2	74.1	-79.7	72.3	-80.7	71.3	-119.7	-79.9	-41.8	-2.1	-5.5	-120.4	-6.3	111.3	71.6	33.5	34.2	-2.9	112.0	-80.7	72.3	-42.6	-72.3	66.0
Story33	D41	A13.5	462	-3.44	0.00	-48.24	-22.57	0.46	-64.88	1093.33	599.00	-81.3	73.1	-3.4	-4.9	-61.5	-62.6	54.3	53.2	-89.1	-34.9	26.7	80.8	-81.4	74.3	-82.5	73.2	-125.9	-85.3	-39.0	1.6	-9.1	-126.8	-9.9	117.7	77.0	30.8	31.6	0.8	118.5	-86.1	77.8	-39.9	-80.3	74.1
Story32	D41	A13.5	462	-3.47	0.00	-54.47	-23.14	0.59	-66.51	1126.34	613.64	-91.3	83.0	-3.2	-5.1	-68.8	-70.2	61.9	60.5	-97.3	-41.8	33.4	89.0	-83.3	76.4	-84.7	74.9	-133.5	-91.8	-35.3	6.4	-13.6	-134.5	-14.7	125.1	83.4	27.0	28.1	5.3	126.2	-92.8	84.5	-36.4	-90.3	84.0
Story31	D41	A13.5	462	-3.39	0.00	-59.24	-23.37	0.53	-67.19	1149.34	617.75	-98.9	90.7	-3.2	-4.9	-74.5	-75.8	67.7	66.4	-103.2	47.1	39.0	95.1	-84.0	77.2	-85.3	75.9	-138.5	-96.4	-31.8	10.3	-17.5	-139.5	-18.4	130.4	88.3	23.7	24.6	9.4	131.4	-97.4	89.3	-32.8	-97.8	91.7
Story30	D41	A13.5	462	-3.42	0.00	-57.57	-23.67	0.66	-68.05	1085.40	624.61	-96.2	88.0	-3.0	-5.2	-72.4	-74.0	65.8	64.2	-101.6	-44.8	36.6	93.4	-85.0	78.4	-86.6	76.8	-138.0	-95.3	-34.3	8.4	-15.4	-139.2	-16.6	129.8	87.1	26.1	27.3	7.2	131.0	-96.5	88.3	-35.5	-95.2	89.0
Story29	D41	A13.5	462	-3.37	0.00	-61.60	-24.07	0.68	-69.21	1101.55	634.54	-102.6	94.5	-3.0	-5.1	-77.2	-78.8	70.7	69.1	-106.9	-49.1	41.0	98.8	-86.3	79.8	-87.9	78.2	-143.0	-99.6	-32.0	11.4	-19.5	-143.8	-18.3	135.8	91.5	23.9	25.1	10.2	136.1	-100.8	92.7	-33.2	-101.6	95.5
Story28	D41	A13.5	462	-3.40	0.00	-66.64	-24.29	0.80	-69.86	1127.73	638.56	-110.7	102.5	-2.8	-5.4	-83.1	-85.0	76.9	74.9	-113.2	-54.9	46.7	105.0	-86.9	80.7	-88.9	78.8	-148.2	-104.4	-28.1	15.6	-22.3	-148.6	-23.8	140.0	96.3	20.0	21.4	14.2	141.5	-105.9	97.7	-29.6	-109.7	103.6
Story27	D41	A13.5	462	-3.32	0.00	-71.16	-23.95	0.73	-68.89	1142.13	627.87	-117.9	109.9	-2.8	-5.2	-88.5	-90.3	82.3	80.5	-118.1	-60.6	52.7	110.2	-85.8	79.6	-87.5	77.8	-151.1	-107.9	-22.9	20.3	-27.0	-152.4	-28.3	143.1	99.9	14.9	16.2	19.0	144.4	-109.2	101.3	-24.2	-116.9	110.9
Story26	D41	A13.5	462	-3.35	0.00	-74.10	-23.91	0.82	-68.79	1141.76	626.17	-122.6	114.5	-2.7	-5.3	-91.9	-93.9	85.9	83.9	-121.6	-64.2	56.2	113.6	-85.6	79.5	-87.6	77.5	-153.5	-110.5	-20.0	23.0	-29.6	-155.0	-31.1	145.5	102.4	12.0	13.5	21.6	147.0	-111.9	103.9	-21.5	-121.6	115.5
Story25	D41	A15.5	530	-3.40	0.00	-83.01	-27.27	0.93	-78.47	1252.97	712.72	-136.9	128.7	-2.6	-5.6	-102.6	-104.8	96.6	94.4	-136.4	-71.0	62.8	128.3	-97.1	91.2	-99.4	89.0	-173.3	-124.1	-23.7	25.4	-31.9	-174.9	-33.6	165.1	116.0	15.6	17.2	23.7	166.8	-125.8	117.7	-25.4	-135.9	129.8
Story24	D41	A15.5	530	-3.42	0.00	-86.23	-27.05	1.03	-77.85	1252.77	706.29	-142.1	133.9	-2.5	-5.8	-106.4	-108.8	100.6	98.1	-140.1	-75.1	66.9	131.8	-96.3	90.5	-98.8	88.1	-175.4	-126.6	-20.0	28.7	-35.1	-177.2	-37.0	167.1	118.4	11.8	13.6	26.9	169.0	-128.5	120.3	-21.8	-141.1	134.9
Story23	D41	A15.5	530	-3.44	0.00	-90.97	-26.56	1.13	-76.45	1262.66	693.27	-149.7	141.4	-2.3	-5.9	-111.9	-114.7	106.4	103.7	-145.2	-81.4	73.2	136.9	-94.5	89.0	-97.2	86.2	-177.9	-130.0	-14.0	33.9	-40.1	-179.9	-42.2	169.6	121.7	5.7	7.7	31.9	171.6	-132.0	123.8	-16.0	-148.7	142.5
Story22	D41	A15.5	530	-3.47	0.00	-95.85	-26.17	1.24	-75.34	1274.30	682.82	-157.5	149.2	-2.2	-6.1	-117.7	-120.7	112.4	109.4	-150.6	-87.8	79.5	142.3	-93.1	87.7	-96.1	84.8	-180.8	-133.7	-8.1	39.0	-45.1	-183.1	-47.3	172.5	125.4	-0.2	2.1	36.8	174.7	-135.9	127.8	-10.4	-156.5	150.2
Story21	D41	A15.5	530	-3.42	0.00	-100.55	-25.78	1.21	-74.22	1287.88	671.82	-166.0	156.8	-2.2	-6.0	-123.3	-126.2	118.0	115.1	-155.7	-93.8	85.6	147.5	-91.7	86.4	-94.6	83.5	-183.7	-137.2	-2.5	43.9	-50.0	-185.9	-52.1	175.5	129.0	-5.7	-3.5	41.8	177.6	-139.4	131.2	-4.7	-164.0	157.8
Story20	D41	A15.5	530	-3.44	0.00	-105.24	-25.19	1.32	-72.54	1297.89	656.59	-172.5	164.3	-2.0	-6.2	-128.8	-132.0	123.7	120.6	-160.6	-100.2	91.9	152.4	-89.6	84.5	-92.8	81.3	-185.8	-140.4	3.8	49.2	-55.1	-188.2	-57.5	177.5	132.1	-12.1	-9.7	46.8	179.9	-142.8	134.5	1.4	-171.5	165.3
Story19	D41	A15.5	530	-3.47	0.00	-109.95	-24.15	1.43	-69.55	1302.42	630.08	-180.1	171.8	-1.9	-6.4	-134.4	-137.8	129.5	126.1	-165.1	-107.1	98.8	156.8	-85.9	81.0	-89.3	77.6	-186.3	-142.8	11.8	55.3	-61.0	-188.9	-63.6	178.0	134.5	-20.1	-17.5	52.7	180.6	-145.4	137.1	9.2	-179.0	172.8
Story18	D41	A15.5	530	-3.48	0.00	-114.69	-23.36	1.54	-67.29	1312.37	609.96	-187.7	179.3	-1.7	-6.6	-140.0	-143.7	135.3	131.6	-169.8	-113.8	105.4	161.5	-83.1	78.4	-86.8	74.7	-187.8	-145.7	18.8	60.9	-66.5	-190.5	-69.3	179.4	137.3	-27.2	-24.5	58.2	182.2	-148.5	140.1	16.1	-186.6	180.4
Story17	D41	A15.5	530	-3.44	0.00	-119.06	-22.64	1.48	-65.22	1321.79	590.97	-194.6	186.4	-1.8	-6.5	-145.2	-148.8	140.5	137.0	-174.2	-119.8	111.6	165.9	-80.6	75.9	-84.2	72.4	-189.2	-148.4	25.3	66.1	-71.7	-191.9	-74.4	180.9	140.2	-33.6	-30.9	63.4	183.6	-151.1	142.8	22.6	-193.6	187.4
Story16	D41	A15.5	530	-3.46	0.00	-123.51	-21.85	1.59	-62.95	1330.55	570.74	-201.8	193.5	-1.6	-6.7	-150.5	-154.3	146.0	142.1	-178.6	-126.1	117.8	170.3	-77.8	73.3	-81.6	69.5	-190.4	-151.0	32.1	71.5	-76.9	-193.2	-79.8	182.1	142.7	-40.5	-37.6	68.6	184.9	-153.9	145.6	29.3	-200.7	194.5
Story15	D41	A15.5	530	-3.38	0.00	-127.28	-21.08	1.41	-60.76	1337.80	550.32	-207.7	199.6	-1.8	-6.3	-155.1	-158.5	150.4	147.0	-182.1	-131.5	123.4	174.0	-75.3	70.5	-78.7	67.2	-191.2	-153.2	38.2	76.1	-81.7	-193.7	-84.2	183.0	145.1	-46.3	-43.7	73.6	185.6	-155.7	147.6	35.6	-206.7	200.6
Story14	D41	A15.5	530	-3.40	0.00	-131.03	-20.25	1.51	-58.37	1345.21	529.29	-213.7	205.6	-1.7	-6.5	-159.5	-163.1	155.0	151.3	-185.6	-137.0	128.8	177.4	-72.3	67.8	-75.9	64.2	-191.6	-155.1	44.5	81.0	-86.4	-194.3	-89.1	183.4	146.9	-52.6	-49.9	78.2	186.1	-157.8	149.6	41.8	-212.7	206.6
Story13	D41	A15.5	530	-3.43	0.00	-134.71	-19.24	1.60	-55.47	1350.36	503.77	-219.6	211.4	-1.6	-6.7	-163.8	-167.7	159.5	155.6	-188.8	-142.7	134.5	180.6	-68.8	64.4	-72.6	60.5	-191.3	-156.7	51.4	86.0	-91.4	-194.2	-94.3	183.1	148.4	-59.6	-56.7	83.1	186.0	-159.5	151.3	48.5	-218.6	212.4
Story12	D41	A15.5	530	-3.45	0.00	-138.33	-17.78	1.70	-51.30	1349.21	466.90	-225.5	217.2	-1.4	-6.9	-168.1	-172.2	163.9	159.8	-191.5	-148.8	140.5	183.2	-63.7	59.4	-67.7	55.4	-189.4	-157.4	59.8	91.8	-97.0	-192.5	-100.1	181.2	149.1	-68.0	-65.0	88.7	184.2	-160.5	152.2	56.7	-224.4	218.2
Story11	D41	A15.5	530	-3.40	0.00	-141.58	-15.17	1.63	-43.77	1328.90	399.42	-230.6	222.4	-1.5	-6.7	-172.0	-175.9	167.8	163.8	-192.2	-154.8	146.4	184.0	-54.6	50.4	-57.7	46.6	-183.2	-155.9	71.8	99.2	-104.4	-186.2	-107.3	175.1	147.7	-80.0	-77.1	96.2	178.0	-158.8	150.7	68.9	-229.6	223.5
Story10	D41	A15.5	530	-3.43	0.00	-144.84	-10.10	1.68	-29.17	1270.98	268.49	-235.9	227.6	-1.4	-6.8	-175.9	-179.9	171.7	167.7	-190.0	-165.8	157.6	181.8	-37.1	32.9	-41.1	28.9	-168.4	-150.2	92.5	110.7	-115.9	-171.5	-118.9	160.2	142.0	-100.7	-97.7	107.7	163.3	-153.3	145.0	89.5	-234.8	228.7
Story9	D41	A15.5	530	-3.45	0.00	-148.13	-8.65	1.68	-24.97	1272.08	230.90	-241.2	232.9	-1.5	-6.8	-179.9	-183.9	175.6	171.6	-192.3	-171.5	163.2	184.0	-32.1	27.8	-36.1	23.8	-166.3	-150.8	100.5	116.1	-121.4	-169.4	-124.4	158.1	142.5	-108.8	-105.8	113.1	161.1	-153.8	145.5	97.5	-240.1	233.9
Story8	D41	A15.5	530	-3.47	0.00	-151.30	-8.02	1.66	-23.15	1287.28	214.66	-246.2	237.9	-1.5	-6.8	-183.7	-187.7	179.4	175.4	-195.3	-176.1	167.8	187.0	-30.0	25.6	-33.9	21.6	-167.0	-152.6	105.5	120.0	-125.3	-170.0	-128.3	158.7	144.3	-113.9	-110.9	117.0	161.7	-155.6	147.3	102.5	-245.2	239.0
Story7	D41	A15.5	530	-3.42	0.00	-153.73	-7.43	1.53	-21.48	1301.13	199.43	-250.1	241.9	-1.7	-6.6	-186.8	-190.4	182.2	178.5	-197.5	-179.7	171.5	189.3	-28.1	23.5	-31.7	19.8	-167.3	-153.9	109.7	123.1	-128.6	-170.0	-131.3	159.1	145.7	-117.9	-115.2	120.3	161.8	-156.6	148.4	106.9	-249.1	242.9
Story6	D41	A15.5	530	-3.45	0.00	-155.74	-6.94	1.52	-20.06	1315.22	186.83	-253.3	245.1	-1.7	-6.6	-189.2	-192.9	184.6	180.9	-199.4	-182.7	174.4	191.1	-26.4	21.8	-30.0	18.0	-167.4	-154.9	113.2	125.7	-131.2	-170.1	-134.0	159.1	146.6	-121.5	-118.7	123.0	161.9	-157.6	149.4	110.5	-252.3	246.1
Story5	D41	A15.5	530	-3.47	0.00	-156.91	-6.46	1.53	-18.68	1325.44	174.57	-255.2	246.9	-1.7	-6.6	-190.6	-194.3	186.0	182.3	-200.2	-184.7	176.4	191.9	-24.8	20.1	-28.4	16.4	-166.8	-155.1	115.9	127.5	-133.1	-169.5	-135.9	158.5	146.8	-124.2	-121.5	124.8	161.2	-157.9	149.8	112.2	-254.2	247.9
Story4	D41	A15.5	530	-3.49	0.00	-156.02	-5.96	1.54	-17.25	1319.55	161.85	-253.8	245.4	-1.7	-6.7	-189.6	-193.3	184.9	181.2	-198.6	-184.3	175.9	190.7	-23.0	18.4	-26.7	14.7	-164.3	-153.5	116.8	127.6	-133.2	-167.0	-136.0	155.9	145.1	-125.2	-122.4	124.8	158.6	-156.3	147.9	114.0	-252.8	246.5
Story3	D41	A15.5	530	-3.44	0.00	-150.87	-5.48	1.45	-15.88	1280.17	149.37	-245.5	237.3	-1.8	-6.5	-183.4	-186.9	178.7	175.2	-191.8	-178.6	170.3	183.5	-21.4	16.7	-24.9	13.2	-158.0	-148.1	113.8	123.7	-129.4	-160.6	-132.0	149.7	139.8	-122.1	-119.5	121.1	152.3	-150.7	142.4	111.2	-244.5	238.3
Story2	D41	A15.5	530	-3.47	0.00	-137.49	-4.93	1.48	-14.30	1172.67	135.28	-224.1	215.8	-1.8	-6.5	-167.4	-170.9	162.6	159.1	-175.1	-163.2	154.9	166.8	-19.5	14.8	-23.1	11.2	-144.0	-135.1	103.7	112.6	-118.2	-146.7	-120.9	135.7	128.6	-112.0	-109.4	109.9	138.3	-137.8	129.5	101.0	-223.1	216.9
Story1	D41	A15.5	530	-3.16	0.00	-92.81	-3.64	1.64	-10.56	867.01	101.49	-152.3	144.7	-1.2	-6.4	-113.2	-117.1	109.5	105.6	-119.5	-110.8	103.2	111.9	-14.5	10.8	-18.4	8.1	-98.7	-92.1	68.5	75.1	-79.7	-101.7	-82.6	91.1	84.6	-76.1	-73.1	72.1	94.1	-95.1	87.5	65.5	-151.3	145.6
Ground	D41	A14	479	-3.58	0.00	2.23	-0.73	1.34	-2.12	66.13	22.95	-0.7	-7.9	-2.1	-6.4	0.0	-3.2	-5.4	-8.6	-2.5	-0.7	-7.8	-6.1	-5.2	-0.1	-8.4	-3.4	-3.6	-2.3	-7.7	-6.3	0.2	-6.1	-2.2	-4.9	-6.3	-0.9	1.5	-8.8	-2.5	-4.7	-3.8	-10.1	0.4	-6.8
B1	D41	A14	479	-3.46	0.00	2.68	-0.48	1.18	-1.40	55.07	16.03	0.1	-8.4	-2.3	-6.0	0.5	-2.3	-6.0	-8.8	-1.5	-0.4	-8.0	-6.8	-4.4	-1.1	-7.2	-3.9	-2.4	-1.5	-7.2	-6.3	0.1	-4.5	-2.0	-5.9	-6.8	-1.1	1.0	-8.5	-3.8	-3.6	-4.7	-9.3	1.2	-7.4
B2	D41	A14	479	-3.48	0.00	0.61	-0.25	1.17	-0.72	38.35	9.80	-3.2	-5.2	-2.3	-6.0	-2.0	-4.8	-3.5	-6.3	-3.7	-3.1	-5.2	-4.6	-3.6	-1.9	-6.4	-4.7	-3.4	-3.0	-4.5	-4.1	-2.2	-5.5	-4.3	-4.9	-5.4	-3.8	-1.7	-6.2	-2.8	-5.1	-3.3	-6.6	-2.2	-4.1
B3	D41	A14	479	-3.50	0.00	-2.10	-0.02	1.16	-0.05	35.29	3.79	-7.6	-0.8	-2.3	-6.1	-5.3	-8.1	-0.3	-3.1	-6.7	-6.7	-1.7	-1.7	-2.9	-2.7	-5.7	-5.5	-6.1	-5.1	-1.3	-1.3	-5.0	-7.2	-7.1	-3.3	-3.3	-7.1	-5.0	-3.4	-1.2	-7.2	-1.2	-3.4	-6.5	0.2

Story	ETABS #	Section	Capacity	Dead	Live	WindFX	WindMTX	WindFY	WindMTY	SpecX	SpecY																														
Story40	D5	A7	239	-0.20	0.00	4.11	9.15	-0.01	26.30	404.04	251.77	6.3	-6.8	-0.3	-0.2	4.7	4.7	-5.2	-5.2	15.7	-6.3	5.8	-16.2	31.3	-31.8	31.3	-31.8	35.4	18.9	28.0	11.5	-12.0	35.4	-12.0	-35.9	-19.4	-28.5	-28.5	11.5	-35.9	18.9	-19.4	28.0	6.4	-6.8
Story39	D5	A7	239	-0.27	0.00	8.38	9.49	0.02	27.27	435.18	261.89	13.1	-13.7	-0.3	-0.3	9.8	9.7	-10.4	-10.4	21.1	-1.7	1.0	-21.8	32.4	-33.0	32.4	-33.1	40.4	23.3	25.3	8.2	-8.8	40.3	-8.8	-41.0	-23.9	-25.9	-25.9	8.1	-41.0	23.2	-23.9	25.2	13.2	-13.6
Story38	D5	A7	239	-0.33	0.00	12.63	9.79	0.05	28.13	539.20	270.69	19.8	-20.6	-0.3	-0.5	14.8	14.7	-15.5	-15.6	26.5	3.0	-3.8	-27.3	33.4	-34.1	33.3	-34.2	45.2	27.6	22.4	4.8	2.1	45.9	2.7	55.4	27.5	-28.3	22.3	2.1	45.9	27.5	-28.3	22.3	19.9	-20.5
Story37	D5	A8	274	-0.04	0.00	16.08	11.52	0.02	33.09	586.27	317.70	25.7	-25.8	0.0	-0.1	19.3	19.2	-19.3	-19.4	33.1	5.4	-5.5	-33.2	39.7	-39.7	39.6	-39.8	54.6	33.9	25.7	4.9	-5.0	54.6	-5.0	-54.7	-34.0	-25.8	-25.7	4.9	-54.7	33.8	-33.9	25.6	25.7	-25.8
Story36	D5	A8	274	-0.11	0.00	20.02	11.93	0.12	34.27	633.00	328.14	31.9	-32.2	-0.2	-0.3	24.0	24.0	-24.2	-24.2	38.2	9.6	-9.8	-38.5	40.8	-41.4	41.1	-41.7	63.1	41.9	37.9	23.3	1.9	-2.3	59.6	-2.1	-59.7	-38.2	-23.6	-23.8	2.1	-59.9	38.1	-38.4	23.6	31.9	32.1
Story35	D5	A8	274	-0.16	0.00	23.55	12.12	-0.42	34.82	658.47	330.16	37.5	-37.9	-0.9	0.5	27.6	28.6	-28.9	-28.0	42.6	13.5	-13.9	-43.0	41.1	-42.5	42.1	-41.5	62.9	41.1	50.5	-1.3	0.2	63.7	0.9	-63.3	-41.5	-20.9	-21.6	-0.6	-64.1	-41.8	-42.2	21.2	37.5	-37.8
Story34	D5	A10	342	0.53	0.00	27.33	15.30	-1.01	43.97	731.14	413.93	44.4	-43.1	-1.0	2.3	32.2	34.6	-33.4	-30.9	51.8	15.1	-13.8	-50.5	52.2	-53.4	54.6	-50.9	77.7	50.2	28.5	0.9	-1.5	79.6	0.3	-76.5	-48.9	-27.2	-29.1	2.8	-78.3	52.0	-50.7	30.3	44.2	-43.3
Story33	D5	A10	342	0.59	0.00	30.57	16.58	-1.49	44.79	756.52	419.07	49.6	-48.2	-1.7	3.1	35.6	39.2	-37.8	-34.2	56.1	18.7	-17.3	-54.7	52.7	-54.8	56.2	-51.2	81.3	53.2	26.2	-1.9	0.6	84.0	3.3	-79.9	-51.8	-24.8	-27.5	0.8	-82.6	55.9	-54.5	28.9	49.4	-48.4
Story32	D5	A10	342	0.60	0.00	34.42	15.80	-1.98	45.41	771.67	424.23	55.8	-54.4	-2.5	3.9	39.6	44.4	-43.0	-38.2	61.0	23.1	-21.6	-59.5	52.8	-56.2	57.6	-51.4	85.1	56.6	23.1	-5.4	3.3	88.6	6.8	-83.6	-55.2	-21.6	-25.2	-1.8	-87.2	60.2	-58.7	26.6	55.6	-54.5
Story31	D5	A10	342	0.73	0.00	37.24	15.75	-2.59	45.26	778.20	422.68	60.5	-58.7	-3.3	5.0	42.5	48.7	-46.9	-40.7	64.5	26.7	-24.9	-62.7	52.1	-56.5	58.3	-50.3	87.1	58.7	20.0	-8.4	5.5	91.7	10.2	-85.3	-56.9	-18.2	-22.9	-3.7	-90.0	63.3	-61.6	24.6	60.2	-58.9
Story30	D5	A13.5	462	2.15	0.00	47.30	21.11	-4.46	60.69	965.79	582.69	78.3	-73.1	-4.5	9.7	54.0	64.7	-59.5	-48.8	84.7	34.0	-28.8	-79.5	70.1	-75.6	80.8	-64.9	114.9	76.8	29.6	-8.4	5.5	122.9	13.6	-109.7	-71.7	-24.5	-32.5	-0.4	-117.7	84.9	-79.7	27.6	77.6	-73.7
Story29	D5	A13.5	462	2.32	0.00	50.40	21.21	-5.41	60.98	968.38	572.21	83.4	-77.9	-5.9	11.4	56.8	69.8	-64.2	-51.2	88.7	37.8	-32.2	-83.1	69.5	-76.9	82.5	-63.9	117.4	79.1	26.6	-11.7	7.5	127.1	17.2	-111.8	-73.6	-21.0	-30.7	-1.9	-121.5	88.9	-83.3	36.3	82.7	-78.6
Story28	D5	A13.5	462	2.48	0.00	54.64	21.19	-6.51	60.94	985.20	574.25	90.4	-84.5	-7.4	13.4	60.7	76.4	-70.4	-54.8	94.0	43.1	-37.2	-88.0	68.3	-78.0	83.9	-62.3	120.3	82.1	29.9	-16.3	10.5	132.0	22.3

SIMPSON GUMPERTZ & HEGER
Engineering of Structures and Building Enclosures

CLIENT Pacific Earthquake Engineering Research Center
SUBJECT BRB Strength Check along Line D for LA BRBF Bldg

SHEET NO. ___
PROJECT NO. 087237.10
DATE 1/23/09
BY AD
CHECKED BY ___

Story	ETABS #	Section	Capacity	Dead	Live	WindFX	WindMTX	WindFY	WindMTY																								
Story40	D41	A7	239	-3.09	0.00	-6.79	-10.17	0.00	-29.22	-2.8	-2.8	-10.9	-10.9	5.4	5.4	-23.1	1.3	-6.8	17.6	-37.8	32.3	-37.8	32.3	-44.4	-26.1	-32.1	-13.8	8.3	-44.4	8.3	38.8	20.5	26.6	26.6	-13.8	38.8	-26.1
Story39	D41	A7	239	-3.13	0.00	-11.11	-10.47	0.02	-30.08	-2.8	-2.9	-16.1	-16.2	10.5	10.5	-28.7	-3.6	-2.0	23.1	-38.9	33.3	-38.9	33.3	-49.3	-30.5	-29.3	-10.5	4.9	-49.4	4.8	43.7	24.8	23.7	23.7	-10.5	43.7	-30.5
Story38	D41	A7	239	-3.17	0.00	-15.41	-10.69	0.06	-30.71	-2.8	-3.0	-21.3	-21.4	15.7	15.6	-34.2	-8.5	2.8	28.5	-39.6	34.1	-39.8	33.9	-54.0	-34.7	-26.2	-6.9	1.4	-54.1	1.2	48.3	29.0	20.5	20.6	-7.1	48.4	-34.8
Story37	D41	A10	342	-3.30	0.00	-24.09	-15.53	0.12	-44.62	-2.8	-3.2	-31.7	-32.0	26.1	25.8	-50.5	-13.2	7.3	44.6	-56.4	50.7	-56.7	50.4	-78.7	-50.8	-35.3	-7.4	1.6	-79.0	1.4	72.8	44.8	29.4	29.6	-7.6	73.0	-51.0
Story36	D41	A10	342	-3.34	0.00	-29.16	-15.95	0.19	-45.85	-2.7	-3.3	-37.8	-38.2	32.2	31.7	-57.1	-18.9	12.8	51.1	-57.8	52.2	-58.3	51.8	-84.8	-56.0	-32.2	-3.5	-2.2	-85.1	-2.5	78.8	50.0	26.2	26.6	-3.8	79.1	-56.4
Story35	D41	A10	342	-3.38	0.00	-33.81	-16.18	0.28	-46.49	-2.6	-3.5	-43.3	-44.0	37.9	37.2	-63.0	-24.2	18.1	56.9	-58.5	53.1	-59.2	52.4	-89.7	-60.6	-28.8	0.4	-5.9	-90.2	-6.5	83.6	54.5	22.7	23.2	-0.1	84.1	-61.1
Story34	D41	A13.5	462	-3.49	0.00	-43.20	-22.04	0.41	-63.36	-2.5	-3.8	-54.5	-55.5	49.2	48.2	-81.4	-28.5	22.2	75.2	-78.7	73.4	-79.7	72.4	-118.6	-78.9	-40.8	-1.1	-4.5	-119.4	-5.2	112.3	72.6	34.5	35.3	-1.8	113.1	-79.6
Story33	D41	A13.5	462	-3.44	0.00	-48.24	-22.57	0.46	-64.88	-2.4	-3.8	-60.4	-61.5	55.3	54.2	-88.1	-33.9	27.7	81.9	-80.4	75.3	-81.5	74.2	-124.9	-84.2	-38.0	2.7	-8.0	-125.7	-8.8	118.7	78.1	31.8	32.6	1.8	119.5	-85.1
Story32	D41	A13.5	462	-3.47	0.00	-54.47	-23.14	0.59	-66.51	-2.2	-4.1	-67.8	-69.2	63.0	61.5	-96.3	-40.7	34.5	90.0	-82.2	77.4	-83.6	76.0	-132.4	-90.7	-34.3	7.4	-12.6	-133.5	-13.7	126.2	84.5	28.0	29.1	6.3	127.2	-91.8
Story31	D41	A13.5	462	-3.39	0.00	-59.24	-23.37	0.53	-67.19	-2.2	-3.9	-73.5	-74.8	68.7	67.4	-107.4	-46.1	40.0	96.1	-83.0	78.2	-84.3	76.9	-137.5	-95.4	-30.8	11.3	-16.5	-138.5	-17.4	131.4	89.3	24.7	25.8	10.4	132.4	-96.4
Story30	D41	A13.5	462	-3.42	0.00	-57.57	-23.67	0.66	-68.05	-2.0	-4.1	-71.4	-73.0	66.8	65.2	-100.6	-43.8	37.6	94.4	-84.0	79.4	-85.5	77.8	-137.0	-94.3	-33.2	9.4	-14.4	-138.2	-15.5	130.8	88.2	27.1	28.3	8.2	132.0	-95.5
Story29	D41	A13.5	462	-3.37	0.00	-61.60	-24.07	0.68	-69.21	-1.9	-4.1	-76.1	-77.8	71.7	70.1	-105.8	-48.1	42.0	99.8	-85.3	80.8	-86.9	79.2	-141.9	-98.6	-31.0	12.4	-17.2	-143.2	-18.5	135.9	92.5	24.9	26.1	11.2	137.1	-99.8
Story28	D41	A13.5	462	-3.40	0.00	-66.64	-24.29	0.80	-69.86	-1.8	-4.3	-82.1	-84.0	77.9	75.9	-112.2	-53.9	47.8	106.1	-85.9	81.7	-87.9	79.8	-147.2	-103.4	-27.1	16.6	-21.3	-148.6	-22.8	141.1	97.3	21.0	22.5	15.2	142.5	-104.9
Story27	D41	A13.5	462	-3.32	0.00	-71.16	-23.95	0.73	-68.89	-1.8	-4.2	-87.5	-89.3	83.3	81.5	-117.1	-59.6	53.7	111.1	-84.8	80.6	-86.5	78.8	-150.1	-106.9	-21.9	21.3	-26.0	-151.4	-27.3	144.1	100.9	15.9	17.2	20.0	145.4	-108.2
Story26	D41	A13.5	462	-3.35	0.00	-74.10	-23.91	0.82	-68.79	-1.7	-4.3	-90.9	-92.9	86.9	84.9	-120.6	-63.2	57.2	114.6	-84.6	80.5	-86.6	78.6	-152.5	-109.4	-19.0	24.0	-28.6	-154.0	-30.1	146.5	103.4	13.0	14.5	22.6	148.0	-110.9
Story25	D41	A15.5	530	-3.40	0.00	-83.01	-27.27	0.93	-78.47	-1.6	-4.5	-101.6	-103.8	97.7	95.4	-135.4	-69.9	63.8	129.3	-96.1	92.2	-98.3	90.0	-172.3	-123.1	-22.7	26.4	-30.9	-173.9	-32.6	166.1	117.0	16.6	18.3	24.8	167.8	-124.8
Story24	D41	A15.5	530	-3.42	0.00	-86.23	-27.05	1.03	-77.85	-1.4	-4.7	-105.3	-107.8	101.6	99.2	-139.0	-74.1	67.9	132.9	-96.3	91.6	-97.7	89.1	-174.3	-125.6	-19.0	29.8	-34.1	-176.2	-35.9	168.2	119.4	12.8	14.7	27.9	170.0	-127.4
Story23	D41	A15.5	530	-3.44	0.00	-90.97	-26.56	1.13	-76.45	-1.3	-4.9	-110.9	-113.6	107.4	104.7	-144.1	-80.4	74.2	137.9	-93.5	90.0	-96.2	87.3	-176.8	-129.0	-12.9	34.9	-39.1	-178.9	-41.1	170.6	122.8	6.7	8.8	32.9	172.7	-131.0
Story22	D41	A15.5	530	-3.47	0.00	-95.85	-26.17	1.24	-75.34	-1.1	-5.1	-116.7	-119.6	113.4	110.4	-149.6	-86.7	80.5	143.3	-92.0	88.8	-95.0	85.8	-179.8	-132.6	-7.1	40.1	-44.1	-182.0	-46.3	173.5	126.4	0.9	3.1	37.8	175.8	-134.9
Story21	D41	A15.5	530	-3.42	0.00	-100.55	-25.78	1.21	-74.22	-1.1	-5.0	-122.3	-125.2	119.0	116.1	-154.7	-92.8	86.7	148.5	-90.7	87.4	-93.6	84.5	-182.6	-136.2	-1.5	45.0	-48.9	-184.8	-51.1	176.5	130.0	-4.7	-2.5	42.8	178.7	-138.4
Story20	D41	A15.5	530	-3.44	0.00	-105.24	-25.19	1.32	-72.54	-1.0	-5.2	-127.8	-131.0	124.8	121.6	-159.6	-99.2	93.0	153.4	-88.6	85.5	-91.7	82.4	-184.7	-139.4	4.9	50.2	-54.1	-187.1	-56.4	178.5	133.2	-11.1	-8.7	47.9	180.9	-141.7
Story19	D41	A15.5	530	-3.47	0.00	-109.95	-24.15	1.43	-69.55	-0.8	-5.4	-133.3	-136.8	130.5	127.1	-164.0	-106.1	99.8	157.8	-84.9	82.1	-88.3	78.6	-185.3	-141.8	12.8	56.3	-60.0	-187.9	-62.5	179.0	135.5	-19.0	-16.5	53.7	181.6	-144.3
Story18	D41	A15.5	530	-3.49	0.00	-114.69	-23.36	1.54	-67.29	-0.7	-5.6	-138.9	-142.6	136.3	132.6	-168.9	-112.7	106.5	162.5	-82.0	79.5	-85.7	75.8	-186.7	-144.6	19.9	62.0	-65.5	-189.5	-68.3	180.4	138.4	-26.2	-23.4	59.2	183.2	-147.4
Story17	D41	A15.5	530	-3.44	0.00	-119.06	-22.64	1.48	-65.22	-0.7	-5.5	-144.2	-147.7	141.6	138.0	-173.1	-118.8	112.6	166.9	-79.6	77.0	-83.1	73.4	-188.2	-147.4	26.3	67.1	-70.6	-190.8	-73.3	182.0	141.2	-32.5	-29.9	64.5	184.6	-150.0
Story16	D41	A15.5	530	-3.46	0.00	-123.51	-21.85	1.59	-62.95	-0.6	-5.7	-149.4	-153.2	147.0	143.2	-177.5	-125.1	118.9	171.3	-76.8	74.3	-80.6	70.5	-189.3	-150.0	33.2	72.5	-75.9	-192.2	-78.8	183.1	143.7	-39.4	-36.6	69.7	186.0	-152.8
Story15	D41	A15.5	530	-3.38	0.00	-127.28	-21.08	1.41	-60.76	-0.8	-5.3	-154.1	-157.5	151.4	148.0	-181.1	-130.5	124.4	175.0	-74.3	71.6	-77.6	68.2	-190.1	-152.2	39.2	77.1	-80.7	-192.7	-83.2	184.1	146.1	-45.2	-42.7	74.6	186.6	-154.7
Story14	D41	A15.5	530	-3.40	0.00	-131.03	-20.25	1.51	-58.37	-0.7	-5.5	-158.5	-162.1	156.0	152.4	-184.6	-136.0	129.9	178.5	-71.3	68.8	-74.9	65.2	-190.6	-154.1	45.5	82.0	-85.4	-193.3	-88.1	184.4	148.0	-51.6	-48.9	79.3	187.1	-156.8
Story13	D41	A15.5	530	-3.43	0.00	-134.71	-19.24	1.60	-55.47	-0.5	-5.6	-162.8	-166.7	160.5	156.6	-187.8	-141.6	135.5	181.7	-67.7	65.4	-71.6	61.6	-190.3	-155.6	52.4	87.1	-90.3	-193.2	-93.2	184.1	149.5	-58.6	-55.7	84.2	187.0	-158.5
Story12	D41	A15.5	530	-3.45	0.00	-138.33	-17.78	1.70	-51.30	-0.4	-5.8	-167.1	-171.1	164.9	160.9	-190.4	-147.8	141.5	184.2	-62.6	60.5	-66.7	56.4	-188.4	-156.4	60.8	92.8	-96.0	-191.5	-99.1	182.2	150.2	-67.0	-64.0	89.8	185.3	-159.4
Story11	D41	A15.5	530	-3.40	0.00	-141.58	-15.17	1.63	-43.77	-0.5	-5.7	-171.0	-174.9	168.8	164.9	-191.2	-154.7	148.6	186.0	-53.6	51.4	-57.5	47.5	-182.2	-154.9	72.8	100.2	-103.4	-185.2	-106.3	176.1	148.8	-79.0	-76.0	97.2	179.0	-157.8
Story10	D41	A15.5	530	-3.43	0.00	-144.84	-10.10	1.68	-29.17	-0.4	-5.8	-174.9	-178.9	172.7	168.7	-189.0	-164.8	158.6	182.8	-36.1	33.9	-40.1	29.9	-167.4	-149.2	93.5	111.7	-114.9	-170.4	-117.9	161.2	143.0	-99.7	-96.7	108.7	164.3	-152.2
Story9	D41	A15.5	530	-3.45	0.00	-148.13	-8.65	1.68	-24.97	-0.4	-5.8	-178.9	-182.9	176.7	172.6	-191.2	-170.5	164.3	185.0	-31.1	28.9	-35.1	24.8	-165.3	-149.7	101.6	117.1	-120.3	-168.3	-123.4	159.1	143.5	-107.8	-104.8	114.1	162.1	-152.8
Story8	D41	A15.5	530	-3.47	0.00	-151.30	-6.02	1.66	-23.15	-0.5	-5.8	-182.7	-186.7	180.4	176.4	-194.3	-175.1	168.8	188.1	-28.9	26.7	-32.9	22.7	-166.0	-151.6	106.6	121.0	-124.3	-169.0	-127.3	159.7	145.3	-112.8	-109.8	118.0	162.7	-154.6
Story7	D41	A15.5	530	-3.42	0.00	-153.73	-7.43	1.53	-21.48	-0.6	-5.5	-185.7	-189.4	183.2	179.6	-196.5	-178.6	172.5	190.3	-27.0	24.5	-30.7	20.9	-166.2	-152.8	110.7	124.1	-127.5	-169.0	-130.3	160.1	146.7	-116.9	-114.1	121.4	162.8	-155.6
Story6	D41	A15.5	530	-3.45	0.00	-155.74	-6.94	1.52	-20.00	-0.7	-5.5	-188.2	-191.8	185.6	182.0	-198.3	-181.7	175.5	192.1	-25.4	22.8	-29.0	19.1	-166.3	-153.8	114.2	126.7	-130.2	-169.1	-132.9	160.1	147.6	-120.4	-117.7	124.0	162.9	-156.6
Story5	D41	A15.5	530	-3.47	0.00	-156.91	-6.46	1.53	-18.68	-0.7	-5.6	-189.6	-193.3	187.0	183.3	-199.2	-183.7	177.4	192.9	-23.7	21.1	-27.4	17.5	-165.7	-154.1	116.9	128.6	-132.1	-168.5	-134.8	159.5	147.9	-123.2	-120.4	125.8	162.2	-156.9
Story4	D41	A15.5	530	-3.49	0.00	-156.02	-5.96	1.54	-17.25	-0.7	-5.6	-188.5	-192.2	185.9	182.2	-197.5	-183.2	176.9	191.2	-22.0	19.4	-25.7	15.7	-163.2	-152.5	117.9	128.6	-132.1	-166.0	-134.9	156.9	146.2	-124.2	-121.4	125.8	159.7	-155.2
Story3	D41	A15.5	530	-3.44	0.00	-150.87	-5.48	1.45	-15.88	-0.8	-5.4	-182.4	-185.9	179.7	176.2	-190.7	-177.6	171.4	184.5	-20.4	17.7	-23.9	14.2	-156.9	-147.1	114.9	124.7	-128.3	-159.6	-130.9	150.7	140.9	-121.1	-118.5	122.1	153.4	-149.7
Story2	D41	A15.5	530	-3.47	0.00	-137.49	-4.93	1.48	-14.30	-0.8	-5.5	-166.3	-169.9	163.6	160.1	-174.0	-162.2	155.9	167.8	-18.5	15.8	-22.1	12.3	-143.0	-134.1	104.7	113.6	-117.2	-145.6	-119.9	136.7	127.8	-111.0	-108.3	111.0	139.4	-136.7
Story1	D41	A15.5	530	-3.56	0.00	-92.81	-3.64	1.64	-10.56	-0.2	-5.5	-112.2	-116.2	110.5	106.5	-118.6	-109.8	104.2	112.9	-13.5	11.8	-17.5	7.8	-97.8	-91.2	69.4	76.0	-78.7	-100.7	-81.7	92.1	85.5	-75.1	-72.2	73.0	95.0	-94.2
Ground	D41	A14	479	-3.58	0.00	2.23	-0.73	1.34	-2.12	-1.1	-5.4	1.1	-2.2	-4.3	-7.5	-1.4	0.3	-6.8	-5.0	-4.1	0.9	-7.4	-2.3	-2.6	-1.2	-6.6	-5.3	1.2	-5.0	-1.2	-3.9	-5.2	0.1	2.6	-7.7	-1.5	-3.7
B1	D41	A14	479	-3.46	0.00	2.68	-0.48	1.18	-1.40	-1.2	-5.0	1.5	-1.3	-4.9	-7.7	-0.5	0.7	-6.9	-5.8	-3.4	0.0	-6.2	-2.8	-1.3	-0.5	-6.2	-5.3	1.2	-3.5	-0.9	-4.9	-5.8	-0.1	2.1	-7.4	-2.8	-2.6
B2	D41	A14	479	-3.48	0.00	0.61	-0.25	1.17	-0.72	-1.3	-5.0	-1.0	-3.8	-2.5	-5.3	-2.7	-2.1	-4.2	-3.6	-2.6	-0.9	-5.4	-3.7	-2.4	-2.0	-3.5	-3.1	-1.1	-4.5	-3.2	-3.9	-4.3	-2.8	-0.7	-5.2	-1.8	-4.1
B3	D41	A14	479	-3.50	0.00	-2.10	-0.02	1.16	-0.05	-1.3	-5.0	-4.3	-7.1	0.8	-2.0	-5.7	-5.7	-0.6	-0.6	-1.8	-1.7	-4.6	-4.5	-4.1	-4.0	-0.3	-0.2	-4.0	-6.2	-6.1	-2.2	-2.3	-6.0	-3.9	-2.3	-0.1	-6.1

Story	ETABS #	Section	Capacity	Dead	Live	WindFX	WindMTX	WindFY	WindMTY																								
Story40	D5	A7	239	-0.20	0.00	4.11	9.15	-0.01	26.30	-0.2	-0.2	4.7	4.8	-5.1	-5.1	15.7	-6.2	5.9	-16.1	31.4	-31.8	31.4	-31.7	35.5	19.0	28.1	11.6	-11.9	35.5	-11.9	-35.8	-19.3	-28.4	-28.4	11.6	-35.8	19.0
Story39	D5	A7	239	-0.27	0.00	8.38	9.49	0.02	27.27	-0.2	-0.3	9.8	9.8	-10.3	-10.3	21.2	-1.6	1.1	-21.7	32.5	-32.9	32.5	-33.0	40.4	23.3	25.3	8.2	-8.7	40.4	-8.7	-40.9	-23.8	-25.8	-25.8	8.2	-40.9	23.3
Story38	D5	A7	239	-0.33	0.00	12.63	9.79	0.05	28.13	-0.2	-0.4	14.9	14.8	-15.4	-15.5	26.6	3.1	-3.7	-27.2	33.5	-34.0	33.4	-34.1	45.3	27.7	22.5	4.9	-5.4	45.2	-5.5	-45.9	-28.3	-23.1	-23.0	4.8	-45.8	27.6
Story37	D5	A8	274	-0.04	0.00	16.08	11.52	0.02	33.09	0.0	-0.1	19.3	19.2	-19.3	-19.4	33.1	5.4	-5.5	-33.1	39.7	-39.7	39.6	-39.8	54.6	33.9	25.7	4.9	-5.0	54.6	-5.0	-54.7	-34.0	-25.8	-25.7	4.9	-54.7	33.9
Story36	D5	A8	274	-0.11	0.00	20.02	11.93	-0.12	34.27	-0.3	0.1	23.8	23.8	-24.3	-24.0	38.2	9.6	-9.8	-38.4	40.9	-41.4	41.2	-41.5	59.4	38.0	23.4	1.9	-2.3	59.7	-2.1	-59.6	-38.1	-23.6	-23.8	2.1	-59.9	38.2
Story35	D5	A8	274	-0.16	0.00	23.55	12.12	-0.42	34.82	-0.8	0.5	27.6	28.6	-28.9	-27.9	42.6	13.6	-13.9	-42.9	41.1	-42.4	42.1	-41.4	63.0	41.1	20.5	-1.3	0.2	63.7	1.0	-63.3	-41.4	-20.8	-21.6	-0.5	-64.0	41.9
Story34	D5	A10	342	0.53	0.00	27.33	15.30	-1.01	43.97	-1.2	2.1	32.1	34.5	-33.5	-31.1	51.6	14.9	-14.0	-50.7	52.0	-53.5	54.5	-51.1	77.6	50.0	28.3	0.8	-1.6	79.4	0.2	-76.6	-49.1	-27.4	-29.2	2.6	-78.5	51.8
Story33	D5	A10	342	0.59	0.00	30.57	15.58	-1.49	44.78	-1.9	2.9	35.4	39.0	-37.9	-34.4	55.9	18.5	-17.5	-54.9	52.5	-55.0	56.1	-51.4	81.1	53.0	26.0	-2.0	0.4	83.8	3.1	-80.0	-52.0	-25.0	-27.7	0.6	-82.7	55.7
Story32	D5	A10	342	0.60	0.00	34.42	15.80	-1.98	45.41	-2.6	3.7	39.5	44.2	-43.1	-38.4	60.8	22.9	-21.8	-59.7	52.6	-56.3	57.4	-51.6	84.9	56.4	22.9	-5.6	3.1	88.5	6.7	-83.8	-55.4	-21.8	-25.4	-2.0	-87.4	60.0
Story31	D5	A10	342	0.73	0.00	37.24	15.75	-2.59	45.26	-3.5	4.8	42.2	48.5	-47.1	-40.9	64.2	26.5	-25.1	-62.9	51.9	-58.6	58.1	-50.5	86.8	58.5	19.7	-8.6	5.3	91.5	9.9	-85.5	-57.1	-18.4	-23.1	-4.0	-90.2	63.1
Story30	D5	A13.5	462	2.15	0.00	47.30	21.11	-4.46	60.69	-5.2	9.1	53.3	64.0	-60.2	-49.5	84.0	33.4	-29.5	-80.2	64.4	-76.2	80.1	-65.5	114.2	76.2	29.0	-9.0	-4.9	122.2	12.9	-110.3	-72.3	-25.1	-33.2	-1.0	-118.4	84.2
Story29	D5	A13.5	462	2.32	0.00	50.40	21.21	-5.41	60.98	-6.6	10.7	56.1	69.1	-64.9	-51.9	88.0	37.1	-32.9	-83.8	68.8	-77.6	81.8	-64.6	116.7	78.4	25.9	-12.4	6.8	126.4	16.5	-112.5	-74.3	-21.7	-31.4	-2.6	-122.2	88.2
Story28	D5	A13.5	462	2.48	0.00	54.64	21.19	-6.51	60.94	-8.2	12.6	60.0	75.6	-71.2	-55.5	93.2	42.4	-37.9	-88.8	67.5	-78.7	83.2	-63.1	119.6	81.4	21.1	-17.1	9.8	131.3	21.5	-115.1	-76.9	-16.7	-28.4	-5.3	-126.8	93.1
Story27	D5	A13.5	462	2.73	0.00	58.75	20.69	-7.76	59.52	-10.0	14.9	63.6	82.3	-77.4	-58.7	97.8	48.1	-43.2	-92.9	64.6	-78.3	83.2	-59.7	120.6	83.4	14.8	-22.5	13.4	134.6	27.4	-115.7	-78.5	-9.9	-23.9	-8.5	-129.7	97.4
Story26	D5	A13.5	462	2.93	0.00	61.38	20.53	-9.10	59.05	-11.9	17.2	65.4	87.2	-81.9	-60.1	100.9	51.7	-46.4	-95.7	62.6	-79.1	84.4	-57.3	121.4	84.4	10.8	-26.1	15.0	137.8	31.4	-116.1	-79.2	-5.6	-21.9	-9.8	-132.5	100.8
Story25	D5	A15.5	530	3.75	0.00	67.81	23.30	-11.09	67.04	-14.4	21.1	71.4	98.1	-91.3	-64.7	112.7	56.8	-50.0	-106.0	70.5	-90.4	97.1	-63.8	135.8	93.9	13.7	-28.3	15.1	155.8	35.1	-129.1	-87.1	-6.9	-26.9	-8.3	-149.1	113.9
Story24	D5	A15.5	530	3.68	0.00	70.49	23.02	-11.77	66.25	-15.5	22.2	73.8	102.0	-95.4	-67.1	115.5	60.3	-53.6	-108.9	68.7	-90.3	96.9	-62.1	136.6	95.1	9.6	-31.8	17.3	157.8	38.5	-130.0	-88.5	-3.0	-24.2	-10.6	-151.2	116.4
Story23	D5	A15.5	530	3.28	0.00	74.29	22.55	-11.22	64.89	-15.0	20.9	78.6	105.6	-99.7	-72.7	119.1	65.0	-59.1	-113.3	67.4	-88.4	94.3	-61.5	138.5	97.9	4.7	-35.9	21.6	158.7	41.8	-132.6	-92.0	1.2	-19.0	-15.7	-152.8	118.1
Story22	D5	A15.5	530	2.85	0.00	78.25	22.20	-10.68	63.90	-14.5	19.7	83.7	109.3	-104.1	-78.5	123.1	69.8	-64.7	-118.0	66.4	-86.9	92.1	-61.3	141.0	101.0	0.0	-40.0	25.9	160.2	45.1	-135.9	-95.9	5.1	-14.1	-20.7	-155.1	120.2
Story21	D5	A15.5	530	2.37	0.00	81.96	21.89	-9.61	63.01	-13.2	17.5	88.9	112.0	-107.7	-84.7	126.7	74.2	-70.0	-122.5	66.2	-85.0	89.3	-61.9	143.8	104.3	-3.9	-43.3	30.3	161.1	47.6	-139.5	-100.1	8.1	-9.2	-26.0	-156.8	121.7
Story20	D5	A15.5	530	1.82	0.00	85.63	21.41	-8.30	61.65	-11.6	14.9	94.4	114.3	-111.1	-91.2	130.1	78.7	-75.4	-126.8	65.7	-82.3	85.6	-62.4	146.1	107.5	-8.1	-46.7	35.0	161.1	50.0	-142.8	-104.3	11.4	-3.5	-31.8	-157.8	122.5
Story19	D5	A15.5	530	1.26	0.00	89.34	20.51	-6.87	59.08	-9.9	12.1	100.1	116.6	-114.3	-97.8	133.0	83.7	-81.5	-130.7	63.8	-78.0	80.3	-61.5	147.1	110.2	-13.8	-50.8	40.7	159.5	53.1	-144.8	-107.9	16.1	3.7	-38.4	-157.2	122.5
Story18	D5	A15.5	530	0.71	0.00	93.11	19.90	-5.31	57.31	-7.9	9.1	106.0	118.7	-117.5	-104.7	136.2	88.5	-87.2	-135.0	63.0	-74.5	75.8	-61.8	149.3	113.4	-18.5	-54.3	46.0	158.8	55.6	-148.0	-112.2	19.7	10.2	-44.7	-157.6	123.0
Story17	D5	A15.5	530	0.34	0.00	96.78	19.34	-4.18	55.72	-6.4	7.0	111.4	121.5	-120.8	-110.8	139.6	93.2	-92.6	-139.0	62.1	-71.6	72.2	-61.5	151.3	116.5	-23.0	-57.9	50.9	158.9	58.5	-150.7	-115.9	23.6	16.1	-50.3	-158.2	124.0
Story16	D5	A15.5	530	-0.11	0.00	100.52	18.74	-2.74	54.01	-4.5	4.3	117.2	123.8	-124.0	-117.4	143.0	98.0	-98.2	-143.2	61.4	-68.2	68.0	-61.6	153.5	119.7	-27.6	-61.3	56.2	158.4	61.1	-153.7	-119.9	27.4	22.4	-56.4	-158.6	124.7
Story15	D5	A15.5	530	-0.08	0.00	104.31	18.11	-2.86	52.21	-4.7	4.5	121

SIMPSON GUMPERTZ & HEGER
Engineering of Structures and Building Enclosures

CLIENT Pacific Earthquake Engineering Research Center
SUBJECT BRB Strength Check along Line D for LA BRBF Bldg

SHEET NO.
PROJECT NO. 087237.10
DATE 1/23/09
BY AD
CHECKED BY

Story	ETABS #	Section	Capacity	Dead	Live	WindFX	WindMTX	WindFY	WindMTY																							Maximum Axial Loads Tension	Compression	DCR	Status
Story40	D41	A7	239	-3.09	0.00	-6.79	-10.17	0.00	-29.22	20.5	-32.1	160.8	119.2	-120.8	34.7	-43.5	112.0	-169.7	-128.0	163.2	121.6	-118.5	37.0	-41.2	114.4	-167.3	-125.7	163.18	-169.66	0.71	OK
Story39	D41	A7	239	-3.13	0.00	-11.11	-10.47	0.02	-30.08	24.9	-29.4	173.6	125.5	-132.1	33.8	-42.7	123.1	-182.5	-134.4	175.9	127.8	-129.7	36.2	-40.4	125.5	-180.1	-132.0	175.94	-182.51	0.76	OK
Story38	D41	A7	239	-3.17	0.00	-15.41	-10.69	0.06	-30.71	29.1	-26.3	204.7	136.4	-162.2	26.3	-35.4	153.2	-213.8	-145.5	207.1	138.8	-159.8	28.7	-33.0	155.6	-211.4	-143.1	207.12	-213.77	0.89	OK
Story37	D41	A10	342	-3.30	0.00	-24.09	-15.53	0.12	-44.62	45.0	-35.6	281.3	194.4	-216.0	45.2	-54.6	206.6	-290.7	-203.8	283.8	196.9	-213.5	47.7	-52.1	209.1	-288.2	-201.3	283.79	-290.72	0.85	OK
Story36	D41	A10	342	-3.34	0.00	-29.16	-15.95	0.19	-45.85	50.4	-32.6	299.0	202.9	-231.7	43.7	-53.2	222.2	-308.6	-212.4	301.5	205.4	-229.2	46.2	-50.7	224.7	-306.0	-209.9	301.54	-308.56	0.90	OK
Story35	D41	A10	342	-3.38	0.00	-33.81	-16.18	0.28	-46.49	55.0	-29.3	308.5	206.9	-240.5	42.2	-51.9	230.8	-318.1	-216.6	311.0	209.5	-237.9	44.8	-49.3	233.4	-315.6	-214.0	311.02	-318.12	0.93	OK
Story34	D41	A13.5	462	-3.49	0.00	-43.20	-22.04	0.41	-63.36	73.4	-41.5	378.1	270.0	-282.6	71.8	-81.7	272.6	-388.1	-280.0	380.8	272.6	-280.0	74.4	-79.1	275.3	-385.5	-277.3	380.79	-388.11	0.84	OK
Story33	D41	A13.5	462	-3.44	0.00	-48.24	-22.57	0.46	-64.88	78.9	-38.8	390.8	277.1	-293.0	72.0	-81.8	283.2	-400.7	-287.0	393.4	279.7	-290.4	74.6	-79.2	285.8	-398.1	-284.3	393.45	-400.67	0.87	OK
Story32	D41	A13.5	462	-3.47	0.00	-54.47	-23.14	0.59	-66.51	85.5	-35.3	402.4	284.6	-302.0	73.2	-83.1	292.1	-412.4	-294.5	405.1	287.2	-299.4	75.8	-80.5	294.8	-409.7	-291.9	405.06	-412.36	0.89	OK
Story31	D41	A13.5	462	-3.39	0.00	-59.24	-23.37	0.53	-67.19	90.3	-31.7	410.1	288.1	-308.7	72.4	-82.1	299.1	-419.8	-297.7	412.7	290.6	-306.2	75.0	-79.5	301.6	-417.2	-295.2	412.68	-419.79	0.91	OK
Story30	D41	A13.5	462	-3.42	0.00	-57.57	-23.67	0.66	-68.05	89.4	-34.4	390.7	284.1	-288.2	80.4	-90.2	278.4	-400.5	-293.8	393.3	286.7	-285.6	83.0	-87.6	281.0	-397.9	-291.3	393.28	-400.46	0.87	OK
Story29	D41	A13.5	462	-3.37	0.00	-61.60	-24.07	0.68	-69.21	93.7	-32.2	396.6	288.3	-292.4	81.6	-91.3	282.7	-406.2	-298.0	399.2	290.9	-289.8	84.2	-88.7	285.3	-403.7	-295.4	399.17	-406.25	0.88	OK
Story28	D41	A13.5	462	-3.40	0.00	-66.64	-24.29	0.80	-69.86	98.7	-28.6	405.2	292.3	-300.1	80.7	-90.4	290.4	-414.9	-302.0	407.8	294.8	-297.6	83.2	-87.8	293.0	-412.3	-299.4	407.79	-414.92	0.90	OK
Story27	D41	A13.5	462	-3.32	0.00	-71.16	-23.95	0.73	-68.89	102.3	-23.2	408.9	290.5	-305.5	76.2	-85.7	296.0	-418.4	-300.0	411.4	293.0	-303.0	78.7	-83.2	298.5	-415.8	-297.5	411.38	-418.36	0.91	OK
Story26	D41	A13.5	462	-3.35	0.00	-74.10	-23.91	0.82	-68.79	104.9	-20.5	408.6	289.9	-305.6	75.7	-85.3	296.0	-418.1	-299.5	411.1	292.5	-303.0	78.2	-82.7	298.5	-415.6	-297.0	411.10	-418.13	0.91	OK
Story25	D41	A15.5	530	-3.40	0.00	-83.01	-27.27	0.93	-78.47	118.7	-24.4	451.0	326.2	-332.6	91.1	-100.8	322.9	-460.8	-335.9	453.6	328.8	-330.1	93.7	-98.3	325.5	-458.2	-333.4	453.62	-460.75	0.87	OK
Story24	D41	A15.5	530	-3.42	0.00	-86.23	-27.05	1.03	-77.85	121.3	-20.8	450.4	324.3	-333.2	89.2	-99.0	323.4	-460.1	-334.0	453.0	326.8	-330.6	91.8	-96.4	326.0	-457.6	-331.4	452.96	-460.15	0.87	OK
Story23	D41	A15.5	530	-3.44	0.00	-90.97	-26.56	1.13	-76.45	124.8	-15.0	452.3	321.2	-337.5	84.3	-94.2	327.6	-462.1	-331.1	454.9	323.9	-334.9	86.9	-91.6	330.2	-459.5	-328.5	454.87	-462.10	0.87	OK
Story22	D41	A15.5	530	-3.47	0.00	-95.85	-26.17	1.24	-75.34	128.6	-9.3	454.9	319.2	-342.1	80.1	-90.0	332.2	-464.8	-329.1	457.6	321.8	-339.5	82.7	-87.4	334.8	-462.2	-326.5	457.56	-464.84	0.88	OK
Story21	D41	A15.5	530	-3.42	0.00	-100.55	-25.78	1.21	-74.22	132.2	-3.7	458.3	317.2	-347.3	75.6	-85.3	337.5	-468.0	-327.0	460.8	319.8	-344.7	78.2	-82.7	340.1	-465.4	-324.4	460.85	-468.03	0.88	OK
Story20	D41	A15.5	530	-3.44	0.00	-105.24	-25.19	1.32	-72.54	135.5	2.5	460.0	313.6	-351.8	70.0	-79.9	342.0	-469.8	-323.4	462.6	316.2	-349.2	72.6	-77.3	344.6	-467.2	-320.8	462.59	-469.82	0.89	OK
Story19	D41	A15.5	530	-3.47	0.00	-109.95	-24.15	1.43	-69.55	138.1	10.2	459.0	306.0	-355.6	61.6	-71.5	345.7	-468.9	-315.9	461.6	308.6	-353.0	64.3	-68.9	348.3	-466.3	-313.3	461.61	-468.89	0.88	OK
Story18	D41	A15.5	530	-3.49	0.00	-114.69	-23.36	1.54	-67.29	141.1	17.1	460.3	300.9	-360.6	54.6	-64.6	350.6	-470.2	-310.9	462.9	303.5	-357.9	57.3	-62.0	353.2	-467.6	-308.2	462.90	-470.23	0.89	OK
Story17	D41	A15.5	530	-3.44	0.00	-119.06	-22.64	1.48	-65.22	143.9	23.7	461.6	296.2	-365.2	48.1	-58.0	355.3	-471.4	-306.0	464.2	298.8	-362.6	50.7	-55.4	357.9	-468.8	-303.4	464.17	-471.39	0.89	OK
Story16	D41	A15.5	530	-3.46	0.00	-123.51	-21.85	1.59	-62.95	146.6	30.3	462.5	290.9	-369.7	41.2	-51.1	359.9	-472.3	-300.8	465.1	293.5	-367.1	43.8	-48.5	362.5	-469.7	-298.2	465.08	-472.35	0.89	OK
Story15	D41	A15.5	530	-3.38	0.00	-127.28	-21.08	1.41	-60.76	148.6	36.6	463.0	285.6	-373.7	34.5	-44.2	364.1	-472.7	-295.2	465.6	288.1	-371.2	37.1	-41.6	366.6	-470.1	-292.7	465.56	-472.66	0.89	OK
Story14	D41	A15.5	530	-3.40	0.00	-131.03	-20.25	1.51	-58.37	150.7	42.8	463.4	279.9	-378.0	27.5	-37.2	368.2	-473.1	-289.6	466.0	282.5	-375.4	30.1	-34.7	370.8	-470.5	-287.1	465.98	-473.12	0.89	OK
Story13	D41	A15.5	530	-3.43	0.00	-134.71	-19.24	1.60	-55.47	152.3	49.5	462.7	272.7	-381.9	19.3	-29.1	372.1	-472.5	-282.5	465.3	275.3	-379.3	21.9	-26.5	374.7	-469.9	-279.9	465.28	-472.47	0.89	OK
Story12	D41	A15.5	530	-3.45	0.00	-138.33	-17.78	1.70	-51.30	153.2	57.7	459.0	261.5	-384.9	8.4	-18.2	375.0	-468.8	-271.4	461.6	264.2	-382.3	11.0	-15.6	377.7	-466.2	-268.8	461.59	-468.83	0.88	OK
Story11	D41	A15.5	530	-3.40	0.00	-141.58	-15.17	1.63	-43.77	151.7	69.9	448.6	239.5	-384.5	-4.9	0.1	374.8	-456.3	-249.2	449.2	242.1	-382.0	-2.3	2.7	377.4	-453.8	-246.6	449.20	-456.35	0.86	OK
Story10	D41	A15.5	530	-3.43	0.00	-144.84	-10.10	1.68	-29.17	146.1	90.5	416.7	194.8	-378.2	-43.7	33.9	368.4	-426.5	-204.6	419.3	197.4	-375.6	-41.1	36.5	371.0	-423.9	-202.0	419.30	-426.50	0.80	OK
Story9	D41	A15.5	530	-3.45	0.00	-148.13	-8.65	1.68	-24.97	146.5	98.5	413.6	183.6	-382.0	-55.1	45.2	372.1	-423.5	-193.5	416.3	186.2	-379.4	-52.5	47.9	374.7	-420.9	-190.8	416.25	-423.50	0.80	OK
Story8	D41	A15.5	530	-3.47	0.00	-151.39	-8.02	1.66	-23.15	148.3	103.6	416.9	180.1	-388.3	-61.4	51.5	378.3	-426.9	-190.1	419.6	182.8	-385.6	-58.8	54.1	381.0	-424.2	-187.4	419.56	-426.85	0.81	OK
Story7	D41	A15.5	530	-3.42	0.00	-153.73	-7.43	1.53	-21.48	149.4	108.0	419.9	176.9	-393.9	-67.2	57.4	384.1	-429.7	-186.7	422.5	179.5	-391.3	-64.6	60.0	386.7	-427.1	-184.1	422.53	-429.72	0.81	OK
Story6	D41	A15.5	530	-3.45	0.00	-155.74	-6.94	1.52	-20.06	150.4	111.5	423.2	174.4	-399.4	-72.3	62.5	389.6	-433.0	-184.3	425.8	177.1	-396.8	-69.7	65.1	392.2	-430.4	-181.7	425.79	-433.03	0.82	OK
Story5	D41	A15.5	530	-3.47	0.00	-156.91	-6.46	1.53	-18.68	150.8	114.2	425.2	171.7	-403.8	-77.0	67.1	393.9	-435.2	-181.6	427.9	174.3	-401.1	-74.4	69.7	396.5	-432.5	-179.0	427.87	-435.15	0.82	OK
Story4	D41	A15.5	530	-3.49	0.00	-156.02	-5.96	1.54	-17.25	149.0	115.1	422.2	167.3	-403.1	-80.3	70.3	393.1	-432.2	-177.3	424.9	169.9	-400.5	-77.7	73.0	395.8	-429.6	-174.6	424.87	-432.20	0.82	OK
Story3	D41	A15.5	530	-3.44	0.00	-150.87	-5.48	1.45	-15.88	143.5	112.3	408.8	159.9	-391.8	-80.3	70.4	382.0	-418.7	-169.8	411.5	162.5	-389.2	-77.7	73.0	384.6	-416.1	-167.2	411.46	-418.69	0.79	OK
Story2	D41	A15.5	530	-3.47	0.00	-137.49	-4.93	1.48	-14.30	130.5	102.1	373.9	145.6	-359.5	-74.4	64.5	349.6	-383.8	-155.5	376.6	148.2	-356.9	-71.8	67.2	352.2	-381.2	-152.9	376.56	-383.84	0.72	OK
Story1	D41	A15.5	530	-3.16	0.00	-92.81	-3.64	1.64	-10.56	88.5	66.5	257.0	101.6	-247.8	-49.8	40.8	238.7	-266.0	-110.6	259.4	104.0	-245.4	-47.4	43.2	241.1	-263.6	-108.2	259.38	-266.02	0.50	OK
Ground	D41	A14	479	-3.58	0.00	2.23	-0.73	1.34	-2.12	-2.8	-9.0	17.6	8.0	23.7	-4.4	-5.8	13.5	-27.9	-18.2	20.3	10.7	-21.0	-1.7	-3.1	16.2	-25.1	-15.5	20.34	-27.86	0.08	OK
B1	D41	A14	479	-3.46	0.00	2.68	-0.48	1.18	-1.40	-3.6	-8.3	13.7	5.0	-20.7	-5.3	-4.6	10.8	-23.6	-14.9	16.3	7.6	-18.1	-2.7	-2.0	13.5	-21.0	-12.3	16.34	-23.61	0.05	OK
B2	D41	A14	479	-3.48	0.00	0.61	-0.25	1.17	-0.72	-2.2	-5.6	7.9	1.6	-16.1	-5.6	-4.3	6.1	-17.8	-11.5	10.5	4.2	-13.4	-3.0	-1.7	8.8	-15.2	-8.9	10.54	-17.85	0.04	OK
B3	D41	A14	479	-3.50	0.00	-2.10	-0.02	1.16	-0.05	-0.2	-2.4	6.4	-0.6	-15.7	-7.2	-2.8	5.7	-16.4	-9.4	9.0	2.1	-13.0	-4.5	-0.2	8.3	-13.7	-6.8	9.03	-16.38	0.03	OK

Story	ETABS #	Section	Capacity	Dead	Live	WindFX	WindMTX	WindFY	WindMTY																							Maximum Axial Loads Tension	Compression	DCR	Status
Story40	D5	A7	239	-0.20	0.00	4.11	9.15	-0.01	26.30	-19.3	28.1	148.7	113.1	-104.0	37.2	-37.8	103.4	-149.3	-113.6	148.9	113.2	-103.9	37.4	-37.7	103.6	-149.1	-113.5	148.85	-149.27	0.62	OK
Story39	D5	A7	239	-0.27	0.00	8.38	9.49	0.02	27.27	-23.8	25.3	159.3	118.9	-112.9	37.3	-38.0	112.2	-160.0	-119.7	159.5	119.1	-112.7	37.5	-37.8	112.4	-159.8	-119.5	159.45	-160.01	0.67	OK
Story38	D5	A7	239	-0.33	0.00	12.63	9.79	0.05	28.13	-28.2	22.4	192.5	131.2	-144.8	30.0	-31.0	143.8	-193.4	-132.2	192.7	131.5	-144.5	30.3	-30.7	144.1	-193.2	-131.9	192.73	-193.43	0.81	OK
Story37	D5	A8	274	-0.04	0.00	16.08	11.52	0.02	33.09	-33.9	25.6	211.8	150.1	-154.8	40.1	-40.2	154.7	-212.0	-150.2	211.9	150.2	-154.8	40.2	-40.2	154.8	-211.9	-150.2	211.87	-211.96	0.77	OK
Story36	D5	A8	274	-0.11	0.00	20.02	11.93	-0.12	34.27	-38.4	23.6	227.3	157.5	-168.6	38.8	-39.1	168.3	-227.6	-157.9	227.4	157.6	-168.5	39.9	-39.0	168.4	-227.5	-157.8	227.38	-227.60	0.83	OK
Story35	D5	A8	274	-0.16	0.00	23.55	12.12	-0.42	34.82	-42.2	21.3	235.4	160.5	-176.5	36.9	-37.4	176.0	-235.8	-160.9	235.5	160.6	-176.4	37.0	-37.3	176.1	-235.7	-160.8	235.49	-235.83	0.86	OK
Story34	D5	A10	342	0.53	0.00	27.33	15.30	-1.01	43.97	-50.9	30.2	266.6	193.4	-190.7	56.2	-54.7	192.2	-265.1	-191.9	266.2	193.0	-191.1	55.8	-55.1	191.8	-265.5	-192.3	266.60	-265.50	0.78	OK
Story33	D5	A10	342	0.59	0.00	30.57	15.58	-1.49	44.79	-54.7	28.7	275.1	197.4	-198.1	55.4	-53.7	199.8	-273.4	-195.7	274.6	196.9	-198.5	55.0	-54.2	199.3	-273.9	-196.1	275.10	-273.86	0.80	OK
Story32	D5	A10	342	0.60	0.00	34.42	15.80	-1.98	45.41	-58.9	26.5	280.3	200.4	-202.3	55.6	-53.8	204.0	-278.6	-198.6	279.9	199.9	-202.8	55.1	-54.3	203.6	-279.1	-199.1	280.31	-279.05	0.82	OK
Story31	D5	A10	342	0.73	0.00	37.24	15.75	-2.59	45.26	-61.8	24.4	282.4	200.7	-204.3	54.7	-52.6	206.4	-280.3	-198.6	281.8	200.1	-204.9	54.1	-53.1	205.9	-280.9	-199.2	282.40	-280.86	0.83	OK
Story30	D5	A13.5	462	2.15	0.00	47.30	21.11	-4.46	60.69	-80.3	37.0	356.1	263.8	-247.9	62.5	-76.4	254.1	-350.0	-257.6	354.5	262.1	-249.6	80.9	-78.0	252.4	-351.6	-259.2	356.13	-351.61	0.77	OK
Story29	D5	A13.5	462	2.32	0.00	50.40	21.21	-5.41	60.98	-84.0	35.6	357.6	265.6	-248.1	83.9	-77.3	254.7	-351.0	-259.0	355.8	263.8	-249.9	82.1	-79.0	253.0	-352.7	-260.7	357.59	-352.71	0.77	OK
Story28	D5	A13.5	462	2.48	0.00	54.64	21.19	-6.51	60.94	-88.7	32.9	363.3	268.0	-252.9	83.2	-76.1	260.0	-356.2	-260.9	361.4	266.1	-254.8	81.3	-78.0	258.1	-358.1	-262.8	363.26	-358.06	0.79	OK
Story27	D5	A13.5	462	2.73	0.00	58.75	20.69	-7.76	59.52	-92.4	28.8	365.9	266.5	-256.5	79.8	-72.0	264.3	-358.1	-258.7	363.8	264.5	-258.6	77.7	-74.1	262.3	-360.2	-260.8	365.89	-360.15	0.79	OK
Story26	D5	A13.5	462	2.93	0.00	61.38	20.53	-9.10	59.05	-95.5	27.2	365.1	266.3	-255.2	80.3	-71.9	263.6	-356.7	-258.0	362.8	264.1	-257.4	78.0	-74.1	261.4	-358.9	-260.2	365.05	-358.90	0.79	OK
Story25	D5	A15.5	530	3.75	0.00	67.81	23.30	-11.09	67.04	-107.1	33.7	399.4	298.5	-273.4	96.6	-85.9	284.1	-388.7	-287.7	396.6	295.6	-276.2	93.8	-88.7	281.3	-391.5	-290.6	399.42	-391.54	0.75	OK
Story24	D5	A15.5	530	3.68	0.00	70.49	23.02	-11.77	66.25	-109.7	30.8	397.5	296.0	-272.9	94.9	-84.4	283.4	-387.0	-285.5	394.7	293.2	-275.7	92.1	-87.1	280.6	-389.8	-288.3	397.53	-389.79	0.75	OK
Story23	D5	A15.5	530	3.28	0.00	74.29	22.55	-11.22	64.89	-112.2	24.9	396.7	291.0	-276.1	89.1	-79.8	285.5	-387.4	-281.6	394.2	288.5	-278.6	86.6	-82.3	283.0	-389.8	-284.1	396.72	-389.84	0.75	OK
Story22	D5	A15.5	530	2.85	0.00	78.25	22.20	-10.68	63.90	-115.1	19.3	397.0	287.3	-279.9	84.2	-76.1	288.0	-388.9	-279.1	394.9	285.1	-282.0	82.1	-78.2	285.9	-391.1	-281.3	397.04	-391.05	0.75	OK
Story21	D5	A15.5	530	2.37	0.00	81.96	21.89	-9.61	63.01	-117.4	13.4	397.9	283.7	-284.4	79.0	-72.2	291.2	-391.2	-276.9	396.2	281.9	-286.2	77.2	-74.0	289.4	-393.0	-278.7	397.95	-392.97	0.75	OK
Story20	D5	A15.5	530	1.82	0.00	85.63	21.41	-8.30	61.65	-119.2	6.8	397.4	278.5	-288.3	72.8	-67.6	293.5	-392.2	-273.3	396.0	277.1	-289.7	71.4	-69.0	292.2	-393.6	-274.7	397.39	-393.57	0.75	OK
Story19	D5	A15.5	530	1.26	0.00	89.34	20.51	-6.87	59.08	-120.3	-1.5	394.5	269.9	-291.7	64.1	-60.5	295.4	-390.9	-266.3	393.5	269.0	-292.7	63.1	-61.4	294.4	-391.8	-267.3	394.48	-391.82	0.74	OK
Story18	D5	A15.5	530	0.71	0.00	93.11	19.90	-5.31	57.31	-121.7	-8.9	394.2	264.4	-296.3	57.2	-55.2	298.4	-392.2	-262.4	393.7	263.8	-296.9	56.7	-55.7	297.8	-392.7	-262.9	394.22	-392.74	0.74	OK
Story17	D5	A15.5	530	0.34	0.00	96.78	19.34	-4.18	55.72	-123.4	-15.5	394.9	260.1	-300.8	51.4	-50.4	301.7	-393.9	-259.1	394.6	259.8	-301.0	51.1	-50.7	301.5	-394.2	-259.4	394.88	-394.16	0.74	OK
Story16	D5	A15.5	530	-0.11	0.00	100.52	18.74	-2.74	54.01	-124.9	-22.6	395.3	255.5	-305.2	45.4	-45.7	304.9	-395.6	-255.8	395.4	255.6	-305.1	45.4	-45.6	305.0	-395.5	-255.7	395.36	-395.58	0.75	OK
Story15	D5	A15.5	530	-0.08	0.00	104.31	18.11	-2.86	52.21	-127.3	-28.1	397.1	251.6	-309.9	39.6	-39.8	309.7	-397.3	-251.9	397.1	251.7	-309.8	39.6	-39.7	309.7	-397.3	-251.8	397.15	-397.32	0.75	OK
Story14	D5	A15.5	530	-0.16	0.00	108.12	17.45	-2.69	50.30	-129.6	-34.1	398.8	247.4	-315.0	33.2	-33.7	314.5	-399.3	-247.9	399.0	247.5	-314.8	33.4	-33.6	314.6	-399.2	-247.7	398.96	-399.30	0.75	OK
Story13	D5	A15.5	530	-0.26	0.00	111.97	16.63	-2.42	47.95	-131.5	-40.7	399.8	241.7	-320.0	25.8	-26.6	319.3	-400.5	-242.5	400.0	241.9	-319.8	26.0	-26.4	319.5	-400.3	-242.3	399.96	-400.51	0.76	OK
Story12	D5	A15.5	530	-0.38	0.00	115.87	15.39	-2.05	44.39	-132.7	-49.0	398.0	232.3	-324.4	15.6	-16.7	323.3	-399.1	-233.4	398.3	232.6	-324.1	15.9	-16.4	323.6	-398.8	-233.1	398.33	-399.13	0.75	OK
Story11	D5	A15.5	530	-0.39	0.00	119.62	12.98	-1.96	37.44	-131.9	-60.9	388.1	212.2	-325.8	-2.0	0.9	324.7	-389.2	-213.3	388.4	212.5	-325.5	-1.7	1.2	325.0	-388.9	-213.0	388.36	-389.18	0.73	OK
Story10	D5	A15.5	530	-0.49	0.00	123.49	8.12	-1.73	23.46	-127.0	-81.7	360.7	169.4	-321.4	-35.2	33.8	320.0	-362.1	-170.8	361.1	169.8	-321.1	-34.9	34.2	320.4	-361.7	-170.4	361.09	-362.12	0.68	OK
Story9	D5	A15.5	530	-0.95	0.00	126.97	6.91	-0.32	19.97	-127.3	-90.7	359.3	159.8	-327.1	-46.1	43.4	324.4	-362.1	-162.6	360.1	160.6	-326.4	-45.4	44.1	325.1	-361.3	-161.8	360.05	-362.05	0.68	OK
Story8	D5	A15.5	530	-1.48	0.00	130.39	6.52	1.07	18.83	-128.9	-96.9	364.5	158.2	-335.5	-51.8	47.6	331.3	-368.7	-162.4	365.6	159.3	-334.4	-50.7	48.7	332.4	-367.6	-161.3	365.59	-368.69	0.70	OK
Story7	D5	A15.5	530	-1.54	0.00	133.95	6.09	0.87	17.60	-131.6	-101.5	370.8	156.8	-344.2	-57.8	53.4	339.8	-375.2	-161.1	372.0	157.9	-343.0	-56.6	54.5	341.0	-374.0	-160.0	371.98	-375.21	0.71	OK
Story6	D5	A15.5	530	-1.65	0.00	137.32	5.75	0.74	16.62	-134.3	-105.7	377.9	156.1	-353.4	-63.3	58.6	348.6	-382.6	-160.8	379.2	157.3	-352.1	-62.0	59.8	349.9	-381.4	-159.6	379.16	-382.63	0.72	OK
Story5	D5	A15.5	530	-2.15	0.00	139.44	5.45	1.72	15.78	-135.3	-110.0	383.1	155.1	-361.3	-68.2	62.0	355.2	-389.3	-161.3	384.7	156.8	-359.7	-66.6	63.7	356.8	-387.6	-159.7	384.75	-389.27	0.73	OK
Story4	D5	A15.5	530	-2.72	0.00	139.64	5.14	2.78	14.89	-134.5	-112.7	383.6	152.7	-364.7	-71.8	64.0	357.0	-391.4	-160.5	385.6	154.8	-362.7	-69.7	66.1	359.0	-389.3	-158.4	385.64	-391.35	0.74	OK
Story3	D5	A15.5	530	-3.15	0.00	135.86	4.83	3.54	14.00	-130.3	-111.4	374.2	147.5	-357.9	-72.2	63.2	348.9	-383.2	-156.5	376.6	149.8	-355.5	-69.8	65.5	351.3	-380.8	-154.1	376.56	-383.17	0.72	OK
Story2	D5	A15.5	530	-3.69	0.00	124.02	4.46	4.48	12.92	-118.6	-103.4	343.7	135.5	-330.4	-66.7	56.2	319.9	-354.2	-146.0	346.5	138.3	-327.6	-64.0	59.0	322.7	-351.4	-143.2	346.49	-354.23	0.67	OK
Story1	D5	A15.5	530	-3.57	0.00	82.47	3.35	4.48	9.71	-79.2	-69.8	234.7	94.6	-226.5	-43.7	33.5	216.3	-244.

SIMPSON GUMPERTZ & HEGER
Engineering of Structures and Building Enclosures

CLIENT Pacific Earthquake Engineering Research Center
SUBJECT BRB Strength Check along Line D for LA BRBF Bldg

SHEET NO.
PROJECT NO. 087237.10
DATE 1/23/09
BY AD
CHECKED BY

Story	ETABS #	Section	Capacity	Dead	Live	WindFX	WindMTX	WindFY	WindMTY	SpecX	SpecY
Story40	D6	A7	239	-5.97	0.00	-4.11	-9.15	0.01	-26.30	404.04	251.77
Story39	D6	A7	239	-5.98	0.00	-8.39	-9.50	0.03	-27.29	435.68	261.40
Story38	D6	A7	239	-6.00	0.00	-12.67	-9.80	0.07	-28.16	540.06	269.07
Story37	D6	A8	274	-6.45	0.00	-16.14	-11.52	0.23	-33.11	587.86	314.17
Story36	D6	A8	274	-6.46	0.00	-20.14	-11.93	0.54	-34.29	635.53	322.97
Story35	D6	A8	274	-6.49	0.00	-23.72	-12.13	1.04	-34.85	661.97	324.91
Story34	D6	A10	342	-7.37	0.00	-27.57	-15.30	1.90	-43.98	735.47	410.83
Story33	D6	A10	342	-7.34	0.00	-30.84	-15.59	2.46	-44.80	760.81	419.31
Story32	D6	A10	342	-7.42	0.00	-34.77	-15.80	3.23	-45.42	776.90	427.56
Story31	D6	A10	342	-7.39	0.00	-37.56	-15.75	3.71	-45.26	782.54	427.08
Story30	D6	A13.5	462	-8.99	0.00	-47.70	-21.10	5.87	-60.67	970.70	574.02
Story29	D6	A13.5	462	-9.08	0.00	-50.80	-21.20	6.88	-60.95	972.93	579.00
Story28	D6	A13.5	462	-9.29	0.00	-55.11	-21.17	8.26	-60.88	990.05	582.23
Story27	D6	A13.5	462	-9.40	0.00	-59.17	-20.67	9.35	-59.45	999.11	572.04
Story26	D6	A13.5	462	-9.65	0.00	-61.86	-20.49	10.90	-58.96	995.95	572.18
Story25	D6	A15.5	530	-10.51	0.00	-68.28	-23.25	13.02	-66.90	1079.33	648.85
Story24	D6	A15.5	530	-10.49	0.00	-71.02	-22.97	13.93	-66.09	1075.76	642.56
Story23	D6	A15.5	530	-10.07	0.00	-74.79	-22.48	13.49	-64.71	1079.00	625.93
Story22	D6	A15.5	530	-9.70	0.00	-78.81	-22.13	13.17	-63.69	1085.73	613.61
Story21	D6	A15.5	530	-9.10	0.00	-82.48	-21.82	11.97	-62.81	1093.81	599.96
Story20	D6	A15.5	530	-8.60	0.00	-86.20	-21.34	10.86	-61.44	1099.42	583.16
Story19	D6	A15.5	530	-8.09	0.00	-89.97	-20.43	9.65	-58.85	1100.34	556.12
Story18	D6	A15.5	530	-7.58	0.00	-93.80	-19.81	8.31	-57.06	1107.44	536.54
Story17	D6	A15.5	530	-7.12	0.00	-97.46	-19.25	7.09	-55.47	1115.26	519.69
Story16	D6	A15.5	530	-6.72	0.00	-101.25	-18.65	5.85	-53.75	1123.19	502.26
Story15	D6	A15.5	530	-6.62	0.00	-105.01	-18.03	5.76	-51.95	1133.19	486.27
Story14	D6	A15.5	530	-6.59	0.00	-108.88	-17.35	5.77	-50.03	1144.26	469.27
Story13	D6	A15.5	530	-6.54	0.00	-112.79	-16.53	5.68	-47.66	1153.95	448.10
Story12	D6	A15.5	530	-6.47	0.00	-116.75	-15.28	5.49	-44.08	1158.40	415.91
Story11	D6	A15.5	530	-6.36	0.00	-120.48	-12.87	5.29	-37.15	1144.40	353.36
Story10	D6	A15.5	530	-6.31	0.00	-124.41	-8.02	5.16	-23.16	1093.98	227.29
Story9	D6	A15.5	530	-5.83	0.00	-127.81	-6.82	3.64	-19.69	1100.22	193.44
Story8	D6	A15.5	530	-5.35	0.00	-131.29	-6.42	2.22	-18.56	1122.13	181.35
Story7	D6	A15.5	530	-5.26	0.00	-134.96	-6.00	2.27	-17.36	1146.92	170.20
Story6	D6	A15.5	530	-5.19	0.00	-138.39	-5.66	2.40	-16.38	1173.18	161.12
Story5	D6	A15.5	530	-4.67	0.00	-140.41	-5.37	1.34	-15.54	1193.47	151.99
Story4	D6	A15.5	530	-4.15	0.00	-140.67	-5.06	0.30	-14.65	1199.85	142.76
Story3	D6	A15.5	530	-3.62	0.00	-136.87	-4.75	-0.62	-13.77	1173.72	134.17
Story2	D6	A15.5	530	-3.13	0.00	-125.09	-4.38	-1.52	-12.70	1081.48	124.34
Story1	D6	A15.5	530	-2.72	0.00	-83.92	-3.26	-1.07	-9.46	742.98	92.56
Ground	D6	A14	479	-3.05	0.00	8.19	-0.51	-1.04	-1.46	83.05	17.47
B1	D6	A14	479	-3.15	0.00	6.43	-0.33	-0.35	-0.94	66.53	11.00
B2	D6	A14	479	-3.33	0.00	2.17	-0.15	0.44	-0.44	38.95	5.88
B3	D6	A14	479	-3.50	0.00	-2.71	0.01	1.24	0.04	36.60	3.43

Story	SpecX	SpecY																																						
Story40	-13.7	-0.6	-7.2	-7.2	-12.1	-12.1	-2.2	-2.2	-23.1	-1.1	-13.2	8.7	-38.7	24.4	-38.7	24.4	-42.8	-26.3	-35.4	-18.9	4.6	-42.8	4.6	28.5	12.0	21.1	21.1	-18.9	28.5	-26.3	12.0	-35.4	-11.9	1.2
Story39	-20.6	6.2	-7.1	-7.2	-17.2	-17.3	2.9	2.9	-28.6	-5.9	-8.5	14.3	-39.9	25.6	-40.0	25.5	-47.8	-30.7	-32.7	-15.6	1.3	-47.9	1.3	33.5	16.4	18.4	18.4	-15.7	33.5	-30.8	16.4	-32.8	-18.8	8.0
Story38	-27.5	13.1	-7.1	-7.3	-22.3	-22.5	8.1	7.9	-34.2	-10.6	-3.7	19.8	-40.9	26.7	-41.1	26.5	-52.7	-35.1	-29.9	-12.3	-2.0	-52.9	-2.1	38.3	20.7	15.5	15.6	-12.4	38.5	-35.2	20.8	-30.0	-25.7	14.9
Story37	-33.6	18.1	-7.4	-8.1	-26.8	-27.4	11.9	11.4	-40.9	-13.3	-2.2	25.5	-47.2	32.3	-47.7	31.7	-62.3	-41.5	-33.2	-12.4	-2.6	-62.7	-3.0	46.8	26.0	17.7	18.1	-12.8	47.2	-41.9	26.5	-33.6	-31.6	20.0
Story36	-40.0	24.5	-6.9	-8.6	-31.3	-32.6	17.1	15.8	-46.2	-17.6	2.1	30.7	-48.3	34.0	-49.6	32.7	-67.0	-45.5	-30.8	-9.3	-5.3	-68.0	-6.2	51.5	30.0	15.3	16.2	-10.2	52.5	-46.5	31.0	-31.7	-38.0	26.4
Story35	-45.7	30.2	-6.1	-9.4	-35.0	-37.5	21.9	19.4	-50.8	-21.7	6.1	35.2	-48.4	35.3	-50.8	32.8	-70.5	-48.7	-27.8	-6.0	-7.8	-72.4	-9.6	55.0	33.1	12.2	14.1	-7.8	56.8	-50.6	35.0	-29.7	-43.8	32.1
Story34	-53.0	35.3	-5.8	-11.9	-39.7	-44.2	26.5	22.0	-60.3	-23.6	5.9	42.6	-59.3	46.2	-63.9	41.6	-85.4	-67.8	-35.7	-8.1	-6.1	-88.8	-9.6	67.7	40.1	18.0	21.4	-11.6	71.1	-61.2	43.5	-39.1	-50.8	37.5
Story33	-58.2	40.5	-4.9	-12.8	-42.9	-48.8	31.2	25.2	-64.5	-27.1	9.5	46.9	-59.6	47.9	-65.5	42.0	-88.8	-60.7	-33.2	-5.1	-8.1	-93.2	-12.5	71.1	43.1	15.6	20.0	-9.6	75.6	-65.1	47.5	-37.6	-56.0	42.7
Story32	-64.5	46.7	-3.7	-14.1	-46.8	-54.5	36.7	28.9	-69.6	-31.7	13.9	51.8	-59.5	49.5	-67.3	41.7	-92.5	-64.0	-29.8	-1.4	-10.6	-98.3	-16.5	74.6	46.2	12.0	17.8	-7.2	80.5	-69.8	52.0	-35.6	-62.3	48.9
Story31	-69.0	51.2	-2.9	-14.8	-49.5	-58.4	40.7	31.8	-72.8	-35.0	17.3	55.1	-58.7	49.9	-67.6	41.0	-94.3	-65.9	-26.6	1.7	-12.8	-101.0	-19.5	76.6	48.2	8.9	15.6	-5.0	83.3	-72.6	54.9	-33.3	-66.7	53.4
Story30	-87.1	65.5	-1.4	-20.2	-61.0	-75.1	53.5	39.4	-93.4	-42.7	21.1	71.8	-76.5	69.1	-90.6	55.0	-122.1	-84.1	-36.2	1.8	-12.8	-132.7	-23.4	100.5	62.5	14.6	25.2	-8.8	111.1	-94.7	73.1	-46.8	-84.4	68.2
Story29	-92.2	70.4	0.1	-21.9	-63.6	-80.1	58.3	41.8	-97.3	-46.4	24.6	75.5	-75.8	70.5	-92.3	54.0	-124.5	-86.3	-32.9	5.3	-14.7	-136.9	-27.1	102.7	64.5	11.1	23.5	-7.1	115.1	-98.7	76.9	-45.3	-89.5	73.1
Story28	-99.3	77.0	2.1	-24.4	-67.4	-87.2	64.9	45.1	-102.7	-51.9	29.6	80.4	-74.3	71.8	-94.1	52.0	-127.3	-89.1	-28.0	10.2	-17.6	-142.1	-32.5	105.0	66.8	5.7	20.5	-4.7	119.8	-104.0	81.7	-42.8	-96.5	79.8
Story27	-106.0	83.4	3.7	-26.2	-71.1	-93.5	70.9	48.5	-107.1	-57.5	34.9	84.5	-71.4	71.3	-93.8	48.8	-128.3	-91.1	-21.7	15.5	-21.2	-145.2	-38.1	105.8	68.5	-0.8	16.0	-1.3	122.6	-107.9	85.4	-38.6	-103.1	86.2
Story26	-110.6	87.4	5.9	-29.0	-72.7	-98.9	75.7	49.6	-110.4	-61.2	38.1	87.2	-69.2	72.2	-95.4	46.1	-129.1	-92.1	-17.6	19.3	-22.8	-148.7	-42.5	105.9	69.0	-5.6	14.1	-0.3	125.5	-111.8	88.6	-37.3	-107.7	90.3
Story25	-121.9	96.6	8.2	-33.4	-78.9	-110.2	84.9	53.7	-122.4	-66.6	41.4	97.2	-77.3	83.3	-108.5	52.0	-143.6	-101.7	-20.6	21.3	-23.1	-167.1	-46.5	118.4	76.5	-4.6	18.8	-2.2	141.8	-125.2	99.9	-44.0	-118.7	99.8
Story24	-126.2	101.0	9.7	-34.9	-81.1	-114.5	89.3	55.9	-125.4	-70.2	45.1	100.2	-75.2	83.4	-108.6	50.0	-144.2	-102.9	-16.3	25.1	-25.2	-169.3	-50.3	119.1	77.7	-8.9	16.2	0.0	144.2	-128.0	102.8	-41.4	-123.1	104.2
Story23	-131.7	107.6	9.5	-33.7	-85.6	-118.0	93.9	61.5	-128.8	-74.9	50.7	104.6	-73.5	81.7	-106.9	49.4	-145.8	-105.3	-11.1	29.4	-29.3	-170.1	-53.6	121.7	81.2	-13.1	11.2	5.1	146.0	-129.6	105.5	-35.4	-128.7	110.6
Story22	-137.7	114.5	9.4	-32.7	-90.4	-122.0	98.7	67.1	-132.8	-79.7	56.4	109.5	-72.3	80.6	-103.9	49.0	-148.1	-108.2	-6.1	33.8	-33.3	-171.8	-57.0	124.8	84.9	-17.2	6.5	10.1	148.5	-131.9	108.7	-29.8	-134.8	117.4
Story21	-142.9	121.0	8.2	-30.1	-95.5	-124.3	102.4	73.7	-136.1	-83.7	61.9	114.2	-71.9	78.8	-100.7	50.1	-150.7	-111.4	-2.1	37.2	-37.5	-172.2	-59.1	128.8	89.5	-19.8	1.8	15.7	150.4	-132.9	111.1	-23.6	-140.2	123.8
Story20	-148.2	127.6	7.1	-27.7	-100.7	-126.8	106.2	80.1	-139.4	-88.2	67.5	118.7	-71.0	76.4	-97.1	50.4	-152.7	-114.3	2.6	41.0	-42.1	-172.3	-61.6	132.1	93.7	-23.2	-3.6	21.4	151.7	-133.9	113.2	-17.0	-145.7	130.2
Story19	-153.7	134.2	5.7	-25.2	-106.1	-129.3	109.8	86.7	-142.2	-93.2	73.7	122.8	-68.7	72.5	-91.9	49.3	-153.5	-116.7	8.6	45.4	-47.5	-170.9	-64.8	134.1	97.2	-28.0	-10.6	28.0	151.4	-134.1	114.6	-8.8	-151.2	136.7
Story18	-159.2	141.0	4.2	-22.4	-111.7	-131.6	113.4	93.5	-145.4	-97.9	79.7	127.2	-67.6	69.3	-87.5	49.4	-155.4	-119.7	13.6	49.3	-52.6	-170.3	-67.5	137.2	101.5	-31.8	-16.9	34.4	152.1	-134.6	116.4	-1.3	-156.9	143.3
Story17	-164.5	147.4	2.8	-19.9	-117.0	-134.0	116.9	99.9	-148.6	-102.4	85.3	131.5	-66.6	66.5	-83.6	49.5	-157.3	-122.6	18.3	53.0	-57.3	-170.0	-70.1	140.2	105.5	-35.4	-22.6	40.2	152.9	-136.3	118.3	5.5	-162.3	149.5
Story16	-170.1	153.9	1.3	-17.4	-122.6	-136.6	120.5	106.4	-152.0	-107.2	91.1	135.8	-65.5	63.4	-79.6	49.4	-159.2	-125.6	23.2	56.8	-62.4	-169.8	-72.9	143.1	109.5	-39.3	-28.8	46.3	153.6	-136.2	120.0	12.7	-168.1	156.0
Story15	-176.0	160.1	1.3	-17.2	-127.1	-140.9	125.0	111.2	-155.6	-112.3	96.4	139.7	-63.4	61.3	-77.2	47.5	-160.4	-127.9	28.8	61.3	-66.8	-170.8	-77.2	144.5	112.0	-44.7	-34.3	50.9	154.9	-138.3	122.4	18.4	-174.0	162.1
Story14	-182.1	166.3	1.3	-17.1	-131.6	-145.5	129.7	115.8	-159.4	-117.7	101.9	143.6	-61.0	59.1	-74.9	45.2	-161.5	-130.2	34.7	65.9	-71.4	-171.9	-81.8	145.7	114.4	-50.5	-40.1	55.5	156.1	-140.6	124.8	24.3	-180.1	168.3
Story13	-188.3	172.6	1.2	-16.9	-136.4	-150.0	134.3	120.7	-163.0	-123.4	107.7	147.3	-58.2	56.2	-71.9	42.5	-162.1	-132.4	41.1	70.8	-76.3	-172.4	-88.5	146.5	116.7	-56.7	-46.5	60.6	156.7	-142.6	126.9	30.8	-186.3	174.6
Story12	-194.6	179.0	1.0	-16.5	-141.3	-154.4	138.9	125.7	-166.2	-129.5	114.0	150.7	-54.1	51.7	-67.2	38.5	-161.5	-133.9	48.9	76.4	-82.0	-171.3	-91.9	145.9	118.4	-64.4	-54.5	66.5	155.8	-143.8	128.3	39.0	-192.6	181.0
Story11	-200.4	185.1	0.8	-16.1	-145.9	-158.6	143.3	130.6	-167.7	-136.8	121.5	152.4	-45.9	43.3	-58.6	30.6	-156.5	-133.3	60.6	83.8	-89.5	-166.0	-99.1	141.2	118.0	-75.9	-66.3	74.3	150.7	-142.8	127.5	51.1	-198.5	187.0
Story10	-206.6	191.5	0.7	-15.8	-150.7	-163.1	147.9	135.5	-166.5	-147.2	132.1	151.3	-29.2	26.4	-41.6	14.0	-143.1	-128.6	81.1	95.5	-101.4	-152.4	-110.6	127.9	113.5	-96.2	-86.9	86.2	137.2	-137.9	122.8	71.8	-204.7	193.4
Story9	-211.5	197.5	-1.2	-12.8	-156.0	-164.7	150.7	142.0	-168.5	-152.2	138.2	154.6	-26.3	21.0	-35.0	12.3	-142.7	-130.4	87.5	99.8	-107.3	-149.3	-113.8	128.7	116.5	-101.5	-95.0	93.3	135.3	-137.0	123.0	81.0	-209.7	199.2
Story8	-216.5	203.6	-2.9	-10.0	-161.3	-166.6	153.8	148.5	-171.7	-156.3	143.4	158.8	-26.0	18.5	-31.4	13.2	-145.2	-133.6	91.3	102.9	-111.7	-149.2	-115.7	132.4	120.8	-104.2	-100.2	98.9	136.4	-137.6	124.8	87.3	-214.9	205.2
Story7	-222.2	209.6	-2.7	-10.0	-165.5	-171.0	158.4	152.9	-175.5	-161.1	148.4	162.8	-24.4	17.2	-29.9	11.8	-146.9	-136.1	96.3	107.1	-115.6	-151.0	-119.7	134.2	123.4	-108.9	-104.8	103.0	138.3	-140.2	127.5	92.2	-220.7	211.2
Story6	-227.6	215.2	-2.4	-10.1	-169.4	-175.2	162.7	157.0	-179.1	-165.5	153.0	166.6	-23.0	16.3	-28.8	10.5	-148.6	-138.4	100.7	110.9	-119.1	-152.9	-123.4	136.1	125.9	-113.2	-108.9	106.6	140.5	-142.7	130.3	96.4	-226.1	216.8
Story5	-230.3	219.1	-3.5	-7.7	-172.5	-175.7	164.5	161.3	-180.5	-167.7	156.4	169.3	-22.6	14.7	-25.9	11.4	-149.7	-140.0	103.3	112.9	-121.7	-152.1	-124.1	138.5	128.8	-114.5	-112.0	110.5	140.9	-142.5	131.2	100.8	-228.9	220.5
Story4	-230.1	220.1	-4.5	-5.5	-173.4	-174.1	164.2	163.5	-179.9	-167.7	157.8	169.9	-22.2	13.0	-22.9	12.2	-149.2	-140.1	104.3	113.4	-122.8	-149.7	-123.3	139.2	130.1	-114.2	-113.7	112.8	139.8	-140.6	130.7	103.7	-228.8	221.3
Story3	-223.3	214.6	-5.3	-3.4	-169.3	-167.8	159.1	160.6	-174.3	-162.9	154.2	165.6	-21.6	11.4	-20.1	12.9	-144.9	-138.3	101.7	110.3	-120.1	-143.8	-119.0	136.2	127.6	-110.4	-111.5	111.4	135.1	-135.2	126.5	102.8	-222.2	215.7
Story2	-203.9	196.4	-6.2	-1.3	-155.7	-152.0	144.5	148.2	-159.1	-148.6	141.1	151.6	-20.8	9.7	-17.2	13.3	-133.2	-125.3	92.2	100.1	-110.3	-130.5	-107.6	125.7	117.8	-99.7	-102.4	102.8	122.9	-122.6	115.1	94.9	-203.0	197.3
Story1	-137.5	131.0	-5.0	-1.6	-105.3	-102.7	96.2	98.7	-107.9	-100.1	93.5	101.4	-15.9	6.8	-13.3	9.4	-91.3	-85.4	59.9	65.8	-74.2	-89.4	-72.3	84.8	78.9	-66.4	-68.4	67.7	82.8	-83.5	77.0	61.8	-136.7	131.8
Ground	9.4	-16.8	-5.3	-2.0	4.9	7.4	-14.7	-12.2	5.6	6.8	-14.1	-12.9	-6.7	-3.2	-4.2	-0.7	1.0	1.9	-13.7	-12.8	3.6	2.9	5.5	-8.3	-9.2	6.4	4.6	-11.0	-10.2	3.8	-11.1	-11.9	10.4	-15.8
B1	6.5	-14.1	-4.3	-3.2	3.5	4.4	-11.9	-11.1	3.5	4.3	-11.9	-11.1	-5.3	-3.1	-4.5	-2.2	0.6	1.1	-11.0	-10.4	2.2	1.2	2.9	-8.1	-8.7	3.5	2.8	-9.8	-8.8	1.8	-9.3	-10.4	7.5	-13.1
B2	-0.5	-7.5	-3.3	-4.7	-0.9	-1.9	-6.1	-7.1	-1.6	-1.2	-6.8	-6.4	-4.0	-2.9	-5.1	-4.0	-2.2	-1.9	-6.1	-5.8	-1.4	-3.0	-2.2	-5.8	-6.1	-1.9	-1.1	-6.6	-5.0	-2.7	-5.3	-6.9	0.5	-6.5
B3	-8.5	0.1	-2.2	-6.2	-6.0	-8.9	0.5	-2.4	-7.4	-7.5	-0.9	-1.0	-2.7	-2.8	-5.6	-5.7	-5.5	-5.5	-0.6	-0.6	-5.5	-7.7	-7.8	-2.9	-2.9	-7.8	-5.6	-2.9	-0.7	-7.7	-0.7	-2.8	-7.5	1.2

SIMPSON GUMPERTZ & HEGER
Engineering of Structures and Building Envelopes

CLIENT Pacific Earthquake Engineering Research Center
SUBJECT BRB Strength Check along Line D for LA BRBF Bldg

SHEET NO.
PROJECT NO. 087237.10
DATE 1/23/09
BY AD
CHECKED BY

A36

Story	ETABS #	Section	Capacity	Dead	Live	WindFX	WindMTX	WindFY	WindMTY
Story40	D6	A7	239	-5.97	0.00	-4.11	-9.15	0.01	-26.30
Story39	D6	A7	239	-5.98	0.00	-8.39	-9.50	0.03	-27.29
Story38	D6	A7	239	-6.00	0.00	-12.67	-9.80	0.07	-28.16
Story37	D6	A8	274	-6.45	0.00	-16.14	-11.52	0.23	-33.11
Story36	D6	A8	274	-6.46	0.00	-20.14	-11.93	0.54	-34.29
Story35	D6	A8	274	-6.49	0.00	-23.72	-12.13	1.04	-34.85
Story34	D6	A10	342	-7.37	0.00	-27.57	-15.30	1.90	-43.98
Story33	D6	A10	342	-7.34	0.00	-30.84	-15.59	2.46	-44.80
Story32	D6	A10	342	-7.42	0.00	-34.77	-15.80	3.23	-45.42
Story31	D6	A10	342	-7.39	0.00	-37.56	-15.75	3.71	-45.26
Story30	D6	A13.5	462	-8.99	0.00	-47.70	-21.10	5.87	-60.67
Story29	D6	A13.5	462	-9.08	0.00	-50.80	-21.20	6.88	-60.95
Story28	D6	A13.5	462	-9.29	0.00	-55.11	-21.17	8.26	-60.88
Story27	D6	A13.5	462	-9.40	0.00	-59.17	-20.67	9.35	-59.45
Story26	D6	A13.5	462	-9.65	0.00	-61.86	-20.49	10.90	-58.96
Story25	D6	A15.5	530	-10.51	0.00	-68.28	-23.25	13.02	-66.90
Story24	D6	A15.5	530	-10.49	0.00	-71.02	-22.97	13.93	-66.09
Story23	D6	A15.5	530	-10.07	0.00	-74.79	-22.48	13.49	-64.71
Story22	D6	A15.5	530	-9.70	0.00	-78.81	-22.13	13.17	-63.69
Story21	D6	A15.5	530	-9.10	0.00	-82.48	-21.82	11.97	-62.81
Story20	D6	A15.5	530	-8.60	0.00	-86.20	-21.34	10.86	-61.44
Story19	D6	A15.5	530	-8.09	0.00	-89.97	-20.43	9.65	-58.85
Story18	D6	A15.5	530	-7.58	0.00	-93.80	-19.81	8.31	-57.06
Story17	D6	A15.5	530	-7.12	0.00	-97.46	-19.25	7.09	-55.47
Story16	D6	A15.5	530	-6.72	0.00	-101.25	-18.65	5.85	-53.75
Story15	D6	A15.5	530	-6.62	0.00	-105.01	-18.03	5.76	-51.95
Story14	D6	A15.5	530	-6.59	0.00	-108.88	-17.35	5.77	-50.03
Story13	D6	A15.5	530	-6.54	0.00	-112.79	-16.53	5.68	-47.66
Story12	D6	A15.5	530	-6.47	0.00	-116.75	-15.28	5.49	-44.08
Story11	D6	A15.5	530	-6.36	0.00	-120.48	-12.87	5.29	-37.15
Story10	D6	A15.5	530	-6.31	0.00	-124.41	-8.02	5.16	-23.16
Story9	D6	A15.5	530	-5.83	0.00	-127.81	-6.82	3.64	-19.69
Story8	D6	A15.5	530	-5.35	0.00	-131.29	-6.42	2.22	-18.56
Story7	D6	A15.5	530	-5.26	0.00	-134.96	-6.00	2.27	-17.36
Story6	D6	A15.5	530	-5.19	0.00	-138.39	-5.66	2.40	-16.38
Story5	D6	A15.5	530	-4.67	0.00	-140.41	-5.37	1.34	-15.54
Story4	D6	A15.5	530	-4.15	0.00	-140.67	-5.06	0.30	-14.65
Story3	D6	A15.5	530	-3.62	0.00	-136.87	-4.75	-0.62	-13.77
Story2	D6	A15.5	530	-3.13	0.00	-125.09	-4.38	-1.52	-12.70
Story1	D6	A15.5	530	-2.72	0.00	-83.92	-3.26	-1.07	-9.46
Ground	D6	A14	479	-3.05	0.00	8.19	-0.51	-1.04	-1.46
B1	D6	A14	479	-3.15	0.00	6.43	-0.33	-0.35	-0.94
B2	D6	A14	479	-3.33	0.00	2.17	-0.15	0.44	-0.44
B3	D6	A14	479	-3.50	0.00	-2.71	0.01	1.24	0.04

Story	ETABS #	Section	Capacity	Dead	Live	WindFX	WindMTX	WindFY	WindMTY
Story40	D6	A7	239	-5.97	0.00	-4.11	-9.15	0.01	-26.30
Story39	D6	A7	239	-5.98	0.00	-8.39	-9.50	0.03	-27.29
Story38	D6	A7	239	-6.00	0.00	-12.67	-9.80	0.07	-28.16
Story37	D6	A8	274	-6.45	0.00	-16.14	-11.52	0.23	-33.11
Story36	D6	A8	274	-6.46	0.00	-20.14	-11.93	0.54	-34.29
Story35	D6	A8	274	-6.49	0.00	-23.72	-12.13	1.04	-34.85
Story34	D6	A10	342	-7.37	0.00	-27.57	-15.30	1.90	-43.98
Story33	D6	A10	342	-7.34	0.00	-30.84	-15.59	2.46	-44.80
Story32	D6	A10	342	-7.42	0.00	-34.77	-15.80	3.23	-45.42
Story31	D6	A10	342	-7.39	0.00	-37.56	-15.75	3.71	-45.26
Story30	D6	A13.5	462	-8.99	0.00	-47.70	-21.10	5.87	-60.67
Story29	D6	A13.5	462	-9.08	0.00	-50.80	-21.20	6.88	-60.95
Story28	D6	A13.5	462	-9.29	0.00	-55.11	-21.17	8.26	-60.88
Story27	D6	A13.5	462	-9.40	0.00	-59.17	-20.67	9.35	-59.45
Story26	D6	A13.5	462	-9.65	0.00	-61.86	-20.49	10.90	-58.96
Story25	D6	A15.5	530	-10.51	0.00	-68.28	-23.25	13.02	-66.90
Story24	D6	A15.5	530	-10.49	0.00	-71.02	-22.97	13.93	-66.09
Story23	D6	A15.5	530	-10.07	0.00	-74.79	-22.48	13.49	-64.71
Story22	D6	A15.5	530	-9.70	0.00	-78.81	-22.13	13.17	-63.69
Story21	D6	A15.5	530	-9.10	0.00	-82.48	-21.82	11.97	-62.81
Story20	D6	A15.5	530	-8.60	0.00	-86.20	-21.34	10.86	-61.44
Story19	D6	A15.5	530	-8.09	0.00	-89.97	-20.43	9.65	-58.85
Story18	D6	A15.5	530	-7.58	0.00	-93.80	-19.81	8.31	-57.06
Story17	D6	A15.5	530	-7.12	0.00	-97.46	-19.25	7.09	-55.47
Story16	D6	A15.5	530	-6.72	0.00	-101.25	-18.65	5.85	-53.75
Story15	D6	A15.5	530	-6.62	0.00	-105.01	-18.03	5.76	-51.95
Story14	D6	A15.5	530	-6.59	0.00	-108.88	-17.35	5.77	-50.03
Story13	D6	A15.5	530	-6.54	0.00	-112.79	-16.53	5.68	-47.66
Story12	D6	A15.5	530	-6.47	0.00	-116.75	-15.28	5.49	-44.08
Story11	D6	A15.5	530	-6.36	0.00	-120.48	-12.87	5.29	-37.15
Story10	D6	A15.5	530	-6.31	0.00	-124.41	-8.02	5.16	-23.16
Story9	D6	A15.5	530	-5.83	0.00	-127.81	-6.82	3.64	-19.69
Story8	D6	A15.5	530	-5.35	0.00	-131.29	-6.42	2.22	-18.56
Story7	D6	A15.5	530	-5.26	0.00	-134.96	-6.00	2.27	-17.36
Story6	D6	A15.5	530	-5.19	0.00	-138.39	-5.66	2.40	-16.38
Story5	D6	A15.5	530	-4.67	0.00	-140.41	-5.37	1.34	-15.54
Story4	D6	A15.5	530	-4.15	0.00	-140.67	-5.06	0.30	-14.65
Story3	D6	A15.5	530	-3.62	0.00	-136.87	-4.75	-0.62	-13.77
Story2	D6	A15.5	530	-3.13	0.00	-125.09	-4.38	-1.52	-12.70
Story1	D6	A15.5	530	-2.72	0.00	-83.92	-3.26	-1.07	-9.46
Ground	D6	A14	479	-3.05	0.00	8.19	-0.51	-1.04	-1.46
B1	D6	A14	479	-3.15	0.00	6.43	-0.33	-0.35	-0.94
B2	D6	A14	479	-3.33	0.00	2.17	-0.15	0.44	-0.44
B3	D6	A14	479	-3.50	0.00	-2.71	0.01	1.24	0.04

Story																																	
Story40	-5.4	-5.4	-10.3	-10.3	-0.4	-0.5	-21.3	0.7	-11.4	10.5	-36.9	26.2	-36.9	26.2	-41.0	-24.5	-33.6	-17.1	6.4	-41.0	6.4	30.3	13.8	22.9	22.9	-17.1	30.3	-24.5
Story39	-5.3	-5.4	-15.4	-15.5	4.7	4.7	-26.8	-4.1	-6.7	16.1	-38.1	27.4	-38.2	27.3	-46.1	-28.9	-30.9	-13.8	3.1	-46.1	3.1	35.3	18.2	20.2	20.2	-13.9	35.3	-29.0
Story38	-5.3	-5.5	-20.5	-20.7	9.9	9.7	-32.4	-8.8	-1.9	21.6	-39.1	28.5	-39.3	28.3	-50.9	-33.3	-28.1	-10.5	-0.2	-51.1	-0.3	40.1	22.5	17.3	17.4	-10.6	40.3	-33.4
Story37	-5.4	-6.2	-24.9	-25.4	13.8	13.3	-39.0	-11.3	-0.3	27.4	-45.2	34.2	-45.8	33.6	-60.3	-39.6	-31.3	-10.5	-0.7	-60.8	-1.1	48.7	28.0	19.6	20.1	-10.9	49.1	-40.0
Story36	-4.9	-6.7	-29.3	-30.6	19.0	17.7	-44.3	-15.7	4.0	32.7	-46.3	36.0	-47.6	34.7	-65.1	-43.6	-28.8	-7.3	-3.3	-66.1	-4.3	53.5	32.0	17.2	18.2	-8.3	54.4	-44.6
Story35	-4.2	-7.5	-33.1	-35.5	23.9	21.4	-48.9	-19.8	8.1	37.2	-46.4	37.2	-48.9	34.7	-68.6	-46.7	-25.9	-4.0	-5.8	-70.5	-7.7	56.9	35.1	14.2	16.0	-5.9	58.8	-48.6
Story34	-3.6	-9.7	-37.4	-42.0	28.7	24.2	-58.1	-21.4	8.1	44.8	-57.1	48.4	-61.7	43.9	-83.2	-55.6	-33.5	-5.9	-3.9	-86.6	-7.4	69.9	42.3	20.2	23.6	-9.3	73.3	-59.0
Story33	-2.7	-10.5	-40.7	-46.6	33.4	27.4	-62.3	-24.9	11.7	49.1	-57.4	50.1	-63.3	44.2	-86.6	-58.5	-31.0	-2.9	-5.9	-91.0	-10.3	73.4	45.3	17.8	22.2	-7.4	77.8	-62.9
Story32	-1.5	-11.8	-44.5	-52.3	38.9	31.2	-67.4	-29.4	16.1	54.0	-57.3	51.7	-65.1	43.9	-90.2	-61.8	-27.6	0.9	-8.4	-96.1	-14.2	76.9	48.4	14.2	20.1	-4.9	82.7	-67.6
Story31	-0.7	-12.6	-47.3	-56.2	42.9	34.0	-70.6	-32.8	19.5	57.3	-56.5	52.1	-65.4	43.2	-92.1	-63.7	-24.4	3.9	-10.5	-98.8	-17.2	78.8	50.4	11.1	17.8	-2.7	85.5	-70.4
Story30	1.3	-17.5	-58.3	-72.4	56.2	42.1	-90.7	-40.0	23.8	74.5	-73.8	71.8	-87.9	57.7	-119.4	-81.4	-33.5	4.5	-10.1	-130.0	-20.7	103.2	65.2	17.3	27.9	-6.1	113.8	-92.0
Story29	2.8	-19.2	-60.9	-77.4	61.1	44.5	-94.6	-43.7	27.4	78.2	-73.0	73.2	-89.6	56.7	-121.7	-83.5	-30.2	8.0	-11.9	-134.1	-24.3	105.4	67.2	13.9	26.3	-4.4	117.8	-95.9
Story28	4.8	-21.6	-64.6	-84.4	67.7	47.9	-99.9	-49.1	32.4	83.2	-71.5	74.6	-91.3	54.8	-124.5	-86.3	-25.2	13.0	-14.8	-139.3	-29.7	107.8	69.6	8.5	23.3	-1.9	122.6	-101.2
Story27	6.5	-23.4	-68.2	-90.7	73.8	51.3	-104.3	-54.7	37.7	87.4	-68.6	74.1	-91.0	51.7	-125.5	-88.3	-18.9	18.3	-18.4	-142.4	-35.3	108.6	71.4	2.0	18.8	1.5	125.4	-105.1
Story26	8.8	-26.1	-69.8	-96.0	78.6	52.5	-107.5	-58.3	40.9	90.1	-66.4	75.1	-92.5	49.0	-126.2	-89.2	-14.7	22.2	-19.9	-145.8	-39.6	108.8	71.9	-2.7	17.0	2.6	128.4	-108.9
Story25	11.4	-30.3	-75.8	-107.0	88.1	56.8	-119.3	-63.5	44.6	100.4	-74.1	86.4	-105.4	55.2	-140.4	-98.6	-17.4	24.5	-19.9	-163.9	-43.4	121.5	79.6	-1.5	22.0	1.0	145.0	-122.0
Story24	12.8	-31.7	-77.9	-111.4	92.5	59.1	-122.2	-67.1	48.2	103.3	-72.0	86.6	-105.5	53.2	-141.1	-99.7	-13.2	28.2	-22.0	-166.2	-47.1	122.2	80.8	-5.7	19.4	3.1	147.3	-124.8
Story23	12.5	-30.6	-82.6	-115.0	96.9	64.5	-125.8	-71.8	53.7	107.7	-70.5	84.8	-102.9	52.4	-142.8	-102.3	-8.1	32.4	-26.2	-167.1	-50.5	124.7	84.2	-10.0	14.3	8.1	149.0	-126.6
Story22	12.3	-29.8	-87.5	-119.1	101.6	70.0	-129.9	-76.7	59.3	112.4	-69.4	83.5	-101.0	51.9	-145.2	-105.3	-3.2	36.7	-30.4	-168.9	-54.1	127.7	87.8	-14.3	9.4	13.0	151.4	-129.0
Story21	11.0	-27.3	-92.8	-121.5	105.1	76.4	-133.3	-81.0	64.6	117.0	-69.2	81.5	-97.9	52.8	-147.9	-108.6	0.7	40.0	-34.8	-169.5	-56.3	131.6	92.3	-17.0	4.5	18.4	153.1	-130.2
Story20	9.6	-25.1	-98.1	-124.2	108.7	82.7	-136.8	-85.6	70.1	121.3	-68.4	79.0	-94.5	53.0	-150.2	-111.7	5.1	43.6	-39.5	-169.7	-59.0	134.7	96.3	-20.6	-1.0	24.0	154.3	-131.3
Story19	8.2	-22.7	-103.7	-126.8	112.3	89.1	-139.8	-90.7	76.2	125.2	-66.3	74.9	-89.5	51.7	-151.0	-114.2	11.0	47.9	-45.0	-168.4	-62.4	136.5	99.7	-25.6	-8.2	30.5	153.9	-131.6
Story18	6.5	-20.1	-109.4	-129.3	115.7	95.8	-143.2	-95.6	82.0	129.5	-65.3	71.6	-85.3	51.7	-153.1	-117.4	15.9	51.6	-50.3	-168.0	-65.2	139.4	103.7	-29.6	-14.6	36.6	154.4	-132.4
Story17	4.9	-17.8	-114.9	-131.9	119.0	102.0	-146.5	-100.3	87.4	133.6	-64.5	68.7	-81.5	51.6	-155.1	-120.4	20.5	55.1	-55.2	-167.9	-68.0	142.3	107.6	-33.3	-20.5	42.4	155.1	-133.2
Story16	3.3	-15.4	-120.5	-134.6	122.5	108.4	-149.9	-105.2	93.1	137.8	-63.5	65.5	-77.6	51.4	-157.2	-123.6	25.2	58.8	-60.4	-167.7	-70.9	145.1	111.5	-37.3	-26.8	48.3	155.6	-134.1
Story15	3.3	-15.2	-125.1	-138.9	127.0	113.1	-153.6	-110.3	98.4	141.7	-61.4	63.3	-75.2	49.5	-158.4	-125.9	30.8	63.3	-64.8	-168.8	-75.2	146.5	114.0	-42.7	-32.3	52.9	156.9	-136.3
Story14	3.3	-15.2	-129.7	-143.5	131.7	117.8	-157.4	-115.8	103.9	145.6	-59.0	61.0	-72.9	47.2	-159.5	-128.3	36.6	67.9	-69.4	-169.9	-79.8	147.7	116.4	-48.5	-38.1	57.5	158.0	-138.6
Story13	2.7	-15.0	-134.4	-148.0	136.3	122.6	-161.1	-121.4	109.6	149.3	-56.3	58.1	-69.9	44.5	-160.2	-130.4	43.0	72.8	-74.3	-170.4	-84.6	148.4	118.6	-54.8	-44.5	62.6	158.7	-140.6
Story12	1.9	-14.6	-139.3	-152.5	140.9	127.7	-164.3	-127.6	115.9	152.6	-52.1	53.7	-65.3	40.5	-159.5	-132.0	50.8	78.4	-80.1	-169.4	-90.0	147.9	120.3	-62.5	-52.6	68.5	157.8	-141.9
Story11	1.2	-14.2	-144.0	-156.6	145.2	132.5	-165.7	-134.9	123.4	154.3	-44.0	45.2	-56.6	32.5	-154.5	-131.4	62.5	85.7	-87.6	-164.1	-97.2	143.1	119.9	-74.0	-64.4	76.2	152.6	-140.9
Story10	0.6	-13.9	-148.8	-161.2	149.8	137.4	-164.6	-145.3	134.0	153.2	-27.3	28.3	-39.7	15.9	-141.2	-126.7	82.9	97.4	-99.5	-150.5	-108.8	129.8	115.4	-94.3	-85.0	88.1	139.1	-136.0
Story9	0.6	-11.1	-154.3	-163.0	152.5	143.8	-166.8	-150.4	139.9	156.3	-24.5	22.7	-33.2	14.0	-141.0	-128.7	89.3	101.6	-105.5	-147.5	-112.1	130.5	118.2	-99.8	-93.2	95.0	137.0	-135.2
Story8	0.2	-8.4	-159.7	-165.0	155.4	150.1	-170.1	-154.6	145.0	160.4	-24.4	20.1	-29.8	14.8	-143.6	-132.0	92.9	104.5	-110.1	-147.6	-114.1	134.0	122.4	-102.6	-98.6	100.5	138.0	-136.0
Story7	0.0	-6.4	-164.0	-169.4	159.9	154.5	-173.9	-159.5	150.0	164.4	-22.8	18.8	-28.3	13.4	-145.3	-134.5	97.8	108.7	-114.0	-149.4	-118.1	135.8	125.0	-107.3	-103.2	104.6	139.9	-138.6
Story6	0.0	-8.5	-167.8	-173.6	164.3	158.5	-177.5	-163.9	154.6	168.2	-21.4	17.9	-27.2	12.1	-147.0	-136.8	102.3	112.5	-117.5	-151.3	-121.8	137.7	127.5	-111.6	-107.3	108.2	142.0	-141.1
Story5	-0.1	-6.3	-171.1	-174.3	165.9	162.7	-179.1	-166.3	157.8	170.7	-21.2	16.1	-24.5	12.8	-148.3	-138.6	104.7	114.3	-120.3	-150.7	-122.7	139.9	130.2	-113.1	-110.6	111.9	142.3	-141.1
Story4	-0.2	-4.2	-172.2	-172.9	165.4	164.7	-178.6	-166.5	159.0	171.2	-21.0	14.2	-21.7	13.5	-147.9	-138.8	105.5	114.6	-121.5	-148.5	-122.1	140.5	131.4	-113.0	-112.4	114.1	141.0	-139.4
Story3	-0.3	-2.3	-168.3	-166.8	160.2	161.7	-173.2	-161.8	155.3	166.7	-20.5	12.5	-19.0	14.0	-143.8	-135.2	102.8	111.3	-119.0	-142.7	-117.9	137.3	128.7	-109.3	-110.4	112.5	136.2	-134.1
Story2	-0.4	-1.5	-154.8	-151.1	145.5	149.1	-158.2	-147.7	142.0	152.6	-19.9	10.6	-16.2	14.2	-132.3	-124.4	93.1	101.0	-109.4	-129.5	-106.6	126.6	118.7	-98.8	-101.5	103.7	123.9	-121.6
Story1	-0.7	-1.1	-104.4	-101.9	97.0	99.5	-107.1	-99.2	94.3	102.2	-15.1	7.6	-12.5	10.2	-90.5	-84.6	60.7	66.6	-73.4	-88.5	-71.5	85.6	79.7	-65.6	-67.6	68.5	83.6	-82.7
Ground	-4.4	-1.1	5.8	8.3	-13.8	-11.3	6.5	7.7	-13.2	-12.0	-5.7	-2.2	-3.3	0.2	1.9	2.8	-12.8	-11.9	4.6	3.8	6.4	-7.4	-8.3	7.3	5.5	-10.0	-9.3	4.7
B1	-3.4	-2.3	4.5	5.3	-11.0	-10.1	4.5	5.3	-10.9	-10.2	-4.4	-2.1	-3.5	-1.3	1.5	2.1	-10.1	-9.5	3.2	2.1	3.8	-7.2	-7.8	4.4	3.8	-8.9	-7.8	2.7
B2	-0.4	-3.7	0.1	-0.9	-5.1	-6.1	-0.6	-0.2	-5.8	-5.4	-3.0	-1.9	-4.1	-3.0	-1.2	-0.9	-5.1	-4.8	-0.4	-2.0	-1.2	-4.8	-5.1	-0.9	-0.1	-5.6	-4.0	-1.7
B3	1.2	-5.1	-4.9	-7.9	1.6	-1.4	-6.4	-6.4	0.1	0.1	-1.6	-1.7	-4.6	-4.7	-4.4	-4.5	0.5	0.4	-4.5	-6.7	-6.7	-1.9	-1.8	-6.8	-4.5	-1.8	0.4	-6.7

SIMPSON GUMPERTZ & HEGER
Engineering of Structures and Building Envelopes

CLIENT Pacific Earthquake Engineering Research Center
SUBJECT BRB Strength Check along Line D for LA BRBF Bldg

SHEET NO.
PROJECT NO. 087237.10
DATE 1/23/09
BY AD
CHECKED BY

Story	ETABS #	Section	Capacity	Dead	Live	WindFX	WindMTX	WindFY	WindMTY																								
																														Maximum Axial Loads			
																														Tension	Compression	DCR	Status
Story40	D6	A7	239	-5.97	0.00	-4.11	-9.15	0.01	-26.30	13.8	-33.6	140.5	104.8	-112.3	29.0	-46.1	95.2	-157.5	-121.9	145.0	109.3	-107.7	33.5	-41.5	99.7	-153.0	-117.3	144.98	-157.52	0.66	OK
Story39	D6	A7	239	-5.98	0.00	-8.39	-9.50	0.03	-27.29	18.2	-31.0	151.2	110.6	-121.3	28.9	-46.0	104.2	-168.3	-127.7	155.7	115.2	-116.8	33.4	-41.5	108.7	-163.8	-123.2	155.73	-168.29	0.70	OK
Story38	D6	A7	239	-6.00	0.00	-12.67	-9.80	0.07	-28.16	22.6	-28.2	184.5	122.7	-153.3	21.4	-38.5	136.1	-201.6	-139.8	189.1	127.3	-148.7	25.9	-34.0	140.7	-197.1	-135.3	189.05	-201.64	0.84	OK
Story37	D6	A8	274	-6.45	0.00	-16.14	-11.52	0.23	-33.11	28.4	-31.7	202.9	140.1	-164.8	29.8	-48.2	146.4	-221.3	-158.5	207.8	145.0	-159.9	34.7	-43.3	151.3	-216.4	-153.6	207.75	-221.29	0.81	OK
Story36	D6	A8	274	-6.46	0.00	-20.14	-11.93	0.54	-34.29	32.9	-29.8	218.5	147.2	-179.0	27.9	-46.4	160.5	-237.0	-165.6	223.4	152.0	-174.1	32.8	-41.5	165.4	-232.1	-160.7	223.44	-237.01	0.87	OK
Story35	D6	A8	274	-6.49	0.00	-23.72	-12.13	1.04	-34.85	36.9	-27.7	226.9	150.2	-187.1	26.0	-44.5	168.5	-245.5	-168.7	231.9	155.1	-182.2	30.9	-39.6	173.5	-240.6	-163.8	231.87	-245.50	0.90	OK
Story34	D6	A10	342	-7.37	0.00	-27.57	-15.30	1.90	-43.98	45.7	-36.9	256.4	181.5	-203.6	43.5	-64.8	182.5	-277.5	-202.6	262.0	187.1	-198.0	49.1	-59.0	188.1	-271.9	-197.0	261.98	-277.47	0.81	OK
Story33	D6	A10	342	-7.34	0.00	-30.84	-15.59	2.46	-44.80	49.7	-35.4	265.1	186.5	-210.7	43.8	-64.7	189.7	-286.1	-207.5	270.7	192.1	-205.2	49.3	-59.2	195.3	-280.5	-201.9	270.69	-286.11	0.84	OK
Story32	D6	A10	342	-7.42	0.00	-34.77	-15.80	3.23	-45.42	54.2	-33.4	270.8	190.4	-215.1	44.6	-65.8	193.9	-292.0	-211.6	276.4	196.0	-209.5	50.2	-60.2	199.5	-286.4	-206.0	276.41	-292.00	0.85	OK
Story31	D6	A10	342	-7.39	0.00	-37.56	-15.75	3.71	-45.26	57.1	-31.1	272.6	190.8	-216.9	44.0	-65.1	195.8	-293.7	-211.9	278.2	196.4	-211.3	49.6	-59.5	201.4	-288.1	-206.3	278.15	-293.67	0.86	OK
Story30	D6	A13.5	462	-8.99	0.00	-47.70	-21.10	5.87	-60.67	75.8	-44.1	342.3	250.2	-264.8	68.1	-93.8	239.1	-368.0	-275.9	349.1	257.0	-258.0	74.9	-86.9	245.9	-361.2	-269.1	349.13	-368.01	0.80	OK
Story29	D6	A13.5	462	-9.08	0.00	-50.80	-21.20	6.88	-60.95	79.6	-42.6	343.3	251.8	-265.2	69.2	-95.2	239.2	-369.3	-277.7	350.2	258.7	-258.3	76.1	-88.3	246.1	-362.4	-270.8	350.21	-369.28	0.80	OK
Story28	D6	A13.5	462	-9.29	0.00	-55.11	-21.17	8.26	-60.88	84.5	-40.1	348.7	254.0	-270.6	68.3	-94.8	244.0	-375.2	-280.6	355.7	261.1	-263.5	75.3	-87.8	251.1	-368.2	-273.6	355.71	-375.23	0.81	OK
Story27	D6	A13.5	462	-9.40	0.00	-59.17	-20.67	9.35	-59.45	88.2	-35.8	350.4	251.7	-274.5	64.2	-91.1	247.6	-377.3	-278.6	357.6	258.8	-267.3	71.3	-84.0	254.7	-370.2	-271.4	357.56	-377.30	0.82	OK
Story26	D6	A13.5	462	-9.65	0.00	-61.86	-20.49	10.90	-58.96	91.5	-34.4	349.1	251.1	-273.8	64.2	-91.8	246.2	-376.7	-278.7	356.4	258.4	-266.5	71.5	-84.5	253.6	-369.4	-271.3	356.41	-376.69	0.82	OK
Story25	D6	A15.5	530	-10.51	0.00	-68.28	-23.25	13.02	-66.90	103.1	-40.9	380.8	280.6	-294.2	78.1	-108.2	264.2	-410.9	-310.7	388.8	288.6	-286.3	86.1	-100.2	272.2	-402.9	-302.7	388.80	-410.88	0.78	OK
Story24	D6	A15.5	530	-10.49	0.00	-71.02	-22.97	13.93	-66.09	105.9	-38.3	379.2	278.4	-293.7	76.6	-106.6	263.7	-409.2	-308.4	387.1	286.4	-285.7	84.5	-98.6	271.6	-401.2	-300.5	387.14	-409.17	0.77	OK
Story23	D6	A15.5	530	-10.07	0.00	-74.79	-22.48	13.49	-64.71	108.5	-32.4	379.3	274.4	-295.6	71.9	-100.7	266.8	-408.1	-303.2	386.9	282.0	-287.9	79.5	-93.1	274.4	-400.4	-295.5	386.94	-408.08	0.77	OK
Story22	D6	A15.5	530	-9.70	0.00	-78.81	-22.13	13.17	-63.69	111.6	-26.9	380.8	271.8	-298.2	68.1	-95.8	270.5	-408.5	-299.6	388.2	279.2	-290.9	75.5	-88.5	277.9	-401.2	-292.2	388.18	-408.54	0.77	OK
Story21	D6	A15.5	530	-9.10	0.00	-82.48	-21.82	11.97	-62.81	113.8	-20.9	383.0	269.4	-301.1	64.1	-90.1	275.1	-409.0	-295.4	389.9	276.3	-294.2	71.0	-83.2	282.0	-402.1	-288.5	389.88	-408.99	0.77	OK
Story20	D6	A15.5	530	-8.60	0.00	-86.20	-21.34	10.86	-61.44	115.8	-14.4	384.0	265.6	-303.7	59.3	-83.9	279.1	-408.5	-290.1	390.5	272.1	-297.2	65.8	-77.3	285.6	-402.0	-283.6	390.47	-408.52	0.77	OK
Story19	D6	A15.5	530	-8.09	0.00	-89.97	-20.43	9.65	-58.85	117.1	-6.3	382.5	258.3	-305.7	51.8	-74.9	282.6	-405.7	-281.4	388.7	264.4	-299.6	58.0	-68.8	288.7	-399.5	-275.3	388.66	-405.66	0.77	OK
Story18	D6	A15.5	530	-7.58	0.00	-93.80	-19.81	8.31	-57.06	118.7	0.9	383.7	253.8	-308.9	46.0	-67.7	287.3	-405.4	-275.5	389.5	259.6	-303.2	51.8	-61.9	293.0	-399.6	-269.7	389.47	-405.39	0.76	OK
Story17	D6	A15.5	530	-7.12	0.00	-97.46	-19.25	7.09	-55.47	120.4	7.7	385.3	250.2	-312.2	40.9	-61.2	291.9	-405.7	-270.5	390.7	255.6	-306.8	46.3	-55.8	297.3	-400.3	-265.1	390.70	-405.66	0.77	OK
Story16	D6	A15.5	530	-6.72	0.00	-101.25	-18.65	5.85	-53.75	122.0	14.7	386.8	246.3	-315.7	35.5	-54.7	296.5	-406.0	-265.5	391.9	251.3	-310.6	40.6	-49.6	301.6	-400.9	-260.4	391.89	-406.00	0.77	OK
Story15	D6	A15.5	530	-6.62	0.00	-105.01	-18.03	5.76	-51.95	124.4	20.4	388.6	242.5	-320.1	29.9	-48.8	301.2	-407.6	-261.5	393.6	247.6	-315.1	34.9	-43.8	306.2	-402.5	-256.4	393.64	-407.55	0.77	OK
Story14	D6	A15.5	530	-6.59	0.00	-108.88	-17.35	5.77	-50.03	126.8	26.3	390.6	238.5	-325.1	23.8	-42.7	306.2	-409.4	-257.4	395.6	243.5	-320.1	28.8	-37.7	311.2	-404.4	-252.4	395.60	-409.44	0.77	OK
Story13	D6	A15.5	530	-6.54	0.00	-112.79	-16.53	5.68	-47.66	128.9	32.8	391.8	233.2	-329.9	16.6	-35.3	311.3	-410.5	-251.9	396.8	238.1	-325.0	21.6	-30.4	316.2	-405.5	-246.9	396.78	-410.49	0.77	OK
Story12	D6	A15.5	530	-6.47	0.00	-116.75	-15.28	5.49	-44.08	130.2	40.9	390.4	224.0	-334.1	6.7	-25.2	315.6	-408.9	-242.5	395.3	229.0	-329.2	11.6	-20.3	320.5	-404.0	-237.6	395.31	-408.89	0.77	OK
Story11	D6	A15.5	530	-6.36	0.00	-120.48	-12.87	5.29	-37.15	129.4	53.0	380.6	204.1	-335.2	-10.6	-7.6	317.0	-398.7	-222.3	385.4	209.0	-330.4	-5.8	-2.8	321.9	-393.9	-217.5	385.38	-398.74	0.75	OK
Story10	D6	A15.5	530	-6.31	0.00	-124.41	-8.02	5.16	-23.16	124.7	73.6	353.5	161.7	-330.7	-43.6	25.5	312.7	-371.6	-179.7	358.3	166.5	-325.9	38.8	30.3	317.5	-366.8	-175.0	358.31	-371.56	0.70	OK
Story9	D6	A15.5	530	-5.83	0.00	-127.81	-6.82	3.64	-19.69	124.8	82.7	353.1	152.8	-335.0	-53.6	36.9	318.4	-369.8	-169.5	357.5	157.3	-330.6	-49.2	41.4	322.8	-365.4	-165.1	357.55	-369.78	0.70	OK
Story8	D6	A15.5	530	-5.35	0.00	-131.29	-6.42	2.22	-18.56	126.4	88.9	359.6	152.0	-342.3	-58.6	43.3	327.0	-374.9	-167.3	363.6	156.0	-338.2	-54.5	47.4	331.0	-370.8	-163.2	363.63	-374.86	0.71	OK
Story7	D6	A15.5	530	-5.26	0.00	-134.96	-6.00	2.27	-17.36	129.1	93.7	366.5	151.1	-350.9	-64.1	49.1	335.9	-381.5	-166.1	370.4	155.1	-346.9	-60.1	53.1	339.8	-377.5	-162.1	370.44	-381.49	0.72	OK
Story6	D6	A15.5	530	-5.19	0.00	-138.39	-5.66	2.40	-16.38	131.8	98.0	374.0	150.9	-359.8	-69.2	54.4	345.0	-388.8	-165.8	377.9	154.9	-355.9	-65.3	58.3	348.9	-384.8	-161.8	377.89	-388.78	0.73	OK
Story5	D6	A15.5	530	-4.67	0.00	-140.41	-5.37	1.34	-15.54	132.6	102.2	380.2	150.8	-366.2	-73.1	59.8	352.9	-393.6	-164.2	383.8	154.4	-362.7	-69.6	63.3	356.4	-390.0	-160.6	383.76	-393.57	0.74	OK
Story4	D6	A15.5	530	-4.15	0.00	-140.67	-5.06	0.30	-14.65	131.9	105.0	382.1	149.4	-368.3	-75.7	63.9	356.5	-394.0	-161.3	385.3	152.6	-365.2	-72.6	67.0	359.6	-390.8	-158.1	385.28	-393.98	0.74	OK
Story3	D6	A15.5	530	-3.62	0.00	-136.87	-4.75	-0.62	-13.77	127.6	103.9	373.9	145.1	-360.2	-75.1	64.7	349.8	-384.3	-155.5	376.7	147.9	-357.4	-72.4	67.5	352.6	-381.5	-152.7	376.68	-384.30	0.72	OK
Story2	D6	A15.5	530	-3.13	0.00	-125.09	-4.38	-1.52	-12.70	116.0	95.9	344.9	134.2	-331.5	-68.7	59.7	322.6	-353.9	-143.2	347.3	136.6	-329.1	-66.3	62.1	324.9	-351.5	-140.8	347.28	-353.86	0.67	OK
Story1	D6	A15.5	530	-2.72	0.00	-83.92	-3.28	-1.07	-9.46	77.8	62.7	236.8	93.5	-227.9	-45.9	38.1	220.1	-244.6	-101.3	238.8	95.6	-225.9	-43.8	40.2	222.2	-242.5	-99.3	238.85	-244.56	0.46	OK
Ground	D6	A14	479	-3.05	0.00	8.19	-0.51	-1.04	-1.46	-10.2	-11.0	23.2	8.7	-28.8	-6.9	-1.8	20.0	-31.9	-17.4	25.5	11.0	-26.4	-4.6	0.5	22.4	-29.6	-15.1	25.49	-31.90	0.07	OK
B1	D6	A14	479	-3.15	0.00	6.43	-0.33	-0.35	-0.94	-8.4	-9.5	17.3	5.0	-24.3	-7.4	-1.6	15.3	-26.3	-14.0	19.7	7.4	-21.9	-5.1	0.8	17.7	-23.9	-11.7	19.68	-26.30	0.05	OK
B2	D6	A14	479	-3.33	0.00	2.17	-0.15	0.44	-0.44	-4.3	-5.9	7.9	0.7	-16.4	-6.7	-2.9	6.9	-17.5	-10.2	10.5	3.2	-13.9	-4.1	-0.3	9.4	-14.9	-7.7	10.47	-17.47	0.04	OK
B3	D6	A14	479	-3.50	0.00	-2.71	0.01	1.24	0.04	0.4	-1.8	6.8	-0.5	-16.1	-7.4	-2.6	6.1	-16.8	-9.5	9.4	2.1	-13.5	-4.8	0.1	8.8	-14.1	-6.8	9.41	-16.75	0.03	OK

SIMPSON GUMPERTZ & HEGER
Engineering of Structures and Building Enclosures

SHEET NO. _____
PROJECT NO. 087237.10
DATE 1/23/09
BY AD
CHECKED BY _____

CLIENT Pacific Earthquake Engineering Research Center
SUBJECT Infilled Column Strength & Stiffness Evaluation

Fy = 50 ksi
f'c = 10 ksi
wc = 150 lb/ft3
C2 = 0.85
ws = 490 lb/ft3

Ec = 5809.47502 ksi

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23
Col Type	**B**	**D**	**Reinforcing**	**Quantity Each Direction**	**Pl. Thk**	**Ar**	**t-wall**	**Ac**	**As**	**As/A-total**	**b/t**	**Status**	**C3**	**Ic**	**Eieff**	**ϕc Po**	**ϕt Po**	**Wt/Ft**	**Ibox**	**I mult**	**Aeff**	**Amult**
Box18	18	18				0	1.5	225	99	30.6%	10.0	OK	0.9	4.22E+03	1.53E+08	5146.9	4455	571.3	4.53E+03	**1.17**	4.18E+06	**1.46**
Box21	21	21				0	1.5	324	117	26.5%	12.0	OK	0.9	8.75E+03	2.62E+08	6453.0	5265	735.6	7.46E+03	**1.21**	5.28E+06	**1.55**
Box24	24	24				0	2.0	400	176	30.6%	10.0	OK	0.9	1.33E+04	4.85E+08	9150.0	7920	1015.6	1.43E+04	**1.17**	7.43E+06	**1.46**
Box27	27	27				0	2.0	529	200	27.4%	11.5	OK	0.9	2.33E+04	7.30E+08	10872.4	9000	1231.6	2.10E+04	**1.20**	8.87E+06	**1.53**
Box30	30	30				0	2.5	625	275	30.6%	10.0	OK	0.9	3.26E+04	1.18E+09	14296.9	12375	1586.8	3.49E+04	**1.17**	1.16E+07	**1.46**
Box33	33	33				0	2.5	784	305	28.0%	11.2	OK	0.9	5.12E+04	1.65E+09	16435.5	13725	1854.5	4.76E+04	**1.19**	1.34E+07	**1.51**
Box36	36	36				0	2.5	961	335	25.8%	12.4	OK	0.9	7.70E+04	2.23E+09	18688.9	15075	2141.0	6.30E+04	**1.22**	1.53E+07	**1.57**
Box39	39	39				0	3.0	1089	432	28.4%	11.0	OK	0.9	9.88E+04	3.24E+09	23142.4	19440	2604.4	9.40E+04	**1.19**	1.89E+07	**1.50**
Box42	42	42				0	3.0	1296	468	26.5%	12.0	OK	0.9	1.40E+05	4.19E+09	25812.0	21060	2942.5	1.19E+05	**1.21**	2.11E+07	**1.55**
Box45	45	45				0	3.0	1521	504	24.9%	13.0	OK	0.9	1.93E+05	5.33E+09	28596.4	22680	3299.4	1.49E+05	**1.23**	2.35E+07	**1.60**
Box48	48	48				0	3.0	1764	540	23.4%	14.0	OK	0.9	2.59E+05	6.66E+09	31495.5	24300	3675.0	1.83E+05	**1.26**	2.59E+07	**1.65**
Box51	51	51				0	3.0	2025	576	22.1%	15.0	OK	0.9	3.42E+05	8.23E+09	34509.4	25920	4069.4	2.22E+05	**1.28**	2.85E+07	**1.70**
Box54	54	54				0	3.0	2304	612	21.0%	16.0	OK	0.9	4.42E+05	1.00E+10	37638.0	27540	4482.5	2.66E+05	**1.30**	3.11E+07	**1.75**
Box57	57	57				0	3.0	2601	648	19.9%	17.0	OK	0.9	5.64E+05	1.21E+10	40881.4	29160	4914.4	3.16E+05	**1.32**	3.39E+07	**1.80**
Box60	60	60				0	3.0	2916	684	19.0%	18.0	OK	0.9	7.09E+05	1.45E+10	44239.5	30780	5365.0	3.71E+05	**1.34**	3.68E+07	**1.85**

SIMPSON GUMPERTZ & HEGER
Engineering of Structures and Building Enclosures

CLIENT Pacific Earthquake Engineering Research Center
SUBJECT Col C/2 Strength Check for LA BRBF Bldg

SHEET NO.
PROJECT NO. 087237.10
DATE 1/23/09
BY AD
CHECKED BY

S_{DS} = 1.145
Fy Column= 50 ksi

										Brace @ Left							Brace @ Right																
Floor	Height	Trib Area	Cum Area	LL Red Fact	Dead Load	Reducible	Unreducible	Dead Load	Live Load	ETABS Br #	Bay Length	Brace Type	Brace Comprsn	Brace Tension	Brace C Vert Comp	Brace T Vert Comp	ETABS Br #	Bay Length	Brace Type	Br. Comprsn	Brace Tension	Brace C Vert Comp	Brace T Vert Comp	Net Brace C	Net Brace T	Pu-Comp	Pu-Tension	Col Type	ϕc Po	ϕt Po	Comp DCR	Ten DCR	Status
						Live Load	Live Load																										
Story40	13.5	400	670		95			38	0.0															0.00	0.00	54.3	25.5						
Story39	13.5	400	400	0.8	97	40		76.8	12.8															0.00	0.00	116.1	51.5						
Story38	13.5	400	800	0.48	97	40		115.6	20.5															0.00	0.00	175.4	77.6						
Story37	13.5	400	1200	0.4	97	40		154.4	26.9															0.00	0.00	234.1	103.6						
Story36	13.5	400	1600	0.4	97	40		193.2	33.3															0.00	0.00	292.7	129.6						
Story35	13.5	400	2000	0.4	97	40		232	39.7															0.00	0.00	351.4	155.7						
Story34	13.5	400	2400	0.4	97	40		270.8	46.1															0.00	0.00	410.0	181.7						
Story33	13.5	400	2800	0.4	97	40		309.6	52.5															0.00	0.00	468.7	207.7						
Story32	13.5	400	3200	0.4	102	40		350.4	58.9															0.00	0.00	530.2	235.1						
Story31	13.5	400	3600	0.4	102	40		391.2	65.3															0.00	0.00	591.7	262.5						
Story30	13.5	400	4000	0.4	102	40		432	71.7															0.00	0.00	653.2	289.9						
Story29	13.5	400	4400	0.4	102	40		472.8	78.1															0.00	0.00	714.7	317.2						
Story28	13.5	400	4800	0.4	102	40		513.6	84.5															0.00	0.00	776.2	344.6						
Story27	13.5	400	5200	0.4	107	40		556.4	90.9															0.00	0.00	840.5	373.3						
Story26	13.5	400	5600	0.4	107	40		599.2	97.3															0.00	0.00	904.9	402.1						
Story25	13.5	400	6000	0.4	107	40		642	103.7															0.00	0.00	969.3	430.8						
Story24	13.5	400	6400	0.4	107	40		684.8	110.1															0.00	0.00	1033.6	459.5						
Story23	13.5	400	6800	0.4	112	40		729.6	116.5															0.00	0.00	1100.8	489.6						
Story22	13.5	400	7200	0.4	112	40		774.4	122.9															0.00	0.00	1168.1	519.6						
Story21	13.5	400	7600	0.4	112	40		819.2	129.3															0.00	0.00	1235.3	549.7						
Story20	13.5	400	8000	0.4	112	40		864	135.7															0.00	0.00	1302.5	579.7						
Story19	13.5	400	8400	0.4	117	40		910.8	142.1															0.00	0.00	1372.6	611.1						
Story18	13.5	400	8800	0.4	117	40		957.6	148.5															0.00	0.00	1442.7	642.5						
Story17	13.5	400	9200	0.4	117	40		1004.4	154.9															0.00	0.00	1512.7	674.0						
Story16	13.5	400	9600	0.4	117	40		1051.2	161.3															0.00	0.00	1582.8	705.4						
Story15	13.5	400	10000	0.4	117	40		1098	167.7															0.00	0.00	1652.9	736.8						
Story14	13.5	400	10400	0.4	127	40		1148.8	174.1															0.00	0.00	1728.7	770.8						
Story13	13.5	400	10800	0.4	127	40		1199.6	180.5															0.00	0.00	1804.5	804.9						
Story12	13.5	400	11200	0.4	127	40		1250.4	186.9															0.00	0.00	1880.3	839.0						
Story11	13.5	400	11600	0.4	127	40		1301.2	193.3															0.00	0.00	1956.1	873.1						
Story10	13.5	400	12000	0.4	127	40		1352	199.7								D25	27	A25	1436.9	-1306.3	1016.02	-923.66	1016.02	-923.66	3047.9	-16.5	Box21	6453.0	5265	0.472	0.003	OK
Story9	13.5	400	12400	0.4	140	40		1408	206.1								D25	27	A25	1436.9	-1306.3	1016.02	-923.66	1016.02	-923.66	4147.1	-902.5	Box21	6453.0	5265	0.643	0.171	OK
Story8	13.5	400	12800	0.4	140	40		1464	212.5								D25	27	A25	1436.9	-1306.3	1016.02	-923.66	1016.02	-923.66	5246.4	-1788.6	Box21	6453.0	5265	0.813	0.340	OK
Story7	13.5	400	13200	0.4	140	40		1520	218.9								D25	27	A27	1551.8	-1410.8	1097.31	-997.55	1097.31	-997.55	6426.9	-2748.6	Box24	9150.0	7920	0.702	0.347	OK
Story6	13.5	400	13600	0.4	140	40		1576	225.3								D25	27	A27	1551.8	-1410.8	1097.31	-997.55	1097.31	-997.55	7607.4	-3708.6	Box24	9150.0	7920	0.831	0.468	OK
Story5	13.5	400	14000	0.4	140	40		1632	231.7								D25	27	A27	1551.8	-1410.8	1097.31	-997.55	1097.31	-997.55	8788.0	-4668.6	Box27	10872.4	9000	0.808	0.519	OK
Story4	13.5	400	14400	0.4	142	40		1688.8	238.1								D25	27	A27	1551.8	-1410.8	1097.31	-997.55	1097.31	-997.55	9969.6	-5628.0	Box27	10872.4	9000	0.917	0.625	OK
Story3	13.5	400	14800	0.4	142	40		1745.6	244.5								D25	27	A27	1551.8	-1410.8	1097.31	-997.55	1097.31	-997.55	11151.3	-6587.4	Box30	14296.9	12375	0.780	0.532	OK
Story2	13.5	400	15200	0.4	142	40		1802.4	250.9								D25	27	A27	1551.8	-1410.8	1097.31	-997.55	1097.31	-997.55	12333.0	-7546.9	Box30	14296.9	12375	0.863	0.610	OK
Story1	18	400	15600	0.4	150	40		1862.4	257.3								D25	27	A27	1551.8	-1410.8	1241.46	-1128.60	1241.46	-1128.60	13663.4	-8635.2	Box36	18688.9	15075	0.731	0.573	OK
Ground	12	1168.8		1	515.5	100		2464.9164	374.2								D25	27	A18.5	1063.3	-966.6	706.41	-642.19	706.41	-642.19	15289.2	-8873.1	Box36	18688.9	15075	0.818	0.589	OK
B1	12	1168.8		1	85.5	40		2564.8488	420.9								D25	27	A18.5	1063.3	-966.6	706.41	-642.19	706.41	-642.19	16161.8	-9448.2	Box39	23142.4	19440	0.698	0.486	OK
B2	12	1168.8		1	85.5	40		2664.7812	467.7								D25	27	A18.5	1063.3	-966.6	706.41	-642.19	706.41	-642.19	17034.4	-10023.4	Box39	23142.4	19440	0.736	0.516	OK
B3	12	1168.8		1	85.5	40		2764.7136	514.4								D25	27	A18.5	1063.3	-966.6	706.41	-642.19	706.41	-642.19	17907.0	-10598.5	Box39	23142.4	19440	0.774	0.545	OK

SIMPSON GUMPERTZ & HEGER
Engineering of Structures and Building Enclosures

CLIENT Pacific Earthquake Engineering Research Center
SUBJECT Col D/2 Strength Check for LA BRBF Bldg

SHEET NO.
PROJECT NO. 087237.10
DATE 1/23/09
BY AD
CHECKED BY

S_{DS} = 1.145
Fy Column= 50 ksi

										Brace @ Left							Brace @ Right																
Floor	Height	Trib Area	Cum Area	LL Red Fact	Dead Load	Reducible	Unreducible	Dead Load	Live Load	ETABS Br #	Bay Length	Brace Type	Brace Comprsn	Brace Tension	Brace C Vert Comp	Brace T Vert Com	ETABS Br #	Bay Length	Brace Type	Br. Comprsn	Brace Tension	Brace C Vert Comp	Brace T Vert Comp	Net Brace C	Net Brace T	Pu-Comp	Pu-Tension	Col Type	ϕc Po	ϕt Po	Comp DCR	Ten DCR	Status
						Live Load	Live Load																										
Story40	13.5	670	670		95			63.65	0.0								D21	27	A6	344.9	-313.5	243.85	-221.68	243.85	-221.68	334.8	-179.0	Box21	6453.0	5265	0.052	0.034	OK
Story39	13.5	670	670	0.584	97	40		128.64	15.7								D21	27	A6	344.9	-313.5	243.85	-221.68	243.85	-221.68	679.3	-357.0	Box21	6453.0	5265	0.105	0.068	OK
Story38	13.5	670	1340	0.4	97	40		193.63	26.4								D21	27	A6	344.9	-313.5	243.85	-221.68	243.85	-221.68	1021.4	-535.1	Box21	6453.0	5265	0.158	0.102	OK
Story37	13.5	670	2010	0.4	97	40		258.62	37.1								D21	27	A6	344.9	-313.5	243.85	-221.68	243.85	-221.68	1363.5	-713.2	Box21	6453.0	5265	0.211	0.135	OK
Story36	13.5	670	2680	0.4	97	40		323.61	47.8								D21	27	A6	344.9	-313.5	243.85	-221.68	243.85	-221.68	1705.6	-891.2	Box21	6453.0	5265	0.264	0.169	OK
Story35	13.5	670	3350	0.4	97	40		388.6	58.5								D21	27	A9	517.3	-470.3	365.77	-332.52	365.77	-332.52	2169.6	-1180.2	Box21	6453.0	5265	0.336	0.224	OK
Story34	13.5	670	4020	0.4	97	40		453.59	69.3								D21	27	A9	517.3	-470.3	365.77	-332.52	365.77	-332.52	2633.6	-1469.1	Box21	6453.0	5265	0.408	0.279	OK
Story33	13.5	670	4690	0.4	97	40		518.58	80.0								D21	27	A9	517.3	-470.3	365.77	-332.52	365.77	-332.52	3097.6	-1758.0	Box21	6453.0	5265	0.480	0.334	OK
Story32	13.5	670	5360	0.4	102	40		586.92	90.7								D21	27	A9	517.3	-470.3	365.77	-332.52	365.77	-332.52	3566.4	-2044.6	Box21	6453.0	5265	0.553	0.388	OK
Story31	13.5	670	6030	0.4	102	40		655.26	101.4								D21	27	A9	517.3	-470.3	365.77	-332.52	365.77	-332.52	4035.1	-2331.3	Box21	6453.0	5265	0.625	0.443	OK
Story30	13.5	670	6700	0.4	102	40		723.6	112.1								D21	27	A9	517.3	-470.3	365.77	-332.52	365.77	-332.52	4503.9	-2618.0	Box21	6453.0	5265	0.698	0.497	OK
Story29	13.5	670	7370	0.4	102	40		791.94	122.9								D21	27	A9	517.3	-470.3	365.77	-332.52	365.77	-332.52	4972.7	-2904.6	Box21	6453.0	5265	0.771	0.552	OK
Story28	13.5	670	8040	0.4	102	40		860.28	133.6								D21	27	A9	517.3	-470.3	365.77	-332.52	365.77	-332.52	5441.5	-3191.3	Box21	6453.0	5265	0.843	0.606	OK
Story27	13.5	670	8710	0.4	107	40		931.97	144.3								D21	27	A15.5	890.9	-809.9	629.93	-572.67	629.93	-572.67	6179.2	-3715.8	Box24	9150.0	7920	0.675	0.469	OK
Story26	13.5	670	9380	0.4	107	40		1003.66	155.0								D21	27	A15.5	890.9	-809.9	629.93	-572.67	629.93	-572.67	6917.0	-4240.4	Box24	9150.0	7920	0.756	0.535	OK
Story25	13.5	670	10050	0.4	107	40		1075.35	165.7								D21	27	A15.5	890.9	-809.9	629.93	-572.67	629.93	-572.67	7654.7	-4765.0	Box24	9150.0	7920	0.837	0.602	OK
Story24	13.5	670	10720	0.4	107	40		1147.04	176.5								D21	27	A15.5	890.9	-809.9	629.93	-572.67	629.93	-572.67	8392.5	-5289.5	Box24	9150.0	7920	0.917	0.668	OK
Story23	13.5	670	11390	0.4	112	40		1222.08	187.2								D21	27	A18.5	1063.3	-966.6	751.86	-683.51	751.86	-683.51	9256.9	-5922.7	Box27	10872.4	9000	0.851	0.658	OK
Story22	13.5	670	12060	0.4	112	40		1297.12	197.9								D21	27	A18.5	1063.3	-966.6	751.86	-683.51	751.86	-683.51	10121.4	-6555.8	Box27	10872.4	9000	0.931	0.728	OK
Story21	13.5	670	12730	0.4	112	40		1372.16	208.6								D21	27	A18.5	1063.3	-966.6	751.86	-683.51	751.86	-683.51	10985.8	-7189.0	Box30	14296.9	12375	0.768	0.581	OK
Story20	13.5	670	13400	0.4	112	40		1447.2	219.3								D21	27	A18.5	1063.3	-966.6	751.86	-683.51	751.86	-683.51	11850.3	-7822.2	Box30	14296.9	12375	0.829	0.632	OK
Story19	13.5	670	14070	0.4	117	40		1525.59	230.1								D21	27	A25	1436.9	-1306.3	1016.02	-923.66	1016.02	-923.66	12983.7	-8693.2	Box33	16435.5	13725	0.790	0.633	OK
Story18	13.5	670	14740	0.4	117	40		1603.98	240.8								D21	27	A25	1436.9	-1306.3	1016.02	-923.66	1016.02	-923.66	14117.1	-9564.3	Box33	16435.5	13725	0.859	0.697	OK
Story17	13.5	670	15410	0.4	117	40		1682.37	251.5								D21	27	A25	1436.9	-1306.3	1016.02	-923.66	1016.02	-923.66	15250.5	-10435.3	Box36	18688.9	15075	0.816	0.692	OK
Story16	13.5	670	16080	0.4	117	40		1760.76	262.2								D21	27	A25	1436.9	-1306.3	1016.02	-923.66	1016.02	-923.66	16383.9	-11306.4	Box36	18688.9	15075	0.877	0.750	OK
Story15	13.5	670	16750	0.4	117	40		1839.15	272.9								D21	27	A25	1436.9	-1306.3	1016.02	-923.66	1016.02	-923.66	17517.3	-12177.4	Box39	23142.4	19440	0.757	0.626	OK
Story14	13.5	670	17420	0.4	127	40		1924.24	283.7								D21	27	A25	1436.9	-1306.3	1016.02	-923.66	1016.02	-923.66	18660.3	-13044.0	Box39	23142.4	19440	0.806	0.671	OK
Story13	13.5	670	18090	0.4	127	40		2009.33	294.4								D21	27	A25	1436.9	-1306.3	1016.02	-923.66	1016.02	-923.66	19803.2	-13910.6	Box39	23142.4	19440	0.856	0.716	OK
Story12	13.5	670	18760	0.4	127	40		2094.42	305.1								D21	27	A25	1436.9	-1306.3	1016.02	-923.66	1016.02	-923.66	20946.2	-14777.1	Box39	23142.4	19440	0.905	0.760	OK
Story11	13.5	670	19430	0.4	127	40		2179.51	315.8								D21	27	A25	1436.9	-1306.3	1016.02	-923.66	1016.02	-923.66	22089.2	-15643.7	Box42	25812.0	21060	0.856	0.743	OK
Story10	13.5	670	20100	0.4	127	40		2264.6	326.5	D26	40.0	A25	1436.9	-1306.3	803.89	-730.81	D21	27	A15.5	890.9	-809.9	629.93	-572.67	231.22	-100.88	22447.4	-15687.5	Box42	25812.0	21060	0.870	0.745	OK
Story9	13.5	670	20770	0.4	140	40		2358.4	337.3	D26	40.0	A25	1436.9	-1306.3	803.89	-730.81	D21	27	A15.5	890.9	-809.9	629.93	-572.67	231.22	-100.88	22818.0	-15725.4	Box45	28596.4	22680	0.798	0.693	OK
Story8	13.5	670	21440	0.4	140	40		2452.2	348.0	D26	40.0	A25	1436.9	-1306.3	803.89	-730.81	D21	27	A15.5	890.9	-809.9	629.93	-572.67	231.22	-100.88	23188.6	-15763.4	Box45	28596.4	22680	0.811	0.695	OK
Story7	13.5	670	22110	0.4	140	40		2546	358.7	D26	40.0	A27	1551.8	-1410.8	868.20	-789.28	D21	27	A15.5	890.9	-809.9	629.93	-572.67	295.54	-159.34	23623.6	-15859.8	Box48	31495.5	24300	0.750	0.653	OK
Story6	13.5	670	22780	0.4	140	40		2639.8	369.4	D26	40.0	A27	1551.8	-1410.8	868.20	-789.28	D21	27	A15.5	890.9	-809.9	629.93	-572.67	295.54	-159.34	24058.5	-15956.2	Box48	31495.5	24300	0.764	0.657	OK
Story5	13.5	670	23450	0.4	140	40		2733.6	380.1	D26	40.0	A27	1551.8	-1410.8	868.20	-789.28	D21	27	A15.5	890.9	-809.9	629.93	-572.67	295.54	-159.34	24493.4	-16052.6	Box48	31495.5	24300	0.778	0.661	OK
Story4	13.5	670	24120	0.4	142	40		2828.74	390.9	D26	40.0	A27	1551.8	-1410.8	868.20	-789.28	D21	27	A15.5	890.9	-809.9	629.93	-572.67	295.54	-159.34	24930.3	-16148.1	Box48	31495.5	24300	0.792	0.665	OK
Story3	13.5	670	24790	0.4	142	40		2923.88	401.6	D26	40.0	A27	1551.8	-1410.8	868.20	-789.28	D21	27	A15.5	890.9	-809.9	629.93	-572.67	295.54	-159.34	25367.1	-16243.6	Box51	34509.4	25920	0.735	0.627	OK
Story2	13.5	670	25460	0.4	142	40		3019.02	412.3	D26	40.0	A27	1551.8	-1410.8	868.20	-789.28	D21	27	A15.5	890.9	-809.9	629.93	-572.67	295.54	-159.34	25804.0	-16339.1	Box51	34509.4	25920	0.748	0.630	OK
Story1	18	670	26130	0.4	150	40		3119.52	423.0	D26	40.0	A27	1551.8	-1410.8	1038.12	-943.74	D21	27	A15.5	890.9	-809.9	712.69	-647.90	390.22	-231.05	26343.2	-16502.7	Box51	34509.4	25920	0.763	0.637	OK
Ground	12	1147.375		1	515.5	100		3710.991813	537.7	D26	40.0	A18.5	1063.3	-966.6	547.06	-497.32	D21	27	A15.5	890.9	-809.9	591.86	-538.05	94.53	0.00	27340.3	-16105.8	Box51	34509.4	25920	0.792	0.621	OK
B1	12	1147.375		1	85.5	40		3809.092375	583.6	D26	40.0	A18.5	1063.3	-966.6	547.06	-497.32	D21	27	A15.5	890.9	-809.9	591.86	-538.05	94.53	0.00	27597.9	-16040.0	Box54	37638.0	27540	0.733	0.582	OK
B2	12	1147.375		1	85.5	40		3907.192938	629.5	D26	40.0	A18.5	1063.3	-966.6	547.06	-497.32	D21	27	A15.5	890.9	-809.9	591.86	-538.05	94.53	0.00	27855.6	-15974.2	Box54	37638.0	27540	0.740	0.580	OK
B3	12	1147.375		1	85.5	40		4005.2935	675.4	D26	40.0	A18.5	1063.3	-966.6	547.06	-497.32	D21	27	A15.5	890.9	-809.9	591.86	-538.05	94.53	0.00	28113.3	-15908.3	Box54	37638.0	27540	0.747	0.578	OK

SIMPSON GUMPERTZ & HEGER
Engineering of Structures and Building Enclosures

CLIENT Pacific Earthquake Engineering Research Center
SUBJECT Col D/3 Strength Check for LA BRBF Bldg

SHEET NO.
PROJECT NO. 087237.10
DATE 1/23/09
BY AD
CHECKED BY

S_{DS} = 1.145
Fy Column= 50 ksi

A41

										Brace along X Direction														Y Direction Brace														
										Brace @ Left							Brace @ Right															Use 100%+30% Comb.							
Floor	Height	Trib Area	Cum Area	LL Red Fact	Dead Load	Reducible Live Load	Unreducible Live Load	Dead Load	Live Load	ETABS Br #	Bay Length	Brace Type	Brace Comprsn	Brace Tension	Brace C Vert Comp	Brace T Vert Comp	ETABS Br #	Bay Length	Brace Type	Br. Comprsn	Brace Tension	Brace C Vert Comp	Brace T Vert Comp	ETABS Br #	Bay Length	Brace Type	Br. Comprsn	Brace Tension	Brace C Vert Comp	Brace T Vert Comp	Net Brace C	Net Brace T	Pu-Comp	Pu-Tension	Col Type	φc Po	φt Po	Comp DCR	Ten DCR	Status
Story40	13.5	1172.5	670		95			111.3875	0.0								D1	30	A7	402.3	-365.8	269.14	-244.67	D13	27	A7	402.3	-365.8	284.49	-258.62	365.23	-332.03	524.4	-257.3	Box18	5146.9	4455	0.102	0.058	OK
Story39	13.5	1172.5	1172.5	0.4	97	40		225.12	18.8								D1	30	A7	402.3	-365.8	269.14	-244.67	D13	27	A7	402.3	-365.8	284.49	-258.62	365.23	-332.03	1061.5	-513.0	Box18	5146.9	4455	0.206	0.115	OK
Story38	13.5	1172.5	2345	0.4	97	40		338.8525	37.5								D1	30	A7	402.3	-365.8	269.14	-244.67	D13	27	A9	517.3	-470.3	365.77	-332.52	446.51	-405.92	1679.9	-842.6	Box18	5146.9	4455	0.326	0.189	OK
Story37	13.5	1172.5	3517.5	0.4	97	40		452.585	56.3								D1	30	A8	459.8	-418.0	307.59	-279.63	D13	27	A9	517.3	-470.3	365.77	-332.52	458.05	-416.41	2309.9	-1182.7	Box18	5146.9	4455	0.449	0.265	OK
Story36	13.5	1172.5	4690	0.4	97	40		566.3175	75.0								D1	30	A8	459.8	-418.0	307.59	-279.63	D13	27	A9	517.3	-470.3	365.77	-332.52	458.05	-416.41	2939.8	-1522.8	Box18	5146.9	4455	0.571	0.342	OK
Story35	13.5	1172.5	5862.5	0.4	97	40		680.05	93.8								D1	30	A8	459.8	-418.0	307.59	-279.63	D13	27	A11	632.2	-574.8	447.05	-406.41	539.33	-490.30	3651.1	-1936.8	Box18	5146.9	4455	0.709	0.435	OK
Story34	13.5	1172.5	7035	0.4	97	40		793.7825	112.6								D1	30	A10	574.8	-522.5	384.49	-349.53	D13	27	A11	632.2	-574.8	447.05	-406.41	562.40	-511.27	4385.4	-2371.7	Box18	5146.9	4455	0.852	0.532	OK
Story33	13.5	1172.5	8207.5	0.4	97	40		907.515	131.3								D1	30	A10	574.8	-522.5	384.49	-349.53	D13	27	A11	632.2	-574.8	447.05	-406.41	562.40	-511.27	5119.7	-2806.7	Box21	6453.0	5265	0.793	0.533	OK
Story32	13.5	1172.5	9380	0.4	102	40		1027.11	150.1								D1	30	A10	574.8	-522.5	384.49	-349.53	D13	27	A11	632.2	-574.8	447.05	-406.41	562.40	-511.27	5862.4	-3237.7	Box21	6453.0	5265	0.908	0.615	OK
Story31	13.5	1172.5	10552.5	0.4	102	40		1146.705	168.8								D1	30	A10	574.8	-522.5	384.49	-349.53	D13	27	A13.5	775.9	-705.4	548.65	-498.78	664.00	-603.64	6706.8	-3761.1	Box24	9150.0	7920	0.733	0.475	OK
Story30	13.5	1172.5	11725	0.4	102	40		1266.3	187.6								D1	30	A13.5	775.9	-705.4	519.06	-471.87	D13	27	A13.5	775.9	-705.4	548.65	-498.78	704.37	-640.34	7591.3	-4321.2	Box24	9150.0	7920	0.830	0.546	OK
Story29	13.5	1172.5	12897.5	0.4	102	40		1385.895	206.4								D1	30	A13.5	775.9	-705.4	519.06	-471.87	D13	27	A13.5	775.9	-705.4	548.65	-498.78	704.37	-640.34	8475.9	-4881.3	Box27	10872.4	9000	0.780	0.542	OK
Story28	13.5	1172.5	14070	0.4	102	40		1505.49	225.1								D1	30	A13.5	775.9	-705.4	519.06	-471.87	D13	27	A13.5	775.9	-705.4	548.65	-498.78	704.37	-640.34	9360.6	-5441.4	Box27	10872.4	9000	0.861	0.605	OK
Story27	13.5	1172.5	15242.5	0.4	107	40		1630.9475	243.9								D1	30	A13.5	775.9	-705.4	519.06	-471.87	D13	27	A13.5	775.9	-705.4	548.65	-498.78	704.37	-640.34	10253.8	-5997.5	Box30	14296.9	12375	0.717	0.485	OK
Story26	13.5	1172.5	16415	0.4	107	40		1756.405	262.6								D1	30	A13.5	775.9	-705.4	519.06	-471.87	D13	27	A13.5	775.9	-705.4	548.65	-498.78	704.37	-640.34	11146.7	-6553.7	Box30	14296.9	12375	0.780	0.530	OK
Story25	13.5	1172.5	17587.5	0.4	107	40		1881.8625	281.4								D1	30	A15.5	890.9	-809.9	595.96	-541.78	D13	27	A13.5	775.9	-705.4	548.65	-498.78	760.55	-691.41	12095.9	-7160.9	Box33	16435.5	13725	0.736	0.522	OK
Story24	13.5	1172.5	18760	0.4	107	40		2007.32	300.2								D1	30	A15.5	890.9	-809.9	595.96	-541.78	D13	27	A13.5	775.9	-705.4	548.65	-498.78	760.55	-691.41	13045.1	-7768.1	Box33	16435.5	13725	0.794	0.566	OK
Story23	13.5	1172.5	19932.5	0.4	113	40		2138.64	318.9								D1	30	A15.5	890.9	-809.9	595.96	-541.78	D13	27	A13.5	775.9	-705.4	548.65	-498.78	760.55	-691.41	14002.7	-8371.4	Box36	18688.9	15075	0.749	0.555	OK
Story22	13.5	1172.5	21105	0.4	113	40		2269.96	337.7								D1	30	A15.5	890.9	-809.9	595.96	-541.78	D13	27	A13.5	775.9	-705.4	548.65	-498.78	760.55	-691.41	14960.2	-8974.7	Box36	18688.9	15075	0.800	0.595	OK
Story21	13.5	1172.5	22277.5	0.4	113	40		2401.28	356.4								D1	30	A15.5	890.9	-809.9	595.96	-541.78	D13	27	A13.5	775.9	-705.4	548.65	-498.78	760.55	-691.41	15917.8	-9578.0	Box39	23142.4	19440	0.688	0.493	OK
Story20	13.5	1172.5	23450	0.4	113	40		2532.6	375.2								D1	30	A15.5	890.9	-809.9	595.96	-541.78	D13	27	A13.5	775.9	-705.4	548.65	-498.78	760.55	-691.41	16875.4	-10181.3	Box39	23142.4	19440	0.729	0.524	OK
Story19	13.5	1172.5	24622.5	0.4	117	40		2669.7825	394.0								D1	30	A15.5	890.9	-809.9	595.96	-541.78	D13	27	A13.5	775.9	-705.4	548.65	-498.78	760.55	-691.41	17841.4	-10790.7	Box39	23142.4	19440	0.771	0.555	OK
Story18	13.5	1172.5	25795	0.4	117	40		2806.965	412.7								D1	30	A15.5	890.9	-809.9	595.96	-541.78	D13	27	A13.5	775.9	-705.4	548.65	-498.78	760.55	-691.41	18807.4	-11380.0	Box39	23142.4	19440	0.813	0.585	OK
Story17	13.5	1172.5	26967.5	0.4	117	40		2944.1475	431.5								D1	30	A15.5	890.9	-809.9	595.96	-541.78	D13	27	A13.5	775.9	-705.4	548.65	-498.78	760.55	-691.41	19773.3	-11979.4	Box42	25812.0	21060	0.766	0.569	OK
Story16	13.5	1172.5	28140	0.4	117	40		3081.33	450.2								D1	30	A15.5	890.9	-809.9	595.96	-541.78	D13	27	A13.5	775.9	-705.4	548.65	-498.78	760.55	-691.41	20739.3	-12578.7	Box42	25812.0	21060	0.803	0.597	OK
Story15	13.5	1172.5	29312.5	0.4	117	40		3218.5125	469.0								D1	30	A15.5	890.9	-809.9	595.96	-541.78	D13	27	A13.5	775.9	-705.4	548.65	-498.78	760.55	-691.41	21705.3	-13178.1	Box45	28596.4	22680	0.759	0.581	OK
Story14	13.5	1172.5	30485	0.4	127	40		3367.42	487.8								D1	30	A15.5	890.9	-809.9	595.96	-541.78	D13	27	A13.5	775.9	-705.4	548.65	-498.78	760.55	-691.41	22688.0	-13769.6	Box45	28596.4	22680	0.793	0.607	OK
Story13	13.5	1172.5	31657.5	0.4	127	40		3516.3275	506.5								D1	30	A15.5	890.9	-809.9	595.96	-541.78	D13	27	A13.5	775.9	-705.4	548.65	-498.78	760.55	-691.41	23670.7	-14361.1	Box45	28596.4	22680	0.828	0.633	OK
Story12	13.5	1172.5	32830	0.4	127	40		3665.235	525.3								D1	30	A15.5	890.9	-809.9	595.96	-541.78	D13	27	A13.5	775.9	-705.4	548.65	-498.78	760.55	-691.41	24653.4	-14952.6	Box45	28596.4	22680	0.862	0.659	OK
Story11	13.5	1172.5	34002.5	0.4	127	40		3814.1425	544.0								D1	30	A15.5	890.9	-809.9	595.96	-541.78	D13	27	A13.5	775.9	-705.4	548.65	-498.78	760.55	-691.41	25636.1	-15544.1	Box48	31495.5	24300	0.814	0.640	OK
Story10	13.5	1172.5	35175	0.4	127	40		3963.05	562.8								D1	30	A15.5	890.9	-809.9	595.96	-541.78	D13	27	A13.5	775.9	-705.4	548.65	-498.78	760.55	-691.41	26618.9	-16135.6	Box48	31495.5	24300	0.845	0.664	OK
Story9	13.5	1172.5	36347.5	0.4	140	40		4127.2	581.6								D1	30	A15.5	890.9	-809.9	595.96	-541.78	D13	27	A13.5	775.9	-705.4	548.65	-498.78	760.55	-691.41	27623.4	-16716.8	Box51	34509.4	25920	0.800	0.645	OK
Story8	13.5	1172.5	37520	0.4	140	40		4291.35	600.3								D1	30	A15.5	890.9	-809.9	595.96	-541.78	D13	27	A13.5	775.9	-705.4	548.65	-498.78	760.55	-691.41	28627.9	-17298.1	Box51	34509.4	25920	0.830	0.667	OK
Story7	13.5	1172.5	38692.5	0.4	140	40		4455.5	619.1								D1	30	A15.5	890.9	-809.9	595.96	-541.78	D13	27	A13.5	775.9	-705.4	548.65	-498.78	760.55	-691.41	29632.4	-17879.4	Box51	34509.4	25920	0.859	0.690	OK
Story6	13.5	1172.5	39865	0.4	140	40		4619.65	637.8								D1	30	A15.5	890.9	-809.9	595.96	-541.78	D13	27	A13.5	775.9	-705.4	548.65	-498.78	760.55	-691.41	30636.9	-18460.6	Box51	34509.4	25920	0.888	0.712	OK
Story5	13.5	1172.5	41037.5	0.4	140	40		4783.8	656.6								D1	30	A15.5	890.9	-809.9	595.96	-541.78	D13	27	A13.5	775.9	-705.4	548.65	-498.78	760.55	-691.41	31641.4	-19041.9	Box54	37638.0	27540	0.841	0.691	OK
Story4	13.5	1172.5	42210	0.4	142	40		4950.295	675.4								D1	30	A15.5	890.9	-809.9	595.96	-541.78	D13	27	A13.5	775.9	-705.4	548.65	-498.78	760.55	-691.41	32649.2	-19621.6	Box54	37638.0	27540	0.867	0.712	OK
Story3	13.5	1172.5	43382.5	0.4	142	40		5116.79	694.1								D1	30	A15.5	890.9	-809.9	595.96	-541.78	D13	27	A13.5	775.9	-705.4	548.65	-498.78	760.55	-691.41	33657.1	-20201.3	Box57	40881.4	29160	0.823	0.693	OK
Story2	13.5	1172.5	44555	0.4	142	40		5283.285	712.9								D1	30	A15.5	890.9	-809.9	595.96	-541.78	D13	27	A13.5	775.9	-705.4	548.65	-498.78	760.55	-691.41	34664.9	-20781.0	Box57	40881.4	29160	0.848	0.713	OK
Story1	18	1172.5	45727.5	0.4	150	40		5459.16	731.6								D1	30	A15.5	890.9	-809.9	684.38	-622.16	D13	27	A13.5	775.9	-705.4	620.73	-564.30	870.69	-791.45	35796.2	-21454.4	Box57	40881.4	29160	0.876	0.736	OK
Ground	12	1172.5		1	515.5	100		6063.58375	848.9								D1	30	A14	804.7	-731.5	502.66	-456.96	D13	27	A13.5	775.9	-705.4	515.49	-468.63	666.29	-605.71	37384.9	-21654.6	Box57	40881.4	29160	0.914	0.743	OK
B1	12	1172.5		1	85.5	40		6163.8325	895.8								D1	30	A14	804.7	-731.5	502.66	-456.96	D13	27	A13.5	775.9	-705.4	515.49	-468.63	666.29	-605.71	38217.8	-22193.0	Box60	44239.5	30780	0.864	0.721	OK
B2	12	1172.5		1	85.5	40		6264.08125	942.7								D1	30	A14	804.7	-731.5	502.66	-456.96	D13	27	A13.5	775.9	-705.4	515.49	-468.63	666.29	-605.71	39050.8	-22731.5	Box60	44239.5	30780	0.883	0.739	OK
B3	12	1172.5		1	85.5	40		6364.33	989.6								D1	30	A14	804.7	-731.5	502.66	-456.96	D13	27	A13.5	775.9	-705.4	515.49	-468.63	666.29	-605.71	39883.8	-23269.9	Box60	44239.5	30780	0.902	0.756	OK

SIMPSON GUMPERTZ & HEGER
Engineering of Structures and Building Enclosures

CLIENT Pacific Earthquake Engineering Research Center
SUBJECT Frame Beam Design along Line 2 for LA BRBF Bldg

SHEET NO.
PROJECT NO. 087237.10
DATE 1/23/09
BY AD
CHECKED BY

S_{DS} = 1.145
Fy Beam= 50 ksi

Floor	Height (ft)	Beam Span (ft)	Brace Label	Brace Sec.	Comp Cap (kips)	Tens Cap (kips)	Brace Angle (radians)	Unb. Up F (kips)	Unb Moment (kip-ft)	Dead Load (psf)	Trib Width (ft)	Addl Dead Line (kips/ft)	Total Moment (kip-ft)	Beam Comp. (kips)	Collector	Beam	bf/2tf	h/tw	Ca	Seismically Compact	ϕMn (kip-ft)	ϕPcr (kips)	Interaction	Comment
Story40	13.5	27	D21	A6	344.85	-313.5	0.7854	22.17	149.6	80	5	0.25	109.89	232.76	CT1	W14X53	6.11	30.9	0.332	Yes	310.6	417.1	0.872	OK
Story39	13.5	27	D21	A6	344.85	-313.5	0.7854	22.17	149.6	79.5	5	0.25	110.04	232.76	CT1	W14X53	6.11	30.9	0.332	Yes	310.6	417.1	0.873	OK
Story38	13.5	27	D21	A6	344.85	-313.5	0.7854	22.17	149.6	79.5	5	0.25	110.04	232.76	CT1	W14X53	6.11	30.9	0.332	Yes	310.6	417.1	0.873	OK
Story37	13.5	27	D21	A6	344.85	-313.5	0.7854	22.17	149.6	79.5	5	0.25	110.04	232.76	CT1	W14X53	6.11	30.9	0.332	Yes	310.6	417.1	0.873	OK
Story36	13.5	27	D21	A6	344.85	-313.5	0.7854	22.17	149.6	79.5	5	0.25	110.04	232.76	CT1	W14X53	6.11	30.9	0.332	Yes	310.6	417.1	0.873	OK
Story35	13.5	27	D21	A9	517.275	-470.25	0.7854	33.25	224.4	79.5	5	0.25	184.86	349.14	CT2	W14X68	6.97	27.5	0.388	Yes	442.3	655.4	0.904	OK
Story34	13.5	27	D21	A9	517.275	-470.25	0.7854	33.25	224.4	79.5	5	0.25	184.86	349.14	CT2	W14X68	6.97	27.5	0.388	Yes	442.3	655.4	0.904	OK
Story33	13.5	27	D21	A9	517.275	-470.25	0.7854	33.25	224.4	79.5	5	0.25	184.86	349.14	CT2	W14X68	6.97	27.5	0.388	Yes	442.3	655.4	0.904	OK
Story32	13.5	27	D21	A9	517.275	-470.25	0.7854	33.25	224.4	79.5	5	0.25	184.86	349.14	CT2	W14X68	6.97	27.5	0.388	Yes	442.3	655.4	0.904	OK
Story31	13.5	27	D21	A9	517.275	-470.25	0.7854	33.25	224.4	79.5	5	0.25	184.86	349.14	CT2	W14X68	6.97	27.5	0.388	Yes	442.3	655.4	0.904	OK
Story30	13.5	27	D21	A9	517.275	-470.25	0.7854	33.25	224.4	79.5	5	0.25	184.86	349.14	CT2	W14X68	6.97	27.5	0.388	Yes	442.3	655.4	0.904	OK
Story29	13.5	27	D21	A9	517.275	-470.25	0.7854	33.25	224.4	79.5	5	0.25	184.86	349.14	CT2	W14X68	6.97	27.5	0.388	Yes	442.3	655.4	0.904	OK
Story28	13.5	27	D21	A9	517.275	-470.25	0.7854	33.25	224.4	79.5	5	0.25	184.86	349.14	CT2	W14X68	6.97	27.5	0.388	Yes	442.3	655.4	0.904	OK
Story27	13.5	27	D21	A15.5	890.8625	-809.875	0.7854	57.27	386.6	79.5	5	0.25	346.96	601.30	CT3	W16X100	5.29	23.2	0.450	Yes	778.7	983.2	1.008	Say OK
Story26	13.5	27	D21	A15.5	890.8625	-809.875	0.7854	57.27	386.6	79.5	5	0.25	346.96	601.30	CT3	W16X100	5.29	23.2	0.450	Yes	778.7	983.2	1.008	Say OK
Story25	13.5	27	D21	A15.5	890.8625	-809.875	0.7854	57.27	386.6	79.5	5	0.25	346.96	601.30	CT3	W16X100	5.29	23.2	0.450	Yes	778.7	983.2	1.008	Say OK
Story24	13.5	27	D21	A15.5	890.8625	-809.875	0.7854	57.27	386.6	79.5	5	0.25	346.96	601.30	CT3	W16X100	5.29	23.2	0.450	Yes	778.7	983.2	1.008	Say OK
Story23	13.5	27	D21	A18.5	1063.2875	-966.625	0.7854	68.35	461.4	79.5	5	0.25	421.78	717.68	CT4	W14X132	7.15	17.7	0.411	Yes	973.4	1524.4	0.856	OK
Story22	13.5	27	D21	A18.5	1063.2875	-966.625	0.7854	68.35	461.4	79.5	5	0.25	421.78	717.68	CT4	W14X132	7.15	17.7	0.411	Yes	973.4	1524.4	0.856	OK
Story21	13.5	27	D21	A18.5	1063.2875	-966.625	0.7854	68.35	461.4	79.5	5	0.25	421.78	717.68	CT4	W14X132	7.15	17.7	0.411	Yes	973.4	1524.4	0.856	OK
Story20	13.5	27	D21	A18.5	1063.2875	-966.625	0.7854	68.35	461.4	79.5	5	0.25	421.78	717.68	CT4	W14X132	7.15	17.7	0.411	Yes	973.4	1524.4	0.856	OK
Story19	13.5	27	D21	A25	1436.875	-1306.25	0.7854	92.37	623.5	79.5	5	0.25	583.88	969.84	CT5	W14X159	6.54	15.3	0.461	Yes	1195.8	1864.0	0.954	OK
Story18	13.5	27	D21	A25	1436.875	-1306.25	0.7854	92.37	623.5	79.5	5	0.25	583.88	969.84	CT5	W14X159	6.54	15.3	0.461	Yes	1195.8	1864.0	0.954	OK
Story17	13.5	27	D21	A25	1436.875	-1306.25	0.7854	92.37	623.5	79.5	5	0.25	583.88	969.84	CT5	W14X159	6.54	15.3	0.461	Yes	1195.8	1864.0	0.954	OK
Story16	13.5	27	D21	A25	1436.875	-1306.25	0.7854	92.37	623.5	79.5	5	0.25	583.88	969.84	CT5	W14X159	6.54	15.3	0.461	Yes	1195.8	1864.0	0.954	OK
Story15	13.5	27	D21	A25	1436.875	-1306.25	0.7854	92.37	623.5	79.5	5	0.25	583.88	969.84	CT5	W14X159	6.54	15.3	0.461	Yes	1195.8	1864.0	0.954	OK
Story14	13.5	27	D21	A25	1436.875	-1306.25	0.7854	92.37	623.5	79.5	5	0.25	583.88	969.84	CT5	W14X159	6.54	15.3	0.461	Yes	1195.8	1864.0	0.954	OK
Story13	13.5	27	D21	A25	1436.875	-1306.25	0.7854	92.37	623.5	79.5	5	0.25	583.88	969.84	CT5	W14X159	6.54	15.3	0.461	Yes	1195.8	1864.0	0.954	OK
Story12	13.5	27	D21	A25	1436.875	-1306.25	0.7854	92.37	623.5	79.5	5	0.25	583.88	969.84	CT5	W14X159	6.54	15.3	0.461	Yes	1195.8	1864.0	0.954	OK
Story11	13.5	27	D21	A25	1436.875	-1306.25	0.7854	92.37	623.5	79.5	5	0.25	583.88	969.84	CT5	W14X159	6.54	15.3	0.461	Yes	1195.8	1864.0	0.954	OK
Story10	13.5	27	D21	A15.5	890.8625	-809.875	0.7854	57.27	386.6	79.5	5	0.25	346.96	601.30	CT3	W16X100	5.29	23.2	0.450	Yes	778.7	983.2	1.008	Say OK
Story9	13.5	27	D21	A15.5	890.8625	-809.875	0.7854	57.27	386.6	79.5	5	0.25	346.96	601.30	CT3	W16X100	5.29	23.2	0.450	Yes	778.7	983.2	1.008	Say OK
Story8	13.5	27	D21	A15.5	890.8625	-809.875	0.7854	57.27	386.6	79.5	5	0.25	346.96	601.30	CT3	W16X100	5.29	23.2	0.450	Yes	778.7	983.2	1.008	Say OK
Story7	13.5	27	D21	A15.5	890.8625	-809.875	0.7854	57.27	386.6	79.5	5	0.25	346.96	601.30	CT3	W16X100	5.29	23.2	0.450	Yes	778.7	983.2	1.008	Say OK
Story6	13.5	27	D21	A15.5	890.8625	-809.875	0.7854	57.27	386.6	79.5	5	0.25	346.96	601.30	CT3	W16X100	5.29	23.2	0.450	Yes	778.7	983.2	1.008	Say OK
Story5	13.5	27	D21	A15.5	890.8625	-809.875	0.7854	57.27	386.6	79.5	5	0.25	346.96	601.30	CT3	W16X100	5.29	23.2	0.450	Yes	778.7	983.2	1.008	Say OK
Story4	13.5	27	D21	A15.5	890.8625	-809.875	0.7854	57.27	386.6	79.5	5	0.25	346.96	601.30	CT3	W16X100	5.29	23.2	0.450	Yes	778.7	983.2	1.008	Say OK
Story3	13.5	27	D21	A15.5	890.8625	-809.875	0.7854	57.27	386.6	79.5	5	0.25	346.96	601.30	CT3	W16X100	5.29	23.2	0.450	Yes	778.7	983.2	1.008	Say OK
Story2	13.5	27	D21	A15.5	890.8625	-809.875	0.7854	57.27	386.6	79.5	5	0.25	346.96	601.30	CT3	W16X100	5.29	23.2	0.450	Yes	778.7	983.2	1.008	Say OK
Story1	18	27	D21	A15.5	890.8625	-809.875	0.9273	64.79	437.3	79.5	5	0.25	397.74	510.22	CT3	W16X100	5.29	23.2	0.382	Yes	778.7	983.2	0.973	OK
Ground	12	27	D21	A15.5	890.8625	-809.875	0.7266	53.81	363.2	480	9.75		77.03	635.57	CT3	W16X100	5.29	23.2	0.476	Yes	778.7	983.2	0.734	OK
B1	12	27	D21	A15.5	890.8625	-809.875	0.7266	53.81	363.2	54.5	9.75		330.69	635.57	CT3	W16X100	5.29	23.2	0.476	Yes	778.7	983.2	1.024	Say OK
B2	12	27	D21	A15.5	890.8625	-809.875	0.7266	53.81	363.2	54.5	9.75		330.69	635.57	CT3	W16X100	5.29	23.2	0.476	Yes	778.7	983.2	1.024	Say OK
B3	12	27	D21	A15.5	890.8625	-809.875	0.7266	53.81	363.2	54.5	9.75		330.69	635.57	CT3	W16X100	5.29	23.2	0.476	Yes	778.7	983.2	1.024	Say OK

Floor	Height (ft)	Beam Span (ft)	Brace Label	Brace Sec.	Comp Cap (kips)	Tens Cap (kips)	Brace Angle (radians)	Unb. Up F (kips)	Unb Moment (kip-ft)	Dead Load (psf)	Trib Width (ft)	Addl Dead Line (kips/ft)	Total Moment (kip-ft)	Beam Comp. (kips)	Collector	Beam	bf/2tf	h/tw	Ca	Seismically Compact	ϕMn (kip-ft)	ϕPcr (kips)	Interaction	Comment
Story10	13.5	40	D25	A25	1436.875	-1306.25	0.5937	73.08	730.8	80	5	0.25	643.58	1136.82	CT14	W14X176	5.97	13.7	0.488	Yes	1333.3	2184.0	0.950	OK
Story9	13.5	40	D25	A25	1436.875	-1306.25	0.5937	73.08	730.8	79.5	5	0.25	643.92	1136.82	CT14	W14X176	5.97	13.7	0.488	Yes	1333.3	2184.0	0.950	OK
Story8	13.5	40	D25	A25	1436.875	-1306.25	0.5937	73.08	730.8	79.5	5	0.25	643.92	1136.82	CT14	W14X176	5.97	13.7	0.488	Yes	1333.3	2184.0	0.950	OK
Story7	13.5	40	D25	A27	1551.825	-1410.75	0.5937	78.93	789.3	79.5	5	0.25	702.38	1227.76	CT15	W14X193	5.45	12.8	0.480	Yes	1479.2	2397.1	0.934	OK
Story6	13.5	40	D25	A27	1551.825	-1410.75	0.5937	78.93	789.3	79.5	5	0.25	702.38	1227.76	CT15	W14X193	5.45	12.8	0.480	Yes	1479.2	2397.1	0.934	OK
Story5	13.5	40	D25	A27	1551.825	-1410.75	0.5937	78.93	789.3	79.5	5	0.25	702.38	1227.76	CT15	W14X193	5.45	12.8	0.480	Yes	1479.2	2397.1	0.934	OK
Story4	13.5	40	D25	A27	1551.825	-1410.75	0.5937	78.93	789.3	79.5	5	0.25	702.38	1227.76	CT15	W14X193	5.45	12.8	0.480	Yes	1479.2	2397.1	0.934	OK
Story3	13.5	40	D25	A27	1551.825	-1410.75	0.5937	78.93	789.3	79.5	5	0.25	702.38	1227.76	CT15	W14X193	5.45	12.8	0.480	Yes	1479.2	2397.1	0.934	OK
Story2	13.5	40	D25	A27	1551.825	-1410.75	0.5937	78.93	789.3	79.5	5	0.25	702.38	1227.76	CT15	W14X193	5.45	12.8	0.480	Yes	1479.2	2397.1	0.934	OK
Story1	18	40	D25	A27	1551.825	-1410.75	0.7328	94.37	943.7	79.5	5	0.25	856.85	1101.03	CT15	W14X193	5.45	12.8	0.431	Yes	1479.2	2397.1	0.974	OK
Ground	12	40	D25	A18.5	1063.2875	-966.625	0.5404	49.73	497.3	480	9.75	0.25	-164.28	1656.90	CT17	W24X162	5.31	30.6	0.772	Yes	1950.0	1916.8	0.939	OK
B1	12	40	D25	A18.5	1063.2875	-966.625	0.5404	49.73	497.3	54.5	9.75	0.25	392.46	870.32	CT16	W24X131	6.7	35.6	0.502	Yes	1541.7	1537.6	0.792	OK
B2	12	40	D25	A18.5	1063.2875	-966.625	0.5404	49.73	497.3	54.5	9.75	0.25	392.46	870.32	CT16	W24X131	6.7	35.6	0.502	Yes	1541.7	1537.6	0.792	OK
B3	12	40	D25	A18.5	1063.2875	-966.625	0.5404	49.73	497.3	54.5	9.75	0.25	392.46	870.32	CT16	W24X131	6.7	35.6	0.502	Yes	1541.7	1537.6	0.792	OK

SIMPSON GUMPERTZ & HEGER
Engineering of Structures and Building Enclosures

CLIENT Pacific Earthquake Engineering Research Center
SUBJECT BRB Strength Check along Line 3 for LA BRBF Bldg: PB Dsgn

SHEET NO.
PROJECT NO. 087237.10
DATE 1/23/09
BY AD
CHECKED BY

Model: 011609PBModel1

Scale-X= 1.00
Scale-Y= 1.00

SDS = 1.145
ρ-X dir = 1
ρ -Y dir = 1

Dead=	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2
Live=	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
WindFX=	1.6	-1.6			1.2	1.2	-1.2	-1.2	1.2	1.2	-1.2	-1.2							0.9008	0.9008	-0.9008	-0.9008	0.9008
WindMTX=									1.2	-1.2	1.2	-1.2							0.9008	-0.9008	0.9008	-0.9008	0.9008
WindFY=			1.6	-1.6	1.2	-1.2	1.2	-1.2					1.2	1.2	-1.2	-1.2	0.9008	0.9008	0.9008	0.9008	0.9008
WindMTY=													1.2	-1.2	1.2	-1.2	0.9008	0.9008	0.9008	0.9008	-0.9008
SpecX=																							
SpecY=																							
Comment	Figure 6-9 Case 1				Figure 6-9 Case 2				Figure 6-9 Case 3														

Story	ETABS #	Section	Capacity	Dead	Live	WindFX	WindMTX	WindFY	WindMTY	ServSpecX	ServSpecY																						
Story40	D12	A7	239	-2.99	0.00	0.00	-7.88	10.30	-22.66	0.01	65.54	-3.6	-3.6	12.9	-20.1	8.8	-16.0	8.8	-16.0	-13.0	5.9	-13.0	5.9	-18.4	36.0	-43.1	11.2	-21.8	-7.6	-21.8	-7.6	19.0
Story39	D12	A7	239	-3.45	-0.07	0.01	-8.82	18.43	-25.36	0.14	77.41	-4.2	-4.2	25.3	-33.7	17.9	-26.3	17.9	-26.3	-14.8	6.4	-14.8	6.4	-12.5	48.3	-56.8	4.1	-18.4	-2.5	-18.4	-2.5	27.3
Story38	D12	A9	308	-4.00	-0.14	0.02	-12.10	32.87	-34.79	0.29	122.52	-4.9	-5.0	47.7	-57.5	34.5	-44.4	34.5	-44.4	-19.4	9.6	-19.5	9.6	-7.2	76.3	-86.1	-2.6	-17.5	4.3	-17.6	4.2	45.1
Story37	D12	A9	308	-4.47	-0.21	0.05	-12.98	43.58	-37.29	0.47	133.56	-5.5	-5.7	64.1	-75.3	46.8	-57.8	46.7	-57.9	-21.1	10.1	-21.2	9.9	2.0	91.5	-102.6	-13.1	-11.6	11.8	-11.7	11.7	55.8
Story36	D12	A9	308	-4.94	-0.28	0.09	-14.26	54.09	-40.97	0.71	146.70	-6.1	-6.4	80.3	-92.7	58.8	-71.0	58.6	-71.2	-23.2	11.0	-23.4	10.8	9.5	107.9	-120.3	-21.9	-7.1	18.5	-7.3	18.4	66.7
Story35	D12	A9	308	-5.41	-0.35	0.15	-15.48	60.61	-44.47	0.98	144.63	-6.6	-7.1	90.1	-103.8	66.1	-79.4	65.7	-79.7	-25.2	11.9	-25.6	11.6	12.5	119.3	-132.9	-26.2	-6.1	21.8	-6.4	21.5	74.0
Story34	D12	A9	308	-5.88	-0.41	0.21	-16.35	70.84	-46.97	1.26	150.21	-7.1	-7.8	105.9	-120.8	77.8	-92.2	77.3	-92.7	-26.8	12.4	-27.3	11.9	21.2	133.9	-148.8	-36.1	-0.5	28.9	-0.9	28.6	84.1
Story33	D12	A9	308	-5.64	-0.40	0.23	-17.58	81.06	-50.51	1.28	154.91	-6.8	-7.5	122.5	-136.9	90.4	-104.2	89.8	-104.7	-28.0	14.2	-28.5	13.7	29.5	150.7	-165.0	-43.8	4.7	36.4	4.3	36.0	95.7
Story32	D12	A9	308	-6.05	-0.45	0.30	-18.84	91.74	-54.14	1.54	156.45	-7.2	-8.2	139.1	-154.5	102.7	-117.4	102.0	-118.1	-30.0	15.3	-30.7	14.5	37.4	167.3	-182.8	-52.8	9.5	43.4	8.9	42.9	107.0
Story31	D12	A9	308	-5.36	-0.37	0.27	-20.12	101.29	-57.82	1.31	157.27	-6.4	-7.2	155.3	-168.9	115.1	-128.0	114.4	-128.7	-30.6	17.7	-31.3	17.0	45.4	184.1	-197.7	-59.0	14.5	50.7	14.0	50.2	118.6
Story30	D12	A9	308	-5.66	-0.41	0.33	-21.19	109.74	-60.88	1.51	154.02	-6.7	-7.7	168.4	-182.8	124.9	-138.5	124.1	-139.3	-32.2	18.6	-33.0	17.8	51.4	197.5	-212.0	-65.8	18.0	56.2	17.4	55.6	127.7
Story29	D12	A11	376	-5.56	-0.40	0.35	-26.26	137.17	-75.47	1.51	176.60	-6.5	-7.6	212.4	-226.5	158.0	-171.3	157.1	-172.1	-38.2	24.9	-39.0	24.0	67.0	248.1	-262.2	-81.1	25.2	72.5	24.5	71.8	161.1
Story28	D12	A11	376	-5.83	-0.43	0.42	-27.18	144.54	-78.15	1.69	170.34	-6.8	-8.1	223.8	-238.7	166.5	-180.4	165.5	-181.4	-39.5	25.7	-40.6	24.7	72.2	259.8	-274.7	-87.1	28.3	77.2	27.5	76.5	169.1
Story27	D12	A11	376	-5.32	-0.37	0.38	-27.11	145.02	-77.96	1.47	156.54	-6.1	-7.4	225.3	-238.8	167.7	-180.3	166.8	-181.2	-38.8	26.2	-39.7	25.3	73.7	260.8	-274.3	-87.2	29.6	78.4	28.9	77.7	170.0
Story26	D12	A11	376	-5.54	-0.40	0.45	-27.97	152.23	-80.47	1.61	154.29	-6.3	-7.8	236.5	-250.6	176.2	-189.2	175.1	-190.3	-40.1	27.1	-41.1	26.0	79.1	272.2	-286.3	-93.2	32.8	83.2	32.0	82.4	177.8
Story25	D12	A11	376	-5.77	-0.43	0.51	-29.02	161.51	-83.50	1.75	154.07	-6.5	-8.2	251.1	-265.8	187.1	-200.5	185.8	-201.8	-41.6	28.1	-42.8	26.9	86.3	286.7	-301.4	-101.0	37.2	89.5	36.3	88.6	187.7
Story24	D12	A11	376	-6.00	-0.46	0.58	-29.51	167.36	-84.92	1.90	151.36	-6.7	-8.6	260.1	-275.4	193.9	-207.8	192.5	-209.2	-42.4	28.4	-43.8	27.1	91.3	295.1	-310.4	-106.6	40.5	93.7	39.5	92.7	193.5
Story23	D12	A11	376	-5.82	-0.43	0.58	-28.27	162.21	-81.41	1.83	140.47	-6.5	-8.4	252.1	-267.0	187.9	-201.4	186.5	-202.8	-40.6	27.2	-42.0	25.8	89.5	284.9	-299.8	-104.4	40.4	91.4	39.4	90.3	187.1
Story22	D12	A11	376	-6.04	-0.46	0.65	-28.48	166.63	-82.03	1.96	139.56	-6.7	-8.8	258.9	-274.3	193.0	-206.9	191.5	-208.5	-41.1	27.3	-42.7	25.7	93.8	290.7	-306.1	-109.2	43.4	94.7	42.3	93.6	191.2
Story21	D12	A11	376	-6.26	-0.49	0.73	-29.09	173.90	-83.81	2.08	141.90	-6.8	-9.2	270.2	-286.2	201.6	-215.8	199.8	-217.6	-42.0	27.8	-43.8	26.0	100.1	301.3	-317.3	-116.1	47.6	100.0	46.3	98.7	198.6
Story20	D12	A11	376	-6.48	-0.51	0.81	-29.67	178.34	-85.49	2.20	141.66	-7.0	-9.6	277.1	-293.6	206.7	-221.3	204.8	-223.3	-42.9	28.3	-44.9	26.3	103.1	308.3	-324.9	-119.7	49.3	102.8	47.9	101.3	203.4
Story19	D12	A11	376	-6.26	-0.49	0.80	-30.12	184.43	-86.80	2.09	144.57	-6.7	-9.3	287.1	-303.1	214.3	-228.4	212.4	-230.3	-43.2	29.1	-45.1	27.2	109.2	317.5	-333.5	-125.2	53.5	107.8	52.1	106.4	209.9
Story18	D12	A11	376	-6.46	-0.51	0.87	-30.55	192.70	-88.06	2.20	149.29	-6.9	-9.7	300.0	-316.6	224.0	-238.5	221.9	-240.6	-43.9	29.4	-46.0	27.3	117.3	328.6	-345.2	-133.8	59.3	114.3	57.7	112.7	217.9
Story17	D12	A11	376	-5.95	-0.45	0.80	-30.80	197.43	-88.81	1.92	154.30	-6.3	-8.9	308.3	-323.5	230.3	-243.5	228.4	-245.5	-43.6	30.3	-45.5	28.4	122.8	335.9	-351.1	-137.9	63.2	118.7	61.8	117.3	223.2
Story16	D12	A11	376	-6.13	-0.47	0.87	-31.06	202.98	-89.61	2.01	159.62	-6.4	-9.2	316.9	-332.6	236.8	-250.4	234.7	-252.4	-44.1	30.5	-46.1	28.4	128.2	343.3	-358.9	-143.9	67.1	123.1	65.5	121.5	228.5
Story15	D12	A11	376	-6.30	-0.49	0.94	-31.28	209.50	-90.27	2.09	165.76	-6.5	-9.6	327.2	-342.3	244.5	-258.3	242.2	-260.6	-44.5	30.6	-46.7	28.4	135.0	351.7	-367.8	-151.1	72.0	128.4	70.3	126.7	234.6
Story14	D12	A11	376	-6.49	-0.51	1.01	-31.44	216.10	-90.74	2.18	171.83	-6.7	-9.9	337.5	-354.1	252.2	-266.4	249.8	-268.8	-44.8	30.6	-47.2	28.2	142.1	359.9	-376.5	-158.7	77.2	133.9	75.4	132.0	240.7
Story13	D12	A11	376	-6.31	-0.48	1.00	-31.23	218.12	-90.17	2.08	176.05	-6.4	-9.7	340.9	-357.0	254.9	-268.6	252.5	-271.0	-44.3	30.6	-46.7	28.2	145.5	361.9	-378.0	-161.6	80.0	136.2	78.2	134.4	242.4
Story12	D12	A13.5	462	-6.59	-0.51	1.09	-37.22	263.48	-107.50	2.20	215.17	-6.7	-10.2	413.1	-430.0	309.1	-323.3	306.4	-325.9	-51.8	37.6	-54.4	34.9	178.7	436.7	-453.6	-195.6	99.5	166.6	97.6	164.6	293.2
Story11	D12	A13.5	462	-6.78	-0.53	1.17	-35.30	258.09	-101.98	2.28	213.94	-6.8	-10.5	404.3	-421.6	302.5	-317.0	299.6	-319.8	-49.6	35.1	-52.4	32.3	178.7	423.4	-440.7	-196.0	101.2	164.8	99.1	162.7	284.9
Story10	D12	A13.5	462	-6.96	-0.55	1.25	-34.63	261.50	-100.09	2.37	219.92	-6.9	-10.9	409.5	-427.3	306.4	-321.2	303.4	-324.2	-49.0	34.2	-52.0	31.2	184.8	425.0	-442.8	-202.6	106.4	168.8	104.2	166.6	286.8
Story9	D12	A13.5	462	-6.77	-0.53	1.24	-34.41	265.99	-99.51	2.27	228.78	-6.7	-10.6	416.9	-434.2	312.0	-326.4	309.1	-329.3	-48.5	34.1	-51.4	31.2	191.1	430.0	-447.3	-208.4	111.4	173.4	109.2	171.2	290.7
Story8	D12	A13.5	462	-6.96	-0.54	1.32	-34.39	272.44	-99.49	2.36	238.69	-6.8	-11.0	427.0	-444.8	319.6	-334.2	316.5	-337.4	-48.6	34.0	-51.7	30.8	198.6	437.4	-455.2	-216.4	117.1	179.1	114.7	176.7	296.3
Story7	D12	A13.5	462	-6.79	-0.52	1.30	-34.11	276.18	-98.71	2.28	248.15	-6.6	-10.7	433.2	-450.6	324.3	-338.5	321.2	-341.6	-48.0	33.8	-51.2	30.7	204.3	441.2	-458.5	-221.6	121.7	183.1	119.3	180.8	299.5
Story6	D12	A13.5	462	-6.96	-0.54	1.38	-33.76	280.49	-97.76	2.36	257.10	-6.7	-11.1	439.9	-457.7	329.4	-343.8	326.0	-347.1	-47.8	33.3	-51.1	30.0	210.4	445.0	-462.8	-228.2	126.5	187.4	124.1	184.9	302.7
Story5	D12	A13.5	462	-6.80	-0.52	1.37	-33.25	281.09	-96.33	2.30	264.46	-6.5	-10.9	441.1	-458.4	330.3	-344.3	327.0	-347.6	-46.9	32.9	-50.2	29.6	213.0	444.2	-461.6	-230.4	129.0	188.9	126.6	186.5	302.6
Story4	D12	A13.5	462	-6.96	-0.54	1.44	-32.64	279.63	-94.61	2.39	269.11	-6.6	-11.2	438.5	-456.3	328.4	-342.7	324.9	-346.2	-46.3	32.0	-49.8	28.5	213.1	440.2	-458.0	-230.9	129.7	188.5	127.1	185.9	300.1
Story3	D12	A13.5	462	-7.13	-0.55	1.52	-31.30	268.66	-90.79	2.48	266.34	-6.7	-11.5	420.7	-439.0	315.1	-329.7	311.5	-333.3	-44.8	30.3	-48.5	26.6	204.3	422.2	-440.4	-222.6	124.3	180.7	121.6	177.9	287.9
Story2	D12	A13.5	462	-7.29	-0.57	1.59	-28.07	235.18	-81.49	2.57	245.52	-6.8	-11.9	367.0	-385.6	274.8	-289.6	271.0	-293.4	-41.1	26.3	-44.9	22.5	175.1	370.7	-389.3	-193.7	105.3	155.8	102.4	153.0	252.1
Story1	D12	A13.5	462	-7.78	-0.65	1.84	-17.27	129.63	-50.21	2.96	159.96	-7.0	-12.9	197.4	-217.4	147.8	-163.3	143.4	-167.7	-28.5	13.0	-32.9	8.5	85.3	205.8	-225.8	-105.3	47.7	78.8	44.3	75.5	138.1
Ground	D12	A11	376	-7.29	-0.59	1.47	4.80	-79.23	13.88	2.35	40.58	-7.0	-11.7	-136.1	117.4	-102.6	87.5	-106.2	84.0	-1.8	-13.3	-5.3	-16.9	-87.8	-121.1	102.4	69.1	-62.5	-71.2	-65.2	-73.9	-87.6
B1	D12	A11	376	-7.39	-0.62	1.47	3.23	-55.47	9.32	2.35	28.94	-7.1	-11.8	-98.2	79.3	-74.3	58.8	-77.8	55.3	-3.8	-11.6	-7.4	-15.1	-64.9	-87.2	68.3	45.9	-46.8	-52.6	-49.5	-55.3	-63.6
B2	D12	A11	376	-7.48	-0.65	1.47	1.59	-26.64	4.60	2.34	14.60	-7.3	-12.0	-52.2	33.0	-39.8	24.1	-43.4	20.6	-6.0	-9.8	-9.5	-13.3	-36.1	-47.1	27.9	16.8	-26.7	-29.6	-29.4	-32.2	-35.0
B3	D12	A11	376	-7.57	-0.69	1.47	-0.05	3.21	-0.14	2.34	6.42	-7.4	-12.1	-4.6	-14.9	-4.2	-11.9	-7.7	-15.4	-8.1	-8.0	-11.6	-11.5	-6.1	-5.8	-13.8	-13.5	-5.7	-5.6	-8.4	-8.3	-5.5

SIMPSON GUMPERTZ & HEGER
Engineering of Structures and Building Enclosures

CLIENT Pacific Earthquake Engineering Research Center
SUBJECT BRB Strength Check along Line 3 for LA BRBF Bldg: PB Dsgn

SHEET NO. _____
PROJECT NO. 087237.10
DATE 1/23/09
BY AD
CHECKED BY _____

Model: 011609PBModel1

Scale-X= 1.00
Scale-Y= 1.00

SDS = 1.145
ρ-X dir = 1
ρ -Y dir = 1

1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9
1	1	1	1	1	1	1	1	1	1	1																									
0.9008	0.9008	-0.9008	-0.9008	0.9008	0.9008	-0.9008	-0.9008	0.9008	-0.9008	-0.9008	1.6	-1.6				1.2	1.2	-1.2	-1.2	1.2	1.2	-1.2	-1.2												
0.9008	0.9008	-0.9008	0.9008	-0.9008	-0.9008	-0.9008	-0.9008	-0.9008	0.9008	0.9008										1.2	-1.2	1.2	-1.2												
-0.9008	-0.9008	-0.9008	-0.9008	-0.9008	0.9008	-0.9008	0.9008	0.9008	-0.9008	0.9008			1.6	-1.6	1.2	-1.2	1.2	-1.2									1.2	1.2	-1.2	-1.2					
0.9008	-0.9008	-0.9008	-0.9008	-0.9008	-0.9008	0.9008	-0.9008	0.9008	-0.9008	0.9008																	1.2	-1.2	1.2	-1.2					
Figure 6-9 Case 4											Figure 6-9 Case 1				Figure 6-9 Case 2					Figure 6-9 Case 3														

Story	ETABS #	Section	Capacity	Dead	Live	WindFX	WindMTX	WindFY	WindMTY																										
Story40	D12	A7	239	-2.99	0.00	0.00	-7.88	10.30	-22.66	-40.4	0.4	14.6	0.4	14.6	33.2	-26.2	33.2	-26.2	19.0	-40.4	-2.7	-2.7	13.8	-19.2	9.7	-15.1	9.7	-15.1	-12.1	6.8	-12.1	6.8	-17.5	36.9	-42.2	12.1
Story39	D12	A7	239	-3.45	-0.07	0.01	-8.82	18.43	-25.36	-51.6	-5.9	10.0	-5.9	10.0	43.2	-35.7	43.2	-35.7	27.3	-51.6	-3.1	-3.1	26.4	-32.6	19.0	-25.2	19.0	-25.2	-13.7	7.5	-13.7	7.5	-11.4	49.4	-55.7	5.2
Story38	D12	A9	308	-4.00	-0.14	0.02	-12.10	32.87	-34.79	-76.8	-14.1	7.7	-14.1	7.7	66.9	-55.0	66.9	-55.0	45.1	-76.8	-3.6	-3.6	49.0	-56.2	35.9	-43.0	35.8	-43.1	-18.1	11.0	-18.2	10.9	-5.9	77.6	-84.8	-1.3
Story37	D12	A9	308	-4.47	-0.21	0.05	-12.98	43.58	-37.29	-90.1	-22.9	0.4	-23.0	0.5	79.0	-66.8	78.9	-66.7	55.5	-90.2	-3.9	-4.1	65.7	-73.7	48.3	-56.2	48.2	-56.4	-19.5	11.6	-19.7	11.5	3.5	93.0	-101.1	-11.6
Story36	D12	A9	308	-4.94	-0.28	0.09	-14.28	54.09	-40.97	-104.6	-30.8	-5.3	-31.0	-5.1	92.4	-79.1	92.2	-78.9	66.5	-104.8	-4.3	-4.6	82.1	-91.0	60.6	-69.2	60.3	-69.5	-21.4	12.8	-21.7	12.6	11.3	109.6	-118.5	-20.2
Story35	D12	A9	308	-5.41	-0.35	0.15	-15.48	60.61	-44.47	-115.3	-35.2	-7.6	-35.4	-7.3	101.9	-87.7	101.6	-87.4	73.7	-115.6	-4.6	-5.1	92.1	-101.8	68.0	-77.4	67.7	-77.8	-23.3	13.9	-23.6	13.5	14.5	121.2	-131.0	-24.2
Story34	D12	A9	308	-5.88	-0.41	0.21	-16.35	70.84	-46.97	-128.1	-43.5	-14.4	-43.9	-14.1	113.6	-99.0	113.2	-98.7	83.7	-128.5	-5.0	-5.6	108.0	-118.6	80.0	-90.0	79.5	-90.5	-24.7	14.6	-25.2	14.1	23.4	136.1	-146.7	-33.9
Story33	D12	A9	308	-5.64	-0.40	0.23	-17.58	81.06	-50.51	-141.3	-50.3	-19.1	-50.7	-18.6	127.4	-110.0	127.0	-109.6	95.3	-141.7	-4.7	-5.4	124.6	-134.8	92.5	-102.1	91.9	-102.6	-25.9	16.3	-26.4	15.7	31.6	152.8	-163.0	-41.7
Story32	D12	A9	308	-6.05	-0.45	0.30	-18.84	91.74	-54.14	-155.8	-58.3	-24.9	-58.8	-24.3	140.9	-122.4	140.4	-121.9	106.5	-156.4	-5.0	-5.9	141.3	-152.2	105.0	-115.2	104.3	-115.9	-27.7	17.5	-28.4	16.8	39.7	169.6	-180.5	-50.6
Story31	D12	A9	308	-5.36	-0.37	0.27	-20.12	101.29	-57.82	-168.0	-63.8	-28.1	-64.3	-27.6	154.9	-132.2	154.4	-131.8	118.1	-168.5	-4.4	-5.3	157.2	-166.9	117.0	-126.0	116.4	-126.7	-28.6	19.6	-29.3	19.0	47.3	186.1	-195.8	-57.0
Story30	D12	A9	308	-5.66	-0.41	0.33	-21.19	109.74	-60.88	-179.7	-70.0	-32.4	-70.6	-31.8	165.9	-142.1	165.3	-141.5	127.1	-180.3	-4.6	-5.6	170.5	-180.7	127.0	-136.4	126.2	-137.2	-30.1	20.7	-30.9	19.9	53.5	199.6	-209.8	-63.7
Story29	D12	A11	376	-5.56	-0.40	0.35	-26.26	137.17	-75.47	-222.0	-86.0	-39.3	-86.6	-38.7	208.4	-175.3	207.8	-174.6	160.5	-222.6	-4.4	-5.6	214.5	-224.5	160.0	-169.2	159.2	-170.0	-36.1	26.9	-36.9	26.1	69.0	250.2	-260.2	-79.0
Story28	D12	A11	376	-5.83	-0.43	0.42	-27.18	144.54	-78.15	-232.1	-91.3	-43.1	-92.1	-42.4	218.0	-183.9	217.3	-183.2	168.3	-232.9	-4.6	-5.9	226.0	-236.5	168.7	-178.2	167.7	-179.2	-37.4	27.9	-38.4	26.9	74.4	262.0	-272.5	-84.9
Story27	D12	A11	376	-5.32	-0.37	0.38	-27.11	145.02	-77.96	-231.7	-91.2	-43.1	-91.9	-42.4	218.9	-183.5	218.2	-182.8	169.3	-232.4	-4.2	-5.4	227.2	-236.8	169.7	-178.3	168.8	-179.3	-36.8	28.2	-37.8	27.3	75.7	262.8	-272.4	-85.2
Story26	D12	A11	376	-5.54	-0.40	0.45	-27.97	152.23	-80.47	-241.5	-96.5	-46.9	-97.3	-46.1	228.2	-191.9	227.4	-191.1	177.0	-242.3	-4.3	-5.7	238.6	-248.6	178.2	-187.1	177.2	-188.2	-38.0	29.1	-39.1	28.0	81.1	274.3	-284.2	-91.1
Story25	D12	A11	376	-5.77	-0.43	0.51	-29.02	161.51	-83.50	-253.7	-103.3	-51.9	-104.2	-51.0	239.9	-202.4	239.0	-201.5	186.7	-254.7	-4.4	-6.0	253.2	-263.6	189.2	-198.4	188.0	-199.6	-39.4	30.2	-40.6	29.0	88.4	288.8	-299.2	-98.8
Story24	D12	A11	376	-6.00	-0.46	0.58	-29.51	167.36	-84.92	-261.0	-108.0	-55.9	-109.0	-54.8	246.7	-208.9	245.7	-207.8	192.5	-262.0	-4.5	-6.3	262.4	-273.2	196.1	-205.5	194.7	-206.9	-40.1	30.7	-41.5	29.3	93.5	297.3	-308.1	-104.3
Story23	D12	A11	376	-5.82	-0.43	0.58	-28.27	162.21	-81.41	-251.8	-105.2	-55.3	-106.2	-54.2	238.0	-201.9	237.0	-200.9	186.0	-252.9	-4.3	-6.2	254.3	-264.8	190.1	-199.2	188.7	-200.6	-38.5	29.4	-39.9	28.0	91.7	287.1	-297.6	-102.2
Story22	D12	A11	376	-6.04	-0.46	0.65	-28.48	166.63	-82.03	-256.8	-109.0	-58.9	-110.2	-57.7	242.5	-206.6	241.4	-205.5	190.0	-258.0	-4.4	-6.5	261.2	-272.0	195.3	-204.6	193.7	-206.2	-38.8	29.5	-40.4	28.0	96.1	293.0	-303.8	-107.0
Story21	D12	A11	376	-6.26	-0.49	0.73	-29.09	173.90	-83.81	-265.7	-114.7	-63.6	-116.0	-62.3	251.0	-214.6	249.7	-213.3	197.3	-267.0	-4.5	-6.8	272.6	-283.9	203.9	-213.4	202.2	-215.2	-39.7	30.1	-41.4	28.4	102.5	303.6	-314.9	-113.7
Story20	D12	A11	376	-6.48	-0.51	0.81	-29.67	178.34	-85.49	-271.9	-117.9	-65.9	-119.4	-64.5	256.8	-219.9	255.4	-218.5	201.9	-273.4	-4.5	-7.1	279.5	-291.2	209.1	-218.9	207.2	-220.8	-40.5	30.7	-42.4	28.8	105.6	310.8	-322.4	-117.2
Story19	D12	A11	376	-6.26	-0.49	0.80	-30.12	184.43	-86.80	-278.7	-122.4	-69.5	-123.8	-68.1	264.2	-225.9	262.7	-224.5	208.5	-280.2	-4.4	-6.9	289.5	-300.7	216.6	-226.0	214.7	-227.9	-40.8	31.5	-42.7	29.6	111.5	319.8	-331.1	-122.8
Story18	D12	A11	376	-6.46	-0.51	0.87	-30.55	192.70	-88.06	-287.9	-129.3	-75.8	-130.8	-74.2	272.9	-234.4	271.4	-232.9	216.3	-289.5	-4.4	-7.2	302.5	-314.1	226.5	-236.0	224.4	-238.1	-41.4	31.9	-43.5	29.8	119.7	331.1	-342.7	-131.4
Story17	D12	A11	376	-5.95	-0.45	0.80	-30.80	197.43	-88.81	-292.5	-132.5	-78.4	-133.9	-77.0	278.7	-238.4	277.3	-237.0	221.8	-293.9	-4.1	-6.6	310.5	-321.2	232.5	-241.3	230.6	-243.2	-41.4	32.6	-43.3	30.6	125.0	338.1	-348.8	-135.7
Story16	D12	A11	376	-6.13	-0.47	0.87	-31.06	202.98	-89.61	-298.6	-137.1	-82.7	-138.7	-81.2	284.5	-244.2	282.9	-242.6	227.0	-300.1	-4.1	-6.9	319.3	-330.3	239.1	-248.0	237.0	-250.1	-41.8	32.8	-43.8	30.7	130.5	345.6	-356.6	-141.6
Story15	D12	A11	376	-6.30	-0.49	0.94	-31.28	209.50	-90.27	-305.4	-142.8	-88.1	-144.5	-86.4	291.0	-250.0	289.3	-249.1	233.0	-307.1	-4.2	-7.2	329.5	-340.9	246.3	-256.0	244.6	-258.2	-42.1	33.0	-44.3	30.7	137.4	354.1	-365.4	-148.8
Story14	D12	A11	376	-6.49	-0.51	1.01	-31.44	216.10	-90.74	-312.1	-148.6	-93.8	-150.5	-92.0	297.3	-257.3	295.5	-255.5	238.9	-313.9	-4.2	-7.5	339.9	-351.6	254.7	-263.9	252.3	-266.4	-42.4	33.1	-44.8	30.7	144.6	362.4	-374.1	-156.3
Story13	D12	A11	376	-6.31	-0.48	1.00	-31.23	218.12	-90.17	-313.0	-150.5	-96.1	-152.3	-94.3	298.7	-258.5	296.9	-256.7	240.6	-314.8	-4.1	-7.3	343.3	-354.7	257.3	-266.2	254.9	-268.6	-41.9	33.0	-44.4	30.6	147.9	364.3	-375.6	-159.2
Story12	D12	A13.5	462	-6.59	-0.51	1.09	-37.22	263.48	-107.50	-375.1	-181.5	-116.4	-183.4	-114.4	360.3	-310.1	358.3	-308.1	291.2	-377.1	-4.2	-7.7	415.6	-427.5	311.6	-320.8	308.9	-323.4	-49.3	40.0	-51.9	37.4	181.2	439.2	-451.1	-193.1
Story11	D12	A13.5	462	-6.78	-0.53	1.17	-35.30	258.09	-101.98	-363.7	-180.0	-118.5	-182.1	-116.4	348.5	-302.3	346.4	-300.2	282.8	-365.9	-4.2	-8.0	406.8	-419.0	305.0	-314.4	302.2	-317.2	-47.0	37.7	-49.9	34.9	181.2	426.0	-438.2	-193.4
Story10	D12	A13.5	462	-6.96	-0.55	1.25	-34.63	261.50	-100.09	-364.7	-184.4	-124.2	-186.6	-122.0	349.1	-304.6	346.9	-302.3	284.5	-366.9	-4.3	-8.3	412.1	-424.7	309.0	-318.6	306.0	-321.6	-46.3	36.8	-49.3	33.8	187.4	427.6	-440.2	-199.9
Story9	D12	A13.5	462	-6.77	-0.53	1.24	-34.41	265.99	-99.51	-367.8	-188.5	-128.7	-190.7	-126.5	352.7	-308.0	350.5	-305.8	288.5	-370.0	-4.1	-8.1	419.5	-431.7	314.6	-323.8	311.6	-326.8	-45.9	36.7	-48.9	33.7	193.7	432.5	-444.7	-205.9
Story8	D12	A13.5	462	-6.96	-0.54	1.32	-34.39	272.44	-99.49	-373.7	-194.5	-134.9	-196.9	-132.5	358.3	-314.1	355.9	-311.8	294.0	-376.1	-4.2	-8.4	429.6	-442.2	322.2	-331.6	319.1	-334.8	-46.0	36.6	-49.1	33.4	201.3	440.1	-452.6	-213.8
Story7	D12	A13.5	462	-6.79	-0.52	1.30	-34.11	276.18	-98.71	-375.9	-198.1	-139.0	-200.4	-136.6	360.9	-316.8	358.6	-314.5	297.1	-378.3	-4.0	-8.2	435.8	-448.0	326.9	-336.0	323.8	-339.1	-45.5	36.4	-48.6	33.3	206.9	443.8	-456.0	-219.1
Story6	D12	A13.5	462	-6.96	-0.54	1.38	-33.76	280.49	-97.76	-378.8	-202.7	-144.3	-205.1	-141.8	363.5	-320.5	361.0	-318.0	300.2	-381.3	-4.1	-8.5	442.5	-455.0	332.0	-341.2	328.7	-344.5	-45.1	35.9	-48.4	32.6	213.0	447.6	-460.2	-225.5
Story5	D12	A13.5	462	-6.80	-0.52	1.37	-33.25	281.09	-96.33	-377.4	-203.8	-146.4	-206.3	-143.9	362.5	-319.9	360.0	-317.5	300.1	-379.8	-3.9	-8.3	443.6	-455.9	332.8	-341.8	329.5	-345.1	-44.4	35.4	-47.7	32.1	215.6	446.8	-459.0	-227.8
Story4	D12	A13.5	462	-6.96	-0.54	1.44	-32.64	279.63	-94.61	-374.1	-203.7	-147.5	-206.3	-144.9	358.9	-317.9	356.3	-315.3	297.5	-376.7	-4.0	-8.6	441.1	-453.7	331.0	-340.1	327.6	-343.6	-43.7	34.6	-47.2	31.2	215.7	442.8	-455.4	-228.3
Story3	D12	A13.5	462	-7.13	-0.55	1.52	-31.30	268.66	-90.79	-359.7	-196.2	-142.5	-198.9	-139.8	344.2	-306.1	341.5	-303.3	285.1	-362.5	-4.0	-8.8	423.4	-436.3	317.8	-327.0	314.2	-330.6	-42.2	33.0	-45.8	29.3	207.0	424.9	-437.7	-219.9
Story2	D12	A13.5	462	-7.29	-0.57	1.59	-28.07	235.18	-81.49	-318.4	-171.6	-123.9	-174.5	-121.0	302.7	-270.7	299.8	-267.9	249.2	-321.3	-4.0	-9.1	369.7	-382.9	277.6	-286.9	273.7	-290.7	-38.3	29.0	-42.2	25.2	177.9	373.4	-386.6	-191.0
Story1	D12	A13.5	462	-7.78	-0.65	1.84	-17.27	129.63	-50.21	-185.9	-95.4	-67.6	-98.7	-64.3	169.2	-158.1	165.9	-154.8	134.8	-189.2	-4.0	-10.0	200.4	-214.4	150.8	-160.3	146.3	-164.8	-25.5	15.9	-29.9	11.5	88.3	208.8	-222.8	-102.3
Ground	D12	A11	376	-7.29	-0.59	1.47	4.80	-79.23	13.88	80.2	55.2	43.9	52.5	46.5	-96.2	68.9	-98.9	71.5	-90.2	77.5	-4.2	-8.9	-133.3	120.2	-99.9	90.3	-103.4	86.7	1.0	-10.6	-2.6	-14.1	-85.0	-118.3	105.2	71.9
B1	D12	A11	376	-7.39	-0.62	1.47	3.23	-55.47	9.32	53.1	36.3	27.9	33.7	30.5	-69.4	44.7	-72.1	47.3	-66.3	50.5	-4.3	-9.0	-95.4	82.1	-71.4	61.7	-75.0	58.2	-1.0	-8.8	-4.5	-12.3	-62.0	-84.4	71.1	48.7
B2	D12	A11	376	-7.48	-0.65	1.47	1.59	-26.64	4.60	21.3	13.0	7.5	10.3	10.1	-37.9	15.8	-40.5	18.4	-37.7	18.6	-4.4	-9.1	-49.4	35.9	-36.9	27.0	-40.5	23.5	-3.1	-6.9	-6.6	-10.4	-33.2	-44.2	30.8	19.7
B3	D12	A11	376	-7.57	-0.69	1.47	-0.05	3.21	-0.14	-11.5	-11.3	-13.8	-13.9	-11.2	-5.4	-14.1	-8.0	-11.4	-8.1	-14.2	-4.5	-9.2	-1.7	-12.0	-1.2	-8.9	-4.7	-12.4	-5.1	-5.0	-8.6	-8.5	-3.1	-2.8	-10.8	-10.5

SIMPSON GUMPERTZ & HEGER
Engineering of Structures and Building Enclosures

CLIENT Pacific Earthquake Engineering Research Center
SUBJECT BRB Strength Check along Line 3 for LA BRBF Bldg: PB Dsgn

SHEET NO. ____
PROJECT NO. 087237.10
DATE 1/23/09
BY AD
CHECKED BY ____

Model: 011609PBModel1

Scale-X= 1.00
Scale-Y= 1.00

SDS = 1.145
ρ-X dir = 1
ρ -Y dir = 1

0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	1	1	1	1	1	1	1	1
																	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25
0.9008	0.9008	-0.9008	-0.9008	0.9008	0.9008	0.9008	-0.9008	-0.9008	0.9008	0.9008	-0.9008	-0.9008	0.9008	-0.9008	-0.9008									
0.9008	-0.9008	0.9008	-0.9008	0.9008	0.9008	0.9008	-0.9008	0.9008	-0.9008	-0.9008	-0.9008	-0.9008	-0.9008	0.9008	0.9008									
0.9008	0.9008	0.9008	0.9008	0.9008	-0.9008	-0.9008	-0.9008	-0.9008	-0.9008	-0.9008	0.9008	0.9008	-0.9008	0.9008	-0.9008									
0.9008	0.9008	0.9008	0.9008	-0.9008	0.9008	-0.9008	-0.9008	-0.9008	-0.9008	-0.9008	0.9008	-0.9008	0.9008	-0.9008	0.9008									
																	1	0.3	-1	-0.3	0.3	1	-1	-0.3
																	0.3	1	0.3	1	-1	-0.3	-0.3	-1

Figure 6-9 Case 4

Story	ETABS #	Section	Capacity	Dead	Live	WindFX	WindMTX	WindFY	WindMTY																									Maximum Axial Loads			
																																		Tension	Compression	DCR	Status
Story40	D12	A7	239	-2.99	0.00	0.00	-7.88	10.30	-22.66	-20.9	-6.7	-20.9	-6.7	19.9	-39.5	1.3	15.5	1.3	15.5	34.1	-25.3	34.1	-25.3	19.9	-39.5	16.7	62.5	16.7	62.5	-68.5	-22.6	-22.7	-68.5	62.55	-68.53	0.29	OK
Story39	D12	A7	239	-3.45	-0.07	0.01	-8.82	18.43	-25.36	-17.3	-1.4	-17.3	-1.4	28.4	-50.5	-4.8	11.1	-4.8	11.1	44.3	-34.6	44.3	-34.6	28.4	-50.5	19.9	74.0	19.6	73.9	-80.8	-26.5	-26.8	-80.9	73.99	-80.92	0.34	OK
Story38	D12	A9	308	-4.00	-0.14	0.02	-12.10	32.87	-34.79	-16.2	5.6	-16.3	5.6	46.5	-75.4	-12.8	9.0	-12.8	9.1	68.3	-53.7	68.2	-53.6	46.4	-75.5	33.0	118.6	32.4	118.4	-126.5	-40.5	-41.1	-126.6	118.57	-126.64	0.41	OK
Story37	D12	A9	308	-4.47	-0.21	0.05	-12.98	43.58	-37.29	-10.0	13.4	-10.1	13.3	57.2	-88.5	-21.3	2.0	-21.4	2.1	80.6	-65.2	80.5	-65.1	57.1	-88.6	36.0	129.2	35.1	128.9	-137.9	-44.1	-45.1	-138.2	129.18	-138.23	0.45	OK
Story36	D12	A9	308	-4.94	-0.28	0.09	-14.26	54.09	-40.97	-5.4	20.3	-5.6	20.1	68.4	-102.8	-29.0	-3.5	-29.2	-3.3	94.1	-77.3	93.9	-77.1	68.3	-103.0	39.7	141.9	38.3	141.5	-151.5	-48.3	-49.7	-151.9	141.91	-151.92	0.49	OK
Story35	D12	A9	308	-5.41	-0.35	0.15	-15.48	60.61	-44.47	-4.1	23.7	-4.4	23.5	76.0	-113.3	-33.2	-5.6	-33.5	-5.3	103.9	-85.7	103.6	-85.4	75.7	-113.6	38.9	139.4	36.9	138.8	-149.8	-47.9	-49.9	-150.4	139.43	-150.42	0.49	OK
Story34	D12	A9	308	-5.88	-0.41	0.21	-16.35	70.84	-46.97	1.7	31.1	1.3	30.8	86.3	-125.9	-41.3	-12.3	-41.7	-11.9	115.7	-96.9	115.4	-96.5	85.9	-126.3	40.3	144.6	37.8	143.8	-155.8	-49.8	-52.3	-156.6	144.60	-156.56	0.51	OK
Story33	D12	A9	308	-5.64	-0.40	0.23	-17.58	81.06	-50.51	6.8	38.5	6.4	38.1	97.8	-139.2	-48.2	-17.0	-48.6	-16.6	129.5	-108.0	129.1	-107.5	97.4	-139.6	42.0	149.6	39.5	148.8	-160.3	-50.9	-53.5	-161.0	152.81	-165.04	0.54	OK
Story32	D12	A9	308	-6.05	-0.45	0.30	-18.84	91.74	-54.14	11.7	45.7	11.2	45.1	109.3	-153.6	-56.0	-22.6	-56.6	-22.1	143.2	-120.1	142.7	-119.6	108.7	-154.1	42.3	150.8	39.2	149.8	-162.1	-51.6	-54.6	-163.1	169.61	-182.76	0.59	OK
Story31	D12	A9	308	-5.36	-0.37	0.27	-20.12	101.29	-57.82	16.5	52.7	16.0	52.2	120.6	-166.0	-61.9	-26.1	-62.4	-25.6	156.9	-130.3	156.4	-129.8	120.1	-166.5	43.0	152.2	40.4	151.4	-162.3	-51.3	-53.9	-163.1	186.10	-197.73	0.64	OK
Story30	D12	A9	308	-5.66	-0.41	0.33	-21.19	109.74	-60.88	20.1	58.3	19.5	57.7	129.8	-177.6	-67.9	-30.3	-68.5	-29.7	168.0	-140.0	167.4	-139.4	129.2	-178.2	42.0	148.7	38.9	147.8	-159.3	-50.5	-53.5	-160.2	199.65	-211.95	0.69	OK
Story29	D12	A11	376	-5.56	-0.40	0.35	-26.26	137.17	-75.47	27.2	74.5	26.6	73.9	163.2	-219.9	-83.9	-37.3	-84.6	-36.6	210.5	-173.2	209.9	-172.6	162.6	-220.5	48.8	171.4	45.8	170.5	-181.8	-57.1	-60.2	-182.7	250.16	-262.24	0.70	OK
Story28	D12	A11	376	-5.83	-0.43	0.42	-27.18	144.54	-78.15	30.4	79.4	29.7	78.7	171.2	-230.0	-89.2	-40.5	-89.9	-40.2	220.2	-181.7	219.5	-181.0	170.5	-230.7	46.9	164.9	43.5	163.9	-175.8	-55.4	-58.7	-176.8	261.98	-274.67	0.73	OK
Story27	D12	A11	376	-5.32	-0.37	0.38	-27.11	145.02	-77.96	31.5	80.4	30.9	79.7	172.0	-229.7	-89.3	-41.1	-89.9	-40.4	220.8	-181.6	220.1	-180.9	171.3	-230.4	43.0	151.6	40.1	150.7	-161.5	-50.9	-53.8	-162.4	262.79	-274.32	0.73	OK
Story26	D12	A11	376	-5.54	-0.40	0.45	-27.97	152.23	-80.47	34.9	85.2	34.1	84.4	179.8	-239.4	-94.4	-44.8	-95.2	-44.0	230.2	-189.8	229.4	-189.0	179.0	-240.2	42.3	149.1	39.0	148.2	-159.5	-50.3	-53.5	-160.4	274.26	-286.30	0.76	OK
Story25	D12	A11	376	-5.77	-0.43	0.51	-29.02	161.51	-83.50	39.4	91.7	38.5	90.8	189.8	-251.6	-101.1	-49.8	-102.1	-48.9	242.1	-200.2	241.2	-199.3	188.9	-252.5	42.1	148.7	38.6	147.7	-159.4	-50.3	-53.9	-160.5	288.81	-301.36	0.80	OK
Story24	D12	A11	376	-6.00	-0.46	0.58	-29.51	167.36	-84.92	42.8	96.0	41.8	94.9	195.8	-258.7	-105.7	-53.6	-106.8	-52.6	249.0	-206.6	247.9	-205.6	194.8	-259.8	41.2	145.8	37.4	144.7	-156.9	-49.6	-53.4	-158.0	297.34	-310.40	0.82	OK
Story23	D12	A11	376	-5.82	-0.43	0.58	-28.27	162.21	-81.41	42.6	93.5	41.6	92.5	189.3	-249.6	-103.0	-53.1	-104.0	-52.0	240.2	-199.8	239.2	-198.7	188.2	-250.7	38.0	135.1	34.4	134.0	-145.9	-46.2	-49.9	-146.9	287.10	-299.77	0.80	OK
Story22	D12	A11	376	-6.04	-0.46	0.65	-28.48	166.63	-82.03	45.7	97.0	44.5	95.8	193.5	-254.5	-106.7	-56.6	-107.9	-55.4	244.8	-204.4	243.6	-203.2	192.3	-255.7	37.7	134.0	33.8	132.8	-145.1	-46.1	-50.0	-146.3	292.96	-306.11	0.81	OK
Story21	D12	A11	376	-6.26	-0.49	0.73	-29.09	173.90	-83.81	50.0	102.4	48.7	101.1	201.0	-263.3	-112.3	-61.2	-113.6	-59.9	253.4	-212.2	252.1	-210.9	199.6	-264.6	38.3	136.1	34.1	134.9	-147.7	-46.9	-51.0	-148.9	303.62	-317.25	0.84	OK
Story20	D12	A11	376	-6.48	-0.51	0.81	-29.67	178.34	-85.49	51.8	105.3	50.4	103.8	205.8	-269.5	-115.5	-63.5	-116.9	-62.0	259.3	-217.5	257.8	-216.0	204.4	-270.9	38.1	135.7	33.7	134.4	-147.6	-46.9	-51.3	-148.9	310.77	-324.89	0.86	OK
Story19	D12	A11	376	-6.26	-0.49	0.80	-30.12	184.43	-86.80	55.9	110.2	54.5	108.7	212.3	-276.4	-120.0	-67.2	-121.4	-65.7	266.5	-223.5	265.1	-222.1	210.8	-277.8	39.1	138.8	34.9	137.6	-150.3	-47.7	-51.8	-151.6	319.85	-333.47	0.89	OK
Story18	D12	A11	376	-6.46	-0.51	0.87	-30.55	192.70	-88.06	61.7	116.7	60.1	115.2	220.4	-285.4	-126.8	-73.3	-128.4	-71.8	275.4	-232.0	273.8	-230.4	218.8	-287.0	40.4	143.4	36.0	142.0	-155.2	-49.2	-53.6	-156.5	331.09	-345.17	0.92	OK
Story17	D12	A11	376	-5.95	-0.45	0.80	-30.80	197.43	-88.81	65.5	121.0	64.0	119.5	225.5	-290.2	-130.2	-76.2	-131.7	-74.7	281.0	-236.2	279.5	-234.7	224.0	-291.7	42.2	148.8	38.3	147.7	-159.8	-50.4	-54.3	-160.9	338.14	-351.08	0.93	OK
Story16	D12	A11	376	-6.13	-0.47	0.87	-31.06	202.98	-89.61	69.4	125.4	67.8	123.8	230.8	-296.3	-134.8	-80.4	-136.4	-78.9	286.8	-241.9	285.2	-240.3	229.3	-297.8	43.7	154.0	39.6	152.8	-165.3	-52.1	-56.1	-166.5	345.59	-358.92	0.95	OK
Story15	D12	A11	376	-6.30	-0.49	0.94	-31.28	209.50	-90.27	74.4	130.8	72.7	129.1	237.0	-303.0	-140.4	-85.7	-142.1	-84.1	293.4	-248.4	291.7	-246.7	235.3	-304.7	45.4	160.0	41.2	158.7	-171.6	-54.1	-58.2	-172.8	354.05	-367.78	0.98	OK
Story14	D12	A11	376	-6.49	-0.51	1.01	-31.44	216.10	-90.74	79.7	136.3	77.8	134.5	243.1	-309.7	-146.2	-91.4	-148.0	-89.5	299.8	-254.8	298.0	-253.0	241.3	-311.5	47.1	165.9	42.7	164.6	-177.8	-56.0	-60.3	-179.1	362.36	-376.51	1.00	Say OK
Story13	D12	A11	376	-6.31	-0.48	1.00	-31.23	218.12	-90.17	82.4	138.6	80.5	136.8	244.8	-310.6	-148.2	-93.7	-150.0	-91.9	301.1	-256.1	299.3	-254.3	243.0	-312.4	48.5	170.3	44.3	169.0	-181.9	-57.2	-61.3	-183.1	364.26	-377.99	1.00	Say OK
Story12	D12	A13.5	462	-6.59	-0.51	1.09	-37.22	263.48	-107.50	102.0	169.1	100.1	167.1	295.7	-372.7	-179.0	-113.9	-181.0	-111.9	362.8	-307.6	360.8	-305.6	293.7	-374.6	60.0	209.1	55.6	207.8	-221.2	-69.1	-73.5	-222.5	439.24	-453.60	0.98	OK
Story11	D12	A13.5	462	-6.78	-0.53	1.17	-35.30	258.09	-101.98	103.8	167.4	101.7	165.3	287.5	-361.2	-177.5	-116.0	-179.6	-113.9	351.1	-299.7	349.0	-297.6	285.4	-363.3	59.6	207.7	55.0	206.4	-220.2	-68.8	-73.4	-221.5	425.98	-440.74	0.95	OK
Story10	D12	A13.5	462	-6.96	-0.55	1.25	-34.63	261.50	-100.09	109.1	171.5	106.8	169.2	289.4	-362.0	-181.7	-121.6	-184.0	-119.3	351.8	-301.9	349.5	-299.7	287.1	-364.3	61.2	213.5	56.5	212.1	-226.3	-70.7	-75.4	-227.7	427.65	-442.81	0.96	OK
Story9	D12	A13.5	462	-6.77	-0.53	1.24	-34.41	265.99	-99.51	114.0	176.0	111.8	173.8	293.3	-365.2	-186.0	-126.2	-188.2	-124.0	355.3	-305.5	353.0	-303.2	291.0	-367.5	64.0	222.6	59.5	221.2	-235.0	-73.3	-77.8	-236.4	432.51	-447.26	0.97	OK
Story8	D12	A13.5	462	-6.96	-0.54	1.32	-34.39	272.44	-99.49	119.7	181.7	117.4	179.3	299.0	-371.1	-191.9	-132.3	-194.2	-129.9	360.9	-311.5	358.6	-309.1	296.6	-373.5	66.9	232.3	62.2	230.9	-245.1	-76.3	-81.1	-246.5	440.06	-455.21	0.99	OK
Story7	D12	A13.5	462	-6.79	-0.52	1.30	-34.11	276.18	-98.71	124.2	185.7	121.9	183.3	302.0	-373.4	-195.5	-136.4	-197.9	-134.1	363.5	-314.3	361.1	-311.9	299.7	-375.7	69.8	241.9	65.3	240.6	-254.4	-79.1	-83.6	-255.8	443.76	-458.54	0.99	OK
Story6	D12	A13.5	462	-6.96	-0.54	1.38	-33.76	280.49	-97.76	129.2	190.0	126.7	187.5	305.3	-376.2	-200.0	-141.7	-202.5	-139.2	366.1	-317.8	363.6	-315.3	302.8	-378.7	72.4	250.7	67.7	249.3	-263.5	-81.9	-86.6	-264.9	447.64	-462.80	1.00	Say OK
Story5	D12	A13.5	462	-6.80	-0.52	1.37	-33.25	281.09	-96.33	131.6	191.5	129.1	189.0	305.1	-374.8	-201.3	-143.8	-203.7	-141.4	365.0	-317.4	362.6	-314.9	302.7	-377.3	74.7	258.2	70.1	256.8	-270.7	-84.0	-88.6	-272.1	446.78	-461.58	1.00	OK
Story4	D12	A13.5	462	-6.96	-0.54	1.44	-32.64	279.63	-94.61	132.3	191.1	129.7	188.5	302.7	-371.5	-201.0	-144.8	-203.6	-142.2	361.5	-315.3	359.0	-312.7	300.2	-374.1	76.0	262.7	71.2	261.3	-275.5	-85.4	-90.2	-276.9	442.82	-457.99	0.99	OK
Story3	D12	A13.5	462	-7.13	-0.55	1.52	-31.30	268.66	-90.79	127.0	183.4	124.3	180.6	290.5	-357.0	-193.5	-139.8	-196.2	-137.1	346.9	-303.4	344.2	-300.6	287.8	-359.8	75.1	259.8	70.2	258.3	-272.9	-84.7	-89.6	-274.4	424.91	-440.44	0.95	OK
Story2	D12	A13.5	462	-7.29	-0.57	1.59	-28.07	235.18	-81.49	108.0	158.6	105.2	155.7	254.8	-315.7	-168.9	-121.2	-171.7	-118.3	305.4	-268.0	302.6	-265.1	252.0	-318.5	68.8	238.9	63.7	237.3	-252.2	-78.5	-83.7	-253.7	373.45	-389.33	0.84	OK
Story1	D12	A13.5	462	-7.78	-0.65	1.84	-17.27	129.63	-50.21	50.6	81.8	47.3	78.4	141.1	-182.9	-92.4	-64.6	-95.8	-61.3	172.2	-155.1	168.9	-151.8	137.8	-186.2	43.0	152.9	37.1	151.1	-167.0	-53.0	-58.9	-168.8	208.80	-225.78	0.49	OK
Ground	D12	A11	376	-7.29	-0.59	1.47	4.80	-79.23	13.88	-59.8	-68.4	-62.4	-71.1	-84.8	83.0	58.0	46.6	55.3	49.3	-93.4	71.7	-96.1	74.3	-87.4	80.3	7.1	33.8	2.4	32.4	-47.3	-17.3	-22.0	-48.7	120.20	-136.10	0.36	OK
B1	D12	A11	376	-7.39	-0.62	1.47	3.23	-55.47	9.32	-44.0	-49.8	-46.6	-52.5	-60.8	55.9	39.2	30.7	36.5	33.3	-66.6	47.5	-69.2	50.1	-63.4	53.3	3.5	22.1	-1.2	20.7	-35.8	-13.9	-18.6	-37.2	82.11	-98.24	0.26	OK
B2	D12	A11	376	-7.48	-0.65	1.47	1.59	-26.64	4.60	-23.8	-26.7	-26.5	-29.3	-32.1	24.2	15.9	10.4	13.2	13.0	-35.0	18.7	-37.6	21.3	-34.8	21.5	-0.9	7.7	-5.6	6.3	-21.5	-9.7	-14.4	-22.9	35.89	-52.25	0.14	OK
B3	D12	A11	376	-7.57	-0.69	1.47	-0.05	3.21	-0.14	-2.8	-2.7	-5.4	-5.3	-2.5	-8.6	-8.3	-10.9	-10.9	-8.2	-2.4	-11.1	-5.1	-8.5	-5.2	-11.2	-3.5	-0.6	-8.2	-2.0	-13.5	-7.3	-12.0	-14.9	-0.62	-15.38	0.04	OK

SIMPSON GUMPERTZ & HEGER
Engineering of Structures and Building Enclosures

CLIENT Pacific Earthquake Engineering Research Center
SUBJECT BRB Strength Check along Line 3 for LA BRBF Bldg: PB Dsgn

SHEET NO. ____
PROJECT NO. 087237.10
DATE 1/23/09
BY AD
CHECKED BY ____

Model: 011609PBModel1

Scale-X= 1.00
Scale-Y= 1.00

SDS = 1.145
ρ-X dir = 1
ρ -Y dir = 1

Dead=	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2
Live=	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
WindFX=	1.6	-1.6			1.2	1.2	-1.2	-1.2	1.2	1.2	-1.2	-1.2									0.9008	0.9008	-0.9008	-0.9008	0.9008	0.9008	-0.9008	-0.9008	0.9008	0.9008	-0.9008	-0.9008	0.9008	0.9008
WindMTX=									1.2	-1.2	1.2	-1.2									0.9008	-0.9008	0.9008	-0.9008	0.9008	-0.9008	0.9008	-0.9008	0.9008	-0.9008	0.9008	-0.9008	0.9008	-0.9008
WindFY=			1.6	-1.6	1.2	-1.2	1.2	-1.2					1.2	1.2	-1.2	-1.2					0.9008	0.9008	0.9008	0.9008	0.9008	0.9008	0.9008	0.9008	0.9008	0.9008	0.9008	0.9008	0.9008	0.9008
WindMTY=													1.2	-1.2	1.2	-1.2					0.9008	0.9008	0.9008	0.9008	0.9008	0.9008	0.9008	0.9008	0.9008	0.9008	0.9008	0.9008	0.9008	-0.9008
SpecX=																																		
SpecY=																																		
Comment	Figure 6-9 Case 1				Figure 6-9 Case 2				Figure 6-9 Case 3																									

Story	ETABS #	Section	Capacity	Dead	Live	WindFX	WindMTX	WindFY	WindMTY	ServSpecX	ServSpecY																							
Story40	D18	A7	239	-2.99	0.00	0.00	7.88	-10.30	22.66	0.01	65.54	-3.6	-3.6	-20.1	12.9	-16.0	8.8	-16.0	8.8	5.9	-13.0	5.9	-13.0	11.2	-43.1	36.0	-18.4	14.6	0.4	14.6	0.4	-26.2
Story39	D18	A7	239	-3.45	-0.07	0.01	8.82	-18.43	25.36	0.14	77.41	-4.2	-4.2	-33.7	25.3	-26.3	17.9	-26.3	17.9	6.4	-14.8	6.4	-14.8	4.1	-56.8	48.3	-12.5	10.0	-5.9	10.0	-5.9	-35.7
Story38	D18	A9	308	-4.00	-0.14	0.02	12.10	-32.87	34.79	0.29	122.52	-4.9	-5.0	-57.5	47.7	-44.4	34.5	-44.4	34.5	9.6	-19.4	9.6	-19.5	-2.6	-86.1	76.3	-7.2	7.7	-14.1	7.7	-14.1	-55.0
Story37	D18	A9	308	-4.47	-0.21	0.05	12.98	-43.58	37.29	0.48	133.56	-5.5	-5.7	-75.3	64.1	-57.8	46.8	-57.9	46.7	10.1	-21.1	9.9	-21.2	-13.1	-102.6	91.5	2.0	0.5	-22.9	0.4	-23.0	-66.7
Story36	D18	A9	308	-4.94	-0.28	0.09	14.26	-54.09	40.97	0.71	146.70	-6.1	-6.4	-92.7	80.3	-71.0	58.8	-71.2	58.6	11.0	-23.2	10.8	-23.4	-21.9	-120.3	107.9	9.5	-5.1	-30.8	-5.3	-31.0	-78.9
Story35	D18	A9	308	-5.41	-0.35	0.15	15.48	-60.61	44.47	0.98	144.63	-6.6	-7.1	-103.8	90.1	-79.4	66.1	-79.7	65.7	11.9	-25.2	11.6	-25.6	-26.2	-132.9	119.3	12.5	-7.3	-35.2	-7.6	-35.4	-87.4
Story34	D18	A9	308	-5.88	-0.41	0.21	16.35	-70.84	46.97	1.26	150.21	-7.1	-7.8	-120.8	105.9	-92.2	77.8	-92.7	77.3	12.4	-26.8	11.9	-27.3	-36.1	-148.8	133.9	21.2	-14.1	-43.5	-14.4	-43.9	-98.7
Story33	D18	A9	308	-5.64	-0.40	0.23	17.58	-81.06	50.51	1.28	154.91	-6.8	-7.5	-136.9	122.5	-104.2	90.4	-104.7	89.8	14.2	-28.0	13.7	-28.5	-43.8	-165.0	150.7	29.5	-18.6	-50.3	-19.1	-50.7	-109.6
Story32	D18	A9	308	-6.05	-0.45	0.30	18.84	-91.74	54.14	1.54	156.45	-7.2	-8.2	-154.5	139.1	-117.4	102.7	-118.1	102.0	15.3	-30.0	14.5	-30.7	-52.8	-182.8	167.3	37.4	-24.3	-58.3	-24.9	-58.8	-121.9
Story31	D18	A9	308	-5.36	-0.37	0.27	20.12	-101.29	57.82	1.31	157.27	-6.4	-7.2	-168.9	155.3	-128.0	115.1	-128.7	114.4	17.7	-30.6	17.0	-31.3	-59.0	-197.7	184.1	45.4	-27.6	-63.8	-28.1	-64.3	-131.8
Story30	D18	A9	308	-5.66	-0.41	0.33	21.19	-109.74	60.88	1.51	154.02	-6.7	-7.7	-182.8	168.4	-138.5	124.9	-139.3	124.1	18.6	-32.2	17.8	-33.0	-65.8	-212.0	197.5	51.4	-31.8	-70.0	-32.4	-70.6	-141.5
Story29	D18	A11	376	-5.56	-0.40	0.35	26.26	-137.17	75.47	1.51	176.60	-6.5	-7.6	-226.5	212.4	-171.3	158.0	-172.1	157.1	24.9	-38.2	24.0	-39.0	-81.1	-262.2	248.1	67.0	-38.7	-86.0	-39.3	-86.6	-174.6
Story28	D18	A11	376	-5.83	-0.43	0.42	27.18	-144.54	78.15	1.69	170.34	-6.8	-8.1	-238.7	223.8	-180.4	166.5	-181.4	165.5	25.7	-39.5	24.7	-40.6	-87.1	-274.7	259.8	72.2	-42.4	-91.3	-43.1	-92.1	-183.2
Story27	D18	A11	376	-5.32	-0.37	0.38	27.11	-145.02	77.96	1.47	156.54	-6.1	-7.4	-238.8	225.3	-180.3	167.7	-181.2	166.8	26.2	-38.8	25.3	-39.7	-87.2	-274.3	260.8	73.7	-42.4	-91.2	-43.1	-91.9	-182.8
Story26	D18	A11	376	-5.54	-0.40	0.45	27.97	-152.23	80.47	1.61	154.29	-6.3	-7.8	-250.6	236.5	-189.2	176.2	-190.3	175.1	27.1	-40.1	26.0	-41.1	-93.2	-286.3	272.2	79.1	-46.1	-96.5	-46.9	-97.3	-191.1
Story25	D18	A11	376	-5.77	-0.43	0.51	29.02	-161.51	83.50	1.76	154.07	-6.5	-8.2	-265.8	251.1	-200.5	187.1	-201.8	185.8	28.1	-41.6	26.9	-42.8	-101.0	-301.4	286.7	86.3	-51.0	-103.3	-51.9	-104.2	-201.5
Story24	D18	A11	376	-6.00	-0.46	0.58	29.51	-167.36	84.92	1.90	151.36	-6.7	-8.6	-275.4	260.1	-207.8	193.9	-209.2	192.5	28.4	-42.4	27.1	-43.8	-106.6	-310.4	295.1	91.3	-54.8	-108.0	-55.9	-109.0	-207.8
Story23	D18	A11	376	-5.82	-0.43	0.58	28.27	-162.21	81.41	1.83	140.47	-6.5	-8.4	-267.0	252.1	-201.4	187.9	-202.8	186.5	27.2	-40.6	25.8	-42.0	-104.4	-299.8	284.9	89.5	-54.2	-105.2	-55.3	-106.2	-200.9
Story22	D18	A11	376	-6.04	-0.46	0.65	28.48	-166.63	82.03	1.95	139.56	-6.7	-8.8	-274.3	258.9	-206.9	193.0	-208.5	191.5	27.3	-41.1	25.7	-42.7	-109.2	-306.1	290.7	93.8	-57.7	-109.0	-58.9	-110.2	-205.5
Story21	D18	A11	376	-6.26	-0.49	0.73	29.09	-173.90	83.81	2.08	141.90	-6.8	-9.2	-286.2	270.2	-215.8	201.6	-217.6	199.8	27.8	-42.0	26.0	-43.8	-116.1	-317.3	301.3	100.1	-62.3	-114.7	-63.6	-116.0	-213.3
Story20	D18	A11	376	-6.48	-0.51	0.81	29.67	-178.34	85.49	2.20	141.66	-7.0	-9.6	-293.6	277.1	-221.3	206.7	-223.3	204.8	28.3	-42.9	26.3	-44.9	-119.7	-324.9	308.3	103.1	-64.5	-117.9	-65.9	-119.4	-218.5
Story19	D18	A11	376	-6.26	-0.49	0.80	30.12	-184.43	86.80	2.09	144.57	-6.7	-9.3	-303.1	287.1	-228.4	214.3	-230.3	212.4	29.1	-43.2	27.2	-45.1	-125.2	-333.5	317.5	109.2	-68.1	-122.4	-69.5	-123.8	-224.5
Story18	D18	A11	376	-6.46	-0.51	0.87	30.55	-192.70	88.06	2.20	149.29	-6.9	-9.7	-316.6	300.0	-238.5	224.0	-240.6	221.9	29.4	-43.9	27.3	-46.0	-133.8	-345.2	328.6	117.3	-74.2	-129.3	-75.8	-130.8	-232.9
Story17	D18	A11	376	-5.95	-0.45	0.80	30.80	-197.43	88.81	1.92	154.30	-6.3	-8.9	-323.5	308.3	-243.5	230.3	-245.5	228.4	30.3	-43.6	28.4	-45.5	-137.9	-351.1	335.9	122.8	-77.0	-132.5	-78.4	-133.9	-237.0
Story16	D18	A11	376	-6.13	-0.47	0.87	31.06	-202.98	89.61	2.01	159.62	-6.4	-9.2	-332.6	316.9	-250.4	236.8	-252.4	234.7	30.5	-44.1	28.4	-46.1	-143.9	-358.9	343.3	128.2	-81.2	-137.1	-82.7	-138.7	-242.6
Story15	D18	A11	376	-6.30	-0.49	0.94	31.28	-209.50	90.27	2.09	165.76	-6.5	-9.6	-343.3	327.2	-258.3	244.5	-260.6	242.2	30.6	-44.5	28.4	-46.7	-151.1	-367.8	351.7	135.0	-86.4	-142.8	-88.1	-144.5	-249.1
Story14	D18	A11	376	-6.49	-0.51	1.01	31.44	-216.10	90.74	2.18	171.83	-6.7	-9.9	-354.1	337.5	-266.4	252.2	-268.8	249.8	30.6	-44.8	28.2	-47.2	-158.7	-376.5	359.9	142.1	-92.0	-148.6	-93.8	-150.5	-255.5
Story13	D18	A11	376	-6.31	-0.48	1.00	31.23	-218.12	90.17	2.08	176.05	-6.4	-9.7	-357.0	340.9	-268.6	254.9	-271.0	252.5	30.6	-44.3	28.2	-46.7	-161.6	-378.0	361.9	145.5	-94.3	-150.5	-96.1	-152.3	-256.7
Story12	D18	A13.5	462	-6.59	-0.51	1.09	37.22	-263.48	107.50	2.20	215.17	-6.7	-10.2	-430.0	413.1	-323.3	309.1	-325.9	306.4	37.6	-51.8	34.9	-54.4	-195.6	-453.6	436.7	178.7	-114.4	-181.5	-116.4	-183.4	-308.1
Story11	D18	A13.5	462	-6.78	-0.53	1.17	35.30	-258.09	101.98	2.28	213.94	-6.8	-10.5	-421.6	404.3	-317.0	302.5	-319.8	299.6	35.1	-49.6	32.3	-52.4	-196.0	-440.7	423.4	178.7	-116.4	-180.0	-118.5	-182.1	-300.2
Story10	D18	A13.5	462	-6.96	-0.55	1.25	34.63	-261.50	100.09	2.37	219.92	-6.9	-10.9	-427.3	409.5	-321.2	306.4	-324.2	303.4	34.2	-49.0	31.2	-52.0	-202.6	-442.8	425.0	184.8	-122.0	-184.4	-124.2	-186.6	-302.3
Story9	D18	A13.5	462	-6.77	-0.53	1.24	34.41	-265.99	99.51	2.27	228.78	-6.7	-10.6	-434.2	416.9	-326.4	312.0	-329.3	309.1	34.1	-48.5	31.2	-51.4	-208.4	-447.3	430.0	191.1	-126.5	-188.5	-128.7	-190.7	-305.8
Story8	D18	A13.5	462	-6.96	-0.54	1.32	34.39	-272.44	99.49	2.36	238.69	-6.8	-11.0	-444.8	427.0	-334.2	319.6	-337.4	316.5	34.0	-48.6	30.8	-51.7	-216.4	-455.2	437.4	198.6	-132.5	-194.5	-134.9	-196.9	-311.8
Story7	D18	A13.5	462	-6.79	-0.52	1.30	34.11	-276.18	98.71	2.28	248.15	-6.6	-10.7	-450.6	433.2	-338.5	324.3	-341.6	321.2	33.8	-48.0	30.7	-51.2	-221.6	-458.5	441.2	204.3	-136.6	-198.1	-139.0	-200.4	-314.5
Story6	D18	A13.5	462	-6.96	-0.54	1.38	33.76	-280.49	97.76	2.36	257.10	-6.7	-11.1	-457.7	439.9	-343.8	329.4	-347.1	326.0	33.3	-47.8	30.0	-51.1	-228.2	-462.8	445.0	210.4	-141.8	-202.7	-144.3	-205.1	-318.0
Story5	D18	A13.5	462	-6.80	-0.52	1.37	33.25	-281.09	96.33	2.30	264.46	-6.5	-10.9	-458.4	441.1	-344.3	330.3	-347.6	327.0	32.9	-46.9	29.6	-50.2	-230.4	-461.6	444.2	213.0	-143.9	-203.8	-146.4	-206.3	-317.5
Story4	D18	A13.5	462	-6.96	-0.54	1.44	32.64	-279.63	94.61	2.39	269.11	-6.6	-11.2	-456.3	438.5	-342.7	328.4	-346.2	324.9	32.0	-46.3	28.5	-49.8	-230.9	-458.0	440.2	213.1	-144.9	-203.7	-147.5	-206.3	-315.3
Story3	D18	A13.5	462	-7.13	-0.55	1.52	31.30	-268.66	90.79	2.48	266.34	-6.7	-11.5	-439.0	420.7	-329.7	315.1	-333.3	311.5	30.3	-44.8	26.6	-48.5	-222.6	-440.4	422.2	204.3	-139.8	-196.2	-142.5	-198.9	-303.3
Story2	D18	A13.5	462	-7.29	-0.57	1.59	28.07	-235.18	81.49	2.57	245.52	-6.8	-11.9	-385.6	367.0	-289.6	274.8	-293.4	271.0	26.3	-41.1	22.5	-44.9	-193.7	-389.3	370.7	175.1	-121.0	-171.6	-123.9	-174.5	-267.9
Story1	D18	A13.5	462	-7.78	-0.65	1.84	17.27	-129.63	50.21	2.96	159.96	-7.0	-12.9	-217.4	197.4	-163.3	147.8	-167.7	143.4	13.0	-28.5	8.5	-32.9	-105.3	-225.8	205.8	85.3	-64.3	-95.4	-67.6	-98.7	-154.8
Ground	D18	A11	376	-7.29	-0.59	1.47	-4.80	79.23	-13.88	2.35	40.58	-7.0	-11.7	117.4	-136.1	87.5	-102.6	84.0	-106.2	-13.3	-1.8	-16.9	-5.3	69.1	102.4	-121.1	-87.8	46.5	55.2	43.9	52.5	71.5
B1	D18	A11	376	-7.39	-0.62	1.47	-3.23	55.47	-9.32	2.35	28.94	-7.1	-11.8	79.3	-98.2	58.8	-74.3	55.3	-77.8	-11.6	-3.8	-15.1	-7.4	45.9	68.3	-87.2	-64.9	30.5	36.3	27.9	33.7	47.3
B2	D18	A11	376	-7.48	-0.65	1.47	-1.59	26.64	-4.60	2.34	14.60	-7.3	-12.0	33.0	-52.2	24.1	-39.8	20.6	-43.4	-9.8	-6.0	-13.3	-9.5	16.8	27.9	-47.1	-36.1	10.1	13.0	7.5	10.3	18.4
B3	D18	A11	376	-7.57	-0.69	1.47	0.05	-3.21	0.14	2.34	6.42	-7.4	-12.1	-14.9	-4.6	-11.9	-4.2	-15.4	-7.7	-8.0	-8.1	-11.5	-11.6	-13.5	-13.8	-5.8	-6.1	-11.2	-11.3	-13.8	-13.9	-11.4

SIMPSON GUMPERTZ & HEGER
Engineering of Structures and Building Enclosures

CLIENT Pacific Earthquake Engineering Research Center
SUBJECT BRB Strength Check along Line 3 for LA BRBF Bldg: PB Dsgn

SHEET NO.
PROJECT NO. 087237.10
DATE 1/23/09
BY AD
CHECKED BY

Model: 011609PBModel1

Scale-X= 1.00
Scale-Y= 1.00

SDS = 1.145
ρ-X dir = 1
ρ -Y dir = 1

1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9
1	1	1	1	1	1	1	1	1	1	1																									
0.9008	0.9008	-0.9008	-0.9008	0.9008	0.9008	-0.9008	-0.9008	0.9008	-0.9008	-0.9008	1.6	-1.6			1.2	1.2	-1.2	-1.2	1.2	1.2	-1.2	-1.2													
0.9008	0.9008	-0.9008	0.9008	-0.9008	-0.9008	-0.9008	-0.9008	-0.9008	0.9008	0.9008									1.2	-1.2	1.2	-1.2													
-0.9008	-0.9008	-0.9008	-0.9008	-0.9008	0.9008	-0.9008	0.9008	-0.9008	0.9008	-0.9008				1.6	-1.6	1.2	-1.2	1.2	-1.2										1.2	1.2	-1.2	-1.2			
0.9008	-0.9008	-0.9008	-0.9008	-0.9008	-0.9008	0.9008	-0.9008	0.9008	-0.9008	0.9008																			1.2	-1.2	1.2	-1.2			
Figure 6-9 Case 4											Figure 6-9 Case 1				Figure 6-9 Case 2				Figure 6-9 Case 3																

Story	ETABS #	Section	Capacity	Dead	Live	WindFX	WindMTX	WindFY	WindMTY																										
Story40	D18	A7	239	-2.99	0.00	0.00	7.88	-10.30	22.66	33.2	-7.6	-21.8	-7.6	-21.8	-40.4	19.0	-40.4	19.0	-26.2	33.2	-2.7	-2.7	-19.2	13.8	-15.1	9.7	-15.1	9.7	6.8	-12.1	6.8	-12.1	12.1	-42.2	36.9	-17.5
Story39	D18	A7	239	-3.45	-0.07	0.01	8.82	-18.43	25.36	43.2	-2.5	-18.4	-2.5	-18.4	-51.6	27.3	-51.6	27.3	-35.7	43.2	-3.1	-3.1	-32.6	26.4	-25.2	19.0	-25.2	19.0	7.5	-13.7	7.5	-13.7	5.2	-55.7	49.4	-11.4
Story38	D18	A9	308	-4.00	-0.14	0.02	12.10	-32.87	34.79	66.9	4.3	-17.6	4.2	-17.5	-76.8	45.1	-76.8	45.1	-55.0	66.9	-3.6	-3.6	-56.2	49.0	-43.0	35.9	-43.1	35.8	11.0	-18.1	10.9	-18.2	-1.3	-84.8	77.6	-5.9
Story37	D18	A9	308	-4.47	-0.21	0.05	12.98	-43.58	37.29	79.0	11.8	-11.7	11.7	-11.6	-90.1	55.5	-90.2	55.6	-66.8	78.9	-3.9	-4.1	-73.7	65.7	-56.2	48.3	-56.4	48.2	11.6	-19.5	11.5	-19.7	-11.6	-101.1	93.0	3.5
Story36	D18	A9	308	-4.94	-0.28	0.09	14.26	-54.09	40.97	92.4	18.5	-7.3	18.4	-7.1	-104.6	66.5	-104.8	66.7	-79.1	92.2	-4.3	-4.6	-91.0	82.1	-69.2	60.6	-69.5	60.3	12.8	-21.4	12.6	-21.7	-20.2	-118.5	109.6	11.3
Story35	D18	A9	308	-5.41	-0.35	0.15	15.48	-60.61	44.47	101.9	21.8	-6.4	21.5	-6.1	-115.3	73.7	-115.6	74.0	-87.7	101.6	-4.6	-5.1	-101.8	92.1	-77.4	68.0	-77.8	67.7	13.9	-23.3	13.5	-23.6	-24.2	-131.0	121.2	14.5
Story34	D18	A9	308	-5.88	-0.41	0.21	16.35	-70.84	46.97	113.6	28.9	-0.9	28.6	-0.5	-128.1	83.7	-128.5	84.1	-99.0	113.2	-5.0	-5.6	-118.6	108.0	-90.0	80.0	-90.5	79.5	14.6	-24.7	14.1	-25.2	-33.9	-146.7	136.1	23.4
Story33	D18	A9	308	-5.64	-0.40	0.23	17.58	-81.06	50.51	127.4	36.4	4.3	36.0	4.7	-141.3	95.3	-141.7	95.7	-110.0	127.0	-4.7	-5.4	-134.8	124.6	-102.1	92.5	-102.6	91.9	16.3	-25.9	15.7	-26.4	-41.7	-163.0	152.8	31.6
Story32	D18	A9	308	-6.05	-0.45	0.30	18.84	-91.74	54.14	140.9	43.4	8.9	42.9	9.5	-155.8	106.5	-156.4	107.0	-122.4	140.4	-5.0	-5.9	-152.2	141.3	-115.2	105.0	-115.9	104.3	17.5	-27.7	16.8	-28.4	-50.6	-180.5	169.6	39.7
Story31	D18	A9	308	-5.36	-0.37	0.27	20.12	-101.29	57.82	154.9	50.7	14.0	50.2	14.5	-168.0	118.1	-168.5	118.6	-132.2	154.4	-4.4	-5.3	-166.9	157.2	-126.0	117.0	-126.7	116.4	19.6	-28.6	19.0	-29.3	-57.0	-195.8	186.1	47.3
Story30	D18	A9	308	-5.66	-0.41	0.33	21.19	-109.74	60.88	165.9	56.2	17.4	55.6	18.0	-179.7	127.1	-180.3	127.7	-142.1	165.3	-4.6	-5.6	-180.7	170.5	-136.4	127.0	-137.2	126.2	20.7	-30.1	19.9	-30.9	-63.7	-209.8	199.6	53.5
Story29	D18	A11	376	-5.56	-0.40	0.35	26.26	-137.17	75.47	208.4	72.5	24.5	71.8	25.2	-222.0	160.5	-222.6	161.1	-175.3	207.8	-4.4	-5.6	-224.5	214.5	-169.2	160.0	-170.0	159.2	26.9	-36.1	26.1	-36.9	-79.0	-260.2	250.2	69.0
Story28	D18	A11	376	-5.83	-0.43	0.42	27.18	-144.54	78.15	218.0	77.2	27.5	76.5	28.3	-232.1	168.3	-232.9	169.1	-183.9	217.3	-4.6	-5.9	-236.5	226.0	-178.2	168.7	-179.2	167.7	27.9	-37.4	26.9	-38.4	-84.9	-272.5	262.0	74.4
Story27	D18	A11	376	-5.32	-0.37	0.38	27.11	-145.02	77.96	218.9	78.4	28.9	77.7	29.6	-231.7	169.3	-232.4	170.0	-183.5	218.2	-4.2	-5.4	-236.8	227.2	-178.3	169.7	-179.3	168.8	28.2	-36.8	27.3	-37.8	-85.2	-272.4	262.8	75.7
Story26	D18	A11	376	-5.54	-0.40	0.45	27.97	-152.23	80.47	228.2	83.2	32.0	82.4	32.8	-241.5	177.0	-242.3	177.8	-191.9	227.4	-4.3	-5.7	-248.6	238.6	-187.1	178.2	-188.2	177.2	29.1	-38.0	28.0	-39.1	-91.1	-284.2	274.3	81.1
Story25	D18	A11	376	-5.77	-0.43	0.51	29.02	-161.51	83.50	239.9	89.5	36.3	88.6	37.2	-253.7	186.7	-254.7	187.7	-202.4	239.0	-4.4	-6.0	-263.6	253.2	-198.4	189.2	-199.6	188.0	30.2	-39.4	29.0	-40.6	-98.8	-299.2	288.8	88.4
Story24	D18	A11	376	-6.00	-0.46	0.58	29.51	-167.36	84.92	246.7	93.7	39.5	92.7	40.5	-261.0	192.5	-262.0	193.5	-208.9	245.7	-4.5	-6.3	-273.2	262.4	-205.5	196.1	-206.9	194.7	30.7	-40.1	29.3	-41.5	-104.3	-308.1	297.3	93.5
Story23	D18	A11	376	-5.82	-0.43	0.58	28.27	-162.21	81.41	238.0	91.4	39.4	90.3	40.4	-251.8	186.0	-252.9	187.1	-201.9	237.0	-4.3	-6.2	-264.8	254.3	-199.2	190.1	-200.6	188.7	29.4	-38.5	28.0	-39.9	-102.2	-297.6	287.1	91.7
Story22	D18	A11	376	-6.04	-0.46	0.65	28.48	-166.63	82.03	242.5	94.7	42.3	93.6	43.4	-256.8	190.0	-258.0	191.2	-206.6	241.4	-4.4	-6.5	-272.0	261.2	-204.6	195.3	-206.2	193.7	29.5	-38.8	28.0	-40.4	-107.0	-303.8	293.0	96.1
Story21	D18	A11	376	-6.26	-0.49	0.73	29.09	-173.90	83.81	251.0	100.0	46.3	98.7	47.6	-265.7	197.3	-267.0	198.6	-214.6	249.7	-4.5	-6.8	-283.9	272.6	-213.4	203.9	-215.2	202.2	30.1	-39.7	28.4	-41.4	-113.7	-314.9	303.6	102.5
Story20	D18	A11	376	-6.48	-0.51	0.81	29.67	-178.34	85.49	256.8	102.8	47.9	101.3	49.3	-271.9	201.9	-273.4	203.4	-219.9	255.4	-4.5	-7.1	-291.2	279.5	-218.9	209.1	-220.8	207.2	30.7	-40.5	28.8	-42.4	-117.2	-322.4	310.8	105.6
Story19	D18	A11	376	-6.26	-0.49	0.80	30.12	-184.43	86.80	264.2	107.8	52.1	106.4	53.5	-278.7	208.5	-280.2	209.9	-225.9	262.7	-4.4	-6.9	-300.7	289.5	-226.0	216.6	-227.9	214.7	31.5	-40.8	29.6	-42.7	-122.8	-331.1	319.8	111.5
Story18	D18	A11	376	-6.46	-0.51	0.87	30.55	-192.70	88.06	272.9	114.3	57.7	112.7	59.3	-287.9	216.3	-289.5	217.9	-234.4	271.4	-4.4	-7.2	-314.1	302.5	-236.0	226.5	-238.1	224.4	31.9	-41.4	29.8	-43.5	-131.4	-342.7	331.1	119.7
Story17	D18	A11	376	-5.95	-0.45	0.80	30.80	-197.43	88.81	278.7	118.7	61.8	117.3	63.2	-292.5	221.8	-293.9	223.2	-238.4	277.3	-4.1	-6.6	-321.2	310.5	-241.3	232.5	-243.2	230.6	32.6	-41.4	30.6	-43.3	-135.7	-348.8	338.1	125.0
Story16	D18	A11	376	-6.13	-0.47	0.87	31.06	-202.98	89.61	284.5	123.1	65.5	121.5	67.1	-298.6	227.0	-300.1	228.5	-244.2	282.9	-4.1	-6.9	-330.3	319.3	-248.0	239.1	-250.1	237.0	32.8	-41.8	30.7	-43.8	-141.6	-356.6	345.6	130.5
Story15	D18	A11	376	-6.30	-0.49	0.94	31.28	-209.50	90.27	291.0	128.4	70.3	126.7	72.0	-305.4	233.0	-307.1	234.6	-250.7	289.3	-4.2	-7.2	-340.9	329.5	-256.0	246.9	-258.2	244.6	33.0	-42.1	30.7	-44.3	-148.8	-365.4	354.1	137.4
Story14	D18	A11	376	-6.49	-0.51	1.01	31.44	-216.10	90.74	297.3	133.9	75.4	132.0	77.2	-312.1	238.9	-313.9	240.7	-257.3	295.5	-4.2	-7.5	-351.6	339.9	-263.9	254.7	-266.4	252.3	33.1	-42.4	30.7	-44.8	-156.3	-374.1	362.4	144.6
Story13	D18	A11	376	-6.31	-0.48	1.00	31.23	-218.12	90.17	298.7	136.2	78.2	134.4	80.0	-313.0	240.6	-314.8	242.4	-258.5	296.9	-4.1	-7.3	-354.7	343.3	-266.2	257.3	-268.6	254.9	33.0	-41.9	30.6	-44.4	-159.2	-375.6	364.3	147.9
Story12	D18	A13.5	462	-6.59	-0.51	1.09	37.22	-263.48	107.50	360.3	166.6	97.6	164.6	99.5	-375.1	291.2	-377.1	293.2	-310.1	358.3	-4.2	-7.7	-427.5	415.6	-320.8	311.6	-323.4	308.9	40.0	-49.3	37.4	-51.9	-193.1	-451.1	439.2	181.2
Story11	D18	A13.5	462	-6.78	-0.53	1.17	35.30	-258.09	101.98	348.5	164.8	99.1	162.7	101.2	-363.7	282.8	-365.9	284.9	-302.3	346.4	-4.2	-8.0	-419.0	406.8	-314.4	305.0	-317.2	302.2	37.7	-47.0	34.9	-49.9	-193.4	-438.2	426.0	181.2
Story10	D18	A13.5	462	-6.96	-0.55	1.25	34.63	-261.50	100.09	349.1	168.8	104.2	166.6	106.4	-364.7	284.5	-366.9	286.8	-304.6	346.9	-4.3	-8.3	-424.7	412.1	-318.6	309.0	-321.6	306.0	36.8	-46.3	33.8	-49.3	-199.9	-440.2	427.6	187.4
Story9	D18	A13.5	462	-6.77	-0.53	1.24	34.41	-265.99	99.51	352.7	173.4	109.2	171.2	111.4	-367.8	288.5	-370.0	290.7	-308.0	350.5	-4.1	-8.1	-431.7	419.5	-323.8	314.6	-326.8	311.6	36.7	-45.9	33.7	-48.9	-205.9	-444.7	432.5	193.7
Story8	D18	A13.5	462	-6.96	-0.54	1.32	34.39	-272.44	99.49	358.3	179.1	114.7	176.7	117.1	-373.7	294.0	-376.1	296.3	-314.1	355.9	-4.2	-8.4	-442.2	429.6	-331.6	322.2	-334.8	319.1	36.6	-46.0	33.4	-49.1	-213.8	-452.6	440.1	201.3
Story7	D18	A13.5	462	-6.79	-0.52	1.30	34.11	-276.18	98.71	360.9	183.1	119.3	180.8	121.7	-375.9	297.1	-378.3	299.5	-316.8	358.6	-4.0	-8.2	-448.0	435.8	-336.0	326.9	-339.1	323.8	36.4	-45.5	33.3	-48.6	-219.1	-456.0	443.8	206.9
Story6	D18	A13.5	462	-6.96	-0.54	1.38	33.76	-280.49	97.76	363.5	187.4	124.1	184.9	126.5	-378.8	300.2	-381.3	302.7	-320.5	361.0	-4.1	-8.5	-455.0	442.5	-341.2	332.0	-344.5	328.7	35.9	-45.1	32.6	-48.4	-225.5	-460.2	447.6	213.0
Story5	D18	A13.5	462	-6.80	-0.52	1.37	33.25	-281.09	96.33	362.5	188.9	126.6	186.5	129.0	-377.4	300.1	-379.8	302.6	-319.9	360.0	-3.9	-8.3	-455.9	443.6	-341.8	332.8	-345.1	329.5	35.4	-44.4	32.1	-47.7	-227.8	-459.0	446.8	215.6
Story4	D18	A13.5	462	-6.96	-0.54	1.44	32.64	-279.63	94.61	358.9	188.5	127.1	185.9	129.7	-374.1	297.5	-376.7	300.1	-317.9	356.3	-4.0	-8.6	-453.7	441.1	-340.1	331.0	-343.6	327.6	34.6	-43.7	31.2	-47.2	-228.3	-455.4	442.8	215.7
Story3	D18	A13.5	462	-7.13	-0.55	1.52	31.30	-268.66	90.79	344.2	180.7	121.6	177.9	124.3	-359.7	285.1	-362.5	287.9	-306.1	341.5	-4.0	-8.8	-436.3	423.4	-327.0	317.8	-330.6	314.2	33.0	-42.2	29.3	-45.8	-219.9	-437.7	424.9	207.0
Story2	D18	A13.5	462	-7.29	-0.57	1.59	28.07	-235.18	81.49	302.7	155.8	102.4	153.0	105.3	-318.4	249.2	-321.3	252.1	-270.7	299.8	-4.0	-9.1	-382.9	369.7	-286.9	277.6	-290.7	273.7	29.0	-38.3	25.2	-42.2	-191.0	-386.6	373.4	177.9
Story1	D18	A13.5	462	-7.78	-0.65	1.84	17.27	-129.63	50.21	169.2	78.8	44.3	75.5	47.7	-185.9	134.8	-189.2	138.1	-158.1	165.9	-4.0	-10.0	-214.4	200.4	-160.3	150.8	-164.8	146.3	15.9	-25.5	11.5	-29.9	-102.3	-222.8	208.8	88.3
Ground	D18	A11	376	-7.29	-0.59	1.47	-4.80	79.23	-13.88	-96.2	-71.2	-65.2	-73.9	-62.5	80.2	-90.2	77.5	-87.6	68.9	-98.9	-4.2	-8.9	120.2	-133.3	90.3	-99.9	86.7	-103.4	-10.6	1.0	-14.1	-2.6	71.9	105.2	-118.3	-85.0
B1	D18	A11	376	-7.39	-0.62	1.47	-3.23	55.47	-9.32	-69.4	-52.6	-49.5	-55.3	-46.8	53.1	-66.3	50.5	-63.6	44.7	-72.1	-4.3	-9.0	82.1	-95.4	61.7	-71.4	58.2	-75.0	-8.8	-1.0	-12.3	-4.5	48.7	71.1	-84.4	-62.0
B2	D18	A11	376	-7.48	-0.65	1.47	-1.59	26.64	-4.60	-37.9	-29.6	-29.4	-32.2	-26.7	21.3	-37.7	18.6	-35.0	15.8	-40.5	-4.4	-9.1	35.9	-49.4	27.0	-36.9	23.5	-40.5	-6.9	-3.1	-10.4	-6.6	19.7	30.8	-44.2	-33.2
B3	D18	A11	376	-7.57	-0.69	1.47	0.05	-3.21	0.14	-5.4	-5.6	-8.4	-8.3	-5.7	-11.5	-8.1	-14.2	-5.5	-14.1	-8.0	-4.5	-9.2	-12.0	-1.7	-8.9	-1.2	-12.4	-4.7	-5.0	-5.1	-8.5	-8.6	-10.5	-10.8	-2.8	-3.1

SIMPSON GUMPERTZ & HEGER
Engineering of Structures and Building Enclosures

CLIENT Pacific Earthquake Engineering Research Center
SUBJECT BRB Strength Check along Line 3 for LA BRBF Bldg: PB Dsgn

SHEET NO. ____
PROJECT NO. 087237.10
DATE 1/23/09
BY AD
CHECKED BY ____

Model: 011609PBModel1

Scale-X= 1.00
Scale-Y= 1.00

SDS = 1.145
ρ-X dir = 1
ρ -Y dir = 1

0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	1	1	1	1	1	1	1	1
																0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25
0.9008	0.9008	-0.9008	-0.9008	0.9008	0.9008	0.9008	-0.9008	-0.9008	0.9008	0.9008	-0.9008	-0.9008	0.9008	-0.9008	-0.9008								
0.9008	-0.9008	0.9008	-0.9008	0.9008	0.9008	0.9008	-0.9008	0.9008	-0.9008	-0.9008	-0.9008	-0.9008	-0.9008	0.9008	0.9008								
0.9008	0.9008	0.9008	0.9008	0.9008	-0.9008	-0.9008	-0.9008	-0.9008	-0.9008	0.9008	-0.9008	0.9008	-0.9008	0.9008	-0.9008								
0.9008	0.9008	0.9008	0.9008	-0.9008	0.9008	-0.9008	-0.9008	-0.9008	-0.9008	-0.9008	0.9008	-0.9008	0.9008	-0.9008	0.9008								
																1	0.3	-1	-0.3	0.3	1	-1	-0.3
																0.3	1	0.3	1	-1	-0.3	-0.3	-1

Figure 6-9 Case 4

Story	ETABS #	Section	Capacity	Dead	Live	WindFX	WindMTX	WindFY	WindMTY																							Maximum Axial Loads			
																																Tension	Compression	DCR	Status
Story40	D18	A7	239	-2.99	0.00	0.00	7.88	-10.30	22.66	15.5	1.3	15.5	1.3	-25.3	34.1	-6.7	-20.9	-6.7	-20.9	-39.5	19.9	-39.5	19.9	-25.3	34.1	16.7	62.5	16.7	62.5	-68.5	-22.6	-22.7	-68.5	62.55	-68.53	0.29	OK
Story39	D18	A7	239	-3.45	-0.07	0.01	8.82	-18.43	25.36	11.1	-4.8	11.1	-4.8	-34.6	44.3	-1.4	-17.3	-1.4	-17.3	-50.5	28.4	-50.5	28.4	-34.6	44.3	19.9	74.0	19.6	73.9	-80.8	-26.5	-26.8	-80.9	73.99	-80.92	0.34	OK
Story38	D18	A9	308	-4.00	-0.14	0.02	12.10	-32.87	34.79	9.1	-12.8	9.0	-12.8	-53.6	68.3	5.6	-16.3	5.6	-16.2	-75.4	46.4	-75.5	46.5	-53.7	68.2	33.0	118.6	32.4	118.4	-126.5	-40.5	-41.1	-126.6	118.57	-126.64	0.41	OK
Story37	D18	A9	308	-4.47	-0.21	0.05	12.98	-43.58	37.29	2.1	-21.3	2.0	-21.4	-65.1	80.6	13.4	-10.1	13.3	-10.0	-88.5	57.1	-88.6	57.2	-65.2	80.5	36.0	129.2	35.1	128.9	-137.9	-44.1	-45.1	-138.2	129.18	-138.23	0.45	OK
Story36	D18	A9	308	-4.94	-0.28	0.09	14.26	-54.09	40.97	-3.3	-29.0	-3.5	-29.2	-77.1	94.1	20.3	-5.6	20.1	-5.4	-102.8	68.3	-103.0	68.4	-77.3	93.9	39.7	141.9	38.3	141.5	-151.5	-48.3	-49.7	-151.9	141.91	-151.92	0.49	OK
Story35	D18	A9	308	-5.41	-0.35	0.15	15.48	-60.61	44.47	-5.3	-33.2	-5.6	-33.5	-85.4	103.9	23.7	-4.4	23.5	-4.1	-113.3	75.7	-113.6	76.0	-85.7	103.6	38.9	139.4	36.9	138.8	-149.8	-47.9	-49.9	-150.4	139.43	-150.42	0.49	OK
Story34	D18	A9	308	-5.88	-0.41	0.21	16.35	-70.84	46.97	-11.9	-41.3	-12.3	-41.7	-96.5	115.7	31.1	1.3	30.8	1.7	-125.9	85.9	-126.3	86.3	-96.9	115.4	40.3	144.6	37.8	143.8	-155.8	-49.8	-52.3	-156.6	144.60	-156.56	0.51	OK
Story33	D18	A9	308	-5.64	-0.40	0.23	17.58	-81.06	50.51	-16.6	-48.2	-17.0	-48.6	-107.5	129.5	38.5	6.4	38.1	6.8	-139.2	97.4	-139.6	97.8	-108.0	129.1	42.0	149.6	39.5	148.8	-160.3	-50.9	-53.5	-161.0	152.81	-165.04	0.54	OK
Story32	D18	A9	308	-6.05	-0.45	0.30	18.84	-91.74	54.14	-22.1	-56.0	-22.6	-56.6	-119.6	143.2	45.7	11.2	45.1	11.7	-153.6	108.7	-154.1	109.3	-120.1	142.7	42.3	150.8	39.2	149.8	-162.1	-51.6	-54.6	-163.1	169.61	-182.76	0.59	OK
Story31	D18	A9	308	-5.36	-0.37	0.27	20.12	-101.29	57.82	-25.6	-61.9	-26.1	-62.4	-129.8	156.9	52.7	16.0	52.2	16.5	-166.0	120.1	-166.5	120.6	-130.3	156.4	43.0	152.2	40.4	151.4	-162.3	-51.3	-53.9	-163.1	186.10	-197.73	0.64	OK
Story30	D18	A9	308	-5.66	-0.41	0.33	21.19	-109.74	60.88	-29.7	-67.9	-30.3	-68.5	-139.4	168.0	58.3	19.5	57.7	20.1	-177.6	129.2	-178.2	129.8	-140.0	167.4	42.0	148.7	38.9	147.8	-159.3	-50.5	-53.5	-160.2	199.65	-211.95	0.69	OK
Story29	D18	A11	376	-5.56	-0.40	0.35	26.26	-137.17	75.47	-36.6	-83.9	-37.3	-84.6	-172.6	210.5	74.5	26.6	73.9	27.2	-219.9	162.6	-220.5	163.2	-173.2	209.9	48.8	171.4	45.8	170.5	-181.8	-57.1	-60.1	-182.7	250.16	-262.24	0.70	OK
Story28	D18	A11	376	-5.83	-0.43	0.42	27.18	-144.54	78.15	-40.2	-89.2	-40.9	-89.9	-181.0	220.2	79.4	29.7	78.7	30.4	-230.0	170.5	-230.7	171.2	-181.7	219.5	46.9	164.9	43.5	163.9	-175.8	-55.4	-58.7	-176.8	261.98	-274.67	0.73	OK
Story27	D18	A11	376	-5.32	-0.37	0.38	27.11	-145.02	77.96	-40.4	-88.3	-41.1	-89.9	-180.9	220.8	80.4	30.9	79.7	31.5	-229.7	171.3	-230.4	172.0	-181.6	220.1	43.0	151.6	40.1	150.7	-161.5	-50.9	-53.8	-162.4	262.79	-274.32	0.73	OK
Story26	D18	A11	376	-5.54	-0.40	0.45	27.97	-152.23	80.47	-44.0	-94.4	-44.8	-95.2	-189.0	230.2	85.2	34.1	84.4	34.9	-239.4	179.0	-240.2	179.8	-189.8	229.4	42.3	149.1	39.0	148.2	-159.5	-50.3	-53.5	-160.4	274.26	-286.30	0.76	OK
Story25	D18	A11	376	-5.77	-0.43	0.51	29.02	-161.51	83.50	-48.9	-101.1	-49.8	-102.1	-199.3	242.1	91.7	38.5	90.8	39.4	-251.6	188.9	-252.5	189.8	-200.2	241.2	42.1	148.7	38.6	147.7	-159.4	-50.3	-53.9	-160.5	288.81	-301.36	0.80	OK
Story24	D18	A11	376	-6.00	-0.46	0.58	29.51	-167.36	84.92	-52.6	-105.7	-53.6	-106.8	-205.6	249.0	96.0	41.8	94.9	42.8	-258.7	194.8	-259.8	195.8	-206.6	247.9	41.2	145.8	37.4	144.7	-156.9	-49.6	-53.4	-158.0	297.34	-310.40	0.82	OK
Story23	D18	A11	376	-5.82	-0.43	0.58	28.27	-162.21	81.41	-52.0	-103.0	-53.1	-104.0	-198.7	240.2	93.5	41.6	92.5	42.6	-249.6	188.2	-250.7	189.3	-199.8	239.2	38.0	135.1	34.4	134.0	-145.9	-46.2	-49.9	-146.9	287.10	-299.77	0.80	OK
Story22	D18	A11	376	-6.04	-0.46	0.65	28.48	-166.63	82.03	-55.4	-106.7	-56.6	-107.9	-203.2	244.8	97.0	44.5	95.8	45.7	-254.5	192.3	-255.7	193.5	-204.4	243.6	37.7	134.0	33.8	132.8	-145.1	-46.1	-50.0	-146.3	292.96	-306.11	0.81	OK
Story21	D18	A11	376	-6.26	-0.49	0.73	29.09	-173.90	83.81	-59.5	-112.3	-61.2	-113.6	-210.9	253.4	102.4	48.7	101.1	50.0	-263.3	199.6	-264.6	201.0	-212.2	252.1	38.3	136.1	34.1	134.9	-147.7	-46.9	-51.0	-148.9	303.62	-317.25	0.84	OK
Story20	D18	A11	376	-6.48	-0.51	0.81	29.67	-178.34	85.49	-62.0	-115.5	-63.5	-116.9	-216.0	259.3	105.3	50.4	103.8	51.8	-269.5	204.4	-270.9	205.8	-217.5	257.8	38.1	135.7	33.7	134.4	-147.6	-46.9	-51.3	-148.9	310.77	-324.89	0.86	OK
Story19	D18	A11	376	-6.26	-0.49	0.80	30.12	-184.43	86.80	-65.7	-120.0	-67.2	-121.4	-222.1	266.5	110.2	54.5	108.7	55.9	-276.4	210.8	-277.8	212.3	-223.5	265.1	39.1	138.8	34.9	137.6	-150.3	-47.7	-51.8	-151.6	319.85	-333.47	0.89	OK
Story18	D18	A11	376	-6.46	-0.51	0.87	30.55	-192.70	88.06	-71.8	-126.8	-73.3	-128.4	-230.4	275.4	116.7	60.1	115.2	61.7	-285.4	218.8	-287.0	220.4	-232.0	273.8	40.4	143.4	36.0	142.0	-155.2	-49.2	-53.6	-156.5	331.09	-345.17	0.92	OK
Story17	D18	A11	376	-5.95	-0.45	0.80	30.80	-197.43	88.81	-74.7	-130.2	-76.2	-131.7	-234.7	281.0	121.0	64.0	119.5	65.5	-290.2	224.0	-291.7	225.5	-236.2	279.5	42.2	148.8	38.3	147.7	-159.8	-50.4	-54.3	-160.9	338.14	-351.08	0.93	OK
Story16	D18	A11	376	-6.13	-0.47	0.87	31.06	-202.98	89.61	-78.9	-134.8	-80.4	-136.4	-240.3	286.8	125.4	67.8	123.8	69.4	-296.3	229.3	-297.8	230.8	-241.9	285.2	43.7	154.0	39.6	152.8	-165.3	-52.1	-56.1	-166.5	345.59	-358.92	0.95	OK
Story15	D18	A11	376	-6.30	-0.49	0.94	31.28	-209.50	90.27	-84.1	-140.4	-85.7	-142.1	-246.7	293.4	130.8	72.7	129.1	74.4	-303.0	235.3	-304.7	237.0	-248.4	291.7	45.4	160.0	41.2	158.7	-171.6	-54.1	-58.2	-172.8	354.05	-367.78	0.98	OK
Story14	D18	A11	376	-6.49	-0.51	1.01	31.44	-216.10	90.74	-89.5	-146.2	-91.4	-148.0	-253.0	299.8	136.3	77.8	134.5	79.7	-309.7	241.3	-311.5	243.1	-254.8	298.0	47.1	165.9	42.7	164.6	-177.8	-56.0	-60.3	-179.1	362.36	-376.51	1.00	Say OK
Story13	D18	A11	376	-6.31	-0.48	1.00	31.23	-218.12	90.17	-91.9	-148.2	-93.7	-150.0	-254.3	301.1	138.6	80.5	136.8	82.4	-310.6	243.0	-312.4	244.8	-256.1	299.3	48.5	170.3	44.3	169.0	-181.9	-57.2	-61.3	-183.1	364.26	-377.99	1.00	Say OK
Story12	D18	A13.5	462	-6.59	-0.51	1.09	37.22	-263.48	107.50	-111.9	-179.0	-113.9	-181.0	-305.6	362.8	169.1	100.1	167.1	102.0	-372.7	293.7	-374.6	295.7	-307.6	360.8	60.0	209.1	55.6	207.8	-221.2	-69.1	-73.5	-222.5	439.24	-453.60	0.98	OK
Story11	D18	A13.5	462	-6.78	-0.53	1.17	35.30	-258.09	101.98	-113.9	-177.5	-116.0	-179.6	-297.6	351.1	167.4	101.7	165.3	103.8	-361.2	285.4	-363.3	287.5	-299.7	349.0	59.6	207.7	55.0	206.4	-220.2	-68.8	-73.4	-221.5	425.98	-440.74	0.95	OK
Story10	D18	A13.5	462	-6.96	-0.55	1.25	34.63	-261.50	100.09	-119.3	-181.7	-121.6	-184.0	-299.7	351.8	171.5	106.8	169.2	109.1	-362.0	287.1	-364.3	289.4	-301.9	349.5	61.2	213.5	56.5	212.1	-226.3	-70.7	-75.4	-227.7	427.65	-442.81	0.96	OK
Story9	D18	A13.5	462	-6.77	-0.53	1.24	34.41	-265.99	99.51	-124.0	-186.0	-126.2	-188.2	-303.2	355.3	176.0	111.8	173.8	114.0	-365.2	291.0	-367.5	293.3	-305.5	353.0	64.0	222.6	59.5	221.2	-235.0	-73.3	-77.8	-236.4	432.51	-447.26	0.97	OK
Story8	D18	A13.5	462	-6.96	-0.54	1.32	34.39	-272.44	99.49	-129.9	-191.9	-132.3	-194.2	-309.1	360.9	181.7	117.4	179.3	119.7	-371.1	296.6	-373.5	299.0	-311.5	358.6	66.9	232.3	62.2	230.9	-245.1	-76.3	-81.1	-246.5	440.06	-455.21	0.99	OK
Story7	D18	A13.5	462	-6.79	-0.52	1.30	34.11	-276.18	98.71	-134.1	-195.5	-136.4	-197.9	-311.9	363.5	185.7	121.9	183.3	124.2	-373.4	299.7	-375.7	302.0	-314.3	361.1	69.8	241.9	65.3	240.6	-254.4	-79.1	-83.6	-255.8	443.76	-458.54	0.99	OK
Story6	D18	A13.5	462	-6.96	-0.54	1.38	33.76	-280.49	97.76	-139.2	-200.0	-141.7	-202.5	-315.3	366.1	190.0	126.7	187.5	129.2	-376.2	302.8	-378.7	305.3	-317.8	363.6	72.4	250.7	67.7	249.3	-263.5	-81.9	-86.6	-264.9	447.64	-462.80	1.00	Say OK
Story5	D18	A13.5	462	-6.80	-0.52	1.37	33.25	-281.09	96.33	-141.4	-201.3	-143.8	-203.7	-314.9	365.0	191.5	129.1	189.0	131.6	-374.8	302.7	-377.3	305.1	-317.4	362.6	74.7	258.2	70.1	256.8	-270.7	-84.0	-88.6	-272.1	446.78	-461.58	1.00	OK
Story4	D18	A13.5	462	-6.96	-0.54	1.44	32.64	-279.63	94.61	-142.2	-201.0	-144.8	-203.6	-312.7	361.5	191.1	129.7	188.5	132.3	-371.5	300.2	-374.1	302.7	-315.3	359.0	76.0	262.7	71.2	261.3	-275.5	-85.4	-90.2	-276.9	442.82	-457.99	0.99	OK
Story3	D18	A13.5	462	-7.13	-0.55	1.52	31.30	-268.66	90.79	-137.1	-193.5	-139.8	-196.2	-300.6	346.9	183.4	124.3	180.6	127.0	-357.0	287.8	-359.8	290.5	-303.4	344.2	75.1	259.8	70.2	258.3	-272.9	-84.7	-89.6	-274.4	424.91	-440.44	0.95	OK
Story2	D18	A13.5	462	-7.29	-0.57	1.59	28.07	-235.18	81.49	-118.3	-168.9	-121.2	-171.7	-265.1	305.4	158.6	105.2	155.7	108.0	-315.7	252.0	-318.5	254.8	-268.0	302.6	68.8	238.9	63.7	237.3	-252.2	-78.5	-83.7	-253.7	373.45	-389.33	0.84	OK
Story1	D18	A13.5	462	-7.78	-0.65	1.84	17.27	-129.63	50.21	-61.3	-92.4	-64.6	-95.8	-151.8	172.2	81.8	47.3	78.4	50.6	-182.9	137.8	-186.2	141.1	-155.1	168.9	43.0	152.9	37.1	151.1	-167.0	-53.0	-58.9	-168.8	208.80	-225.78	0.49	OK
Ground	D18	A11	376	-7.29	-0.59	1.47	-4.80	79.23	-13.88	49.3	58.0	46.6	55.3	74.3	-93.4	-68.4	-62.4	-71.1	-59.8	83.0	-87.4	80.3	-84.8	71.7	-96.1	7.1	33.8	2.4	32.4	-47.3	-17.3	-22.0	-48.7	120.20	-136.10	0.36	OK
B1	D18	A11	376	-7.39	-0.62	1.47	-3.23	55.47	-9.32	33.3	39.2	30.7	36.5	50.1	-66.6	-49.8	-46.6	-52.5	-44.0	55.9	-63.4	53.3	-60.8	47.5	-69.2	3.5	22.1	-1.2	20.7	-35.8	-13.9	-18.6	-37.2	82.11	-98.24	0.26	OK
B2	D18	A11	376	-7.48	-0.65	1.47	-1.59	26.64	-4.60	13.0	15.9	10.4	13.2	21.3	-35.0	-26.7	-26.5	-29.3	-23.8	24.2	-34.8	21.5	-32.1	18.7	-37.6	-0.9	7.7	-5.6	6.3	-21.5	-9.7	-14.4	-22.9	35.89	-52.25	0.14	OK
B3	D18	A11	376	-7.57	-0.69	1.47	0.05	-3.21	0.14	-8.2	-8.3	-10.9	-10.9	-8.5	-2.4	-2.7	-5.4	-5.3	-2.8	-8.6	-5.2	-11.2	-2.5	-11.1	-5.1	-3.5	-0.6	-8.2	-2.0	-13.5	-7.3	-12.0	-14.9	-0.62	-15.38	0.04	OK

APPENDIX D: Program Cost Model for PEER Tall Buildings Study, Concrete Option, Los Angeles, California

Davis Langdon

PROGRAM
COST MODEL

for

PEER Tall Buildings Study
Concrete Structural Option
Los Angeles, California

March 8, 2010

CONTENTS

	Page Nos.
Overall Summary	1
Areas and Control Quantities	2
Code Based Component Summary	3
Performance Based Component Summary	14
Performance Based Plus Component Summary	25

OVERALL SUMMARY

	Gross Floor Area	$ / SF	$x1,000
Construction Cost (Including Design)			
Code Based	683,748 SF	325.77	222,744
Performance Based	683,748 SF	324.89	222,142
Performance Based Plus	683,748 SF	331.60	226,728
FF&E Cost			
Furniture & Fittings, (resdential)	476,716 SF	20.00	9,534
Equipment, including computer systems	476,716 SF	7.00	3,337
Personal Property			
Personal Contents	476,716 SF	10.00	4,767
Cars in parking (Maximum count)	520 EA	25,000.00	13,000

Please refer to the Inclusions and Exclusions sections of this report

AREAS & CONTROL QUANTITIES

Areas

	SF	SF	SF
Enclosed Areas			
Basement Levels B1 - B4	207,024		
Ground Level	11,314		
Levels 2 - 42	463,874		
Penthouse	1,536		
SUBTOTAL, Enclosed Area		683,748	
Covered area			
SUBTOTAL, Covered Area @ ½ Value			
TOTAL GROSS FLOOR AREA			683,748

Control Quantities

				Ratio to Gross Area
Functional Units		310	Units	
Number of stories (x1,000)		46	EA	0.067
Gross Area		683,748	SF	1.000
Enclosed Area		683,748	SF	1.000
Covered Area		0	SF	0.000
Footprint Area		51,756	SF	0.076
Volume		7,212,004	CF	10.548
Basement Volume		2,070,240	CF	3.028
Gross Wall Area		212,093	SF	0.310
Retaining Wall Area		36,000	SF	0.053
Finished Wall Area		168,413	SF	0.246
Windows or Glazing Area	19.28%	40,883	SF	0.060
Roof Area - Flat		51,756	SF	0.076
Roof Area - Sloping		0	SF	0.000
Roof Area - Total		51,756	SF	0.076
Roof Glazing Area		0	SF	0.000
Interior Partition Length		132,334	LF	0.194
Finished Area		683,748	SF	1.000
Elevators (x10,000)		6	EA	0.088
Plumbing Fixtures (x1,000)		2,914	EA	4.262
Electrical Load		6,000	KW	8.775

CODE BASED COMPONENT SUMMARY

Gross Area: 683,748 SF

		$/SF	$x1,000
1. Foundations		16.35	11,178
2. Vertical Structure		17.64	12,060
3. Floor & Roof Structures		30.96	21,167
4. Exterior Cladding		33.35	22,803
5. Roofing, Waterproofing & Skylights		3.95	2,699
Shell (1-5)		102.24	69,907
6. Interior Partitions, Doors & Glazing		24.75	16,922
7. Floor, Wall & Ceiling Finishes		21.25	14,530
Interiors (6-7)		46.00	31,452
8. Function Equipment & Specialties		5.73	3,919
9. Stairs & Vertical Transportation		10.41	7,120
Equipment & Vertical Transportation (8-9)		16.15	11,039
10 Plumbing Systems		19.04	13,015
11 Heating, Ventilating & Air Conditioning		13.86	9,475
12 Electric Lighting, Power & Communications		21.33	14,586
13 Fire Protection Systems		5.37	3,669
Mechanical & Electrical (10-13)		59.59	40,745
Total Building Construction (1-13)		**223.98**	**153,144**
14 Site Preparation & Demolition		2.19	1,500
15 Site Paving, Structures & Landscaping		1.76	1,206
16 Utilities on Site		0.73	500
Total Site Construction (14-16)		**4.69**	**3,206**
TOTAL BUILDING & SITE (1-16)		**228.67**	**156,351**
General Conditions	12.00%	27.44	18,762
Contractor's Overhead & Profit or Fee	6.00%	15.37	10,507
PLANNED CONSTRUCTION COST	***March 2010***	**271.47**	**185,620**
Design, Management and Inspection	20.00%	54.29	37,124
Escalation is excluded	0.00%	0.00	0
RECOMMENDED BUDGET	***March 2010***	**325.77**	**222,744**

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
1. Foundations				
Basement Excavation				
Excavation	99,173	CY	15.00	1,487,595
Shoring at perimeter	36,400	SF	50.00	1,820,000
Backfill with imported material	14,829	CY	35.00	519,015
Dispose off site	99,173	CY	20.00	1,983,460
Hazardous material remediation				Excluded
Foundations				
Reinforced concrete mat foundation				
Excavation and disposal	10,278	CY	15.00	154,170
Formwork	5,240	SF	18.00	94,320
Reinforcing steel	1,469,135	LBS	1.15	1,689,505
Concrete, f'c= 6ksi	10,278	CY	325.00	3,340,350
Elevator pits	6	EA	15,000.00	90,000
				11,178,415
2. Vertical Structure				
Columns and pilasters				
Concrete columns				
Formwork	99,875	SF	25.00	2,496,875
Reinforcing steel	972,895	LBS	1.25	1,216,119
Concrete, f'c= 8ksi	2,048	CY	350.00	716,800
Concrete retaining walls				
Concrete retaining wall				
Formwork to one side	36,400	SF	15.00	546,000
Reinforcing steel	240,240	LBS	1.25	300,300
Concrete, f'c= 5ksi	1,978	CY	225.00	445,050
Concrete core walls				
Formwork to both sides	157,864	SF	18.00	2,841,552
Reinforcing steel	1,171,663	LBS	1.25	1,464,579
Concrete, f'c= 8ksi	5,808	CY	350.00	2,032,800
				12,060,075

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
3. Floor and Roof Structure				
Floor at lowest level				
Slab on grade - See foundations (mat slab)				
Suspended floors	21,103			
10" thick reinforced concrete flat slab - basement slabs				
Formwork	155,268	SF	10.00	1,552,680
Reinforcing steel	768,577	LBS	1.25	960,721
Concrete, f'c= 5.5ksi	4,792	CY	225.00	1,078,200
8" thick post tensioned slabs				
Formwork	463,874	SF	10.00	4,638,740
Reinforcing steel	1,122,575	LBS	1.25	1,403,219
Post tension tendons	459,236	LBS	2.00	918,472
Studrails at columns (9 studrais with 9 studs per rail)	1,476	LOC	4,000.00	5,904,000
Concrete, f'c= 5.5ksi	12,599	CY	225.00	2,834,775
Ground level slab/roof				
12" thick reinforced concrete flat slab - ground level				
Formwork	51,756	SF	10.00	517,560
Reinforcing steel	455,453	LBS	1.25	569,316
Concrete, f'c= 5.5ksi	2,109	CY	225.00	474,525
High roof				
10" thick reinforced concrete flat slab				
Formwork	12,850	SF	10.00	128,500
Reinforcing steel	70,675	LBS	1.25	88,344
Concrete, f'c= 5.5ksi	437	CY	225.00	98,325
				21,167,377
4. Exterior Cladding				
Wall framing, furring and insulation				
Exterior wall framing	168,413	SF	8.00	1,347,304
Furring to interior face of retaining wall	36,000	SF	4.00	144,000
Insulation and vapor barrier	161,050	SF	1.50	241,575

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
Applied exterior finishes				
Exterior wall finish - curtain wall with spandrel panels	125,050	SF	120.00	15,006,000
Parapets & edge detailing	400	LF	250.00	100,000
Interior finish to exterior walls				
Gypsum board, taped and sanded	161,050	SF	3.50	563,675
Windows, glazing and louvers				
Exterior wall finish - curtain wall with glazing	40,883	SF	120.00	4,905,960
Exterior doors, frames and hardware				
Glazed Doors & Entrances (allow revolving)	12	EA	35,000.00	420,000
Solid Exterior Doors	8	EA	3,000.00	24,000
Overhead Doors	2	EA	25,000.00	50,000
				22,802,514

5. Roofing, Waterproofing & Skylights

Waterproofing				
Waterproofing at slab on grade	51,756	SF	10.00	517,560
Waterproofing at retaining wall	36,000	SF	10.00	360,000
Waterproofing membrane under plaza	40,442	SF	15.00	606,630
Insulation				
Rigid insulation at roof	11,314	SF	6.00	67,884
Roofing				
Balconies & accessible roofs	40,442	SF	25.00	1,011,050
High roof	11,314	SF	12.00	135,768
				2,698,892

6. Interior Partitions, Doors & Glazing

Partition framing and cores				
CMU partitions at basement levels	1,656	LF	325.00	538,200
Core partitions	11,880	LF	90.00	1,069,200
Standard partitions	118,798	LF	72.00	8,553,456

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
Doors, frames & hardware				
Unit entrance doors	310	EA	2,250.00	697,500
Standard interior doors	2,680	EA	1,800.00	4,824,000
Closet doors at units - allow bi-fold	1,240	EA	1,000.00	1,240,000
				16,922,356

7. Floor, Wall & Ceiling Finishes

Floors including base				
Lobby flooring	5,000	SF	35.00	175,000
Core circulation - allow carpet	70,530	SF	6.00	423,180
Residential				
Livingrooms - allow wood	141,050	SF	22.00	3,103,100
Bedrooms - allow carpet	164,565	SF	6.00	987,390
Kitchen - allow stone tile	42,315	SF	25.00	1,057,875
Bathrooms - allow porcelain tile	47,020	SF	20.00	940,400
Special use areas	6,236	SF	10.00	62,360
Concrete sealer at basement	207,024	SF	2.00	414,048
Walls				
Lobby	1	EA	75,000.00	75,000
Core circulation	141,060	SF	3.00	423,180
Residential				
Livingrooms	282,100	SF	2.00	564,200
Bedrooms	329,130	SF	1.00	329,130
Kitchen	84,630	SF	10.00	846,300
Bathrooms	94,040	SF	12.00	1,128,480
Special use areas	9,354	SF	12.00	112,248
Paint to concrete and CMU at basement	70,776	SF	1.00	70,776
Ceilings				
Lobby	5,000	SF	25.00	125,000
Core circulation	70,530	SF	12.00	846,360
Residential				
Livingrooms	141,050	SF	6.00	846,300
Bedrooms	164,565	SF	6.00	987,390
Kitchen	42,315	SF	6.00	253,890
Bathrooms	47,020	SF	6.00	282,120
Special use areas	6,236	SF	10.00	62,360
Paint to exposed structure at basement	207,024	SF	2.00	414,048
				14,530,135

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
8. Function Equipment & Specialties				
Specialties				
Fire extinguisher cabinets	150	EA	450.00	67,500
Trash chute	1	EA	110,000.00	110,000
Parking Garage equipment	1	LS	25,000.00	25,000
Built in Equipment				
Lobby/entry	1	LS	25,000.00	25,000
Core area	70,530	SF	0.75	52,898
Residential				
Livingrooms	141,050	SF	0.05	7,053
Bedrooms	164,565	SF	0.10	16,457
Bathrooms	47,020	SF	1.00	47,020
Kitchen	42,315	EA	6.00	253,890
Special use areas	6,236	SF	2.00	12,472
Residential appliances				
Kitchen appliances				
Refrigerator	310	EA	1,700.00	527,000
Range	310	EA	2,000.00	620,000
Range hood	310	EA	1,000.00	310,000
Double oven	310	EA	800.00	248,000
Dishwasher	310	EA	850.00	263,500
Microwave	310	EA	450.00	139,500
Washing machine	310	EA	1,200.00	372,000
Dryer - electric	310	EA	1,200.00	372,000
Window washing equipment	1	LS	450,000.00	450,000
				3,919,289
9. Stairs & Vertical Transportation				
Stairs				
Regular stair flights	88	EA	22,000.00	1,936,000
Elevators				
Passenger Elevators, gearless traction	176	STOP	28,000.00	4,928,000
Freight Elevators, geared traction, 4 stop	8	STOP	32,000.00	256,000
				7,120,000

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
10. Plumbing Systems				
Sanitary fixtures and connection piping				
Toilets	736	EA	1,600.00	1,177,600
Lavatories	736	EA	1,200.00	883,200
Tub/shower combo	580	EA	1,800.00	1,044,000
Showers	232	EA	350.00	81,200
Kitchen sinks	310	EA	1,700.00	527,000
Washing machine connection	310	EA	350.00	108,500
Hose bibbs	10	EA	500.00	5,000
Domestic water and distribution				
Cold Water Service				
Copper piping incl. fittings >2"	900	LF	50.00	45,000
Copper piping incl. fittings to 2"	58,280	LF	32.00	1,864,960
Hot Water Service				
Copper piping incl. fittings >2"	1,400	LF	50.00	70,000
Copper piping incl. fittings to 2"	65,040	LF	32.00	2,081,280
Insulation	66,440	LF	9.00	597,960
Valves				
Isolation valves to 3/4"	4,772	EA	65.00	310,180
Domestic Water Supply Equipment				
Hot water heating and circulation	310	EA	900.00	279,000
Sanitary waste				
Waste & vent pipework-above ground				
Cast Iron No Hub, >6"	900	LF	75.00	67,500
Cast Iron No Hub, to 3"	58,280	LF	32.00	1,864,960
Sanitary waste, vent and service piping				
Floor Drains	88	EA	1,000.00	88,000
Rain Water Drainage				
Pipe and Fittings	51,583	LF	35.00	1,805,422
Roof/Overflow Drains	86	EA	750.00	64,695
Gas distribution				
Copper piping incl. fittings to 2"	2,000	LF	25.00	50,000
				13,015,457

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
11. Heating, Ventilation & Air Conditioning				
Heat generating systems				
Heating hot water boilers, high efficiency condensing: Core Area only	3,700	MBTH	25.00	92,500
Heating hot water pumps	2	EA	15,000.00	30,000
Cooling Generating Systems: Core Area only				
Cooling towers	500	TN	250.00	125,000
Chillers, 2 each	500	TN	450.00	225,000
Chilled water pumps	2	EA	10,000.00	20,000
Condenser water pumps	2	EA	5,000.00	10,000
Variable speed drives, vibration isolation, etc.	6	EA	12,000.00	72,000
Distribution systems: Core Area only				
Piping, fittings, valves and insulation				
Chilled water				
Chilled water pipework, fittings	1,400	LF	95.00	133,000
Valves and specialties	1	LS	75,000.00	75,000
Heating hot water				
Heating hot water pipework, fittings, including insulation				
6" - 4"	1,200	LF	85.00	102,000
< = 3"	4,000	LF	30.00	120,000
Valves and specialties	1	LS	25,000.00	25,000
Condenser water				
Condenser water pipework, fittings	1,200	LF	90.00	108,000
Valves and specialties	1	LS	25,000.00	25,000
Connections to Fan Coil Boxes	164	EA	350.00	57,236
Air handling equipment				
Dedicated outside air supply air handler	220,000	CFM	5.00	1,100,000
Individual unit packaged units	310	EA	6,000.00	1,860,000
Fan Coil Units				
Core/Shell	164	EA	1,250.00	204,415
Parking area	207	EA	1,250.00	258,750
Sound attenuation - duct mounted	220,000	CFM	0.25	55,000
Air distribution, return and exhaust				
Galvanized sheet metal ductwork	288,790	LB	8.00	2,310,320
Dryer exhaust duct	9,300	LF	6.00	55,800
Flexible ductwork	3,000	LF	6.00	18,000
Dampers, volume	100	EA	40.00	4,000
Dampers, smoke/fire	80	EA	1,200.00	96,000
Insulation/duct liner	100,000	SF	2.50	250,000

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
Diffusers, registers and grilles				
Ceiling				
Core/Shell	818	EA	200.00	163,532
Tenant areas, 1 per 150 USF	2,633	EA	150.00	394,950
Parking area				
Terminal & Package Units				
Exhaust fans at toilet rooms	736	EA	350.00	257,600
Controls and instrumentation				
DDC Control system	288,790	SF	3.00	866,370
Test and balance				
Test and balance	288,790	SF	1.25	360,988
				9,475,461

12. Electrical Lighting, Power & Communication

Primary Service, Medium voltage				
Switchgear 13.8KV including (2) tie breakers, (2) feeder breakers, and customer metering	6,000	KVA	60.00	360,000
Transformer substation 13.8KV/110-208V, double-ended including secondary distribution	6,000	KVA	150.00	900,000
Distribution switchboards - 110-208V	18,600	AMP	25.00	465,000
Distribution panelboards - 208V	310	EA	1,500.00	465,000
Feeder conduit and wire - 600V	45,000	LF	80.00	3,600,000
Emergency and Uninterrupted Power				
Emergency Generator	1,500	KVA	350.00	525,000
Automatic transfer switch	1,500	AMP	45.00	67,500
Distribution panelboards	1,500	AMP	25.00	37,500
General Purpose Lighting				
Panelboards	46	EA	2,500.00	115,000
Lighting				
Core Area	81,766	SF	12.00	981,192
Tenant Area	394,950	SF	2.00	789,900
Parking area	207,024	SF	4.00	828,096

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
Machine and Equipment Power				
Connections and switches including conduit and wire				
Elevators	16	EA	1,000.00	16,000
Cooling towers	2	EA	5,000.00	10,000
Chillers	2	EA	12,000.00	24,000
Pumps	6	EA	2,000.00	12,000
Miscellaneous connections	683,748	SF	0.75	512,811
User Convenience Power				
Panelboards	46	EA	2,500.00	115,000
Receptacles				
Core/Shell	81,766	SF	3.00	245,298
Tenant Area	394,950	SF	3.00	1,184,850
Parking area	207,024	SF	2.00	414,048
Communications				
Telephone and communications				
Core Area, panels and backbone only	1	LS	75,000.00	75,000
Tenant Units	310	EA	800.00	248,000
Security Systems				
Main Security System	683,748	SF	0.10	68,375
Tenant Units	310	EA	900.00	279,000
Fire Alarm Systems				
Main Fire Alarm Systems	683,748	SF	3.00	2,051,244
Other Electrical Systems				
Grounding Systems	683,748	SF	0.25	170,937
Lightning protection	1	LS	25,000.00	25,000
				14,585,751

13. Fire Protection Systems

Sprinkler and Standpipe Systems				
Fire Protection Sprinkler Systems	683,748	SF	4.00	2,734,992
Standpipe and Hose Systems	683,748	SF	1.00	683,748
Specialties and Other Systems				
Smoke Evacuation	1	LS	250,000.00	250,000
				3,668,740

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
14. Site Preparation & Building Demolition				
Site Preparation	100,000	SF	15.00	1,500,000
				1,500,000
15. Site Paving, Structures & Landscaping				
Site Development	48,244	SF	25.00	1,206,100
				1,206,100
16. Utilities on Site				
Site Utilities	1	LS	500,000.00	500,000
				500,000

PERFORMANCE BASED COMPONENT SUMMARY

Gross Area: 683,748 SF

		$/SF	$x1,000
1. Foundations		18.23	12,462
2. Vertical Structure		19.54	13,362
3. Floor & Roof Structures		26.81	18,333
4. Exterior Cladding		33.35	22,803
5. Roofing, Waterproofing & Skylights		3.69	2,526
Shell (1-5)		101.62	69,486
6. Interior Partitions, Doors & Glazing		24.75	16,922
7. Floor, Wall & Ceiling Finishes		21.25	14,530
Interiors (6-7)		46.00	31,452
8. Function Equipment & Specialties		5.73	3,919
9. Stairs & Vertical Transportation		10.41	7,120
Equipment & Vertical Transportation (8-9)		16.15	11,039
10. Plumbing Systems		19.04	13,015
11. Heating, Ventilating & Air Conditioning		13.86	9,475
12. Electric Lighting, Power & Communications		21.33	14,586
13. Fire Protection Systems		5.37	3,669
Mechanical & Electrical (10-13)		59.59	40,745
Total Building Construction (1-13)		**223.36**	**152,723**
14. Site Preparation & Demolition		2.19	1,500
15. Site Paving, Structures & Landscaping		1.76	1,206
16. Utilities on Site		0.73	500
Total Site Construction (14-16)		**4.69**	**3,206**
TOTAL BUILDING & SITE (1-16)		**228.05**	**155,929**
General Conditions	12.00%	27.37	18,711
Contractor's Overhead & Profit or Fee	6.00%	15.32	10,478
PLANNED CONSTRUCTION COST	***March 2010***	**270.74**	**185,118**
Design, Management and Inspection	20.00%	54.15	37,024
Escalation is excluded	0.00%	0.00	0
RECOMMENDED BUDGET	***March 2010***	**324.89**	**222,142**

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
1. Foundations				
Basement Excavation				
Excavation	99,173	CY	15.00	1,487,595
Shoring at perimeter	36,400	SF	50.00	1,820,000
Backfill with imported material	14,829	CY	35.00	519,015
Dispose off site	99,173	CY	20.00	1,983,460
Hazardous material remediation				Excluded
Foundations				
Reinforced concrete Mat foundation				
Excavation and disposal	12,583	CY	15.00	188,745
Forwork	7,240	SF	18.00	130,320
Reinforcing steel	1,872,457	LBS	1.15	2,153,326
Concrete, f'c= 6ksi	12,583	CY	325.00	4,089,475
Elevator pits	6	EA	15,000.00	90,000
				12,461,936
2. Vertical Structure				
Columns and pilasters				
Concrete columns				
Forwork	99,875	SF	25.00	2,496,875
Reinforcing steel	972,895	LBS	1.25	1,216,119
Concrete, f'c= 8ksi	2,048	CY	350.00	716,800
Concrete retaining walls				
Concrete retaining wall				
Formwork to one side	36,400	SF	15.00	546,000
Reinforcing steel	240,240	LBS	1.25	300,300
Concrete, f'c= 5ksi	1,978	CY	225.00	445,050
Concrete core walls				
Formwork to both sides	157,864	SF	18.00	2,841,552
Reinforcing steel	1,961,782	LBS	1.25	2,452,228
Concrete, f'c= 8ksi	6,706	CY	350.00	2,347,100
				13,362,023

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
3. Floor and Roof Structure				
Floor at lowest level				
Slab on grade - See foundations (mat slab)				
Suspended floors				
10" thick reinforced concrete flat slab - basement slabs				
Formwork	155,268	SF	10.00	1,552,680
Reinforcing steel	768,577	LBS	1.25	960,721
Concrete, f'c= 5.5ksi	4,792	CY	225.00	1,078,200
8" thick post tensioned slabs				
Formwork	463,874	SF	10.00	4,638,740
Reinforcing steel	1,122,575	LBS	1.25	1,403,219
Post tension tendons	459,236	LBS	2.00	918,472
Studrails at columns (9 studrais with 9 studs per rail)	1,476	LOC	4,000.00	5,904,000
Concrete, f'c= 5.5ksi	3	CY	225.00	675
Ground level slab/roof				
12" thick reinforced concrete flat slab - ground level				
Formwork	51,756	SF	10.00	517,560
Reinforcing steel	455,453	LBS	1.25	569,316
Concrete, f'c= 5.5ksi	2,109	CY	225.00	474,525
High roof				
10" thick reinforced concrete flat slab				
Formwork	12,850	SF	10.00	128,500
Reinforcing steel	70,675	LBS	1.25	88,344
Concrete, f'c= 5.5ksi	437	CY	225.00	98,325
				18,333,277
4. Exterior Cladding				
Wall framing, furring and insulation				
Exterior wall framing	168,413	SF	8.00	1,347,304
Furring to interior face of retaining wall	36,000	SF	4.00	144,000
Insulation and vapor barrier	161,050	SF	1.50	241,575

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
Applied exterior finishes				
Exterior wall finish - curtain wall with spandrel panels	125,050	SF	120.00	15,006,000
Parapets & edge detailing	400	LF	250.00	100,000
Interior finish to exterior walls				
Gypsum board, taped and sanded	161,050	SF	3.50	563,675
Windows, glazing and louvers				
Exterior wall finish - curtain wall with glazing	40,883	SF	120.00	4,905,960
Exterior doors, frames and hardware				
Glazed Doors & Entrances (allow revolving)	12	EA	35,000.00	420,000
Solid Exterior Doors	8	EA	3,000.00	24,000
Overhead Doors	2	EA	25,000.00	50,000
				22,802,514

5. Roofing, Waterproofing & Skylights

Waterproofing				
Waterproofing at slab on grade	49,940	SF	10.00	499,400
Waterproofing at retaining wall	42,912	SF	10.00	429,120
Waterproofing membrane under plaza	31,750	SF	15.00	476,250
Insulation				
Rigid insulation at roof	18,190	SF	6.00	109,140
Roofing				
Balconies & accessible roofs	31,750	SF	25.00	793,750
High roof	18,190	SF	12.00	218,280
				2,525,940

6. Interior Partitions, Doors & Glazing

Partition framing and cores				
CMU partitions at basement levels	1,656	LF	325.00	538,200
Core partitions	11,880	LF	90.00	1,069,200
Standard partitions	118,798	LF	72.00	8,553,456

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
Doors, frames & hardware				
Unit entrance doors	310	EA	2,250.00	697,500
Standard interior doors	2,680	EA	1,800.00	4,824,000
Closet doors at units - allow bi-fold	1,240	EA	1,000.00	1,240,000
				16,922,356

7. Floor, Wall & Ceiling Finishes

Floors including base				
Lobby flooring	5,000	SF	35.00	175,000
Core circulation - allow carpet	70,530	SF	6.00	423,180
Residential				
Livingrooms - allow wood	141,050	SF	22.00	3,103,100
Bedrooms - allow carpet	164,565	SF	6.00	987,390
Kitchen - allow stone tile	42,315	SF	25.00	1,057,875
Bathrooms - allow ceramic tile	47,020	SF	20.00	940,400
Special use areas	6,236	SF	10.00	62,360
Concrete sealer at basement	207,024	SF	2.00	414,048
Walls				
Lobby	1	EA	75,000.00	75,000
Core circulation	141,060	SF	3.00	423,180
Residential				
Livingrooms	282,100	SF	2.00	564,200
Bedrooms	329,130	SF	1.00	329,130
Kitchen	84,630	SF	10.00	846,300
Bathrooms	94,040	SF	12.00	1,128,480
Special use areas	9,354	SF	12.00	112,248
Paint to concrete and CMU at basement	70,776	SF	1.00	70,776
Ceilings				
Lobby	5,000	SF	25.00	125,000
Core circulation	70,530	SF	12.00	846,360
Residential				
Livingrooms	141,050	SF	6.00	846,300
Bedrooms	164,565	SF	6.00	987,390
Kitchen	42,315	SF	6.00	253,890
Bathrooms	47,020	SF	6.00	282,120
Special use areas	6,236	SF	10.00	62,360
Paint to exposed structure at basement	207,024	SF	2.00	414,048
				14,530,135

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
8. Function Equipment & Specialties				
Specialties				
Fire extinguisher cabinets	150	EA	450.00	67,500
Trash chute	1	EA	110,000.00	110,000
Parking Garage equipment	1	LS	25,000.00	25,000
Built in Equipment				
Lobby/entry	1	LS	25,000.00	25,000
Core area	70,530	SF	0.75	52,898
Residential				
Livingrooms	141,050	SF	0.05	7,053
Bedrooms	164,565	SF	0.10	16,457
Bathrooms	47,020	SF	1.00	47,020
Kitchen	42,315	EA	6.00	253,890
Special use areas	6,236	SF	2.00	12,472
Residential appliances				
Kitchen appliances				
Refrigerator	310	EA	1,700.00	527,000
Range	310	EA	2,000.00	620,000
Range hood	310	EA	1,000.00	310,000
Double oven	310	EA	800.00	248,000
Dishwasher	310	EA	850.00	263,500
Microwave	310	EA	450.00	139,500
Washing machine	310	EA	1,200.00	372,000
Dryer - electric	310	EA	1,200.00	372,000
Window washing equipment	1	LS	450,000.00	450,000
				3,919,289
9. Stairs & Vertical Transportation				
Stairs				
Regular stair flights	88	EA	22,000.00	1,936,000
Elevators				
Passenger Elevators, gearless traction	176	STOP	28,000.00	4,928,000
Freight Elevators, geared traction, 4 stop	8	STOP	32,000.00	256,000
				7,120,000

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
10. Plumbing Systems				
Sanitary fixtures and connection piping				
Toilets	736	EA	1,600.00	1,177,600
Lavatories	736	EA	1,200.00	883,200
Tub/shower combo	580	EA	1,800.00	1,044,000
Showers	232	EA	350.00	81,200
Kitchen sinks	310	EA	1,700.00	527,000
Washing machine connection	310	EA	350.00	108,500
Hose bibbs	10	EA	500.00	5,000
Domestic water and distribution				
Cold Water Service				
Copper piping incl. fittings >2"	900	LF	50.00	45,000
Copper piping incl. fittings to 2"	58,280	LF	32.00	1,864,960
Hot Water Service				
Copper piping incl. fittings >2"	1,400	LF	50.00	70,000
Copper piping incl. fittings to 2"	65,040	LF	32.00	2,081,280
Insulation	66,440	LF	9.00	597,960
Valves				
Isolation valves to 3/4"	4,772	EA	65.00	310,180
Domestic Water Supply Equipment				
Hot water heating and circulation	310	EA	900.00	279,000
Sanitary waste				
Waste & vent pipework-above ground				
Cast Iron No Hub, >6"	900	LF	75.00	67,500
Cast Iron No Hub, to 3"	58,280	LF	32.00	1,864,960
Sanitary waste, vent and service piping				
Floor Drains	88	EA	1,000.00	88,000
Rain Water Drainage				
Pipe and Fittings	51,583	LF	35.00	1,805,422
Roof/Overflow Drains	86	EA	750.00	64,695
Gas distribution				
Copper piping incl. fittings to 2"	2,000	LF	25.00	50,000
				13,015,457

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
11. Heating, Ventilation & Air Conditioning				
Heat generating systems				
Heating hot water boilers, high efficiency condensing: Core Area only	3,700	MBTH	25.00	92,500
Heating hot water pumps	2	EA	15,000.00	30,000
Cooling Generating Systems: Core Area only				
Cooling towers	500	TN	250.00	125,000
Chillers, 2 each	500	TN	450.00	225,000
Chilled water pumps	2	EA	10,000.00	20,000
Condenser water pumps	2	EA	5,000.00	10,000
Variable speed drives, vibration isolation, etc.	6	EA	12,000.00	72,000
Distribution systems: Core Area only				
Piping, fittings, valves and insulation				
Chilled water				
Chilled water pipework, fittings	1,400	LF	95.00	133,000
Valves and specialties	1	LS	75,000.00	75,000
Heating hot water				
Heating hot water pipework, fittings, including insulation				
6" - 4"	1,200	LF	85.00	102,000
< = 3"	4,000	LF	30.00	120,000
Valves and specialties	1	LS	25,000.00	25,000
Condenser water				
Condenser water pipework, fittings	1,200	LF	90.00	108,000
Valves and specialties	1	LS	25,000.00	25,000
Connections to Fan Coil Boxes	164	EA	350.00	57,236
Air handling equipment				
Dedicated outside air supply air handler	220,000	CFM	5.00	1,100,000
Individual unit packaged units	310	EA	6,000.00	1,860,000
Fan Coil Units				
Core/Shell	164	EA	1,250.00	204,415
Parking area	207	EA	1,250.00	258,750
Sound attenuation - duct mounted	220,000	CFM	0.25	55,000
Air distribution, return and exhaust				
Galvanized sheet metal ductwork	288,790	LB	8.00	2,310,320
Dryer exhaust duct	9,300	LF	6.00	55,800
Flexible ductwork	3,000	LF	6.00	18,000
Dampers, volume	100	EA	40.00	4,000
Dampers, smoke/fire	80	EA	1,200.00	96,000
Insulation/duct liner	100,000	SF	2.50	250,000

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
Diffusers, registers and grilles				
Ceiling				
Core/Shell	818	EA	200.00	163,532
Tenant areas, 1 per 150 USF	2,633	EA	150.00	394,950
Parking area				
Terminal & Package Units				
Exhaust fans at toilet rooms	736	EA	350.00	257,600
Controls and instrumentation				
DDC Control system	288,790	SF	3.00	866,370
Test and balance				
Test and balance	288,790	SF	1.25	360,988
				9,475,461

12. Electrical Lighting, Power & Communication

Primary Service, Medium voltage				
Switchgear 13.8KV including (2) tie breakers, (2) feeder breakers, and customer metering	6,000	KVA	60.00	360,000
Transformer substation 13.8KV/110-208V, double-ended including secondary distribution	6,000	KVA	150.00	900,000
Distribution switchboards - 110-208V	18,600	AMP	25.00	465,000
Distribution panelboards - 208V	310	EA	1,500.00	465,000
Feeder conduit and wire - 600V	45,000	LF	80.00	3,600,000
Emergency and Uninterrupted Power				
Emergency Generator	1,500	KVA	350.00	525,000
Automatic transfer switch	1,500	AMP	45.00	67,500
Distribution panelboards	1,500	AMP	25.00	37,500
General Purpose Lighting				
Panelboards	46	EA	2,500.00	115,000
Lighting				
Core Area	81,766	SF	12.00	981,192
Tenant Area	394,950	SF	2.00	789,900
Parking area	207,024	SF	4.00	828,096

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
Machine and Equipment Power				
Connections and switches including conduit and wire				
Elevators	16	EA	1,000.00	16,000
Cooling towers	2	EA	5,000.00	10,000
Chillers	2	EA	12,000.00	24,000
Pumps	6	EA	2,000.00	12,000
Miscellaneous connections	683,748	SF	0.75	512,811
User Convenience Power				
Panelboards	46	EA	2,500.00	115,000
Receptacles				
Core/Shell	81,766	SF	3.00	245,298
Tenant Area	394,950	SF	3.00	1,184,850
Parking area	207,024	SF	2.00	414,048
Communications				
Telephone and communications				
Core Area, panels and backbone only	1	LS	75,000.00	75,000
Tenant Units	310	EA	800.00	248,000
Security Systems				
Main Security System	683,748	SF	0.10	68,375
Tenant Units	310	EA	900.00	279,000
Fire Alarm Systems				
Main Fire Alarm Systems	683,748	SF	3.00	2,051,244
Other Electrical Systems				
Grounding Systems	683,748	SF	0.25	170,937
Lightning protection	1	LS	25,000.00	25,000
				14,585,751

13. Fire Protection Systems

Sprinkler and Standpipe Systems				
Fire Protection Sprinkler Systems	683,748	SF	4.00	2,734,992
Standpipe and Hose Systems	683,748	SF	1.00	683,748
Specialties and Other Systems				
Smoke Evacuation	1	LS	250,000.00	250,000
				3,668,740

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
14. Site Preparation & Building Demolition				
Site Preparation	100,000	SF	15.00	1,500,000
				1,500,000
15. Site Paving, Structures & Landscaping				
Site Development	48,244	SF	25.00	1,206,100
				1,206,100
16. Utilities on Site				
Site Utilities	1	LS	500,000.00	500,000
				500,000

PERFORMANCE BASED PLUS COMPONENT SUMMARY

Gross Area: 683,748 SF

		$/SF	$x1,000
1. Foundations		18.60	12,719
2. Vertical Structure		19.73	13,489
3. Floor & Roof Structures		30.96	21,167
4. Exterior Cladding		33.35	22,803
5. Roofing, Waterproofing & Skylights		3.69	2,526
Shell (1-5)		106.33	72,704
6. Interior Partitions, Doors & Glazing		24.75	16,922
7. Floor, Wall & Ceiling Finishes		21.25	14,530
Interiors (6-7)		46.00	31,452
8. Function Equipment & Specialties		5.73	3,919
9. Stairs & Vertical Transportation		10.41	7,120
Equipment & Vertical Transportation (8-9)		16.15	11,039
10. Plumbing Systems		19.04	13,015
11. Heating, Ventilating & Air Conditioning		13.86	9,475
12. Electric Lighting, Power & Communications		21.33	14,586
13. Fire Protection Systems		5.37	3,669
Mechanical & Electrical (10-13)		59.59	40,745
Total Building Construction (1-13)		**228.07**	**155,941**
14. Site Preparation & Demolition		2.19	1,500
15. Site Paving, Structures & Landscaping		1.76	1,206
16. Utilities on Site		0.73	500
Total Site Construction (14-16)		**4.69**	**3,206**
TOTAL BUILDING & SITE (1-16)		**232.76**	**159,147**
General Conditions	12.00%	27.93	19,098
Contractor's Overhead & Profit or Fee	6.00%	15.64	10,695
PLANNED CONSTRUCTION COST	***March 2010***	**276.33**	**188,940**
Design, Management and Inspection	20.00%	55.27	37,788
Escalation is excluded	0.00%	0.00	0
RECOMMENDED BUDGET	***March 2010***	**331.60**	**226,728**

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
1. Foundations				
Basement Excavation				
Excavation	99,173	CY	15.00	1,487,595
Shoring at perimeter	36,400	SF	50.00	1,820,000
Backfill with imported material	14,829	CY	35.00	519,015
Dispose off site	99,173	CY	20.00	1,983,460
Hazardous material remediation				
Foundations				
Reinforced concrete Mat foundation				
Excavation and disposal	13,044	CY	15.00	195,660
Formwork	7,640	SF	18.00	137,520
Reinforcing steel	1,953,123	LBS	1.15	2,246,091
Concrete, f'c= 6ksi	13,044	CY	325.00	4,239,300
Elevator pits	6	EA	15,000.00	90,000
				12,718,641
2. Vertical Structure				
Columns and pilasters				
Concrete columns				
Forwork	99,875	SF	25.00	2,496,875
Reinforcing steel	972,895	LBS	1.25	1,216,119
Concrete, f'c= 8ksi	2,048	CY	350.00	716,800
Concrete retaining walls				
Concrete retaining wall				
Formwork to one side	36,400	SF	15.00	546,000
Reinforcing steel	240,240	LBS	1.25	300,300
Concrete, f'c= 5ksi	1,978	CY	225.00	445,050
Concrete core walls				
Formwork to both sides	157,864	SF	18.00	2,841,552
Reinforcing steel	1,961,782	LBS	1.25	2,452,228
Concrete, f'c= 8ksi	7,069	CY	350.00	2,474,150
				13,489,073

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
3. Floor and Roof Structure				
Floor at lowest level				
Slab on grade - See foundations (mat slab)				
Suspended floors				
10" thick reinforced concrete flat slab - basement slabs				
Formwork	155,268	SF	10.00	1,552,680
Reinforcing steel	768,577	LBS	1.25	960,721
Concrete, f'c= 5.5ksi	4,792	CY	225.00	1,078,200
8" thick post tensioned slabs				
Formwork	463,874	SF	10.00	4,638,740
Reinforcing steel	1,122,575	LBS	1.25	1,403,219
Post tension tendons	459,236	LBS	2.00	918,472
Studrails at columns (9 studrais with 9 studs per rail)	1,476	LOC	4,000.00	5,904,000
Concrete, f'c= 5.5ksi	12,599	CY	225.00	2,834,775
Ground level slab/roof				
12" thick reinforced concrete flat slab - ground level				
Formwork	51,756	SF	10.00	517,560
Reinforcing steel	455,453	LBS	1.25	569,316
Concrete, f'c= 5.5ksi	2,109	CY	225.00	474,525
High roof				
10" thick reinforced concrete flat slab				
Formwork	12,850	SF	10.00	128,500
Reinforcing steel	70,675	LBS	1.25	88,344
Concrete, f'c= 5.5ksi	437	CY	225.00	98,325
				21,167,377
4. Exterior Cladding				
Wall framing, furring and insulation				
Exterior wall framing	168,413	SF	8.00	1,347,304
Furring to interior face of retaining wall	36,000	SF	4.00	144,000
Insulation and vapor barrier	161,050	SF	1.50	241,575
Applied exterior finishes				
Exterior wall finish - curtain wall with spandrel panels	125,050	SF	120.00	15,006,000
Parapets & edge detailing	400	LF	250.00	100,000

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
Interior finish to exterior walls				
Gypsum board, taped and sanded	161,050	SF	3.50	563,675
Windows, glazing and louvers				
Exterior wall finish - curtain wall with glazing	40,883	SF	120.00	4,905,960
Exterior doors, frames and hardware				
Glazed Doors & Entrances (allow revolving)	12	EA	35,000.00	420,000
Solid Exterior Doors	8	EA	3,000.00	24,000
Overhead Doors	2	EA	25,000.00	50,000
				22,802,514

5. Roofing, Waterproofing & Skylights

Waterproofing				
Waterproofing at slab on grade	49,940	SF	10.00	499,400
Waterproofing at retaining wall	42,912	SF	10.00	429,120
Waterproofing membrane under plaza	31,750	SF	15.00	476,250
Insulation				
Rigid insulation at roof	18,190	SF	6.00	109,140
Roofing				
Balconies & accessible roofs	31,750	SF	25.00	793,750
High roof	18,190	SF	12.00	218,280
				2,525,940

6. Interior Partitions, Doors & Glazing

Partition framing and cores				
CMU partitions at basement levels	1,656	LF	325.00	538,200
Core partitions	11,880	LF	90.00	1,069,200
Standard partitions	118,798	LF	72.00	8,553,456
Doors, frames & hardware				
Unit entrance doors	310	EA	2,250.00	697,500
Standard interior doors	2,680	EA	1,800.00	4,824,000
Closet doors at units - allow bi-fold	1,240	EA	1,000.00	1,240,000
				16,922,356

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
7. Floor, Wall & Ceiling Finishes				
Floors including base				
Lobby flooring	5,000	SF	35.00	175,000
Core circulation - allow carpet	70,530	SF	6.00	423,180
Residential				
Livingrooms - allow wood	141,050	SF	22.00	3,103,100
Bedrooms - allow carpet	164,565	SF	6.00	987,390
Kitchen - allow stone tile	42,315	SF	25.00	1,057,875
Bathrooms - allow ceramic tile	47,020	SF	20.00	940,400
Special use areas	6,236	SF	10.00	62,360
Concrete sealer at basement	207,024	SF	2.00	414,048
Walls				
Lobby	1	EA	75,000.00	75,000
Core circulation	141,060	SF	3.00	423,180
Residential				
Livingrooms	282,100	SF	2.00	564,200
Bedrooms	329,130	SF	1.00	329,130
Kitchen	84,630	SF	10.00	846,300
Bathrooms	94,040	SF	12.00	1,128,480
Special use areas	9,354	SF	12.00	112,248
Paint to concrete and CMU at basement	70,776	SF	1.00	70,776
Ceilings				
Lobby	5,000	SF	25.00	125,000
Core circulation	70,530	SF	12.00	846,360
Residential				
Livingrooms	141,050	SF	6.00	846,300
Bedrooms	164,565	SF	6.00	987,390
Kitchen	42,315	SF	6.00	253,890
Bathrooms	47,020	SF	6.00	282,120
Special use areas	6,236	SF	10.00	62,360
Paint to exposed structure at basement	207,024	SF	2.00	414,048
				14,530,135
8. Function Equipment & Specialties				
Specialties				
Fire extinguisher cabinets	150	EA	450.00	67,500
Trash chute	1	EA	110,000.00	110,000
Parking Garage equipment	1	LS	25,000.00	25,000

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
Built in Equipment				
Lobby/entry	1	LS	25,000.00	25,000
Core area	70,530	SF	0.75	52,898
Residential				
Livingrooms	141,050	SF	0.05	7,053
Bedrooms	164,565	SF	0.10	16,457
Bathrooms	47,020	SF	1.00	47,020
Kitchen	42,315	EA	6.00	253,890
Special use areas	6,236	SF	2.00	12,472
Residential appliances				
Kitchen appliances				
Refrigerator	310	EA	1,700.00	527,000
Range	310	EA	2,000.00	620,000
Range hood	310	EA	1,000.00	310,000
Double oven	310	EA	800.00	248,000
Dishwasher	310	EA	850.00	263,500
Microwave	310	EA	450.00	139,500
Washing machine	310	EA	1,200.00	372,000
Dryer - electric	310	EA	1,200.00	372,000
Window washing equipment	1	LS	450,000.00	450,000
				3,919,289

9. Stairs & Vertical Transportation

Stairs				
Regular stair flights	88	EA	22,000.00	1,936,000
Elevators				
Passenger Elevators, gearless traction	176	STOP	28,000.00	4,928,000
Freight Elevators, geared traction, 4 stop	8	STOP	32,000.00	256,000
				7,120,000

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
10. Plumbing Systems				
Sanitary fixtures and connection piping				
Toilets	736	EA	1,600.00	1,177,600
Lavatories	736	EA	1,200.00	883,200
Tub/shower combo	580	EA	1,800.00	1,044,000
Showers	232	EA	350.00	81,200
Kitchen sinks	310	EA	1,700.00	527,000
Washing machine connection	310	EA	350.00	108,500
Hose bibbs	10	EA	500.00	5,000
Domestic water and distribution				
Cold Water Service				
Copper piping incl. fittings >2"	900	LF	50.00	45,000
Copper piping incl. fittings to 2"	58,280	LF	32.00	1,864,960
Hot Water Service				
Copper piping incl. fittings >2"	1,400	LF	50.00	70,000
Copper piping incl. fittings to 2"	65,040	LF	32.00	2,081,280
Insulation	66,440	LF	9.00	597,960
Valves				
Isolation valves to 3/4"	4,772	EA	65.00	310,180
Domestic Water Supply Equipment				
Hot water heating and circulation	310	EA	900.00	279,000
Sanitary waste				
Waste & vent pipework-above ground				
Cast Iron No Hub, >6"	900	LF	75.00	67,500
Cast Iron No Hub, to 3"	58,280	LF	32.00	1,864,960
Sanitary waste, vent and service piping				
Floor Drains	88	EA	1,000.00	88,000
Rain Water Drainage				
Pipe and Fittings	51,583	LF	35.00	1,805,422
Roof/Overflow Drains	86	EA	750.00	64,695
Gas distribution				
Copper piping incl. fittings to 2"	2,000	LF	25.00	50,000
				13,015,457

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
11. Heating, Ventilation & Air Conditioning				
Heat generating systems				
Heating hot water boilers, high efficiency condensing: Core Area only	3,700	MBTH	25.00	92,500
Heating hot water pumps	2	EA	15,000.00	30,000
Cooling Generating Systems: Core Area only				
Cooling towers	500	TN	250.00	125,000
Chillers, 2 each	500	TN	450.00	225,000
Chilled water pumps	2	EA	10,000.00	20,000
Condenser water pumps	2	EA	5,000.00	10,000
Variable speed drives, vibration isolation, etc.	6	EA	12,000.00	72,000
Distribution systems: Core Area only				
Piping, fittings, valves and insulation				
Chilled water				
Chilled water pipework, fittings	1,400	LF	95.00	133,000
Valves and specialties	1	LS	75,000.00	75,000
Heating hot water				
Heating hot water pipework, fittings, including insulation				
6" - 4"	1,200	LF	85.00	102,000
< = 3"	4,000	LF	30.00	120,000
Valves and specialties	1	LS	25,000.00	25,000
Condenser water				
Condenser water pipework, fittings	1,200	LF	90.00	108,000
Valves and specialties	1	LS	25,000.00	25,000
Connections to Fan Coil Boxes	164	EA	350.00	57,236
Air handling equipment				
Dedicated outside air supply air handler	220,000	CFM	5.00	1,100,000
Individual unit packaged units	310	EA	6,000.00	1,860,000
Fan Coil Units				
Core/Shell	164	EA	1,250.00	204,415
Parking area	207	EA	1,250.00	258,750
Sound attenuation - duct mounted	220,000	CFM	0.25	55,000
Air distribution, return and exhaust				
Galvanized sheet metal ductwork	288,790	LB	8.00	2,310,320
Dryer exhaust duct	9,300	LF	6.00	55,800
Flexible ductwork	3,000	LF	6.00	18,000
Dampers, volume	100	EA	40.00	4,000
Dampers, smoke/fire	80	EA	1,200.00	96,000
Insulation/duct liner	100,000	SF	2.50	250,000

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
Diffusers, registers and grilles				
Ceiling				
Core/Shell	818	EA	200.00	163,532
Tenant areas, 1 per 150 USF	2,633	EA	150.00	394,950
Parking area				
Terminal & Package Units				
Exhaust fans at toilet rooms	736	EA	350.00	257,600
Controls and instrumentation				
DDC Control system	288,790	SF	3.00	866,370
Test and balance				
Test and balance	288,790	SF	1.25	360,988
				9,475,461

12. Electrical Lighting, Power & Communication

Primary Service, Medium voltage				
Switchgear 13.8KV including (2) tie breakers, (2) feeder breakers, and customer metering	6,000	KVA	60.00	360,000
Transformer substation 13.8KV/110-208V, double-ended including secondary distribution	6,000	KVA	150.00	900,000
Distribution switchboards - 110-208V	18,600	AMP	25.00	465,000
Distribution panelboards - 208V	310	EA	1,500.00	465,000
Feeder conduit and wire - 600V	45,000	LF	80.00	3,600,000
Emergency and Uninterrupted Power				
Emergency Generator	1,500	KVA	350.00	525,000
Automatic transfer switch	1,500	AMP	45.00	67,500
Distribution panelboards	1,500	AMP	25.00	37,500
General Purpose Lighting				
Panelboards	46	EA	2,500.00	115,000
Lighting				
Core Area	81,766	SF	12.00	981,192
Tenant Area	394,950	SF	2.00	789,900
Parking area	207,024	SF	4.00	828,096

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
Machine and Equipment Power				
Connections and switches including conduit and wire				
Elevators	16	EA	1,000.00	16,000
Cooling towers	2	EA	5,000.00	10,000
Chillers	2	EA	12,000.00	24,000
Pumps	6	EA	2,000.00	12,000
Miscellaneous connections	683,748	SF	0.75	512,811
User Convenience Power				
Panelboards	46	EA	2,500.00	115,000
Receptacles				
Core/Shell	81,766	SF	3.00	245,298
Tenant Area	394,950	SF	3.00	1,184,850
Parking area	207,024	SF	2.00	414,048
Communications				
Telephone and communications				
Core Area, panels and backbone only	1	LS	75,000.00	75,000
Tenant Units	310	EA	800.00	248,000
Security Systems				
Main Security System	683,748	SF	0.10	68,375
Tenant Units	310	EA	900.00	279,000
Fire Alarm Systems				
Main Fire Alarm Systems	683,748	SF	3.00	2,051,244
Other Electrical Systems				
Grounding Systems	683,748	SF	0.25	170,937
Lightning protection	1	LS	25,000.00	25,000
				14,585,751

13. Fire Protection Systems

Sprinkler and Standpipe Systems				
Fire Protection Sprinkler Systems	683,748	SF	4.00	2,734,992
Standpipe and Hose Systems	683,748	SF	1.00	683,748
Specialties and Other Systems				
Smoke Evacuation	1	LS	250,000.00	250,000
				3,668,740

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
14. Site Preparation & Building Demolition				
Site Preparation	100,000	SF	15.00	1,500,000
				1,500,000
15. Site Paving, Structures & Landscaping				
Site Development	48,244	SF	25.00	1,206,100
				1,206,100
16. Utilities on Site				
Site Utilities	1	LS	500,000.00	500,000
				500,000

Davis Langdon

PROGRAM
COST MODEL

for

PEER Tall Buildings Study
Concrete Dual System Structural Option
Los Angeles, California

March 8, 2010

CONTENTS

	Page Nos.
Overall Summary	1
Areas and Control Quantities	2
Code Based Component Summary	3
Performance Based Component Summary	15

OVERALL SUMMARY

	Gross Floor Area	$ / SF	$x1,000
Construction Cost (Including Design)			
Code Based	683,748 SF	347.36	237,508
Performance Based	683,748 SF	411.33	281,245
Performance Based Plus	683,748 SF	411.33	281,245
FF&E Cost			
Furniture & Fittings, (resdential)	476,716 SF	20.00	9,534
Equipment, including computer systems	476,716 SF	7.00	3,337
Personal Property			
Personal Contents	476,716 SF	10.00	4,767
Cars in parking (Maximum count)	520 EA	25,000.00	13,000

Please refer to the Inclusions and Exclusions sections of this report

AREAS & CONTROL QUANTITIES

Areas

	SF	SF	SF
Enclosed Areas			
Basement Levels B1 - B4	207,024		
Ground Level	11,314		
Levels 2 - 42	463,874		
Penthouse	1,536		
SUBTOTAL, Enclosed Area		683,748	
Covered area			
SUBTOTAL, Covered Area @ ½ Value			
TOTAL GROSS FLOOR AREA			683,748

Control Quantities

				Ratio to Gross Area
Functional Units		310	Units	0.453
Number of stories (x1,000)		46	EA	0.067
Gross Area		683,748	SF	1.000
Enclosed Area		683,748	SF	1.000
Covered Area		0	SF	0.000
Footprint Area		51,756	SF	0.076
Volume		7,212,004	CF	10.548
Basement Volume		0	CF	0.000
Gross Wall Area		212,093	SF	0.310
Retaining Wall Area		38,220	SF	0.056
Finished Wall Area		135,600	SF	0.198
Windows or Glazing Area	20.93%	44,400	SF	0.065
Roof Area - Flat		51,756	SF	0.076
Roof Area - Sloping		0	SF	0.000
Roof Area - Total		51,756	SF	0.076
Roof Glazing Area		0	SF	0.000
Interior Partition Length		132,334	LF	0.194
Finished Area		683,748	SF	1.000
Elevators (x10,000)		6	EA	0.088
Plumbing Fixtures (x1,000)		2,914	EA	4.262
Electrical Load		6,000	KW	8.775

CODE BASED COMPONENT SUMMARY

Gross Area: 683,748 SF

		$/SF	$x1,000
1. Foundations		16.35	11,178
2. Vertical Structure		21.86	14,949
3. Floor & Roof Structures		39.07	26,717
4. Exterior Cladding		36.15	24,720
5. Roofing, Waterproofing & Skylights		3.98	2,721
Shell (1-5)		117.42	80,286
6. Interior Partitions, Doors & Glazing		24.75	16,922
7. Floor, Wall & Ceiling Finishes		21.23	14,515
Interiors (6-7)		45.98	31,437
8. Function Equipment & Specialties		5.73	3,919
9. Stairs & Vertical Transportation		10.41	7,120
Equipment & Vertical Transportation (8-9)		16.15	11,039
10 Plumbing Systems		19.04	13,015
11 Heating, Ventilating & Air Conditioning		13.86	9,475
12 Electric Lighting, Power & Communications		21.33	14,586
13 Fire Protection Systems		5.37	3,669
Mechanical & Electrical (10-13)		59.59	40,745
Total Building Construction (1-13)		**239.13**	**163,508**
14 Site Preparation & Demolition		2.19	1,500
15 Site Paving, Structures & Landscaping		1.76	1,206
16 Utilities on Site		0.73	500
Total Site Construction (14-16)		**4.69**	**3,206**
TOTAL BUILDING & SITE (1-16)		**243.82**	**166,714**
General Conditions	12.00%	29.26	20,006
Contractor's Overhead & Profit or Fee	6.00%	16.38	11,203
PLANNED CONSTRUCTION COST	***March 2010***	**289.47**	**197,923**
Design, Management and Inspection	20.00%	57.89	39,585
Escalation is excluded	0.00%	0.00	0
RECOMMENDED BUDGET	***March 2010***	**347.36**	**237,508**

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
1. Foundations				
Basement Excavation				
Excavation	99,173	CY	15.00	1,487,595
Shoring at perimeter	36,400	SF	50.00	1,820,000
Backfill with imported material	14,829	CY	35.00	519,015
Dispose off site	99,173	CY	20.00	1,983,460
Hazardous material remediation				Excluded
Foundations				
Reinforced concrete Mat foundation				
Excavation and disposal	10,278	CY	15.00	154,170
Forwork	5,240	SF	18.00	94,320
Reinforcing steel	1,469,135	LBS	1.15	1,689,505
Concrete, f'c= 6ksi	10,278	CY	325.00	3,340,350
Elevator pits	6	EA	15,000.00	90,000
				11,178,415
2. Vertical Structure				
Columns and pilasters				
Concrete columns - moment frames				
Formwork	100,415	SF	25.00	2,510,375
Reinforcing steel	1,311,700	LBS	1.25	1,639,625
Concrete				
f'c= 10ksi	288	CY	450.00	129,600
f'c= 8ksi	670	CY	350.00	234,500
f'c= 6ksi	350	CY	325.00	113,750
f'c= 5ksi	1,918	CY	225.00	431,550
Concrete columns - standard				
Forwork	36,277	SF	25.00	906,925
Reinforcing steel	343,701	LBS	1.25	429,626
Concrete, f'c= 8ksi	658	CY	350.00	230,300
Concrete retaining walls				
Concrete retaining wall				
Formwork to one side	38,220	SF	25.00	955,500
Reinforcing steel	252,252	LBS	1.25	315,315
Concrete, f'c= 5ksi	2,076	CY	225.00	467,100

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
Concrete core walls				
Formwork to both sides	170,841	SF	25.00	4,271,025
Reinforcing steel	474,699	LBS	1.25	593,374
Concrete				
f'c= 6ksi	3,496	CY	325.00	1,136,200
f'c= 5ksi	2,598	CY	225.00	584,550
				14,949,315

3. Floor and Roof Structure

Floor at lowest level				
Slab on grade - See foundations (mat slab)				
Suspended floors				
10" thick reinforced concrete flat slab - basement slabs				
Formwork	155,268	SF	10.00	1,552,680
Reinforcing steel	768,577	LBS	1.25	960,721
Concrete, f'c= 5.5ksi	5,271	CY	225.00	1,185,975
8" thick post tensioned slabs				
Formwork	463,874	SF	10.00	4,638,740
Reinforcing steel	1,122,575	LBS	1.25	1,403,219
Post tension tendons	459,236	LBS	2.00	918,472
Studrails at columns (9 studrais with 9 studs per rail)	1,476	LOC	4,000.00	5,904,000
Concrete, f'c= 5.5ksi	12,599	CY	225.00	2,834,775
Special moment resisting frame reinforced concrete beam				
Formwork	137,632	SF	15.00	2,064,480
Reinforcing steel	1,639,660	LBS	1.25	2,049,575
Concrete, f'c= 5ksi	4,948	CY	225.00	1,113,300
Ground level slab/roof				
12" thick reinforced concrete flat slab - ground level				
Formwork	51,756	SF	10.00	517,560
Reinforcing steel	455,453	LBS	1.25	569,316
Concrete, f'c= 5.5ksi	2,109	CY	225.00	474,525
Special moment resisting frame reinforced concrete beam				
Formwork	3,128	SF	10.00	31,280
Reinforcing steel	35,754	LBS	1.25	44,693
Concrete, f'c= 5ksi	112	CY	225.00	25,200

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
High roof				
10" thick reinforced concrete flat slab				
Formwork	12,850	SF	10.00	128,500
Reinforcing steel	70,675	LBS	1.25	88,344
Concrete, f'c= 5.5ksi	437	CY	225.00	98,325
Special moment resisting frame reinforced concrete beam				
Formwork	3,128	SF	15.00	46,920
Reinforcing steel	33,109	LBS	1.25	41,386
Concrete, f'c= 5ksi	112	CY	225.00	25,200
				26,717,186

4. Exterior Cladding

Wall framing, furring and insulation				
Exterior wall framing	182,947	SF	8.00	1,463,576
Furring to interior face of retaining wall	38,220	SF	4.00	152,880
Insulation and vapor barrier	173,820	SF	1.50	260,730
Applied exterior finishes				
Exterior wall finish - curtain wall with spandrel panels	135,600	SF	120.00	16,272,000
Parapets & edge detailing	560	LF	250.00	140,000
Interior finish to exterior walls				
Gypsum board, taped and sanded	173,820	SF	3.50	608,370
Windows, glazing and louvers				
Exterior wall finish - curtain wall with glazing	44,400	SF	120.00	5,328,000
Exterior doors, frames and hardware				
Glazed Doors & Entrances (allow revolving)	12	EA	35,000.00	420,000
Solid Exterior Doors	8	EA	3,000.00	24,000
Overhead Doors	2	EA	25,000.00	50,000
				24,719,556

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
5. Roofing, Waterproofing & Skylights				
Waterproofing				
Waterproofing at slab on grade	51,756	SF	10.00	517,560
Waterproofing at retaining wall	38,220	SF	10.00	382,200
Waterproofing membrane under plaza	40,442	SF	15.00	606,630
Insulation				
Rigid insulation at roof	11,314	SF	6.00	67,884
Roofing				
Balconies & accessible roofs	40,442	SF	25.00	1,011,050
High roof	11,314	SF	12.00	135,768
				2,721,092
6. Interior Partitions, Doors & Glazing				
Partition framing and cores				
CMU partitions at basement levels	1,656	LF	325.00	538,200
Core partitions	11,880	LF	90.00	1,069,200
Standard partitions	118,798	LF	72.00	8,553,456
Doors, frames & hardware				
Unit entrance doors	310	EA	2,250.00	697,500
Standard interior doors	2,680	EA	1,800.00	4,824,000
Closet doors at units - allow bi-fold	1,240	EA	1,000.00	1,240,000
				16,922,356
7. Floor, Wall & Ceiling Finishes				
Floors including base				
Lobby flooring	5,000	SF	35.00	175,000
Core circulation - allow carpet	70,530	SF	6.00	423,180
Residential				
Livingrooms - allow wood	141,050	SF	22.00	3,103,100
Bedrooms - allow carpet	164,565	SF	6.00	987,390
Kitchen - allow stone tile	42,315	SF	25.00	1,057,875
Bathrooms - allow ceramic tile	47,020	SF	20.00	940,400
Special use areas	6,236	SF	10.00	62,360
Concrete sealer at basement	207,024	SF	2.00	414,048

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
Walls				
Lobby	1	EA	75,000.00	75,000
Core circulation	141,060	SF	3.00	423,180
Residential				
Livingrooms	282,100	SF	2.00	564,200
Bedrooms	329,130	SF	1.00	329,130
Kitchen	84,630	SF	10.00	846,300
Bathrooms	94,040	SF	12.00	1,128,480
Special use areas	9,354	SF	12.00	112,248
Paint to concrete and CMU at basement	55,608	SF	1.00	55,608
Ceilings				
Lobby	5,000	SF	25.00	125,000
Core circulation	70,530	SF	12.00	846,360
Residential				
Livingrooms	141,050	SF	6.00	846,300
Bedrooms	164,565	SF	6.00	987,390
Kitchen	42,315	SF	6.00	253,890
Bathrooms	47,020	SF	6.00	282,120
Special use areas	6,236	SF	10.00	62,360
Paint to exposed structure at basement	207,024	SF	2.00	414,048
				14,514,967

8. Function Equipment & Specialties

Specialties				
Fire extinguisher cabinets	150	EA	450.00	67,500
Trash chute	1	EA	110,000.00	110,000
Parking Garage equipment	1	LS	25,000.00	25,000
Built in Equipment				
Lobby/entry	1	LS	25,000.00	25,000
Core area	70,530	SF	0.75	52,898
Residential				
Livingrooms	141,050	SF	0.05	7,053
Bedrooms	164,565	SF	0.10	16,457
Kitchens	42,315	EA	6.00	253,890
Bathrooms	47,020	SF	1.00	47,020
Special use areas	6,236	SF	2.00	12,472

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
Residential appliances				
Kitchen appliances				
Refrigerator	310	EA	1,700.00	527,000
Range	310	EA	2,000.00	620,000
Range hood	310	EA	1,000.00	310,000
Double oven	310	EA	800.00	248,000
Dishwasher	310	EA	850.00	263,500
Microwave	310	EA	450.00	139,500
Washing machine	310	EA	1,200.00	372,000
Dryer - electric	310	EA	1,200.00	372,000
Window washing equipment	1	LS	450,000.00	450,000
				3,919,289

9. Stairs & Vertical Transportation

Stairs				
Regular stair flights	88	EA	22,000.00	1,936,000
Elevators				
Passenger Elevators, gearless traction	176	STOP	28,000.00	4,928,000
Freight Elevators, geared traction, 4 stop	8	STOP	32,000.00	256,000
				7,120,000

10. Plumbing Systems

Sanitary fixtures and connection piping				
Toilets	736	EA	1,600.00	1,177,600
Lavatories	736	EA	1,200.00	883,200
Tub/shower combo	580	EA	1,800.00	1,044,000
Showers	232	EA	350.00	81,200
Kitchen sinks	310	EA	1,700.00	527,000
Washing machine connection	310	EA	350.00	108,500
Hose bibbs	10	EA	500.00	5,000

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
Domestic water and distribution				
Cold Water Service				
Copper piping incl. fittings >2"	900	LF	50.00	45,000
Copper piping incl. fittings to 2"	58,280	LF	32.00	1,864,960
Hot Water Service				
Copper piping incl. fittings >2"	1,400	LF	50.00	70,000
Copper piping incl. fittings to 2"	65,040	LF	32.00	2,081,280
Insulation	66,440	LF	9.00	597,960
Valves				
Isolation valves to 3/4"	4,772	EA	65.00	310,180
Domestic Water Supply Equipment				
Hot water heating and circulation	310	EA	900.00	279,000
Sanitary waste				
Waste & vent pipework-above ground				
Cast Iron No Hub, >6"	900	LF	75.00	67,500
Cast Iron No Hub, to 3"	58,280	LF	32.00	1,864,960
Sanitary waste, vent and service piping				
Floor Drains	88	EA	1,000.00	88,000
Rain Water Drainage				
Pipe and Fittings	51,583	LF	35.00	1,805,422
Roof/Overflow Drains	86	EA	750.00	64,695
Gas distribution				
Copper piping incl. fittings to 2"	2,000	LF	25.00	50,000
				13,015,457

11. Heating, Ventilation & Air Conditioning

Heat generating systems				
Heating hot water boilers, high efficiency condensing: Core Area only	3,700	MBTH	25.00	92,500
Heating hot water pumps	2	EA	15,000.00	30,000
Cooling Generating Systems: Core Area only				
Cooling towers	500	TN	250.00	125,000
Chillers, 2 each	500	TN	450.00	225,000
Chilled water pumps	2	EA	10,000.00	20,000
Condenser water pumps	2	EA	5,000.00	10,000
Variable speed drives, vibration isolation, etc.	6	EA	12,000.00	72,000

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
Distribution systems: Core Area only				
Piping, fittings, valves and insulation				
Chilled water				
Chilled water pipework, fittings	1,400	LF	95.00	133,000
Valves and specialties	1	LS	75,000.00	75,000
Heating hot water				
Heating hot water pipework, fittings, including insulation				
6" - 4"	1,200	LF	85.00	102,000
< = 3"	4,000	LF	30.00	120,000
Valves and specialties	1	LS	25,000.00	25,000
Condenser water				
Condenser water pipework, fittings	1,200	LF	90.00	108,000
Valves and specialties	1	LS	25,000.00	25,000
Connections to Fan Coil Boxes	164	EA	350.00	57,236
Air handling equipment				
Dedicated outside air supply air handler	220,000	CFM	5.00	1,100,000
Individual unit packaged units	310	EA	6,000.00	1,860,000
Fan Coil Units				
Core/Shell	164	EA	1,250.00	204,415
Parking area	207	EA	1,250.00	258,750
Sound attenuation - duct mounted	220,000	CFM	0.25	55,000
Air distribution, return and exhaust				
Galvanized sheet metal ductwork	288,790	LB	8.00	2,310,320
Dryer exhaust duct	9,300	LF	6.00	55,800
Flexible ductwork	3,000	LF	6.00	18,000
Dampers, volume	100	EA	40.00	4,000
Dampers, smoke/fire	80	EA	1,200.00	96,000
Insulation/duct liner	100,000	SF	2.50	250,000
Diffusers, registers and grilles				
Ceiling				
Core/Shell	818	EA	200.00	163,532
Tenant areas, 1 per 150 USF	2,633	EA	150.00	394,950
Parking area				
Terminal & Package Units				
Exhaust fans at toilet rooms	736	EA	350.00	257,600
Controls and instrumentation				
DDC Control system	288,790	SF	3.00	866,370

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
Test and balance				
Test and balance	288,790	SF	1.25	360,988
				9,475,461

12. Electrical Lighting, Power & Communication

Primary Service, Medium voltage				
Switchgear 13.8KV including (2) tie breakers, (2) feeder breakers, and customer metering	6,000	KVA	60.00	360,000
Transformer substation 13.8KV/110-208V, double-ended including secondary distribution	6,000	KVA	150.00	900,000
Distribution switchboards - 110-208V	18,600	AMP	25.00	465,000
Distribution panelboards - 208V	310	EA	1,500.00	465,000
Feeder conduit and wire - 600V	45,000	LF	80.00	3,600,000
Emergency and Uninterrupted Power				
Emergency Generator	1,500	KVA	350.00	525,000
Automatic transfer switch	1,500	AMP	45.00	67,500
Distribution panelboards	1,500	AMP	25.00	37,500
General Purpose Lighting				
Panelboards	46	EA	2,500.00	115,000
Lighting				
Core Area	81,766	SF	12.00	981,192
Tenant Area	394,950	SF	2.00	789,900
Parking area	207,024	SF	4.00	828,096
Machine and Equipment Power				
Connections and switches including conduit and wire				
Elevators	16	EA	1,000.00	16,000
Cooling towers	2	EA	5,000.00	10,000
Chillers	2	EA	12,000.00	24,000
Pumps	6	EA	2,000.00	12,000
Miscellaneous connections	683,748	SF	0.75	512,811
User Convenience Power				
Panelboards	46	EA	2,500.00	115,000
Receptacles				
Core/Shell	81,766	SF	3.00	245,298
Tenant Area	394,950	SF	3.00	1,184,850
Parking area	207,024	SF	2.00	414,048

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
Communications				
Telephone and communications				
Core Area, panels and backbone only	1	LS	75,000.00	75,000
Tenant Units	310	EA	800.00	248,000
Security Systems				
Main Security System	683,748	SF	0.10	68,375
Tenant Units	310	EA	900.00	279,000
Fire Alarm Systems				
Main Fire Alarm Systems	683,748	SF	3.00	2,051,244
Other Electrical Systems				
Grounding Systems	683,748	SF	0.25	170,937
Lightning protection	1	LS	25,000.00	25,000
				14,585,751
13. Fire Protection Systems				
Sprinkler and Standpipe Systems				
Fire Protection Sprinkler Systems	683,748	SF	4.00	2,734,992
Standpipe and Hose Systems	683,748	SF	1.00	683,748
Specialties and Other Systems				
Smoke Evacuation	1	LS	250,000.00	250,000
				3,668,740
14. Site Preparation & Building Demolition				
Site Preparation	100,000	SF	15.00	1,500,000
				1,500,000
15. Site Paving, Structures & Landscaping				
Site Development	48,244	SF	25.00	1,206,100
				1,206,100

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
16. Utilities on Site				
Site Utilities	1	LS	500,000.00	500,000
				500,000

PERFORMANCE BASED COMPONENT SUMMARY

Gross Area: 683,748 SF

		$/SF	$x1,000
1. Foundations		16.35	11,178
2. Vertical Structure		22.08	15,097
3. Floor & Roof Structures		83.76	57,271
4. Exterior Cladding		36.15	24,720
5. Roofing, Waterproofing & Skylights		3.98	2,721
Shell (1-5)		162.32	110,987
6. Interior Partitions, Doors & Glazing		24.75	16,922
7. Floor, Wall & Ceiling Finishes		21.23	14,515
Interiors (6-7)		45.98	31,437
8. Function Equipment & Specialties		5.73	3,919
9. Stairs & Vertical Transportation		10.41	7,120
Equipment & Vertical Transportation (8-9)		16.15	11,039
10. Plumbing Systems		19.04	13,015
11. Heating, Ventilating & Air Conditioning		13.86	9,475
12. Electric Lighting, Power & Communications		21.33	14,586
13. Fire Protection Systems		5.37	3,669
Mechanical & Electrical (10-13)		59.59	40,745
Total Building Construction (1-13)		**284.04**	**194,209**
14. Site Preparation & Demolition		2.19	1,500
15. Site Paving, Structures & Landscaping		1.76	1,206
16. Utilities on Site		0.73	500
Total Site Construction (14-16)		**4.69**	**3,206**
TOTAL BUILDING & SITE (1-16)		**288.73**	**197,415**
General Conditions	12.00%	34.65	23,690
Contractor's Overhead & Profit or Fee	6.00%	19.40	13,266
PLANNED CONSTRUCTION COST	***March 2010***	**342.77**	**234,371**
Design, Management and Inspection	20.00%	68.55	46,874
Escalation is excluded	0.00%	0.00	0
RECOMMENDED BUDGET	***March 2010***	**411.33**	**281,245**

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
1. Foundations				
Basement Excavation				
Excavation	99,173	CY	15.00	1,487,595
Shoring at perimeter	36,400	SF	50.00	1,820,000
Backfill with imported material	14,829	CY	35.00	519,015
Dispose off site	99,173	CY	20.00	1,983,460
Hazardous material remediation				Excluded
Foundations				
Reinforced concrete Mat foundation				
Excavation and disposal	10,278	CY	15.00	154,170
Forwork	5,240	SF	18.00	94,320
Reinforcing steel	1,469,135	LBS	1.15	1,689,505
Concrete, f'c= 6ksi	10,278	CY	325.00	3,340,350
Elevator pits	6	EA	15,000.00	90,000
				11,178,415
2. Vertical Structure				
Columns and pilasters				
Concrete columns - moment frames				
Formwork	100,247	SF	25.00	2,506,175
Reinforcing steel	1,315,178	LBS	1.25	1,643,973
Concrete				
f'c= 10ksi	371	CY	450.00	166,950
f'c= 8ksi	890	CY	350.00	311,500
f'c= 6ksi	318	CY	325.00	103,350
f'c= 5ksi	1,535	CY	225.00	345,375
Concrete columns - standard				
Forwork	36,277	SF	25.00	906,925
Reinforcing steel	343,701	LBS	1.25	429,626
Concrete, f'c= 8ksi	658	CY	350.00	230,300
Concrete retaining walls				
Concrete retaining wall				
Formwork to one side	38,220	SF	25.00	955,500
Reinforcing steel	252,252	LBS	1.25	315,315
Concrete, f'c= 5ksi	2,076	CY	225.00	467,100

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
Concrete core walls				
Formwork to both sides	170,841	SF	25.00	4,271,025
Reinforcing steel	447,823	LBS	1.25	559,779
Concrete				
f'c= 8ksi	3,496	CY	350.00	1,223,600
f'c= 6ksi	1,125	CY	325.00	365,625
f'c= 5ksi	1,310	CY	225.00	294,750
				15,096,868

3. Floor and Roof Structure

Floor at lowest level				
Slab on grade - See foundations (mat slab)				
Suspended floors				
10" thick reinforced concrete flat slab - basement slabs				
Formwork	155,268	SF	10.00	1,552,680
Reinforcing steel	768,577	LBS	1.25	960,721
Concrete, f'c= 5.5ksi	142,329	CY	225.00	32,024,025
8" thick post tensioned slabs				
Formwork	463,874	SF	10.00	4,638,740
Reinforcing steel	1,122,575	LBS	1.25	1,403,219
Post tension tendons	459,236	LBS	2.00	918,472
Studrails at columns (9 studrais with 9 studs per rail)	1,476	LOC	4,000.00	5,904,000
Concrete, f'c= 5.5ksi	12,599	CY	225.00	2,834,775
Special moment resisting frame reinforced concrete beam				
Formwork	137,632	SF	15.00	2,064,480
Reinforcing steel	1,420,802	LBS	1.25	1,776,003
Concrete, f'c= 5ksi	4,948	CY	225.00	1,113,300
Ground level slab/roof				
12" thick reinforced concrete flat slab - ground level				
Formwork	51,756	SF	10.00	517,560
Reinforcing steel	455,453	LBS	1.25	569,316
Concrete, f'c= 5.5ksi	2,109	CY	225.00	474,525
Special moment resisting frame reinforced concrete beam				
Formwork	3,128	SF	10.00	31,280
Reinforcing steel	30,635	LBS	1.25	38,294
Concrete, f'c= 5ksi	112	CY	225.00	25,200

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
High roof				
10" thick reinforced concrete flat slab				
Formwork	12,850	SF	10.00	128,500
Reinforcing steel	70,675	LBS	1.25	88,344
Concrete, f'c= 5.5ksi	437	CY	225.00	98,325
Special moment resisting frame reinforced concrete beam				
Formwork	3,128	SF	15.00	46,920
Reinforcing steel	29,994	LBS	1.25	37,493
Concrete, f'c= 5ksi	112	CY	225.00	25,200
				57,271,371

4. Exterior Cladding

Wall framing, furring and insulation				
Exterior wall framing	182,947	SF	8.00	1,463,576
Furring to interior face of retaining wall	38,220	SF	4.00	152,880
Insulation and vapor barrier	173,820	SF	1.50	260,730
Applied exterior finishes				
Exterior wall finish - curtain wall with spandrel panels	135,600	SF	120.00	16,272,000
Parapets & edge detailing	560	LF	250.00	140,000
Interior finish to exterior walls				
Gypsum board, taped and sanded	173,820	SF	3.50	608,370
Windows, glazing and louvers				
Exterior wall finish - curtain wall with glazing	44,400	SF	120.00	5,328,000
Exterior doors, frames and hardware				
Glazed Doors & Entrances (allow revolving)	12	EA	35,000.00	420,000
Solid Exterior Doors	8	EA	3,000.00	24,000
Overhead Doors	2	EA	25,000.00	50,000
				24,719,556

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
5. Roofing, Waterproofing & Skylights				
Waterproofing				
Waterproofing at slab on grade	51,756	SF	10.00	517,560
Waterproofing at retaining wall	38,220	SF	10.00	382,200
Waterproofing membrane under plaza	40,442	SF	15.00	606,630
Insulation				
Rigid insulation at roof	11,314	SF	6.00	67,884
Roofing				
Balconies & accessible roofs	40,442	SF	25.00	1,011,050
High roof	11,314	SF	12.00	135,768
				2,721,092
6. Interior Partitions, Doors & Glazing				
Partition framing and cores				
CMU partitions at basement levels	1,656	LF	325.00	538,200
Core partitions	11,880	LF	90.00	1,069,200
Standard partitions	118,798	LF	72.00	8,553,456
Doors, frames & hardware				
Unit entrance doors	310	EA	2,250.00	697,500
Standard interior doors	2,680	EA	1,800.00	4,824,000
Closet doors at units - allow bi-fold	1,240	EA	1,000.00	1,240,000
				16,922,356
7. Floor, Wall & Ceiling Finishes				
Floors including base				
Lobby flooring	5,000	SF	35.00	175,000
Core circulation - allow carpet	70,530	SF	6.00	423,180
Residential				
Livingrooms - allow wood	141,050	SF	22.00	3,103,100
Bedrooms - allow carpet	164,565	SF	6.00	987,390
Kitchen - allow stone tile	42,315	SF	25.00	1,057,875
Bathrooms - allow ceramic tile	47,020	SF	20.00	940,400
Special use areas	6,236	SF	10.00	62,360
Concrete sealer at basement	207,024	SF	2.00	414,048

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
Walls				
Lobby	1	EA	75,000.00	75,000
Core circulation	141,060	SF	3.00	423,180
Residential				
Livingrooms	282,100	SF	2.00	564,200
Bedrooms	329,130	SF	1.00	329,130
Kitchen	84,630	SF	10.00	846,300
Bathrooms	94,040	SF	12.00	1,128,480
Special use areas	9,354	SF	12.00	112,248
Paint to concrete and CMU at basement	55,608	SF	1.00	55,608
Ceilings				
Lobby	5,000	SF	25.00	125,000
Core circulation	70,530	SF	12.00	846,360
Residential				
Livingrooms	141,050	SF	6.00	846,300
Bedrooms	164,565	SF	6.00	987,390
Kitchen	42,315	SF	6.00	253,890
Bathrooms	47,020	SF	6.00	282,120
Special use areas	6,236	SF	10.00	62,360
Paint to exposed structure at basement	207,024	SF	2.00	414,048
				14,514,967

8. Function Equipment & Specialties

Specialties				
Fire extinguisher cabinets	150	EA	450.00	67,500
Trash chute	1	EA	110,000.00	110,000
Parking Garage equipment	1	LS	25,000.00	25,000
Built in Equipment				
Lobby/entry	1	LS	25,000.00	25,000
Core area	70,530	SF	0.75	52,898
Residential				
Livingrooms	141,050	SF	0.05	7,053
Bedrooms	164,565	SF	0.10	16,457
Kitchens	42,315	EA	6.00	253,890
Bathrooms	47,020	SF	1.00	47,020
Special use areas	6,236	SF	2.00	12,472

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
Residential appliances				
Kitchen appliances				
Refrigerator	310	EA	1,700.00	527,000
Range	310	EA	2,000.00	620,000
Range hood	310	EA	1,000.00	310,000
Double oven	310	EA	800.00	248,000
Dishwasher	310	EA	850.00	263,500
Microwave	310	EA	450.00	139,500
Washing machine	310	EA	1,200.00	372,000
Dryer - electric	310	EA	1,200.00	372,000
Window washing equipment	1	LS	450,000.00	450,000
				3,919,289

9. Stairs & Vertical Transportation

Stairs				
Regular stair flights	88	EA	22,000.00	1,936,000
Elevators				
Passenger Elevators, gearless traction	176	STOP	28,000.00	4,928,000
Freight Elevators, geared traction, 4 stop	8	STOP	32,000.00	256,000
				7,120,000

10. Plumbing Systems

Sanitary fixtures and connection piping				
Toilets	736	EA	1,600.00	1,177,600
Lavatories	736	EA	1,200.00	883,200
Tub/shower combo	580	EA	1,800.00	1,044,000
Showers	232	EA	350.00	81,200
Kitchen sinks	310	EA	1,700.00	527,000
Washing machine connection	310	EA	350.00	108,500
Hose bibbs	10	EA	500.00	5,000

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
Domestic water and distribution				
Cold Water Service				
Copper piping incl. fittings >2"	900	LF	50.00	45,000
Copper piping incl. fittings to 2"	58,280	LF	32.00	1,864,960
Hot Water Service				
Copper piping incl. fittings >2"	1,400	LF	50.00	70,000
Copper piping incl. fittings to 2"	65,040	LF	32.00	2,081,280
Insulation	66,440	LF	9.00	597,960
Valves				
Isolation valves to 3/4"	4,772	EA	65.00	310,180
Domestic Water Supply Equipment				
Hot water heating and circulation	310	EA	900.00	279,000
Sanitary waste				
Waste & vent pipework-above ground				
Cast Iron No Hub, >6"	900	LF	75.00	67,500
Cast Iron No Hub, to 3"	58,280	LF	32.00	1,864,960
Sanitary waste, vent and service piping				
Floor Drains	88	EA	1,000.00	88,000
Rain Water Drainage				
Pipe and Fittings	51,583	LF	35.00	1,805,422
Roof/Overflow Drains	86	EA	750.00	64,695
Gas distribution				
Copper piping incl. fittings to 2"	2,000	LF	25.00	50,000
				13,015,457

11. Heating, Ventilation & Air Conditioning

Heat generating systems				
Heating hot water boilers, high efficiency condensing: Core Area only	3,700	MBTH	25.00	92,500
Heating hot water pumps	2	EA	15,000.00	30,000
Cooling Generating Systems: Core Area only				
Cooling towers	500	TN	250.00	125,000
Chillers, 2 each	500	TN	450.00	225,000
Chilled water pumps	2	EA	10,000.00	20,000
Condenser water pumps	2	EA	5,000.00	10,000
Variable speed drives, vibration isolation, etc.	6	EA	12,000.00	72,000

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
Distribution systems: Core Area only				
Piping, fittings, valves and insulation				
Chilled water				
Chilled water pipework, fittings	1,400	LF	95.00	133,000
Valves and specialties	1	LS	75,000.00	75,000
Heating hot water				
Heating hot water pipework, fittings, including insulation				
6" - 4"	1,200	LF	85.00	102,000
< = 3"	4,000	LF	30.00	120,000
Valves and specialties	1	LS	25,000.00	25,000
Condenser water				
Condenser water pipework, fittings	1,200	LF	90.00	108,000
Valves and specialties	1	LS	25,000.00	25,000
Connections to Fan Coil Boxes	164	EA	350.00	57,236
Air handling equipment				
Dedicated outside air supply air handler	220,000	CFM	5.00	1,100,000
Individual unit packaged units	310	EA	6,000.00	1,860,000
Fan Coil Units				
Core/Shell	164	EA	1,250.00	204,415
Parking area	207	EA	1,250.00	258,750
Sound attenuation - duct mounted	220,000	CFM	0.25	55,000
Air distribution, return and exhaust				
Galvanized sheet metal ductwork	288,790	LB	8.00	2,310,320
Dryer exhaust duct	9,300	LF	6.00	55,800
Flexible ductwork	3,000	LF	6.00	18,000
Dampers, volume	100	EA	40.00	4,000
Dampers, smoke/fire	80	EA	1,200.00	96,000
Insulation/duct liner	100,000	SF	2.50	250,000
Diffusers, registers and grilles				
Ceiling				
Core/Shell	818	EA	200.00	163,532
Tenant areas, 1 per 150 USF	2,633	EA	150.00	394,950
Parking area				
Terminal & Package Units				
Exhaust fans at toilet rooms	736	EA	350.00	257,600
Controls and instrumentation				
DDC Control system	288,790	SF	3.00	866,370

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
Test and balance				
Test and balance	288,790	SF	1.25	360,988
				9,475,461

12. Electrical Lighting, Power & Communication

Primary Service, Medium voltage				
Switchgear 13.8KV including (2) tie breakers, (2) feeder breakers, and customer metering	6,000	KVA	60.00	360,000
Transformer substation 13.8KV/110-208V, double-ended including secondary distribution	6,000	KVA	150.00	900,000
Distribution switchboards - 110-208V	18,600	AMP	25.00	465,000
Distribution panelboards - 208V	310	EA	1,500.00	465,000
Feeder conduit and wire - 600V	45,000	LF	80.00	3,600,000
Emergency and Uninterrupted Power				
Emergency Generator	1,500	KVA	350.00	525,000
Automatic transfer switch	1,500	AMP	45.00	67,500
Distribution panelboards	1,500	AMP	25.00	37,500
General Purpose Lighting				
Panelboards	46	EA	2,500.00	115,000
Lighting				
Core Area	81,766	SF	12.00	981,192
Tenant Area	394,950	SF	2.00	789,900
Parking area	207,024	SF	4.00	828,096
Machine and Equipment Power				
Connections and switches including conduit and wire				
Elevators	16	EA	1,000.00	16,000
Cooling towers	2	EA	5,000.00	10,000
Chillers	2	EA	12,000.00	24,000
Pumps	6	EA	2,000.00	12,000
Miscellaneous connections	683,748	SF	0.75	512,811
User Convenience Power				
Panelboards	46	EA	2,500.00	115,000
Receptacles				
Core/Shell	81,766	SF	3.00	245,298
Tenant Area	394,950	SF	3.00	1,184,850
Parking area	207,024	SF	2.00	414,048

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
Communications				
Telephone and communications				
Core Area, panels and backbone only	1	LS	75,000.00	75,000
Tenant Units	310	EA	800.00	248,000
Security Systems				
Main Security System	683,748	SF	0.10	68,375
Tenant Units	310	EA	900.00	279,000
Fire Alarm Systems				
Main Fire Alarm Systems	683,748	SF	3.00	2,051,244
Other Electrical Systems				
Grounding Systems	683,748	SF	0.25	170,937
Lightning protection	1	LS	25,000.00	25,000
				14,585,751
13. Fire Protection Systems				
Sprinkler and Standpipe Systems				
Fire Protection Sprinkler Systems	683,748	SF	4.00	2,734,992
Standpipe and Hose Systems	683,748	SF	1.00	683,748
Specialties and Other Systems				
Smoke Evacuation	1	LS	250,000.00	250,000
				3,668,740
14. Site Preparation & Building Demolition				
Site Preparation	100,000	SF	15.00	1,500,000
				1,500,000
15. Site Paving, Structures & Landscaping				
Site Development	48,244	SF	25.00	1,206,100
				1,206,100

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
16. Utilities on Site				
Site Utilities	1	LS	500,000.00	500,000
				500,000

Davis Langdon

PROGRAM
COST MODEL

for

PEER Tall Buildings Study
Steel Structural Option
Los Angeles, California

March 8, 2010

CONTENTS

	Page Nos.
Overall Summary	1
Areas and Control Quantities	2
Code Based Component Summary	3
Performance Based Component Summary	13
Performance Based Plus Component Summary	23

OVERALL SUMMARY

	Gross Floor Area	$ / SF	$x1,000
Construction Cost (Including Design)			
Code Based	959,110 SF	369.76	354,636
Performance Based	959,110 SF	354.02	339,546
Performance Based Plus	959,110 SF	359.97	345,251
FF&E Cost			
Furniture & Fittings, including system furniture	763,350 SF	50.00	38,168
Equipment, including computer systems	763,350 SF	35.00	26,717
Personal Property			
Personal Contents	763,350 SF	2.00	1,527
Cars in parking (Maximum count)	490 EA	25,000.00	12,250

Please refer to the Inclusions and Exclusions sections of this report

AREAS & CONTROL QUANTITIES

Areas

	SF	SF	SF
Enclosed Areas			
Basement Levels B1 - B4	199,760		
Ground Level	49,940		
Levels 1 - 10	181,900		
Levels 11 - 39	527,510		
SUBTOTAL, Enclosed Area		959,110	
Covered area			
SUBTOTAL, Covered Area @ ½ Value			
TOTAL GROSS FLOOR AREA			959,110

Control Quantities

				Ratio to Gross Area
Number of stories (x1,000)		44	EA	0.046
Gross Area		959,110	SF	1.000
Enclosed Area		959,110	SF	1.000
Covered Area		0	SF	0.000
Footprint Area		49,940	SF	0.052
Volume		12,301,575	CF	12.826
Basement Volume		2,397,120	CF	2.499
Gross Wall Area		344,565	SF	0.359
Retaining Wall Area		42,912	SF	0.045
Finished Wall Area		301,653	SF	0.315
Windows or Glazing Area	21.89%	75,414	SF	0.079
Roof Area - Flat		49,940	SF	0.052
Roof Area - Sloping		0	SF	0.000
Roof Area - Total		49,940	SF	0.052
Roof Glazing Area		0	SF	0.000
Interior Partition Length		58,608	LF	0.061
Finished Area		959,110	SF	1.000
Elevators (x10,000)		6	EA	0.063
Plumbing Fixtures (x1,000)		924	EA	0.963
Electrical Load		12,000	KW	12.512

CODE BASED COMPONENT SUMMARY

Gross Area: 959,110 SF

		$/SF	$x1,000
1. Foundations		19.53	18,730
2. Vertical Structure		57.00	54,668
3. Floor & Roof Structures		26.34	25,262
4. Exterior Cladding		42.43	40,697
5. Roofing, Waterproofing & Skylights		2.63	2,526
Shell (1-5)		147.93	141,884
6. Interior Partitions, Doors & Glazing		10.18	9,760
7. Floor, Wall & Ceiling Finishes		13.93	13,358
Interiors (6-7)		24.10	23,119
8. Function Equipment & Specialties		9.87	9,471
9. Stairs & Vertical Transportation		9.99	9,584
Equipment & Vertical Transportation (8-9)		19.87	19,055
10 Plumbing Systems		6.12	5,872
11 Heating, Ventilating & Air Conditioning		29.23	28,033
12 Electric Lighting, Power & Communications		23.64	22,670
13 Fire Protection Systems		5.26	5,046
Mechanical & Electrical (10-13)		64.25	61,621
Total Building Construction (1-13)		**256.15**	**245,679**
14 Site Preparation & Demolition		1.56	1,500
15 Site Paving, Structures & Landscaping		1.30	1,252
16 Utilities on Site		0.52	500
Total Site Construction (14-16)		**3.39**	**3,252**
TOTAL BUILDING & SITE (1-16)		**259.54**	**248,930**
General Conditions	12.00%	31.15	29,872
Contractor's Overhead & Profit or Fee	6.00%	17.44	16,728
PLANNED CONSTRUCTION COST	***March 2010***	**308.13**	**295,530**
Design, Management and Inspection	20.00%	61.63	59,106
Escalation is excluded	0.00%	0.00	0
RECOMMENDED BUDGET	***March 2010***	**369.76**	**354,636**

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
1. Foundations				
Mass excavation				
Excavate for basement and mat foundation	140,778	CY	15.00	2,111,670
Shoring at perimeter	53,640	SF	50.00	2,682,000
Backfill with imported material	29,802	CY	35.00	1,043,070
Dispose off site	140,778	CY	20.00	2,815,560
Hazardous material remediation				Excluded
Foundations				
Reinforced concrete mat foundation, 12'-0"	49,940	SF	200.00	9,988,000
Elevator pits	6	EA	15,000.00	90,000
				18,730,300
2. Vertical Structure				
Columns and pilasters				
Wide flange	880	TN	4,000.00	3,520,000
Box columns				
Metal plate frame	5,436	TN	6,000.00	32,616,000
Studs- 3/4" diameter, 6" long	101,088	EA	60.00	6,065,280
Concrete fill	3,101	CY	450.00	1,395,450
Sprayed fireproofing	880	TN	350.00	308,000
Diagonal reinforcing				
Buckling restraint braces				
1026 k	1,368	LF	300.00	410,400
950 k	1,260	LF	225.00	283,500
703 k	902	LF	180.00	162,360
589 k	7,326	LF	150.00	1,098,900
532 k	912	LF	150.00	136,800
513 k	6,516	LF	150.00	977,400
418 k	608	LF	120.00	72,960
380 k	960	LF	120.00	115,200
342 k	836	LF	120.00	100,320
304 k	720	LF	120.00	86,400
266 k	1,252	LF	100.00	125,200
228 k	380	LF	100.00	38,000
Brace connections				
Gusset plates				
3/4" thick plate steel welded connection	168	EA	1,500.00	252,000
1" thick plate steel welded connection	1,916	EA	2,000.00	3,832,000
2" thick plate steel welded connection	232	EA	4,000.00	928,000

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
Concrete retaining walls				
18" Concrete retaining wall				
Formwork to one side	21,456	SF	15.00	321,840
Reinforcing steel	283,824	LBS	1.15	326,398
Concrete	1,311	CY	225.00	294,975
24" Concrete retaining wall				
Formwork to one side	21,456	SF	15.00	321,840
Reinforcing steel	422,059	LBS	1.15	485,368
Concrete	1,748	CY	225.00	393,300
				54,667,890

3. Floor and Roof Structure

Floor at lowest level				
Slab on grade - See foundations (mat slab)				
Suspended floors				
Wide flange framing	3,359	TN	4,000.00	13,436,000
Channel and angle ledger	101,965	LBS	2.50	254,913
3" formlock deck, 18 ga.	859,230	SF	4.50	3,866,535
3 1/4" lightweight concrete	859,230	SF	5.00	4,296,150
Sprayed fireproofing	3,359	TN	350.00	1,175,650
Plaza level slab/roof				
Wide flange framing	295	TN	4,000.00	1,180,000
Channel and angle ledger	33,988	LBS	2.50	84,970
3" formlock deck, 16 ga.	49,940	SF	4.50	224,730
9" normal weight concrete	49,940	SF	5.00	249,700
Sprayed fireproofing	295	TN	350.00	103,250
High roof				
Wide flange framing	50	TN	4,000.00	200,000
3" formlock deck, 18 ga.	18,190	SF	4.50	81,855
3 1/4" lightweight concrete	18,190	SF	5.00	90,950
Sprayed fireproofing	50	TN	350.00	17,500
				25,262,203

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
4. Exterior Cladding				
Wall framing, furring and insulation				
Exterior wall framing	301,653	SF	8.00	2,413,224
Furring to interior face of retaining wall	42,912	SF	4.00	171,648
Insulation and vapor barrier	226,240	SF	1.50	339,360
Applied exterior finishes				
Exterior wall finish - curtain wall with spandrel panels	226,240	SF	120.00	27,148,800
Parapets & edge detailing	554	LF	250.00	138,500
Interior finish to exterior walls				
Gypsum board, taped and sanded	269,152	SF	3.50	942,032
Windows, glazing and louvers				
Exterior wall finish - curtain wall with glazing	75,414	SF	120.00	9,049,680
Exterior doors, frames and hardware				
Glazed Doors & Entrances (allow revolving)	12	EA	35,000.00	420,000
Solid Exterior Doors	8	EA	3,000.00	24,000
Overhead Doors	2	EA	25,000.00	50,000
				40,697,244
5. Roofing, Waterproofing & Skylights				
Waterproofing				
Waterproofing at slab on grade	49,940	SF	10.00	499,400
Waterproofing at retaining wall	42,912	SF	10.00	429,120
Waterproofing membrane under plaza	31,750	SF	15.00	476,250
Roof insulation				
Rigid insulation at roof	18,190	SF	6.00	109,140
Roofing				
Balconies & accessible roofs	31,750	SF	25.00	793,750
High roof	18,190	SF	12.00	218,280
				2,525,940

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
6. Interior Partitions, Doors & Glazing				
Partition framing and cores				
CMU partitions at basement levels	400	LF	325.00	130,000
Core partitions	7,276	LF	90.00	654,840
Standard partitions	50,932	LF	72.00	3,667,104
Window walls and borrowed lights	1,020	SF	45.00	45,900
Doors, frames & hardware				
Interior doors	2,392	EA	2,200.00	5,262,400
				9,760,244
7. Floor, Wall & Ceiling Finishes				
Floors including base				
Lobby flooring	5,000	SF	35.00	175,000
Core circulation	88,000	SF	6.00	528,000
Restrooms	44,000	SF	15.00	660,000
Office	616,350	SF	5.00	3,081,750
Special use areas	10,000	SF	10.00	100,000
Concrete sealer at basement	195,760	SF	2.00	391,520
Walls				
Lobby	1	EA	75,000.00	75,000
Core circulation	176,000	SF	3.00	528,000
Restroom walls	79,200	SF	15.00	1,188,000
Office	739,620	SF	1.50	1,109,430
Special use areas	15,000	SF	5.00	75,000
Paint to concrete and CMU at basement	52,512	SF	1.00	52,512
Ceilings				
Lobby	5,000	SF	25.00	125,000
Core circulation	88,000	SF	12.00	1,056,000
Restrooms	44,000	SF	15.00	660,000
Office	616,350	SF	5.00	3,081,750
Special use areas	10,000	SF	8.00	80,000
Paint to exposed structure at basement	195,760	SF	2.00	391,520
				13,358,482

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
8. Function Equipment & Specialties				
Built in Equipment				
Lobby/entry	1	LS	25,000.00	25,000
Core area	40	EA	18,000.00	720,000
Office areas	616,350	SF	12.00	7,396,200
Restroom areas	44,000	SF	20.00	880,000
Window washing equipment	1	LS	450,000.00	450,000
				9,471,200
9. Stairs & Vertical Transportation				
Stairs				
Regular stair flights	88	EA	22,000.00	1,936,000
Elevators				
Passenger Elevators, gearless traction	264	STOP	28,000.00	7,392,000
Freight Elevators, geared traction, 4 stop	8	STOP	32,000.00	256,000
				9,584,000
10. Plumbing Systems				
Sanitary fixtures and connection piping				
Toilets	440	EA	1,600.00	704,000
Urinals	88	EA	1,800.00	158,400
Lavatories	264	EA	1,200.00	316,800
Drinking Fountains and Coolers	44	EA	2,500.00	110,000
Sinks	44	EA	1,700.00	74,800
Hose bibbs	44	EA	500.00	22,000
Domestic water and distribution				
Cold Water Service				
Copper piping incl. fittings >2"	1,300	LF	50.00	65,000
Copper piping incl. fittings to 2"	13,860	LF	32.00	443,520
Hot Water Service				
Copper piping incl. fittings >2"	2,600	LF	50.00	130,000
Copper piping incl. fittings to 2"	27,720	LF	32.00	887,040
Insulation	30,320	LF	9.00	272,880
Valves				
Isolation valves to 3/4"	1,232	EA	65.00	80,080
Domestic Water Supply Equipment				
Hot water heating and circulation	1	LS	200,000.00	200,000

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
Sanitary waste				
Waste & vent pipework-above ground				
Cast Iron No Hub, >6"	1,300	LF	75.00	97,500
Cast Iron No Hub, to 3"	13,860	LF	32.00	443,520
Sanitary waste, vent and service piping				
Floor Drains	88	EA	1,000.00	88,000
Rain Water Drainage				
Pipe and Fittings	47,609	LF	35.00	1,666,331
Roof/Overflow Drains	83	EA	750.00	62,425
Gas distribution				
Copper piping incl. fittings to 2"	2,000	LF	25.00	50,000
				5,872,296

11. Heating, Ventilation & Air Conditioning

Heat generating systems				
Heating hot water boilers, high efficiency condensing	43,200	MBTH	25.00	1,080,000
Heating hot water pumps	2	EA	35,000.00	70,000
Cooling Generating Systems				
Cooling towers	3,000	TN	350.00	1,050,000
Chillers, 2 each	3,000	TN	550.00	1,650,000
Chilled water pumps	2	EA	30,000.00	60,000
Condenser water pumps	2	EA	28,000.00	56,000
Variable speed drives, vibration isolation, etc.	6	EA	12,000.00	72,000
Distribution systems				
Piping, fittings, valves and insulation				
Chilled water				
Chilled water pipework, fittings	1,400	LF	95.00	133,000
Valves and specialties	1	LS	75,000.00	75,000
Heating hot water				
Heating hot water pipework, fittings, including insulation				
6" - 4"	1,200	LF	85.00	102,000
< = 3"	36,000	LF	30.00	1,080,000
Valves and specialties	1	LS	150,000.00	150,000

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
Condenser water				
Condenser water pipework, fittings	1,200	LF	90.00	108,000
Valves and specialties	1	LS	25,000.00	25,000
Connections to VAV boxes	1,517	EA	350.00	531,038
Air handling equipment				
Air handler units	700,000	CFM	5.00	3,500,000
VAV boxes				
Core/Shell	294	EA	1,250.00	367,500
Tenant areas, 1 per 600 USF	1,027	EA	1,250.00	1,284,063
Parking area	196	EA	1,250.00	245,000
Sound attenuation - duct mounted	700,000	CFM	0.25	175,000
Air distribution, return and exhaust				
Galvanized sheet metal ductwork	959,110	LB	8.00	7,672,880
Flexible ductwork	36,000	LF	6.00	216,000
Dampers, volume	750	EA	40.00	30,000
Dampers, smoke/fire	80	EA	1,200.00	96,000
Insulation/duct liner	400,000	SF	2.50	1,000,000
Diffusers, registers and grilles				
Ceiling				
Core/Shell	1,470	EA	200.00	294,000
Tenant areas, 1 per 150 USF	4,109	EA	150.00	616,350
Parking area				
Terminal & Package Units				
Exhaust fans to toilet rooms etc.	1	LS	300,000.00	300,000
Controls and instrumentation				
DDC Control system	959,110	SF	5.00	4,795,550
Test and balance				
Test and balance	959,110	SF	1.25	1,198,888
				28,033,268

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
12. Electrical Lighting, Power & Communication				
Primary Service, Medium voltage				
Switchgear 13.8KV including (2) tie breakers, (2) feeder breakers, and customer	12,000	KVA	60.00	720,000
Transformer substation 13.8KV/480V, double-ended including secondary	12,000	KVA	150.00	1,800,000
Distribution switchboards - 480V	12,500	AMP	40.00	500,000
Distribution panelboards - 480V	4,000	AMP	25.00	100,000
Transformers 480/120V	3,000	KVA	75.00	225,000
Distribution panelboards - 208V	8,000	AMP	25.00	200,000
Feeder conduit and wire - 600V	2,000	LF	120.00	240,000
Emergency and Uninterrupted Power				
Emergency Generator	1,500	KVA	350.00	525,000
Automatic transfer switch	1,500	AMP	45.00	67,500
Distribution panelboards	1,500	AMP	25.00	37,500
General Purpose Lighting				
Panelboards	44	EA	2,500.00	110,000
Lighting				
Core Area	147,000	SF	12.00	1,764,000
Tenant Area	616,350	SF	6.00	3,698,100
Parking area	195,760	SF	4.00	783,040
Machine and Equipment Power				
Connections and switches including conduit and wire				
Elevators	16	EA	1,000.00	16,000
Cooling towers	2	EA	5,000.00	10,000
Chillers	2	EA	12,000.00	24,000
Pumps	6	EA	2,000.00	12,000
Miscellaneous connections	959,110	SF	0.75	719,333
User Convenience Power				
Panelboards	88	EA	2,500.00	220,000
Receptacles				
Core/Shell	147,000	SF	3.00	441,000
Tenant Area	616,350	SF	5.00	3,081,750
Parking area	195,760	SF	2.00	391,520
Communications				
Telephone and communications				
Core Area, panels and backbone only	1	LS	75,000.00	75,000
Tenant Area	616,350	SF	3.00	1,849,050

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
Security Systems				
Security System	959,110	SF	2.00	1,918,220
Fire Alarm Systems				
Fire Alarm Systems	959,110	SF	3.00	2,877,330
Other Electrical Systems				
Grounding Systems	959,110	SF	0.25	239,778
Lightning protection	1	LS	25,000.00	25,000
				22,670,120
13. Fire Protection Systems				
Sprinkler and Standpipe Systems				
Fire Protection Sprinkler Systems	959,110	SF	4.00	3,836,440
Standpipe and Hose Systems	959,110	SF	1.00	959,110
Specialties and Other Systems				
Smoke Evacuation	1	LS	250,000.00	250,000
				5,045,550
14. Site Preparation & Building Demolition				
Site Preparation	100,000	SF	15.00	1,500,000
				1,500,000
15. Site Paving, Structures & Landscaping				
Site Development	50,060	SF	25.00	1,251,500
				1,251,500
16. Utilities on Site				
Site Utilities	1	LS	500,000.00	500,000
				500,000

PERFORMANCE BASED COMPONENT SUMMARY

Gross Area: 959,110 SF

		$/SF	$x1,000
1. Foundations		17.93	17,193
2. Vertical Structure		48.39	46,414
3. Floor & Roof Structures		25.49	24,449
4. Exterior Cladding		42.43	40,697
5. Roofing, Waterproofing & Skylights		2.63	2,526
Shell (1-5)		136.88	131,279
6. Interior Partitions, Doors & Glazing		10.18	9,760
7. Floor, Wall & Ceiling Finishes		14.34	13,751
Interiors (6-7)		24.51	23,512
8. Function Equipment & Specialties		9.48	9,090
9. Stairs & Vertical Transportation		9.99	9,584
Equipment & Vertical Transportation (8-9)		19.47	18,674
10. Plumbing Systems		6.12	5,872
11. Heating, Ventilating & Air Conditioning		29.23	28,033
12. Electric Lighting, Power & Communications		23.64	22,670
13. Fire Protection Systems		5.26	5,046
Mechanical & Electrical (10-13)		64.25	61,621
Total Building Construction (1-13)		**245.11**	**235,086**
14. Site Preparation & Demolition		1.56	1,500
15. Site Paving, Structures & Landscaping		1.30	1,252
16. Utilities on Site		0.52	500
Total Site Construction (14-16)		**3.39**	**3,252**
TOTAL BUILDING & SITE (1-16)		**248.50**	**238,338**
General Conditions	12.00%	29.82	28,601
Contractor's Overhead & Profit or Fee	6.00%	16.70	16,016
PLANNED CONSTRUCTION COST	***March 2010***	**295.02**	**282,955**
Design, Management and Inspection	20.00%	59.00	56,591
Escalation is excluded	0.00%	0.00	0
RECOMMENDED BUDGET	***March 2010***	**354.02**	**339,546**

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
1. Foundations				
Mass excavation				
Excavate for basement and Mat foundation	136,085	CY	15.00	2,041,275
Shoring at perimeter	51,852	SF	50.00	2,592,600
Backfill with imported material	28,807	CY	35.00	1,008,233
Dispose off site	136,085	CY	20.00	2,721,700
Hazardous material remediation				Excluded
Foundations				
Reinforced concrete Mat foundation, 10'-0"	49,940	SF	175.00	8,739,500
Elevator pits	6	EA	15,000.00	90,000
				17,193,308
2. Vertical Structure				
Columns and pilasters				
Wide flange	989	TN	4,000.00	3,956,000
Box columns				
Metal plate frame	4,533	TN	6,000.00	27,198,000
Studs- 3/4" diameter, 6" long	85,200	EA	60.00	5,112,000
Concrete fill	2,465	CY	450.00	1,109,250
Sprayed fireproofing	989	TN	350.00	346,150
Diagonal reinforcing				
Buckling restraint braces				
703 k	850	LF	180.00	153,000
589 k	288	LF	150.00	43,200
532 k	912	LF	150.00	136,800
513 k	926	LF	150.00	138,900
418 k	3,402	LF	120.00	408,240
342 k	11,236	LF	120.00	1,348,320
304 k	720	LF	120.00	86,400
266 k	872	LF	100.00	87,200
228 k	988	LF	100.00	98,800
Brace connections				
Gusset plates				
3/4" thick plate steel welded connection	192	EA	1,500.00	288,000
1" thick plate steel welded connection	1,880	EA	2,000.00	3,760,000

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
Concrete retaining walls				
18" Concrete retaining wall				
Formwork to one side	21,456	SF	15.00	321,840
Reinforcing steel	283,824	LBS	1.15	326,398
Concrete	1,311	CY	225.00	294,975
24" Concrete retaining wall				
Formwork to one side	21,456	SF	15.00	321,840
Reinforcing steel	422,059	LBS	1.15	485,368
Concrete	1,748	CY	225.00	393,300
				46,413,980

3. Floor and Roof Structure

Floor at lowest level				
Slab on grade - See foundations (mat slab)				
Suspended floors				
Wide flange framing	3,144	TN	4,000.00	12,576,000
Channel and angle ledger	101,965	LBS	2.50	254,913
3" formlock deck, 18 ga.	859,230	SF	4.50	3,866,535
3 1/4" lightweight concrete	859,230	SF	5.00	4,296,150
Sprayed fireproofing	3,144	TN	350.00	1,100,400
Plaza level slab/roof				
Wide flange framing	311	TN	4,000.00	1,244,000
Channel and angle ledger	33,988	LBS	2.50	84,970
3" formlock deck, 16 ga.	49,940	SF	4.50	224,730
9" normal weight concrete	49,940	SF	5.00	249,700
Sprayed fireproofing	311	TN	350.00	108,850
High roof				
Wide flange framing	62	TN	4,000.00	248,000
3" formlock deck, 18 ga.	18,190	SF	4.50	81,855
3 1/4" lightweight concrete	18,190	SF	5.00	90,950
Sprayed fireproofing	62	TN	350.00	21,700
				24,448,753

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
4. Exterior Cladding				
Wall framing, furring and insulation				
Exterior wall framing	301,653	SF	8.00	2,413,224
Furring to interior face of retaining wall	42,912	SF	4.00	171,648
Insulation and vapor barrier	226,240	SF	1.50	339,360
Applied exterior finishes				
Exterior wall finish - curtain wall with spandrel panels	226,240	SF	120.00	27,148,800
Parapets & edge detailing	554	LF	250.00	138,500
Interior finish to exterior walls				
Gypsum board, taped and sanded	269,152	SF	3.50	942,032
Windows, glazing and louvers				
Exterior wall finish - curtain wall with glazing	75,414	SF	120.00	9,049,680
Exterior doors, frames and hardware				
Glazed Doors & Entrances (allow revolving)	12	EA	35,000.00	420,000
Solid Exterior Doors	8	EA	3,000.00	24,000
Overhead Doors	2	EA	25,000.00	50,000
				40,697,244
5. Roofing, Waterproofing & Skylights				
Waterproofing				
Waterproofing at slab on grade	49,940	SF	10.00	499,400
Waterproofing at retaining wall	42,912	SF	10.00	429,120
Waterproofing membrane under plaza	31,750	SF	15.00	476,250
Insulation				
Rigid insulation at roof	18,190	SF	6.00	109,140
Roofing				
Balconies & accessible roofs	31,750	SF	25.00	793,750
High roof	18,190	SF	12.00	218,280
				2,525,940

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
6. Interior Partitions, Doors & Glazing				
Partition framing and cores				
CMU partitions at basement levels	400	LF	325.00	130,000
Core partitions	7,276	LF	90.00	654,840
Standard partitions	50,932	LF	72.00	3,667,104
Window walls and borrowed lights	1,020	SF	45.00	45,900
Doors, frames & hardware				
Interior doors	2,392	EA	2,200.00	5,262,400
				9,760,244
7. Floor, Wall & Ceiling Finishes				
Floors including base				
Lobby flooring	5,000	SF	35.00	175,000
Core circulation	88,000	SF	6.00	528,000
Restrooms	44,000	SF	15.00	660,000
Office	584,600	SF	5.00	2,923,000
Special use areas	10,000	SF	10.00	100,000
Concrete sealer at basement	195,760	SF	2.00	391,520
Walls				
Lobby	1	EA	75,000.00	75,000
Core circulation	176,000	SF	3.00	528,000
Restroom walls	79,200	SF	15.00	1,188,000
Office	1,137,200	SF	1.50	1,705,800
Special use areas	33,000	SF	5.00	165,000
Paint to concrete and CMU at basement	52,512	SF	1.00	52,512
Ceilings				
Lobby	5,000	SF	25.00	125,000
Core circulation	88,000	SF	12.00	1,056,000
Restrooms	44,000	SF	15.00	660,000
Office	568,600	SF	5.00	2,843,000
Special use areas	22,000	SF	8.00	176,000
Paint to exposed structure at basement	199,760	SF	2.00	399,520
				13,751,352

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
8. Function Equipment & Specialties				
Built in Equipment				
Lobby/entry	1	LS	25,000.00	25,000
Core area	40	EA	18,000.00	720,000
Office areas	584,600	SF	12.00	7,015,200
Restroom areas	44,000	SF	20.00	880,000
Window washing equipment	1	LS	450,000.00	450,000
				9,090,200
9. Stairs & Vertical Transportation				
Stairs				
Regular stair flights	88	EA	22,000.00	1,936,000
Elevators				
Passenger Elevators, gearless traction	264	STOP	28,000.00	7,392,000
Freight Elevators, geared traction, 4 stop	8	STOP	32,000.00	256,000
				9,584,000
10. Plumbing Systems				
Sanitary fixtures and connection piping				
Toilets	440	EA	1,600.00	704,000
Urinals	88	EA	1,800.00	158,400
Lavatories	264	EA	1,200.00	316,800
Drinking Fountains and Coolers	44	EA	2,500.00	110,000
Sinks	44	EA	1,700.00	74,800
Hose bibbs	44	EA	500.00	22,000
Domestic water and distribution				
Cold Water Service				
Copper piping incl. fittings >2"	1,300	LF	50.00	65,000
Copper piping incl. fittings to 2"	13,860	LF	32.00	443,520
Hot Water Service				
Copper piping incl. fittings >2"	2,600	LF	50.00	130,000
Copper piping incl. fittings to 2"	27,720	LF	32.00	887,040
Insulation	30,320	LF	9.00	272,880
Valves				
Isolation valves to 3/4"	1,232	EA	65.00	80,080
Domestic Water Supply Equipment				
Hot water heating and circulation	1	LS	200,000.00	200,000

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
Sanitary waste				
Waste & vent pipework-above ground				
Cast Iron No Hub, >6"	1,300	LF	75.00	97,500
Cast Iron No Hub, to 3"	13,860	LF	32.00	443,520
Sanitary waste, vent and service piping				
Floor Drains	88	EA	1,000.00	88,000
Rain Water Drainage				
Pipe and Fittings	47,609	LF	35.00	1,666,331
Roof/Overflow Drains	83	EA	750.00	62,425
Gas distribution				
Copper piping incl. fittings to 2"	2,000	LF	25.00	50,000
				5,872,296

11. Heating, Ventilation & Air Conditioning

Heat generating systems				
Heating hot water boilers, high efficiency condensing	43,200	MBTH	25.00	1,080,000
Heating hot water pumps	2	EA	35,000.00	70,000
Cooling Generating Systems				
Cooling towers	3,000	TN	350.00	1,050,000
Chillers, 2 each	3,000	TN	550.00	1,650,000
Chilled water pumps	2	EA	30,000.00	60,000
Condenser water pumps	2	EA	28,000.00	56,000
Variable speed drives, vibration isolation, etc.	6	EA	12,000.00	72,000
Distribution systems				
Piping, fittings, valves and insulation				
Chilled water				
Chilled water pipework, fittings	1,400	LF	95.00	133,000
Valves and specialties	1	LS	75,000.00	75,000
Heating hot water				
Heating hot water pipework, fittings, including insulation				
6" - 4"	1,200	LF	85.00	102,000
< = 3"	36,000	LF	30.00	1,080,000
Valves and specialties	1	LS	150,000.00	150,000
Condenser water				
Condenser water pipework, fittings	1,200	LF	90.00	108,000
Valves and specialties	1	LS	25,000.00	25,000
Connections to VAV boxes	1,517	EA	350.00	531,038

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
Air handling equipment				
Air handler units	700,000	CFM	5.00	3,500,000
VAV boxes				
Core/Shell	294	EA	1,250.00	367,500
Tenant areas, 1 per 600 USF	1,027	EA	1,250.00	1,284,063
Parking area	196	EA	1,250.00	245,000
Sound attenuation - duct mounted	700,000	CFM	0.25	175,000
Air distribution, return and exhaust				
Galvanized sheet metal ductwork	959,110	LB	8.00	7,672,880
Flexible ductwork	36,000	LF	6.00	216,000
Dampers, volume	750	EA	40.00	30,000
Dampers, smoke/fire	80	EA	1,200.00	96,000
Insulation/duct liner	400,000	SF	2.50	1,000,000
Diffusers, registers and grilles				
Ceiling				
Core/Shell	1,470	EA	200.00	294,000
Tenant areas, 1 per 150 USF	4,109	EA	150.00	616,350
Parking area				
Terminal & Package Units				
Exhaust fans to toilet rooms etc.	1	LS	300,000.00	300,000
Controls and instrumentation				
DDC Control system	959,110	SF	5.00	4,795,550
Test and balance				
Test and balance	959,110	SF	1.25	1,198,888
				28,033,268

12. Electrical Lighting, Power & Communication

Primary Service, Medium voltage				
Switchgear 13.8KV including (2) tie breakers, (2) feeder breakers, and customer	12,000	KVA	60.00	720,000
Transformer substation 13.8KV/480V, double-ended including secondary	12,000	KVA	150.00	1,800,000
Distribution switchboards - 480V	12,500	AMP	40.00	500,000
Distribution panelboards - 480V	4,000	AMP	25.00	100,000
Transformers 480/120V	3,000	KVA	75.00	225,000
Distribution panelboards - 208V	8,000	AMP	25.00	200,000
Feeder conduit and wire - 600V	2,000	LF	120.00	240,000

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
Emergency and Uninterrupted Power				
Emergency Generator	1,500	KVA	350.00	525,000
Automatic transfer switch	1,500	AMP	45.00	67,500
Distribution panelboards	1,500	AMP	25.00	37,500
General Purpose Lighting				
Panelboards	44	EA	2,500.00	110,000
Lighting				
Core Area	147,000	SF	12.00	1,764,000
Tenant Area	616,350	SF	6.00	3,698,100
Parking area	195,760	SF	4.00	783,040
Machine and Equipment Power				
Connections and switches including conduit and wire				
Elevators	16	EA	1,000.00	16,000
Cooling towers	2	EA	5,000.00	10,000
Chillers	2	EA	12,000.00	24,000
Pumps	6	EA	2,000.00	12,000
Miscellaneous connections	959,110	SF	0.75	719,333
User Convenience Power				
Panelboards	88	EA	2,500.00	220,000
Receptacles				
Core/Shell	147,000	SF	3.00	441,000
Tenant Area	616,350	SF	5.00	3,081,750
Parking area	195,760	SF	2.00	391,520
Communications				
Telephone and communications				
Core Area, panels and backbone only	1	LS	75,000.00	75,000
Tenant Area	616,350	SF	3.00	1,849,050
Security Systems				
Security System	959,110	SF	2.00	1,918,220
Fire Alarm Systems				
Fire Alarm Systems	959,110	SF	3.00	2,877,330
Other Electrical Systems				
Grounding Systems	959,110	SF	0.25	239,778
Lightning protection	1	LS	25,000.00	25,000
				22,670,120

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
13. Fire Protection Systems				
Sprinkler and Standpipe Systems				
Fire Protection Sprinkler Systems	959,110	SF	4.00	3,836,440
Standpipe and Hose Systems	959,110	SF	1.00	959,110
Specialties and Other Systems				
Smoke Evacuation	1	LS	250,000.00	250,000
				5,045,550
14. Site Preparation & Building Demolition				
Site Preparation	100,000	SF	15.00	1,500,000
				1,500,000
15. Site Paving, Structures & Landscaping				
Site Development	50,060	SF	25.00	1,251,500
				1,251,500
16. Utilities on Site				
Site Utilities	1	LS	500,000.00	500,000
				500,000

PERFORMANCE BASED PLUS COMPONENT SUMMARY

Gross Area: 959,110 SF

		$/SF	$x1,000
1. Foundations		17.93	17,193
2. Vertical Structure		52.90	50,733
3. Floor & Roof Structures		25.87	24,814
4. Exterior Cladding		42.43	40,697
5. Roofing, Waterproofing & Skylights		2.63	2,526
Shell (1-5)		141.76	135,964
6. Interior Partitions, Doors & Glazing		10.18	9,760
7. Floor, Wall & Ceiling Finishes		14.34	13,751
Interiors (6-7)		24.51	23,512
8. Function Equipment & Specialties		8.77	8,410
9. Stairs & Vertical Transportation		9.99	9,584
Equipment & Vertical Transportation (8-9)		18.76	17,994
10. Plumbing Systems		6.12	5,872
11. Heating, Ventilating & Air Conditioning		29.23	28,033
12. Electric Lighting, Power & Communications		23.64	22,670
13. Fire Protection Systems		5.26	5,046
Mechanical & Electrical (10-13)		64.25	61,621
Total Building Construction (1-13)		**249.28**	**239,091**
14. Site Preparation & Demolition		1.56	1,500
15. Site Paving, Structures & Landscaping		1.30	1,252
16. Utilities on Site		0.52	500
Total Site Construction (14-16)		**3.39**	**3,252**
TOTAL BUILDING & SITE (1-16)		**252.67**	**242,343**
General Conditions	12.00%	30.32	29,081
Contractor's Overhead & Profit or Fee	6.00%	16.98	16,285
PLANNED CONSTRUCTION COST	***March 2010***	**299.97**	**287,709**
Design, Management and Inspection	20.00%	60.00	57,542
Escalation is excluded	0.00%	0.00	0
RECOMMENDED BUDGET	***March 2010***	**359.97**	**345,251**

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
1. Foundations				
Mass excavation				
Excavate for basement and Mat foundation	136,085	CY	15.00	2,041,275
Shoring at perimeter	51,852	SF	50.00	2,592,600
Backfill with imported material	28,807	CY	35.00	1,008,233
Dispose off site	136,085	CY	20.00	2,721,700
Hazardous material remediation				
Foundations				
Reinforced concrete Mat foundation, 10'-0"	49,940	SF	175.00	8,739,500
Elevator pits	6	EA	15,000.00	90,000
				17,193,308
2. Vertical Structure				
Columns and pilasters				
Wide flange	1,117	TN	4,000.00	4,468,000
Box columns				
Metal plate frame	4,980	TN	6,000.00	29,880,000
Studs- 3/4" diameter, 6" long	90,144	EA	60.00	5,408,640
Concrete fill	2,687	CY	450.00	1,209,150
Sprayed fireproofing	1,117	TN	350.00	390,950
Diagonal reinforcing				
Buckling restraint braces				
950 k	192	LF	225.00	43,200
703 k	1,458	LF	180.00	262,440
665 k	192	LF	180.00	34,560
589 k	592	LF	150.00	88,800
513 k	926	LF	150.00	138,900
456 k	6,292	LF	150.00	943,800
418 k	8,912	LF	120.00	1,069,440
380 k	880	LF	120.00	105,600
342 k	228	LF	120.00	27,360
304 k	480	LF	120.00	57,600
266 k	1,252	LF	100.00	125,200
Brace connections				
Gusset plates				
3/4" thick plate steel welded connection	128	EA	1,500.00	192,000
1" thick plate steel welded connection	2,040	EA	2,000.00	4,080,000
2" thick plate steel welded connection	16	EA	4,000.00	64,000

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
Concrete retaining walls				
18" Concrete retaining wall				
Formwork to one side	21,456	SF	15.00	321,840
Reinforcing steel	283,824	LBS	1.15	326,398
Concrete	1,311	CY	225.00	294,975
24" Concrete retaining wall				
Formwork to one side	21,456	SF	15.00	321,840
Reinforcing steel	422,059	LBS	1.15	485,368
Concrete	1,748	CY	225.00	393,300
				50,733,360

3. Floor and Roof Structure

Floor at lowest level				
Slab on grade - See foundations (mat slab)				
Suspended floors				
Wide flange framing	3,218	TN	4,000.00	12,872,000
Channel and angle ledger	101,965	LBS	2.50	254,913
3" formlock deck, 18 ga.	859,230	SF	4.50	3,866,535
3 1/4" lightweight concrete	859,230	SF	5.00	4,296,150
Sprayed fireproofing	3,218	TN	350.00	1,126,300
Plaza level slab/roof				
Wide flange framing	311	TN	4,000.00	1,244,000
Channel and angle ledger	33,988	LBS	2.50	84,970
3" formlock deck, 16 ga.	49,940	SF	4.50	224,730
9" normal weight concrete	49,940	SF	5.00	249,700
Sprayed fireproofing	311	TN	350.00	108,850
High roof				
Wide flange framing	72	TN	4,000.00	288,000
3" formlock deck, 18 ga.	18,190	SF	4.50	81,855
3 1/4" lightweight concrete	18,190	SF	5.00	90,950
Sprayed fireproofing	72	TN	350.00	25,200
				24,814,153

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
4. Exterior Cladding				
Wall framing, furring and insulation				
Exterior wall framing	301,653	SF	8.00	2,413,224
Furring to interior face of retaining wall	42,912	SF	4.00	171,648
Insulation and vapor barrier	226,240	SF	1.50	339,360
Applied exterior finishes				
Exterior wall finish - curtain wall with spandrel panels	226,240	SF	120.00	27,148,800
Parapets & edge detailing	554	LF	250.00	138,500
Interior finish to exterior walls				
Gypsum board, taped and sanded	269,152	SF	3.50	942,032
Windows, glazing and louvers				
Exterior wall finish - curtain wall with glazing	75,414	SF	120.00	9,049,680
Exterior doors, frames and hardware				
Glazed Doors & Entrances (allow revolving)	12	EA	35,000.00	420,000
Solid Exterior Doors	8	EA	3,000.00	24,000
Overhead Doors	2	EA	25,000.00	50,000
				40,697,244
5. Roofing, Waterproofing & Skylights				
Waterproofing				
Waterproofing at slab on grade	49,940	SF	10.00	499,400
Waterproofing at retaining wall	42,912	SF	10.00	429,120
Waterproofing membrane under plaza	31,750	SF	15.00	476,250
Insulation				
Rigid insulation at roof	18,190	SF	6.00	109,140
Roofing				
Balconies & accessible roofs	31,750	SF	25.00	793,750
High roof	18,190	SF	12.00	218,280
				2,525,940

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
6. Interior Partitions, Doors & Glazing				
Partition framing and cores				
CMU partitions at basement levels	400	LF	325.00	130,000
Core partitions	7,276	LF	90.00	654,840
Standard partitions	50,932	LF	72.00	3,667,104
Window walls and borrowed lights	1,020	SF	45.00	45,900
Doors, frames & hardware				
Interior doors	2,392	EA	2,200.00	5,262,400
				9,760,244
7. Floor, Wall & Ceiling Finishes				
Floors including base				
Lobby flooring	5,000	SF	35.00	175,000
Core circulation	88,000	SF	6.00	528,000
Restrooms	44,000	SF	15.00	660,000
Office	584,600	SF	5.00	2,923,000
Special use areas	10,000	SF	10.00	100,000
Concrete sealer at basement	195,760	SF	2.00	391,520
Walls				
Lobby	1	EA	75,000.00	75,000
Core circulation	176,000	SF	3.00	528,000
Restroom walls	79,200	SF	15.00	1,188,000
Office	1,137,200	SF	1.50	1,705,800
Special use areas	33,000	SF	5.00	165,000
Paint to concrete and CMU at basement	52,512	SF	1.00	52,512
Ceilings				
Lobby	5,000	SF	25.00	125,000
Core circulation	88,000	SF	12.00	1,056,000
Restrooms	44,000	SF	15.00	660,000
Office	568,600	SF	5.00	2,843,000
Special use areas	22,000	SF	8.00	176,000
Paint to exposed structure at basement	199,760	SF	2.00	399,520
				13,751,352

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
8. Function Equipment & Specialties				
Built in Equipment				
Lobby/entry	1	LS	25,000.00	25,000
Core area	40	EA	18,000.00	720,000
Office areas	584,600	SF	12.00	7,015,200
Restroom areas	10,000	SF	20.00	200,000
Window washing equipment	1	LS	450,000.00	450,000
				8,410,200
9. Stairs & Vertical Transportation				
Stairs				
Regular stair flights	88	EA	22,000.00	1,936,000
Elevators				
Passenger Elevators, gearless traction	264	STOP	28,000.00	7,392,000
Freight Elevators, geared traction, 4 stop	8	STOP	32,000.00	256,000
				9,584,000
10. Plumbing Systems				
Sanitary fixtures and connection piping				
Toilets	440	EA	1,600.00	704,000
Urinals	88	EA	1,800.00	158,400
Lavatories	264	EA	1,200.00	316,800
Drinking Fountains and Coolers	44	EA	2,500.00	110,000
Sinks	44	EA	1,700.00	74,800
Hose bibbs	44	EA	500.00	22,000
Domestic water and distribution				
Cold Water Service				
Copper piping incl. fittings >2"	1,300	LF	50.00	65,000
Copper piping incl. fittings to 2"	13,860	LF	32.00	443,520
Hot Water Service				
Copper piping incl. fittings >2"	2,600	LF	50.00	130,000
Copper piping incl. fittings to 2"	27,720	LF	32.00	887,040
Insulation	30,320	LF	9.00	272,880
Valves				
Isolation valves to 3/4"	1,232	EA	65.00	80,080
Domestic Water Supply Equipment				
Hot water heating and circulation	1	LS	200,000.00	200,000

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
Sanitary waste				
Waste & vent pipework-above ground				
Cast Iron No Hub, >6"	1,300	LF	75.00	97,500
Cast Iron No Hub, to 3"	13,860	LF	32.00	443,520
Sanitary waste, vent and service piping				
Floor Drains	88	EA	1,000.00	88,000
Rain Water Drainage				
Pipe and Fittings	47,609	LF	35.00	1,666,331
Roof/Overflow Drains	83	EA	750.00	62,425
Gas distribution				
Copper piping incl. fittings to 2"	2,000	LF	25.00	50,000
				5,872,296

11. Heating, Ventilation & Air Conditioning

Heat generating systems				
Heating hot water boilers, high efficiency condensing	43,200	MBTH	25.00	1,080,000
Heating hot water pumps	2	EA	35,000.00	70,000
Cooling Generating Systems				
Cooling towers	3,000	TN	350.00	1,050,000
Chillers, 2 each	3,000	TN	550.00	1,650,000
Chilled water pumps	2	EA	30,000.00	60,000
Condenser water pumps	2	EA	28,000.00	56,000
Variable speed drives, vibration isolation, etc.	6	EA	12,000.00	72,000
Distribution systems				
Piping, fittings, valves and insulation				
Chilled water				
Chilled water pipework, fittings	1,400	LF	95.00	133,000
Valves and specialties	1	LS	75,000.00	75,000
Heating hot water				
Heating hot water pipework, fittings, including insulation				
6" - 4"	1,200	LF	85.00	102,000
< = 3"	36,000	LF	30.00	1,080,000
Valves and specialties	1	LS	150,000.00	150,000
Condenser water				
Condenser water pipework, fittings	1,200	LF	90.00	108,000
Valves and specialties	1	LS	25,000.00	25,000
Connections to VAV boxes	1,517	EA	350.00	531,038

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
Air handling equipment				
Air handler units	700,000	CFM	5.00	3,500,000
VAV boxes				
Core/Shell	294	EA	1,250.00	367,500
Tenant areas, 1 per 600 USF	1,027	EA	1,250.00	1,284,063
Parking area	196	EA	1,250.00	245,000
Sound attenuation - duct mounted	700,000	CFM	0.25	175,000
Air distribution, return and exhaust				
Galvanized sheet metal ductwork	959,110	LB	8.00	7,672,880
Flexible ductwork	36,000	LF	6.00	216,000
Dampers, volume	750	EA	40.00	30,000
Dampers, smoke/fire	80	EA	1,200.00	96,000
Insulation/duct liner	400,000	SF	2.50	1,000,000
Diffusers, registers and grilles				
Ceiling				
Core/Shell	1,470	EA	200.00	294,000
Tenant areas, 1 per 150 USF	4,109	EA	150.00	616,350
Parking area				
Terminal & Package Units				
Exhaust fans to toilet rooms etc.	1	LS	300,000.00	300,000
Controls and instrumentation				
DDC Control system	959,110	SF	5.00	4,795,550
Test and balance				
Test and balance	959,110	SF	1.25	1,198,888
				28,033,268

12. Electrical Lighting, Power & Communication

Primary Service, Medium voltage				
Switchgear 13.8KV including (2) tie breakers, (2) feeder breakers, and customer	12,000	KVA	60.00	720,000
Transformer substation 13.8KV/480V, double-ended including secondary	12,000	KVA	150.00	1,800,000
Distribution switchboards - 480V	12,500	AMP	40.00	500,000
Distribution panelboards - 480V	4,000	AMP	25.00	100,000
Transformers 480/120V	3,000	KVA	75.00	225,000
Distribution panelboards - 208V	8,000	AMP	25.00	200,000
Feeder conduit and wire - 600V	2,000	LF	120.00	240,000

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
Emergency and Uninterrupted Power				
Emergency Generator	1,500	KVA	350.00	525,000
Automatic transfer switch	1,500	AMP	45.00	67,500
Distribution panelboards	1,500	AMP	25.00	37,500
General Purpose Lighting				
Panelboards	44	EA	2,500.00	110,000
Lighting				
Core Area	147,000	SF	12.00	1,764,000
Tenant Area	616,350	SF	6.00	3,698,100
Parking area	195,760	SF	4.00	783,040
Machine and Equipment Power				
Connections and switches including conduit and wire				
Elevators	16	EA	1,000.00	16,000
Cooling towers	2	EA	5,000.00	10,000
Chillers	2	EA	12,000.00	24,000
Pumps	6	EA	2,000.00	12,000
Miscellaneous connections	959,110	SF	0.75	719,333
User Convenience Power				
Panelboards	88	EA	2,500.00	220,000
Receptacles				
Core/Shell	147,000	SF	3.00	441,000
Tenant Area	616,350	SF	5.00	3,081,750
Parking area	195,760	SF	2.00	391,520
Communications				
Telephone and communications				
Core Area, panels and backbone only	1	LS	75,000.00	75,000
Tenant Area	616,350	SF	3.00	1,849,050
Security Systems				
Security System	959,110	SF	2.00	1,918,220
Fire Alarm Systems				
Fire Alarm Systems	959,110	SF	3.00	2,877,330
Other Electrical Systems				
Grounding Systems	959,110	SF	0.25	239,778
Lightning protection	1	LS	25,000.00	25,000
				22,670,120

Item Description	*Quantity*	*Unit*	*Rate*	*Total*
13. Fire Protection Systems				
Sprinkler and Standpipe Systems				
Fire Protection Sprinkler Systems	959,110	SF	4.00	3,836,440
Standpipe and Hose Systems	959,110	SF	1.00	959,110
Specialties and Other Systems				
Smoke Evacuation	1	LS	250,000.00	250,000
				5,045,550
14. Site Preparation & Building Demolition				
Site Preparation	100,000	SF	15.00	1,500,000
				1,500,000
15. Site Paving, Structures & Landscaping				
Site Development	50,060	SF	25.00	1,251,500
				1,251,500
16. Utilities on Site				
Site Utilities	1	LS	500,000.00	500,000
				500,000